




Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"SHORT TERM NOTICE INVITING TENDERS"

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **23/02/2024** up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **22/02/2024** up to 4.00 P.M and the application for issue of tender form shall be received on **21/02/2024** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post off/ice/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	C/o link road from Uscher to Daghai (SW:- Providing and laying Soling 7 Wearing in Km. 0/0 to 0/350) (under MMGSY)	4,06,953/-	8100/-	Two Months	350/-
2	C/o link road from Chhatar to Kandra (SW:- P/L CC work in Km. 0/0 to 0/125) (under MMGSY)	3,87,956/-	7800/-	Two Months	350/-
3	C/o link road from Salan to Lower Salan (SW:- C/o 900 mm dia Hume pipe culvert at Rd 0/150 to 0/450) (under MMGSY)	3,81,365/-	7600/-	Two Months	350/-
4	C/o link road from Kona to Lower Kona (SW:- C/o 1.00 mtr Span culvert Rd 0/180) (under MMGSY)	394,391/-	7900/-	Two Months	350/-
5	C/o link road from Baba Suraj Kund (SW:- C/o 1.00 mtr Span culvert at Rd 0/180) (under MMGSY)	2,95,775/-	5900/-	Two Months	350/-
6	C/o link road from Bhagolu da Ghatta to Village Dehru (SW:- C/o 1.00 mtr span culvert at Rd 0/300) (under MMGSY)	2,96,275/-	5900/-	Two Months	350/-
7	C/o link road from Ballah road to Jol via village Lehar (SW:- Providing and laying CC work in Km. 0/0 to 0/115) (under MMGSY)	2,93,280/-	5900/-	Two Months	350/-
8	C/o link road to Lahar Malancha GP Bhadrol (SW:- C/o Retaining wall at Rd 1/075 to 1/092 and providing and laying Wearing in Km. 1/0 to 1/250) (under MMGSY)	3,92,327/-	7800/-	Two Months	350/-
9	C/o link road to village Rakkad (SW:- Providing and laying CC work in Km. 0/075 to 0/180) (under MMGSY)	2,93,000/-	5900/-	Two Months	350/-
10	C/o link road to village Katyarch Basti (SW:- Providing and laying CC work in Km. 0/250 to 0/356) (under MMGSY)	2,93,806/-	5900/-	Two Months	350/-
11	C/o link road from Dafhain to Dhiman Basti (SW:- C/o 2.00 mtr span RCC slab culvert alongwith approaches at Rd 0/450) (under MMGSY)	4,97,676/-	10,000/-	Two Months	350/-
12	C/o link road to village Thera (SW:- Providing and laying Soling & Wearing in Km. 0/600 to 0/940) (under MMGSY)	3,91,891/-	7800/-	Two Months	350/-
13	C/o link road Bhatlu School to Pandit Basti (SW:- Formation cutting at Rd 0/050 to 0/060 & 0.60 mtr span culvert at Rd 0/025) (under MMGSY)	4,92,755/-	9900/-	Two Months	350/-
14	C/o link road to Chhang Basti & Lamber Basti (SW:- Providing and laying Soling in Km. 0/0 to 0/720) (under MMGSY)	4,91,324/-	9800/-	Two Months	350/-
15	C/o link road from Durga Mata Mandir to Kundru (SW:- P/L CC work in Km. 0/125 to 0/250) (under MMGSY)	3,87,956/-	7800/-	Two Months	350/-



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P.)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

16	C/o link road from Baba Kutiya to Nath Basti GP Gadiara (SW:- P/L Soling & CC work in Km. 0/0 to 0/145) (under MMGSY)	4,90,028/-	9800/-	Two Months	350/-
17	C/o link road to village Gharanu Basti (SW:- C/o 2.00 mtr span RCC culvert at Rd 0/030) (under MMGSY)	3,86,707/-	7700/-	Two Months	350/-
18	C/o Samana to Samana road (SW:- P/L CC work in Km. 0/200 to 0/350 & 0/400 to 0/465) (under MMGSY)	4,91,820/-	9800/-	Two Months	350/-
19	C/o link road to village Phuluni (SW:- P/L CC work in Km. 0/245 to 0/400 & 0/450 to 0/500) (under MMGSY)	4,91,820/-	9800/-	Two Months	350/-
20	C/o link road from Upper Tikker to Lower Tikker via Durga Mahila Mandal (SW:- P/L CC work in Km 0/150 to 0/320) (under MMGSY)	4,82,190/-	9600/-	Two Months	350/-
21	C/o link road from Gharana Basti to Marena Basti (SW:- P/L CC work in Km. 0/100 to 0/275) (under MMGSY)	4,96,404/-	9900/-	Two Months	350/-
22	C/o link road from Garh to Rora (SW:- P/L CC work in Km. 0/100 to 0/175 & 1/200 to 1/315) (under MMGSY)	4,91,820/-	9800/-	Two Months	350/-
23	C/o link road from Bari to Kedara Mandir (SW:- P/LCC work in Km. 4/700 to 4/917) (under MMGSY)	4,96,380/-	9900/-	Two Months	350/-
24	C/o link road to Bhitli Shamshanghatt GP Malnu (SW:- P/L CC work in Km. 0/0 to 0/100 & C/o R/Wallat Rd 0/315 to 0/328) (under MMGSY)	3,93,750/-	7900/-	Two Months	350/-

Terms & Conditions:-

13. The contractor/firm should be registered as or dealer GST No.
14. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
15. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
16. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
17. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
18. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

No. PWD/BWD/Tender/NIT/2023-24/- 15923-82

(On behalf of Governor of Himachal Pradesh)

Dated:- 17/2/2024

Copy to following for information and necessary action:-

25. The Principal Secy.(PW) to the Govt. of H.P. Shimla.
26. The Engineer-in-Chief, HPPWD, Shimla.
27. The Chief Engineer (KZ),HPPWD, Dharamshala.
28. The Director, Information & Publications Department, HP Shimla.
29. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
30. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
31. The Deputy Commissioner, Kangra at Dharamshala.
32. The Sub-Divisional Officer(Civil) Palampur.
33. All the S.E.s/E.E.s under Kangra Zone.
34. All the Assistant Engineers under this Division.
35. The Drawing /Accounts Branch in this office.
36. Notice Board.

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of link road from Uscher to Dagchain. (SH:- Providing and laying Soling & Wearing in Km 0/0 to 0/350)
(Under MMGSY).

Estimate Cost :-Rs. 4,06,953/-
Earnest Money :-Rs. 8100/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1231.13			Per Square metre	0.00
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and reolling the sub- grade completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1231.13			Per Square metre	
3	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	123.11			Per Cubic metre	
4	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	84.06			Per Cubic metre	
Total :-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C/O-Link road from Chhatar to Kandera (SH:- P/L CC work in Km 0/00 to 0/125) under MIMGSY

Estimate Cost :- 3,87,956/-
Earnest Money :- 7800/-

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Km. Static roller in stages to proper grade and camber, applying and brooming, Stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-1 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	38.13			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	47.66			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of link road from Salan to Lower Salan (SH:- C/o 900 mm dia Hume Pipe culvert at Rd 0/150 & 0/450) Under MMGSY

Estimate Cost :- 3,81,365/-
Earnest Money :- 7600/-

Time Limit :- Two Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	61.70			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	7.48			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	24.51			Per Cubic metre	

4	Providing and laying (to level or slope) 900mm dia (Nine hundred millimetre) diameter reinforced cement concrete non pressure pipes IS Class NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2:4 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1100 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.00			Per Running metre
7	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	41.92			Per Cubic metre
8	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8			Each
Total :-					

Amic
 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of link road from Kona to Lower Kona (SH:- C/o Imtr Span Culvert at Rd to 0/180) Under MMGSY

Estimate Cost :- 3,94,391/-
Earnest Money :- 7900/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering, as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	39.21			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	1.84			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete of plain cement concrete nominal mix 1: 2 ½ : 5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments etcetra and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidental . The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	25.73			Per Cubic metre	

4	Providing and laying mechanically mixed and vibrated plain cement concrete Grade M-20 (M-Twenty) design mix with graded crushed stone aggregate 40mm (forty millimeter) nominal size using cement concrete not less than 330 Kg (kilogram) per cubic metre in substructure complete as per drawings and MORD technical specification section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government.	0.60			Per Cubic metre
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.40			Per Cubic metre
6	Supplying, fitting and placing HYSD bar reinforcement in super structure complete with straightening, bending, binding of bars including the cost of binding wire in all heights / depths as per drawing and MORD technical specification section 1000 and 1400 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the government.	0.45			Per Tonne
7	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	41.92			Per Cubic metre
8	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30			Each
Total :-					


 Executive Engineer
 Bhawarna Bhawarna
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of link road from Baba Suraj Kund (SH- C/o-1.00 mtr Span Culvert at Rd to 4/80) Under MMGSY

Estimate Cost :- 2,95,775/-
Earnest Money :- 5900/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ((Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	28.25			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	1.84			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete of plain cement concrete nominal mix 1: 2 ½ : 5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments etcetra and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidental . The rate is including of octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.	25.73			Per Cubic metre	

4	Providing and laying mechanically mixed and vibrated plain cement concrete Grade M-20 (M-Twenty) design mix with graded crushed stone aggregate 40mm (forty millimeter) nominal size using cement concrete not less than 330 Kg (kilogram) per cubic metre in substructure complete as per drawings and MORD technical specification section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government.	0.60			Per Cubic metre
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.40			Per Cubic metre
6	Supplying, fitting and placing HYSD bar reinforcement in super structure complete with straightening, bending, binding of bars including the cost of binding wire in all heights / depths as per drawing and MORD technical specification section 1000 and 1400 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the government.	0.39			Per Tonne
7	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.96			Per Cubic metre
8	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14			Each
Total :-					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of link road from Bhagola Da Ghatta to Village Dehru (SH:- C/o 1.00 mtr Span Culvert at Rd to 0/300). Under
MMGSY
Estimate Cost :- 2,96,275/-
Earnest Money :- 5900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth-work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	28.25			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	1.84			Per Cubic metre	

3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete of plain cement concrete nominal mix 1:2:4 (One cement : two point five sand : five graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments etcetera and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	25.73			Per Cubic metre
4	Providing and laying mechanically mixed and vibrated plain cement concrete Grade M-20 (M-Twenty) design mix with graded crushed stone aggregate 40mm (forty millimeter) nominal size using cement concrete not less than 330 Kg (kilogram) per cubic metre in substructure complete as per drawings and MORD technical specification section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government.	0.60			Per Cubic metre
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.40			Per Cubic metre
6	Supplying, fitting and placing HYSD bar reinforcement in super structure complete with straightening, bending, binding of bars including the cost of binding wire in all heights / depths as per drawing and MORD technical specification section 1000 and 1400 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the government.	0.39			Per Tonne

7	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.96			Per Cubic metre
8	Providing and laying (100mm dia. (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V):20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16			Each
Total :-					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of Link road from Ballah road to Jol via village Lehar. (SH:- Providing and laying CC work in Km:00 to 0/115) (Under MMGSY).

Estimated Cost :- Rs. 2,93,280/-
Earnest Money :- Rs. 5900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (Hundred millimetre) spread thickness (finished work including materials and labour) complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	34.50			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	43.13			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawana Division,
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- C/o link road to Lahar Malancha GP Bhadrol (SH:- C/o Retaining wall at RD 1/075 to 1/092 and Providing and laying Wearing in Km 1/0 to 1/250) (under MMGSY).

Estimated Cost :- Rs. 3,92,237/-
Earnest Money :- Rs. 7800/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	24.82			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana.toll tax, GST or other taxes imposed by the Government.	61.03			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	28			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	19.04			Per Cubic metre	

5	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16.49			Per Cubic metre
6	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	60.05			Per Cubic metre
Total :-					



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of Link road to village Rakkad. (SH:- Providing and laying CC work in Km 0/075 to 0/180)
(Under MMGSY).

Estimated Cost :- Rs. 2,93,000/-
Earnest Money :- Rs. 5900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	5.00			Per Cubic metre	
2		47.25			Per Cubic metre	
Total :-						


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of Work :- Construction of Link road to village Katyarch Basti. (SH:- Providing and laying CC work in Km 0/250 to 0/356) (Under MIMGSY).

Estimated Cost :- Rs. 2,93,300/-
Earnest Money :- Rs. 5900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	47.70			Per Cubic metre	
Total :-						


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of Work :- Construction of link road from Daghain to Dhiman Basti. (SH:- C/o 2.00 mtr span RCC slab culvert alongwith approaches at RD 0/450). (Under MMGSY).

Estimate Cost :- Rs. 4,97,676/-
Earnest Money :- Rs. 10,000/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	40.48			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	4.40			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete of plain cement concrete nominal mix 1: 2 ½ : 5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (Twenty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments etcetera and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidental . The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	58.77			Per Cubic metre	

4	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.60			Per Cubic metre
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.90			Per Cubic metre
6	Supplying, fitting and placing HYSD bar reinforcement in sub structure complete with straightening, bending, binding of bars including the cost of binding wire in all heights / depths as per drawing and MORTH technical specification section 1600 and 2300 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the government.	487.50			Per Kilogram
7	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9			Each
8	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.53			Per Cubic metre
9	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1.5:1:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	9.17			Per Cubic metre

10	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.67			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of link road to village Thera. (SH:- Providing and laying Soling & Wearing in Km 0/600 to 0/940) (Under MMGSY).

Estimate Cost :-Rs. 3,91,891/-
Earnest Money :-Rs. 7800/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub grade to be paid for sepearately depending upon the classification of soil completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1178.10			Per Square metre	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub- grade completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1178.10			Per Square metre	
3	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	117.81			Per Cubic metre	
4	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	81.67			Per Cubic metre	
Total :-						


Executive Engineer
Bhawan Division
HP PWD Bhawan

Schedule of Quantity


Name of Work :- C/o Link road Bhatlu School to Pandit Basti (SH:- Formation cutting at RD 0/050 to 0/060 & 0.60 mtr span culvert at RD 0/025) under MMCSY

Estimate Cost :- 4,92,755/-
Earnest Money :- 9900/-

Time Limit :- Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in Hilly Area in all heights and depths and in all kinds of soil by manual/ mechanical means including saturated soil comprising of ordinary soil soft Rock, Hard rock, chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line grades cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer in charge at site according to the technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of unuseful material for filling in road way, camber, embankments for grade improvement and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and incidentals necessary to complete the 88.92 cubic metre quantity at the rate of Rupees 300/- only (Rupees Three hundred only) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	2963.90			Per Cubic metre	
2	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	4.48			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge. Including carriage of material within all leads and lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	2.68			Per Cubic metre	

4	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg. (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section. 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.40			Per Cubic metre
5	Supplying, fitting and placing HYSD bar reinforcement in super structure complete with straightening, bending, binding of bars including the cost of binding wire in all heights & depths as per drawing and MORD technical specification section 1000 and 1400 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the government.	210.00			Per Kilogram
Total :-					



 Executive Engineer
 Bhawana Bickson
 HP PWD Bawana

Schedule of Quantity

Name of Work :- Construction of link road to Chhang Basti & Lamber Basti. (SH:- Providing and laying Soling in Km 0/0 to 0/720).
(Under MMGSY).

Estimate Cost :-Rs. 4,91,324/-
Earnest Money :-Rs. 9800/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub grade to be paid for sepearately depending upon the classification of soil completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2532.60			Per Square metre	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub- grade completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2532.60			Per Square metre	
3	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	253.26			Per Cubic metre	
Total :-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C/O Link Road From Durga Mata Mandir to Kuandru (SH:- P/L CC work in Km 0/125 to 0/250) under MMGSY

Estimate Cost :- 3,87,956/-
Earnest Money :- 7800/-

		Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
S. No	Description of Item					
1	Providing, laying, Soling: 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-1 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	38.13			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	47.66			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C/O link road from Baba Kutiya to Nath Basti GP Gadiara (SH:- P/L Soling & CC work in Km 0/0 to 0/45) under MMGSY
 Estimate Cost :- 4,90,028/-
 Earnest Money :- 9800/-

Time Limit :- Two Months		Rate		Unit		Amount	
S. No	Description of Item	Quantity	In figure	In Words	Unit	Rs.	
1	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-I, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Km. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-I as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	48.16			Per Cubic metre		
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	60.20			Per Cubic metre		
Total :-							


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C/o link road to Village Charanu Basti (SH- C/o 2.00 mtr span RCC slab culvert at RD 0/030) under MMGSY

Estimate Cost :- Rs. 3,86,707/-

Earnest Money :- Rs. 7700/-

Time Limit :- Two Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	75.02			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	5.92			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete of plain cement concrete nominal mix 1: 2 ½ :5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments etcetera and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidental . The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	43.18			Per Cubic metre	

4	Providing and laying mechanically mixed and vibrated plain cement concrete Grade M-20 (M-Twenty) design mix with graded crushed stone aggregate 40mm (forty millimeter) nominal size using cement concrete not less than 330 Kg (kilogram) per cubic metre in substructure complete as per drawings and MORD technical specification section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government.	2.50			Per Cubic metre
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete in super structure as per drawing and M.O.R.D. technical specification section 800, 900 & 1400 R.C.C. Grade M-25 (M- twenty five) designed mix with minimum cement contents not less than 400 (Four hundred) Kilogram per cubic meter with 20mm (Twenty millimeter) nominal size grade crushed stone aggregate and curing complete including cost of form work, but excluding the cost of reinforcement for reinforced cement concrete work in slab & wheel guard etcetera as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.58			Per Cubic metre
6	Supplying, fitting and placing HYSD bar reinforcement in super structure complete with straightening, bending, binding of bars including the cost of binding wire in all heights / depths as per drawing and MORD technical specification section 1000 and 1400 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the government.	583.00			Per Kilogram
7	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.22			Per Cubic metre

8	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	24				Each
---	--	----	--	--	--	------

Total :-


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C to Link road to Village Phulani (SH :- P/L-CC work in Km 0/245 to 0/400 & 0/450 to 0/500) under MMGSY

Estimate Cost :- 4,91,820/-
Earnest Money :- 9800/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size in open foundation as per drawing and M.O.R.D. technical specifications section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government.	81.97			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work:- G/O Samana to Samana road (SH:- P4)-CC work in Km 0/200 to 0/350 & 0/400 to 0/465) under MMGSY

Estimate Cost :- 4,91,820/-

Earnest Money :- 9800/-

Time Limit :- Two Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size in open foundation as per drawing and M.O.R.D. technical specifications section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government.	81.97			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- C/o Link road from Upper Tikkar to Lower Durga Mahila Mandal (SH:-P/E CC work in Km 0/150 to 0/320) under MMGSY

**Estimate Cost :- 4,82,190-
Earnest Money :- 9600/-**

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-I, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80±100 .Kp. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-I as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	51.85			Per Cubic metre	
2	Providing and laying mechanically mixed and y/brated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size in open foundation as per drawing and M.O.R.D. technical specifications section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government.	64.81			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- C/o Link road from Gharana Basti to Marena Basti (SH- P/L CC work in Km 0/100 to 0/275) under MMGSY

Estimate Cost :- 4,96,404/-
Earnest Money :- 9900/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-I, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kp. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-I as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	53.38			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size in open foundation as per drawing and M.O.R.D. technical specifications section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government.	66.72			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity


Name of Work :- Link road from Garh to Rora (SH-1) P/A CC work in Km 0/100 to 0/175 & 1/200 to 1/315) under MMGSY

Estimate Cost :- 4,91,820/-

Earnest Money :- 9800/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size in open foundation as per drawing and M.O.R.D. technical specifications section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government.	81.97			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bawana

Schedule of Quantity

Name of Work:- C/A Link road from Bari to Kedara Mandir (SH)- P/L CC work in Km 4/700 to 4/917) under MMGSY

Estimate Cost :- 4,96,380/-

Earnest Money :- 9900/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size in open foundation as per drawing and M.O.R.D. technical specifications section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government.	82.73			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C/o Link Road to Bhitli shaminshanghat GP, Malau (SH:- P.A.-CC work in Km 0/00 to 0/100 & C/o R/wall at RD 0/315 to 0/328) under MMGSY

Estimate Cost :- 3,93,750/-
Earnest Money :- 7900/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in Hilly Area in all heights and depths and in all kinds of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft Rock, Hard rock, chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer in charge at site according to the technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of unusable material for filling in road way, camber, embankments for grade improvement and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and incidentals necessary to complete the 15.00 cubic metre quantity at the Rate of Rupees 300/- only (Rupees Three hundred only) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	90.00			Per Cubic metre	
2	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water.) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	11.96			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (Twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	34.06			Per Cubic metre	

4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.03		Per Cubic metre
5	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V):20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.00		Each
6	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, stone, screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.20 cum. (Zero point two zero cubic metre) per ten square metre and binding materials at the rate of 0.06 cum. (Zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimeters to forty five millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22.50		Per Cubic metre
7	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.50		Per Cubic metre

Total :-

Amey
Executive Engineer
Bhawarna Division
HP PWD Bhawarna