



Himachal Pradesh

Public Works Department

HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083

Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"SHORT TERM NOTICE INVITING TENDERS"

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **07/02/2024** up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **06/02/2024** up to 4.00 P.M and the application for issue of tender form shall be received on **5/02/2024** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	C/o Boundary wall in the premises of GSSS Ballah Tehsil Palampur Distt. Kangra (SW:- C/o Boundary wall) (DC Deposit)	2,04,226/-	4100/-	Two Months	350/-
2	Restoration of rain damages due to laying of OFC on Darang Ghanetta Jharet road, Panyali to Tapehar road & Jharet Kanya Devi road (SW:- C/o Unlined drain & Maintenance of earthen shoulder on Jharet Kanya Devi road (Telecomm Deposit)	4,78,800/-	9600/-	Two Months	350/-
3	C/o Hamirpur Sujampur Thural Maranda road Km. 30/0 to 59/775 (SW:- C/o wing walls for 1.00 mts span RCC slab culvert at Rd 44/510 & Filling work for diversion of road)	4,81,790/-	9600/-	Two Months	350/-
4	Balance work of Thural to Bachhwai road Km. 0/0 to 6/195 i/c Bridge over Neugal Khad under NABARD (SW:- P/L Interlocking concrete block in Km. 1/378.10 to 1/430)	4,79,374/-	9600/-	Two months	350/-
5	Balance work of Thural to Bachhwai road Km. 0/0 to 6/195 i/c Bridge over Neugal Khad under NABARD (SW:- P/L Interlocking concrete block in Km. 1/378.10 to 1/430)	4,89,320/-	9800/-	Two Months	350/-
6	Balance work of Duhak Tikri Rakha Basti to Dhaba road Km. 0/0 to 4/380 (SW:- P/L CC work in Km. 0/660 to 0/798) (under NABARD)	4,99,905/-	10,000/-	Two Months	350/-
7	Balance work of Duhak Tikri Rakha Basti to Dhaba road Km. 0/0 to 4/380 (SW:- C/o V-shape drain with edge wall at Rd 0/770 to 0/960) (under NABARD)	4,99,570/-	10,000/-	Two Months	350/-
8	Improvement of Basdi to Nagni road to Join HSTM road (SW:- C/o B/wall at Rd 0/160 to 0/172)	1,13,444/-	2300/-	Two Month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

(On behalf of Governor of Himachal Pradesh)

Dated:- 31.1.2024

No. PWD/BWD/Tender/NIT/2023-24/-

Copy to following for information and necessary action:-

1. The Principal Secy.(PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ), HPPWD, Dharamshala.
4. The Director, Information & Publications Department, HP Shimla.
5. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. The Sub-Divisional Officer (Civil) Palampur.
9. All the S.E.s/E.E.s under Kangra Zone.
10. All the Assistant Engineers under this Division.
11. The Drawing /Accounts Branch in this office.
12. Notice Board.

Executive Engineer
Bhawarna Division
HPPWD Bhawarna


Schedule of Quantity

Name of Work :- Construction of Boundary wall in the premises of GSSS Ballah Tehsil Palampur Distt. Kangra. (SH:- Construction of Boundary wall) (DC Deposit).

Estimate Cost :- Rs. 2,04,226/-
Earnest Money :- Rs. 4100/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimetre) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-in-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. Rate inclusive royalty, malkana, toll tax, GST and other taxes imposed by the government.	9.11			Per Cubic metre	
2	Providing form work with steel plates of 3.15mm (three decimal one five millimetre) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimetre) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in foundation, Footings bases of columns and mass concrete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge Rate inclusive toll tax, GST and any other taxes imposed by the government.	67.50			Per square metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	13.16			Per Cubic metre	
4	Second class brick work using common burnt clay building F.P.S. (non modular) bricks in cement mortar 1:6 (one cement isto six sand) in super structure upto all floor levels as per PWD specification, drawing and design and curing complete including scaffolding and cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	1.98			Per Cubic metre	

5	Second class half brick work using common burnt clay building bricks in cement mortar 1:4 (one cement isto four sand) in super structure up to all floor level as per PWD specification, drawing and design and curing complete including scaffolding. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	60.89			Per Square metre
6	15mm (fifteen millimetre) thick cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto any floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth, in rough side with cement mortar 1:6 (one cement isto six sand) complete including curing as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	173.84			Per Square metre
7	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	173.84			Per Square metre
8	Finishing walls with water proofing cement paint of new work (Two or more coats applied @ 3.84 kg/10 sqm) required shade. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	173.84			Per Square metre
Total :-					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of road damages due to laying of OFC on Darang Ghanetta Jharett road, Panyali to Tapehar road & Jharett Kanya Devi road
(SH:- C/o Unlined drain & Maintenance of earthen shoulder on Jharett Kanya Devi road (Telecomm Deposit))
Estimate Cost :- 4,78,800/-
Earnest Money :- 9600/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Construction of un-lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension: excavated materials to be used in embankment with a lift upto 3-m and lead of 50m (Average lead 25m) as per technical specification clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3800.00			Per Running metre	
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	8100.00			Per Square metre	
Total :-						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of Hamirpur Sujjanpur Thural Maranda road Km 30/0 to 59/775 (SH:- C/o wing walls for 1.00 mts span RCC slab culvert at RD 44/510 & Filling work for diversion of road).

Estimate Cost :- Rs. 4,81,790/-
Earnest Money :- Rs. 9600/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	25.48			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana.toll tax, GST or other taxes imposed by the Government.	82.74			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	38			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	25.62			Per Cubic metre	

5	Construction of embankment for road way with approved materials from borrowpits , or other sources in layers of suitable thickness not exceeding 200mm (Two hundred millimeter) thick each layers and compacted with 80-100 (Eighty - Hundred) K.N static/ vibratory road roller to meet the requirement of table 300.1 and 300.2 of technical specifications to lines, grades, levels and cross sections as per Drawings or direction of the Engineer-in-Charge to Technical specification clause 301 and other relevant clauses including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water where ever required including handling of material for construction of embankments within all leads and lifts. The rate shall include carriage of machineries, equipments, tools and materials and safety measures payment of all taxes, octroi royalty GST and other incidentals necessary to complete the work in all respects.	626.50			Per Cubic metre
Total :-					

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Balance work of Thural to Bachhwai road Km 0/0 to 6/195 i/c Bridge over Neugal Khad under NABARD
(SH:- P/L Interlocking concrete block in Km 1/378.10 to 1/430)

Estimated Cost :- Rs. 4,79,374/-
Earnest Money :- Rs. 9600/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.68			Per Cubic metre	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (Eighty millimetre) of approved make NTC or equivalent having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	249.12			Per Square metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.87			Per Cubic metre	
Total :-						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Balance work of Thural to Bachhwai road Km 0/0 to 6/195 i/c Bridge over Neugal Khad under NABARD
(SH:- P/L Interlocking concrete block in Km 1/435 to 1/488)

Estimated Cost :- Rs. 4,89,320/-
Earnest Money :- Rs. 9800/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	19.08			Per Cubic metre	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (Eighty millimetre) of approved make NTC or equivalent having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	254.40			Per Square metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	4.94			Per Cubic metre	
Total :-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Balance work of Duhak Tikri Rakha Basti to Dhabi road Km 0/00 to 4/380 (SH:- P/L CC work in Km 0/660 to 0/798) (Under NARAD)

Estimate Cost :- 4,99,905/-

Earnest Money :- 10,000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	72.45			Per Cubic metre	
Total :-						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Balance work of Dubak Tikri Rakha Basti to Dhabi road Km 0/00 to 4/380 (SH:- C/o V-shape drain with edge wall at RD 0/770 to 0/960) (under NABARD)

Estimate Cost :- 4,99,570/-
Earnest Money :- 10,000/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work-in-excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	106.40			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and MoRTH technical specification section 1500, 1700 and 2100 as per the direction of the Engineer-in-Charge including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	98.80			Per Cubic metre	

3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	153.00	Each	
Total :-				

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Improvement of Basdi to Nagni road to join HSTM road (SH:- C/o B/wall at RD 0/160 to 0/172).

Estimate Cost :- Rs. 1,13,444/-
Earnest Money :- Rs. 2300/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	12.96			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana.toll tax, GST or other taxes imposed by the Government.	27.36			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14			Each	
Total :-						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna