



E-Mail id - ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 21/02/2024 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 20/02/2024 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	Repair and Maintenance of Rest House at Laraghat Distt. Bilaspur (HP) (SH:- Additional alternation to Chowkidar Room)	Rs. 4,81,877/-	Rs. 9,700/-	Rs. 350/-	Three Month
2	Restoration of Rain damages on link road to village Mayoht Km. 0/0 to 6/930 (SH:- C/o PCC as a R/wall at RD 3/300 to 3/306 and 4/950 to 4/956)	Rs. 3,63,755/-	Rs 7,300/-	Rs. 350/-	Three Month
3	A/R & M/O on Panjpiri Zakatkhana Jeoripattan road Km. 2/540 to 12/0 (SH:- Repair of Pot Holes in Km. 2/540 to 7/200)	Rs. 4,96,037/-	Rs 10,000/-	Rs. 350/-	Three Month
4	Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road Km. 0/0 to 37/300 (SH:- C/o B/wall at RD 28/500 to 28/530)	Rs. 3,82,202/-	Rs 7,700/-	Rs. 350/-	Three Month
5	Restoration of Rain damages on Laraghat Bathoh Bholi road Km. 0/0 to 10/500 (SH:- C/o R/wall at RD 0/308 to 0/314)	Rs. 2,28,561/-	Rs 4,600/-	Rs. 350/-	Three Month
6	Construction of link road from NH-205 to village Kattal Bagheri Km. 0/0 to 2/015 (SH:- C/o Construction of R/wall at RD 1/960 to 1/990)	Rs. 4,92,095/-	Rs 9,900/-	Rs. 350/-	Three Month
7	Restoration of rain damages on Deoth Lagghat Jamli road Km. 0/0 to 13/180 (SH:- C/o R/wall at RD 4/995 to 5/010)	Rs. 2,31,116/-	Rs 4,700/-	Rs. 350/-	Three Month
8	Restoration of Rain damages on CMM road NH-205 Km. 86/0 to 127/0 (SH:- Supply of mixed material at HMP in Km. 116/0 to 121/0) Deposit work	Rs. 4,96,723/-	Rs 10,000/-	Rs. 350/-	Three Month
9	Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road Km. 0/0 to 37/300 (SH:- C/o R/wall at RD 8/270 to 8/282 and 12/375 to 12/390)	Rs. 4,68,886/-	Rs 9,400/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

- The contractor should produce a copy of enlistment/renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
- The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

No.PW/NBT/CB/Tender-State/EA-1/2023-

14026-35

Copy forwarded to the following for information and necessary action:-

- The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
- The Chief Engineer (HZ) HPPWD Hamirpur
- The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
- The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
- All the Assistant Engineers working under this Division.
- Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.
Dated:- 13/02/2024

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.4,81,877/-Only.
		Earnest Money :- Rs.9,700/-
		Time:- Three Months.

NAME OF WORK:- Repair and Maintenance of Rest House at Laraghat Distt.Bilaspur (HP) (SH:- Additional alternation to Chowkidar Room)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Centering and shuttering including strutting, propping etc. and removal of form work for including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same					
1.1	Suspended floors, roofs, landings, balconies and access platform	27.97	Square Metre.		Per Square Metre	
1.2	Lintels, beams, plinth beams, girders, bressumers and cantilevers	9.70	Square Metre		Per Square Metre	
1.3	Edges of slabs and breaks in floors and walls Under 20 cm wide	23.40	Running Metre		Per Running Metre	
2	Providing and laying in position machine batched and machine mixed design mix Providing M-25 (M-Twenty Five) grade concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. Note :- (Note:- Cement content considered in M-25 (M-Twenty Five) is @ 330 kg/cum) All works above plinth level up to Floor-V Level) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	4.10	Cubic Metre		Per Cubic Metre	
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete Above Plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more, including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	376.40	Kilogram.		Per Kilogram	

4	Brick work 23cm (Twenty centimeter) thick brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven point Five) in superstructure above plinth level up to floor all level in all shapes and sizes in : Cement mortar 1:6 (one cement : Six coarse cum sand) as per direction of Engineer-in-Charge. The rates includes of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.55	Cubic Metre			Per Cubic Metre
5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven point Five) in superstructure above plinth level up to floor all level. Cement mortar 1:3 (one cement : Three coarse sand) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.28	Square Metre			Per Square Metre
6	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35 mm (thirty Five millimeter) thick including ISI marked Stainless Steel butt hinges with necessary screws including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.30	Square Metre			Per Square Metre
7	Extra for providing lipping with 2nd class teak wood battens 25 mm (Twenty Five millimeter) minimum depth on all edges of flush door shutters (over all area of door shutter to be measured). including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.30	Square Metre			Per Square Metre
8	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm (One point Four millimeter) in both directions with wire of dia 0.63 mm (zero point Sixty three millimeter), for doors, windows and clerestory windows with hinges and necessary screws : 35 mm (thirty Five millimeter) thick Second class deodar shutters with ISI marked M.S. pressed butt hinges bright finished of required size including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.07	Square Metre			Per Square Metre

9	Providing 40x5 mm (Forty into Five millimeter) flat iron hold fast 40 cm (Forty centimeter) long including fixing to frame with 10 mm (ten millimeter) diameter bolts, nuts and wooden plugs and embedding in cement concrete block 30x10x15cm (Thirty into Ten into Fifteen centimeter) 1:3:6 mix (one cement : Three coarse sand : Six graded stone aggregate 20mm (Twenty millimeter) nominal size), including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.00	Nos.		Each
10	Providing and fixing bright finished brass 100mm.(One hundred millimeter) Mortice latch and lock and a pair of levers, handles with necessary screws etc. complete as per the directions of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	Nos.		Each
11	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm (Seven Hundred millimeter)), with necessary accessories and screws etc. complete, including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	Nos.		Each
12	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. Complete. Single rubber stopper including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	Nos.		Each
13	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc.complete :300x16 mm (Three hundred into Sixteen millimeter) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.00	Nos.		Each
14	Providing and fixing aluminium tower bolts, ISI marked,anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :300x10 mm (Three hundred into Ten millimeter) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.		Each

	18.00	Nos.	Each
15	18.00	Nos.	Each
Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm (one Hundred Twenty Five millimeter) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.			
16	19.25	Running Metre	Per Running Metre
Providing and fixing M.S. Channel frames 75x40mm (Seventy Five into Forty millimeter) for end frames and centre frame channels 75x40mm (Seventy Five into Forty millimeter) with MS flat/ plate 75x5mm (Seventy Five into Five millimeter) in combination welded together to make one frame as per detailed drawing including bright finished or black enamelled mild steel butt hinges 100x58x1.90 mm (one Hundred into Fifty eight into one point ninety millimeter) with provision for locking arrangement and shock absorber as specified and applying a coat of approved steel primer after pretreatment of the surface with in all leads and lifts as directed by Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.			
17	2.23	square metre	Per square metre
Providing and fixing window shutter having style of Z-section with T-section of 25x25x3mm (Twenty Five into Twenty Five into Three Millimeter) and angle iron 25x15x3mm (Twenty Five into Fifteen into Three Millimeter) as per drawing complete with fitting and necessary screws and applying a priming coat with red lead paint complete as per approved specification /design. Side Hung Window including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.			
18	2.23	square metre	Per square metre
Providing and fixing steel wire gauge shutter in Z-section using galvanised M.S Galvanised wire mesh of average width of aperture 1.4 mm (one point four millimeter) and nominal dia of wire 0.63 mm (zero point Sixty Three millimeter) for doors, windows and clerestorey windows with metal beading of approved quality and shape section with necessary screws and applying a priming coat with red lead paint complete as per approved specification /design. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.			
19	19.18	Square Metre	Per Square Metre
Kota stone slab mirror polished flooring of size 55x55 cm (Fifty Five into Fifty Five Centimeter) over 20 mm (Twenty millimeter) (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (one cement : four coarse sand) : 25 mm (twenty Five Millimeter) thick including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.			

20	Kota stone slabs 20 mm (Twenty millimeter) thick in risers of steps, skirting, dado and pillars laid on 12 mm (Twelve millimeter) (average) thick cement mortar 1:3 (one cement: three coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.40	Square Metre		Per Square Metre
21	Providing And fixing glazed white glazed tiles 20x30 cm (Twenty into Thirty centimetre) size & specified thickness of approved Shade and manufacturer in skirting risers of steps and dado 12 mm (Twelve millimeter) thick cement mortar 1:3 (one cement: three sand) and jointed with cement slurry complete as per direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.02	Per Square Metre		Per Square Metre
22	15mm (fifteen millimetre) cement plaster in single coat on the fair side of brick/ concrete/ stone walls for interior plastering up to all floor level including rises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement: six sand) Upto Floor V Level. as per the direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.75	Square Metre		Per Square Metre
23	15 mm (fifteen millimetre) cement plaster on the rough side of single or half brick wall of mix : 1:6 (one cement: Six fine sand) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	66.33	Square Metre		Per Square Metre
24	6 mm (Six millimeter) cement plaster of mix : 1:3 (one Cement : three Sand) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.69	Square Metre		Per Square Metre
25	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004. Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.75	Square metre		Per Square metre

26	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.83	Square metre		Per Square metre
27	Providing and applying white cement based putty of average thickness 1 mm (one millimeter), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	128.77	Square metre		Per Square metre
28	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	95.02	Square metre		Per Square metre
29	Providing and fixing Brass hard drawn hooks and eyes 200mm (Two hundred millimeter) as per the directions of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Nos		Each
30	Providing and fixing 16 mm (Sixteen millimeter) M.S. Fan clamps of standard shape and size in existing R.C.C. slab, including cutting chase, anchoring clamp to reinforcement bar, including cleaning, refilling, making good the chase with matching concrete, plastering and painting the exposed portion of the clamps complete including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Square Metre		Per Square Metre
31	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete Fixed to steel windows by welding including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	104.00	Kilogram		Per Kilogram

32	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.							
32.1	15 mm (Fifteen millimeter) nominal bore	25.00	Running Metre				Per Running Metre	
32.2	20 mm (Twenty Millimeter) nominal bore	30.00	Running Metre				Per Running Metre	
33	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1000.00	Litre				Per litre	
34	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, Green water closet EWC No. 20079 of Hindware or its equivalent with sleek plus dual cistern having dual flush system including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required, as per direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.				Each	
35	Providing and fixing toilet paper holder C.P. Brass as per the direction of Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.				Each	
36	Providing and fixing wash basin with C.I. brackets, 15 mm (Fifteen Millimeter) C.P. brass pillar taps, 32 mm (Thirty two millimeter) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: Wash basin No. 1008 of size 55x40cms (Fifty millimeter into Forty centimeter) in white shade of Hindware or its equivalent as per direction of Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.				Each	

37	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 110 mm (One Hundred Ten Millimeter) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.						
37.1	110 mm (One Hundred Ten Millimeter) dia.	40.00	Running Metre			Per Running Metre	
37.2	75 mm (Seventy Five Millimeter) dia.	25.00	Running Metre			Per Running Metre	
38	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete 25 (Twenty) to 40 mm (Forty Millimeter) nominal bore including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00	No.			Each	
39	Constructing masonry Chamber 30x30x50 cm (Thirty into Thirty into Fifty centimeter) inside, in brick work in cement mortar 1:4 (One cement :Four coarse sand) for stop cock, with C.I. surface box 100x100 x75 mm (one hundred into one Hundred into Seventy Five millimeter) (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (One cement : two coarse sand : Four graded stone aggregate 20 mm (Twenty millimeter) nominal size), i/c necessary excavation, foundation concrete 1:5:10 (one cement : Five fine sand : Ten graded stone aggregate 40mm (Forty Millimeter) nominal size) and inside plastering with cement mortar 1:3 (one cement : Three coarse sand) 12mm (twelve millimeter) thick, finished with a floating coat of neat cement complete as per standard design : With common burnt clay F.P.S (non modular) bricks of class designation 7.5 (Seven point five) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall	2.00	Nos.			Each	
40	Providing and fixing 600x450 mm (Six Hundred into Four Hundred Fifty millimeter) beveled edge mirror of superior glass (of approved quality) complete with 6 mm (Six millimeter) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.			Each	
41	Providing and fixing 600x120x5 mm (Six Hundred into one Twenty into five millimeter) glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm (Forty Millimeter) long screws, rawl plugs etc., complete, including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.			Each	

42	Providing and fixing PTMT soap Dish Holder having length of 138mm (One Hundred Thirty Eight millimeter), breadth 102mm (One hundred two millimeter), height of 75mm (Seventy Five millimeter) with concealed fitting arrangements, weighing not less than 106 gms including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos		Each
43	Providing and fixing 115 mm (One Hundred Fifteen millimeter) nominal bore, 86 mm (Eighty Six millimeter) long, weighing not less than 88 gms PTMT concealed stop cock with flange of Jaguar and approved quality and colour as per the direction of Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos		Each
44	Providing and fixing 8 mm (Eight Millimeter) dia C.P. / S.S. Jet with flexible tube upto 1 (one) metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos		Each
45	Providing and fixing G.I. inlet connection for flush pipe connecting with W.C. Pan including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos		Each
46	Providing and fixing uplasticised PVC connection pipe with brass unions : 45cm (Forty Five centimeter) length 15 mm (Fifteen millimeter)nominal bore including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos		Each
47	Providing and fixing gun metal gate valve with C.I. Wheel of approved quality (screwed end) of 25 mm (Twenty Five Millimeter) nominal bore as per the direction of Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	Nos		Each
48	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete 15 mm (Fifteen millimeter) nominal bore including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos		Each

49	Providing and fixing PVC floor trap of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete. 110 mm X 90 mm (One Hundred Ten into Ninety Millimeter) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00	Nos		Each
50	Providing and fixing PVC single equal branch with oval access door, ISI marked insertion rubber washer 3 mm (three millimetre) thick bolts and nuts complete including fixing with approved adhesive etc. complete as per the direction of Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00 5.00	Nos Nos		Each Each
51	Providing and fixing a PVC plain bends ISI marked including fixing with approved adhesive etc. complete as per the direction of Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00 5.00	Nos Nos		Each Each
52	Providing and fixing PVC Collar ISI marked including fixing with approved adhesive etc. complete as per the direction of Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	**			
52.1	110 mm (One Hundred Ten Millimeter) dia.	1.00	Nos		Each
52.2	75 mm (Seventy Five Millimeter) dia.	1.00	Nos		Each
53	Providing and fixing PVC 'P' or 'S' trap for water closet (squatting pan) ISI marked including jointing the trap with pan and PVC pipe with approved adhesive etc. complete. 110 mm (one hundred ten millimetre) dia as per the direction of Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos		Each
54	Providing and fixing PTMT grating of approved quality for floor, gully or nahani trap including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00	Nos		Each

55	Providing & fixing Electric geyser of 25 Ltrs. Capacity of approved make and manufacture including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	No			Each
56	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour.: 600 mm (Six Hundred Millimeter) long towel rail with total length of 645 mm (Six Forty Five Millimeter), width 78 mm (Seventy Eight millimeter) and effective height of 88 mm (Eighty Eight millimeter), weighing not less than 190 gms.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos			Each
57	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete 32 mm (thirty Two millimeter) dia.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.			Each
58	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms 15 mm (Fifteen Millimeter) nominal bore including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	Nos.			Each
59	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm (Fifteen Millimeter) nominal bore including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.			Each
60	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
60.1	15 mm (Fifteen millimeter) nominal bore	5.00	No			Each
60.2	20 mm (Twenty Millimeter) nominal bore	5.00	No			Each
Total:-						

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.3,63,755/- Only.			
				Earnest Money :- Rs.7,300/- Only.			
				Time:- Three Months.			
NAME OF WORK:- Restoration of Rain Damages on link road to village Mayoith km 0/00 to 6/930 (SH:- C/O PCC as a R/wall at RD 3/300 to 3/306 & 4/950 to 4/956)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.18	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	71.22	Cubic metre			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.08	Cubic metre.			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.00	Nos.			Each	
Total:-							

Executive Engineer,
Bilaspur Division No. 2,
B.P.W.D., Bilaspur (N.P.)

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.4,96,037/-Only.		
				Earnest Money :- Rs.10,000/-		
				Time:- Three Months.		
NAME OF WORK:- A/R & M/O on Panjipiri Zakatkhana Jeoripattan road km 2/540 to 12/000 (SH:- Repair of Pot Holes in km 2/540 to 7/200)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification clause 1904.2.503 & 508.1 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, Malkana toll tax, goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1342.82	Square metre		Per Square metre.	
2	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and any key aggregate and rolling with a three wheel 80-100 kn static roller to achieve the desired degree of compaction as Technical Specification clause 506 50 mm thick (Fifty Millimetre)including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, Malkana toll tax, goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	268.56	Square metre		Per Square metre.	
Total						

Executive Engineer
 PWD Division No. 11
 PWD, Bileasur

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.		Estimated cost:- Rs.3,82,202/-Only.				
		Earnest Money :- Rs.7,700/-				
		Time:- Three Months.				
NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi ji Bakhra road km 0/00 to 37/300 (SH:- C/O B/wall at RD 28/500 to 28/530)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.60	cubic metre		Per cubic metre	
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge, ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.80	cubic metre		Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	70.52	Cubic metre		Per Cubic metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.38	Cubic metre.		Per Cubic Metre	

5	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.00	Nos.			Each	
	Total:-						

Executive Engineer
Bulandpur Division No. 1
J.P. PWD, Bhopal

SCHEDULE OF QUANTITY.									
Estimated cost:- Rs.2,28,561/-Only.									
Earnest Money :- Rs.4,600/-									
Time:- Three Months.									
NAME OF WORK:- Restoration of Rain Damages on Laraghat Bathoh Bholi road km 0/00 to 10/500 (SH:- C/O Rwall at RD 0/308 to 0/314)									
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount		
				Figure.	Words.				
1	2	3		4	5	6	7		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.66	cubic metre			Per cubic metre			
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.76	Cubic metre			Per Cubic metre			
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.64	Cubic metre.			Per Cubic Metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.			Each			
Total:-									

Executive Engineer,
Bathoh Division No. 11
J.P.W.D., Bathoh

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.4,92,095/-Only.						
Earnest Money :- Rs.9,900/-						
Time:- Three Months.						
NAME OF WORK:- Construction of link road from NH-205 to Village Kattal Bagheri km 0/00 to 2/015 (SH:- Construction of R/wall at RD 1/960 to 1/990)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.40	cubic metre		Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	94.50	Cubic metre		Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.80	Cubic metre.		Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	50.00	Nos.		Each	
Total:-						

Executive Engineer,
 District Division No. 11
 H.P. PWD., Bikaner

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.2,31,116/-Only.						
Earnest Money :- Rs.4,700/-						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain Damages on Deoth Lagghat Jamli road 0/00 to 13/180 (SH:- C/o R/wall at RD 4/995 to 5/010)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.90	cubic metre		Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.25	Cubic metre		Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Cubic metre		Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.		Each	
Total:-						

Executive Engineer,
Bilaspur Division Ma. &
P.W.D., Bilaspur P.

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=4,96,723/-Only.		
				Earnest Money:- Rs. =10,000/- only		
				Time:- One Month.		
Name of work :- Restoration of Rain Damages on CMM road NH-205 (old NH-21) Km 86/0 to 127/00 ((SH:- Supplying of mixed material at HMP in Km 116/00 to 121/00) (Deposit Work)						
Sr.No	Sub-head and item of work.	Quantity	Rate		Unit	Amount
			Figure	words.		
1	Providing Mixed material for bitumenious concrete with 100-120 TPH batch type nearest Hot Mix plant producing an average output of 75 Tonnes per hour using crushed aggregates of specified grading ,premixed with bitumenious binder@ 5.4 to 5.6 percent of mix as per Morth specification clause No.503 complete in all respects The bitumenious, aggregate,sand and filler will be arranged by the supplier in all leads and lifts including loading of mixed material at Hot Mix plant . The mixed material will be carried by departmental tipper and work will be executed as per direction and entire satisfaction of Engineer in charge.	61.00			per cubic metre	
					Total Rs.	

Executive Engineer
Bilaspur Division No. 11
HMPWD, Bilaspur

SCHEDULE OF QUANTITY.					
Estimated cost:- Rs.4,68,886/- Only.					
Earnest Money :- Rs.9,400/- Only.					
Time:- Three Months.					
NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi ji Bakhra road km 0/00 to 37/300 (SH:- C/O R/wall at RD 8/270 to 8/282 and 12/375 to 12/390)					
Sr No.	Description of items.	Quantity	Rates in		Unit
			Figure.	Words.	
1	2 Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 38.10	4 cubic metre	5 Per cubic metre	6 7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	90.57	Cubic metre	Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	29.19	Cubic metre.	Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00	Nos.	Each	
Total:-					

Executive Engineer,
Bhakra Division No. 2,
Bhakra, Dist. Bhakra (H.P.)