



E-Mail id - ee-hp2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 04/03/2024 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 02/03/2024 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	Construction of Indore Shed for Kabaddi at Namhol Distt. Bilaspur (HP) (SH:- Providing Steel reinforcement for RCC & Providing structural steel to truss) Deposit work	Rs 4,92,679 /-	Rs. 10,000/-	Rs. 350/-	Three Month
2	Construction of Additional Accommodation to HP.PWD. Rest House at Namhol Distt. Bilaspur (HP) (SH:- Providing and Fixing LG LED)	Rs 4,70,253/-	Rs. 9,500/-	Rs. 350/-	Three Month
3	Balance work for C/o Indore Shed Kabaddi at Govt. Sr. Sec. Jukhala (Providing and Laying Soiling C.C.1:2:4 and C/o Drain) Deposit work	Rs 3,83,166/-	Rs. 7,700/-	Rs. 350/-	Three Month
4	Construction of Indore Shed for Kabaddi at Namhol Distt. Bilaspur (HP) (SH:- Providing structural steel work) Deposit work	Rs 4,37,939 /-	Rs. 8,800/-	Rs. 350/-	Three Month
5	Construction of Additional Accommodation to HP.PWD. Rest House at Namhol Distt. Bilaspur (HP) (SH:- Providing Carpet, Carpet Runner, Double Door Refrigerator, Oil Filled Heater, Plastic Chair, Pillar Jeater and PGI Sheet Box)	Rs 4,19,340/-	Rs. 8,400/-	Rs. 350/-	Three Month
6	Balance work for C/o Indore Shed Kabaddi at Govt. Sr. Sec. Jukhala (Providing and laying C.C. Flooring) Deposit work	Rs 2,68,858/-	Rs. 5,400/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.
Dated:-

27/02/2024

No.PW/NBT/CB/Tender-State/EA-1/2023- 14856-65

Copy forwarded to the following for information and necessary action:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & ee-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.


SCHEDULE OF QUANTITY.		Estimated cost:- Rs.4,92,679/-Only.					
		Earnest Money :- Rs.10,000/-					
		Time:- Three Months.					
NAME OF WORK:- Construction of Indore Shed for Kabaddi at Namhol Distt. Bilaspur (HP)(SH:- Providing Steel reinforcement for R.C.C & Providing Structural steel to truss) (Deposit Work)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Mild steel and Medium Tensile steel bars including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1643.00	Kilogram			Per Kilogram	
2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3400.00	Kilogram			Per Kilogram	
Total:-							

Executive Engineer,
Bilaspur Division No. 2,
Bilaspur (H.P.).

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.4,70,253/-Only.			
				Earnest Money :- Rs 9,500/-			
				Time:- Three Months.			
NAME OF WORK:-Construction of Additional Accommodation to HP.PWD Rest House at Namhol Distt. Bilaspur (HP) (SH:- Providing and Fixing LG LED)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Providing and Fixing LED Brand (LG) 55" Modal 55UR8040 including carriage of material within all leads and lifts and other incidental.The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	No			Each	
2	Providing and Fixing LED Brand (LG) 43" Modal 43LM5600 including carriage of material within all leads and lifts and other incidental.The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.00	No			Each	
Total:-							


 Executive Engineer,
 Bilaspur Division No. 2,
 HP.PWD, Bilaspur (H.P.).


SCHEDULE OF QUANTITY.		Estimated cost:- Rs. 3,83,166/- Only.					
		Earnest Money :- Rs.7,700/- Only					
		Time:- Three Months.					
NAME OF WORK:- Balance work for C/O Indore Shed Kabaddi at Govt. Sr. Sec. Jukhala (Providing and Laying Soling, C.C 1:2:4 and C/O Drain) (Deposit Work)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	69.38	cubic metre			Per cubic metre	
2	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc.complete as per HP.PWD specification. 100 mm (One Hundred milimeter)spread thickness (finished work including materials and labour) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	62.70	Cubic metres			Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.81	Cubic metre.			Per Cubic Metre	
Total							


Executive Engineer,
Bilaspur Division No. 11
HP PWD, Bilaspur M.P.

	SCHEDULE OF QUANTITY.		Estimated cost:- Rs.4,37,939/-Only.				
			Earnest Money :- Rs.8,800/-				
			Time:- Three Months.				
NAME OF WORK:- Construction of Indore Shed for Kabaddi at Namhol Distt. Bilaspur (HP)(SH:- Providing Structural steel work) (Deposit Work)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4425.86	Kilogram			Per Kilogram	
Total:-							

Executive Engineer,
Bilaspur Division No. 2,
H.P., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.4,19,340/-Only.			
				Earnest Money :- Rs 8,400/-			
				Time:- Three Months.			
NAME OF WORK:-Construction of Additional Accommodation to HP.PWD Rest House at Namhol Distt. Bilaspur (HP) (SH:- Providing Carpet, Carpet Runner, Double Door Refrigerator, Oil Filled Heater, Plastic Chair, Pillar Heater and PGI Sheet Box)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Supplying carpet centre piece Red (made in Egpyy) size 9.5 (Nine point Five) x 6.5 (six point Five) (2.90 (two point Ninety x1.98 (One oint Ninety Eight) meter in length and width in all respect including carriage of material within all leads and lifts and other incidental.The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	4.00	No			Each	
2	Supplying carpet runner (green) size in width 0.65 m (Zero point Sixty Five meter) in all respect including carriage of material within all leads and lifts and other incidental.The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	9.49	No			Each	
3	Supplying plastic Tea mat (grey) size in width 0.60 (zero point Sixty) meter in all respect including carriage of material within all leads and lifts and other incidental.The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	4.62	Square meter			Per Square meter	
4	Providing LG Double Door 242 ltrs Refrigerator Model 292 BDSY in all respect including carriage of material within all leads and lifts and other incidental.The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	1.00	Square meter			Per Square meter	
5	Providing Hindware Oil Filled heater Bfins in all respect including carriage of material within all leads and lifts and other incidental.The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	1.00	No			Each	
6	Supplying carbon Fiber Heater Model (star) in all respect including carriage of material within all leads and lifts and other incidental.The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	12.00	No			Each	

7	Providing plastic Chair, Brand (Neel Kamal) in all respect including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.00	No			Each	
8	Supplying Box made with PGI sheet size 6x3 (six into Three) feet in all respect including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	No			Each	
Total:-							

Executive Engineer,
Bilaspur Division No. 2,
B.P. WD, Bilaspur (H.P.).

	SCHEDULE OF QUANTITY.		Estimated cost:- Rs. 2,68,858/- Only.					
			Earnest Money :- Rs.5,400/- Only					
			Time:- Three Months.					
NAME OF WORK:- Balance work for C/O Indore Shed Kabaddi at Govt. Sr. Sec. Jukhala (Providing and Laying C.C Flooring) (Deposit Work)								
Sr No.	Description of items.		Quantity		Rates in		Unit	Amount
					Figure.	Words.		
1	2		3		4	5	6	7
1	52 mm (Fifty Two millimeter) thick cement concrete flooring with concrete hardener topping, under layer 40 mm (Forty Millimeter) thick cement concrete 1:2:4 (one cement : Two coarse sand : Four graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (One cement hardener mix : Two graded stone aggregate 6 mm (Six millimeter) nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per manufacturer's specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.		418.00	Square meter			Per Square meter	
	Total							

Executive Engineer,
 Bhopal Division No. 1,
 PWD, Bhopal