



E-Mail id - ce-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 05/03/2024 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 04/03/2024 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

| Sr. No. | Name of work | Estimated cost | Earnest Money | Cost form | Time limit |
|---------|--|----------------|---------------|-----------|-------------|
| 1 | Restoration of Rain damages on link road Dolra to Bag Mehla Km. 0/0 to 3/810 (SH:- Providing & Laying GSB, G-II & WMM at RD 0/310 to 3/370) Deposit work | Rs 1,98,069/- | Rs. 4,000/- | Rs. 350/- | Three Month |
| 2 | Providing and laying of Paver Blocks on link road to House of Sh.Rattan Chand Shastri and others in villages Ajnol, GP Ghawanal (SH:- Providing & Laying of Paver Blocks at RD 0/0 to 0/075) (Deposit work) | Rs 3,47,471/- | Rs. 7,000/- | Rs. 350/- | Three Month |
| 3 | Construction of link road frm Labana Basti to Kalamghatta village Dollan in GP Kot Khas (SH:- C/o 900mm dia hume pipe culvert at RD 1/360) (Deposit work) | Rs 3,04,668/- | Rs. 6,100/- | Rs. 350/- | Three Month |
| 4 | Construction of Pulley on link road from village Soldha to Subbal, GP Soldha (SH:- C/o of 900mm dia hume pipe culverts at RD 0/530) (Deposit work) | Rs 2,86,036/- | Rs. 5,800/- | Rs. 350/- | Three Month |
| 5 | Construction of Ambulance road to village Junah Km. 0/0 to 0/330 (SH:- Construction of Edge wall at RD 0/0160 to 0/185 along with papapets at RD 0/100 to 0/150 and 0/165 to 0/200) (Deposit work) | Rs 1,92,670/- | Rs. 4,000/- | Rs. 350/- | Three Month |
| 6 | Construction of link road Samethan Neem Wala Baba Mandir to H.B. Chokata in Km.0/0 to 3/0 (SH:- C/o R/wall at RD 0/946.10 to 0/966.10) | Rs 4,39,547/- | Rs. 8,800/- | Rs. 350/- | Three Month |
| 7 | Restoration of Rain damages on link road Dolra to Bag Mehla Km. 0/0 to 3/810 (SH:- Providing & Laying of interlocking paver blocks & Providing C.C 1:3:6 at RD 3/310 to 3/370) Deposit work | Rs 4,91,626/- | Rs. 9,900/- | Rs. 350/- | Three Month |
| 8 | Restoration of Rain damages on Deoth Lagghat Jamli road Km. 0/0 to 13/180 (SH:- Providing and laying interlocking paver block at RD 2/430 to 2/445, 2/960 to 3/0 & 5/860 to 5/865) | Rs 4,96,431/- | Rs. 10,000/- | Rs. 350/- | Three Month |
| 9 | Repair and Maintenance of various road under Sub Division No. III (SH:- Providing and laying Bituminous concrete on patches). | Rs 4,99,616/- | Rs. 10,000/- | Rs. 350/- | Three Month |
| 10 | Restoration of Rain Damages on CMM road NH-205 Km. 86/0 to 127/0 (SH:- C/o PCC as a R/wall at RD 91/965 to 91/975.60) | Rs 4,97,046/- | Rs. 10,000/- | Rs. 350/- | Three Month |
| 11 | A/R & M/O Neri to Ashamajari road Km. 0/0 to 1/600 (SH:- Repair of Pot Holes in Km. 0/0 to 1/300) | Rs 3,78,468/- | Rs. 7,600/- | Rs. 350/- | Three Month |
| 12 | Restoration of Rain Damages on Patwarkhana Plog Dungloo road Km. 0/0 to 7/0 (SH:- C/o R/wall at RD 2/201.35 to 2/210) | Rs 2,24,121/- | Rs. 4,500/- | Rs. 350/- | Three Month |
| 13 | A/R & M/O Kuthela Kirarain Bagchhal road Km. 0/0 to 10/815 (SH:- Preparation of Detailed Project report for constriction of Double lane bridge over Kiratpur Nerchowk four-lane at village Thapna along services lanes on both side) | Rs 1,95,000/- | Rs. 4,000/- | Rs. 350/- | Three Month |

| | | | | | |
|----|--|---------------|-------------|-----------|-------------|
| 14 | Restoration of Rain damages on Navgaon Beri road Km. 4/350 to 23/700 (SH:- Providing and laying interlocking paver block at RD 13/210 to 13/270) | Rs 4,59,600/- | Rs. 9,200/- | Rs. 350/- | Three Month |
| 15 | A/R & M/O Ghwandal to Ajnol Km. 00 to 4/765 (SH:- Construction to Ajnol Km. 0/0 to 4/765 (SH:- C/ of R/wall at RD 2/225 to 2/233 & C/o V-shape drain at RD 2/180 to 2/310) | Rs 4,31,283/- | Rs. 8,700/- | Rs. 350/- | Three Month |
| 16 | A/R & M/O PWD Rest House at Swarghat Tehsil Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- C/o Septic Tank at PWD Rest House) | Rs 4,43,582/- | Rs. 8,900/- | Rs. 350/- | Three Month |
| 17 | Restoration of Rain damages on link road Neri to Ashamajari road Km. 0/0 to 1/600 (SH:- C/o V-Shape drain at various RDs) | Rs 2,98,546/- | Rs. 8,900/- | Rs. 350/- | Three Month |

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

**Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.**

No.PW/NBT/CB/Tender-State/EA-1/2023-

14885-94

Dated:-

28/02/2024

Copy forwarded to the following for information and necessary action:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

**Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.**

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.1,98,069/-Only.

Earnest Money :- Rs.4,000/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on link road Dolra to Bag Mehla km 0/00 to 3/810 (SH:- Providing & Laying GSB, G-II & WMM at RD 0/310 to 3/370) (Deposit Work)

| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
|---------|--|----------|---------------|----------|--------|-------------------|--------|
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Preparation of sub-grade by dressing to camber (Earth work) for the cutting involved for sub-grade to be measured and paid for separately depending upon the classification of soil completed as per HP.PWD, Specification as per direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals .The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 299.25 | Square metre. | | | Per Square metre. | |
| 2 | Consolidation of sub-grade with road roller including making good the undulation etcetra with earth or quarry soil etcetera and re-rolling the sub-grade completed as per HP.PWD, specification including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge .The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 299.25 | Square metre. | | | Per Square metre. | |
| 3 | Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax ,goods and service tax,building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 44.89 | Cubic metres | | | Per Cubic metre | |
| 4 | Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax ,goods and service tax,building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 44.89 | Cubic metres | | | Per Cubic metre | |
| Total:- | | | | | | | |

Executive Engineer,
Bilaspur Division No. 2,
P.W.D., Bilaspur (H.P.)
Bd

| | | | | | | | |
|---|--|----------|-------------------------------------|----------|--------|------------------|--------|
| SCHEDULE OF QUANTITY. | | | Estimated cost:- Rs.3,47,471/-Only. | | | | |
| | | | Earnest Money :- Rs.7,000/- | | | | |
| | | | Time:- Three Months. | | | | |
| NAME OF WORK:- Providing & Laying of paver Blocks on link road to the House of Sh. Ratan Chand Shastri and others in Village Ajnol, GP Ghawandal (SH:- Providing & Laying of paver Blocks at RD 0/00 to 0/075) (Deposit Work) | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge.80 mm (Eighty Millimeter) thick C.C. paver block of M-30 grade with approved color design and pattern. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 228.75 | Square metre | | | Per Square metre | |
| Total:- | | | | | | | |

Executive Engineer.
Bilaspur Division No 11
4th PWD, Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,04,668/-Only.

Earnest Money :- Rs 6,100/-

Time:- Three Months.

NAME OF WORK:- Construction of link road From Labana Basti to Kalamghatta village Dollan in G.P Kot Khas (SH:- C/O 900 mm dia hume pipe culvert at RD 1/360) (Deposit

| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
|-----------|---|----------|--------------|----------|--------|-----------------|--------|
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 44.78 | cubic metre | | | Per cubic metre | |
| 2 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 37.85 | Cubic metre | | | Per Cubic metre | |
| 3 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 3.83 | Cubic Metre | | | Per Cubic Metre | |
| 4 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 11.35 | Cubic metre. | | | Per Cubic Metre | |
| 5 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 0.110 | Cubic metre. | | | Per Cubic Metre | |

| | | | | | | | |
|---------|--|-------|---------------|--|--|-------------------|--|
| 6 | Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement :Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 7.50 | Running Meter | | | Per Running Meter | |
| 7 | Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 13.20 | Cubic metre. | | | Per Cubic Metre | |
| 8 | Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 8.00 | Nos. | | | Each | |
| Total:- | | | | | | | |

Executive Engineer,
Bhagpur Division No. 11
P.W.D., Bhagpur

| SCHEDULE OF QUANTITY. | | | Estimated cost:- Rs.2,86,036/-Only. | | | | |
|---|--|----------|-------------------------------------|----------|--------|-------------------|--------|
| | | | Earnest Money :- Rs 5,800/- | | | | |
| | | | Time:- Three Months. | | | | |
| NAME OF WORK:- Construction of Pulley on link road from village Soldha to Subbal, GP Soldha (SH:- Construction of 900 mm dia Hume pipe culverts at RD 0/530) (Deposit Work) | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 59.69 | cubic metre | | | Per cubic metre | |
| 2 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 33.28 | Cubic metre | | | Per Cubic metre | |
| 3 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 3.12 | Cubic Metre | | | Per Cubic Metre | |
| 4 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 13.07 | Cubic metre. | | | Per Cubic Metre | |
| 5 | Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement :Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 7.50 | Running Meter | | | Per Running Meter | |

| | | | | | | | |
|---------|--|-------|--------------|--|--|-----------------|--|
| 6 | Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 7.02 | Cubic metre. | | | Per Cubic Metre | |
| 7 | Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 14.00 | Nos. | | | Each | |
| Total:- | | | | | | | |

Executive Engineer
Bleasur Division No 11
Hd PWD, Bhamurh P

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.1,92,670/-Only.

Earnest Money :- Rs.4,000/-



Time:- Three Months.

NAME OF WORK:- Construction of Ambulance road to village Junah km 0/00 to 0/330 (SH:- Construction of Edge wall at RD 0/160 to 0/185 along with parapets at R.D. 0/100 to 0/150 and 0/165 to 0/200) (Deposit Work)

| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
|---------|---|----------|-------------|----------|--------|-----------------|--------|
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 13.50 | cubic metre | | | Per cubic metre | |
| 2 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 30.50 | Cubic metre | | | Per Cubic metre | |
| 3 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 10.61 | Cubic Metre | | | Per Cubic Metre | |
| 4 | Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 23.00 | Nos. | | | Each | |
| Total:- | | | | | | | |

Executive Engineer,
Bilaspur Division No. 1,
P.W.D., Bilaspur

| SCHEDULE OF QUANTITY. | | | | Estimated cost:- Rs.4,39,547/-Only. | | | |
|--|---|----------|--------------|-------------------------------------|--------|-----------------|--------|
| | | | | Earnest Money :- Rs.8,800/- | | | |
| | | | | Time:- Three Months. | | | |
| NAME OF WORK:- Construction of Link road Khad Samtehan Neem Wala Baba Mandir to H.B Chokata in km 0/00 to 3/00 (SH:- C/o R/wall at Rd 0/946.10 to 0/966.10) | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 35.20 | cubic metre | | | Per cubic metre | |
| 2 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 83.25 | Cubic metre | | | Per Cubic metre | |
| 3 | Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 27.00 | Cubic metre. | | | Per Cubic Metre | |
| 4 | Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 32.00 | Nos. | | | Each | |
| Total:- | | | | | | | |


 Executive Engineer
 Bilaspur Division No 1
 HP PWD., Bilaspur(H.P.)


SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,91,626/-Only.

Earnest Money :- Rs.9,900/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on link road Dolra to Bag Mehla km 0/00 to 3/810 (SH:- Providing & Laying of interlocking paver Blocks & Providing & Laying C.C 1:3:6 at RD 3/310 to 3/370) (Deposit Work)

| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
|----------------|---|----------|--------------|----------|--------|------------------|--------|
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm (Fifty millimeter) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge. 80 mm (Eighty Millimeter) thick C.C. paver block of M-30 grade with approved color design and pattern. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 299.25 | Square metre | | | Per Square metre | |
| 2 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 40 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 10.26 | Cubic metre. | | | Per Cubic Metre | |
| Total:- | | | | | | | |


 Executive Engineer,
 Bilaspur Division No. 2,
 P.W.D., Bilaspur (M.P.).

| SCHEDULE OF QUANTITY. | | | Estimated cost:- Rs.4,96,431/-Only. | | | | |
|--|--|----------|-------------------------------------|----------|--------|------------------|--------|
| | | | Earnest Money :- Rs 10,000/- | | | | |
| | | | Time:- Three Months. | | | | |
| NAME OF WORK:-Restoration of Rain Damages on Deoth Lagghat Jamli road km 0/000 to 13/180 (SH:- Providing and laying interlocking paver block at RD 2/430 to 2/445, 2/960 to 3/000 & 5/860 to 5/865). | | | | | | | |
| Sr No | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Providing laying ,spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill) carriage of mixed materials by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100 KN(Eighty to hundred)KN weight to achieve the desired density including lighting barricading and maintenance of diversion etc. as per Tables 400.11 and 400.12 and Technical Specification Clause 406 .including carriage of material within all leads and lifts and other incidental.The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 27.00 | Cubic metres | | | Per Cubic metre | |
| 2 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 12.830 | Cubic metre. | | | Per Cubic Metre | |
| 3 | Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge.80 mm (Eighty Millimeter) thick C.C. paver block of M-30 grade with approved color design and pattern. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 225.00 | Square metre | | | Per Square metre | |
| Total:- | | | | | | | |


 Executive Engineer,
 Bilaspur Division No. 1,
 HP PWD, Bilaspur(H.P.),

| SCHEDULE OF QUANTITY. | | Estimated cost:- Rs.4,99,616/-Only. | | | | | |
|---|---|-------------------------------------|---------------|----------|--------|-------------------|--------|
| | | Earnest Money :- Rs.10,000/- | | | | | |
| | | Time:- Three Months. | | | | | |
| NAME OF WORK:- Repair & Maintenance of various Road under Sub-Division No.-III (SH:- Providing and laying Bituminous Concrete in patches) | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| 1 | Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.20 to 0.25 Kg. (Zero point two zero to Zero point two five)Kilogram per square metre on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause-503 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge..The rates includes octroi,royalty ,Malkana toll tax ,goods and service ,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1229.10 | Square metre. | | | Per Square metre. | |
| 2 | Providing and laying bituminous concrete 30 (Thirty) milimeter thick with 100-120 TPH batch type hot mix plant producing an average output of 75 (Seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder VG-30 (Viscosity- Thirty) @ 5.4(Five point four) to 5.6(Five point six) percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respectsincluding carriage of material within all leads and lifts and other incidental.The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess ,royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same. | 36.87 | Cubic metre. | | | Per Cubic metre | |
| Total | | | | | | | |


 Executive Engineer
 Bilaspur Division No. 1.
 HP PWD, Bilaspur(H.P.)


| SCHEDULE OF QUANTITY. | | Estimated cost:- Rs.4,97,046/-Only. | | | | | |
|---|---|-------------------------------------|--------------|----------|--------|-----------------|--------|
| | | Earnest Money :- Rs.10,000/- | | | | | |
| | | Time:- Three Months. | | | | | |
| NAME OF WORK:- Restoration of Rain Damages on CMM Road NH-205 km 86/00 to 127/000 (SH:- C/o PCC as a R/wall at RD 91/965 to 91/975.60) | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 44.20 | cubic metre | | | Per cubic metre | |
| 2 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 100.70 | Cubic metre | | | Per Cubic metre | |
| 3 | Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 22.37 | Cubic metre. | | | Per Cubic Metre | |
| 4 | Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 24.00 | Nos. | | | Each | |
| Total:- | | | | | | | |


 Bilaspur Division No 4
 HP PWD., Bilaspur (M.P.)


| | | | | | | | |
|--|--|----------|--------------|-------------------------------------|--------|-------------------|--------|
| SCHEDULE OF QUANTITY. | | | | Estimated cost:- Rs.3,78,468/-Only. | | | |
| | | | | Earnest Money :- Rs.7,600/- | | | |
| | | | | Time:- Three Months. | | | |
| NAME OF WORK:- A/R & M/O Neri to Ashamajhari road km 0/00 to 1/600 (SH:- Repair of Pot Holes in km 0/000 to 1/300) | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (Twenty millimeter) thick pre-mix carpet and seal coat type B specification clause 1904.2,503 & 508.1 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi, Malkana toll tax ,goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1143.75 | Square metre | | | Per Square metre. | |
| 2 | Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and any key aggregate and rolling with a three wheel 80-100 kn static roller to achieve the desired degree of compaction as Technical Specification clause 506 50 mm thick (Fifty millimetre)including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi, Malkana toll tax ,goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 114.38 | Square metre | | | Per Square metre. | |
| Total | | | | | | | |


 Executive Engineer,
 Bilaspur Division No. 2,
 H.A. P.O.D., Bilaspur (M.P.).

| SCHEDULE OF QUANTITY. | | | Estimated cost:- Rs.2,24,121/-Only. | | | | |
|---|---|----------|-------------------------------------|----------|--------|-----------------|--------|
| | | | Earnest Money :- Rs.4,500/- | | | | |
| | | | Time:- Three Months. | | | | |
| NAME OF WORK:- Restoration of Rain Damages on Patwarkhana Plog Dungloo road km 0/00 to 7/00 (SH:- C/O R/wall at RD 2/201.35 to 2/210) | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 16.69 | cubic metre | | | Per cubic metre | |
| 2 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 45.76 | Cubic metre | | | Per Cubic metre | |
| 3 | Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 16.26 | Cubic metre. | | | Per Cubic Metre | |
| 4 | Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 23.00 | Nos. | | | Each | |
| Total:- | | | | | | | |

Executive Engineer,
Bilaspur Division No. 2,
P.W.D., Bilaspur (H.P.).

| SCHEDULE OF QUANTITY. | | Estimated cost:- Rs.1,95,000/-Only. | | | | | |
|---|---|-------------------------------------|-----|----------|--------|---------|--------|
| | | Earnest Money :- Rs 4,000/- | | | | | |
| | | Time:- Three Months. | | | | | |
| NAME OF WORK:- A/R & M/O on Kutehla Kiyarian Bagchhal road km 0/00 to 10/815 (Sh:- Preparation of Detailed Project Report for Construction of Double Lane Bridge over Kirarapur Nerchowk Four-lane at Village Thapna along with service lanes on both side) | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Preparation of Detailed Project Report for Bridge after conducting Topographical survey plan and mark provisions on the survey plan which include the following provision as given below: (a) Topographical survey by digital total station with two second accuracy ,showing all features on survey plan like trees, culverts, building, electric poles, telephone poles, hand pumps, schools, Habitant villages etc (b) Preparation of Contour Site Plan using total station and modern designing software using Auto Desk civil 3D by showing all provision . (C) Preparation of General Arrangement of Drawings and site plan showing all provision according to existing site condition and Draw cross sections at 15m (fifteen meter) intervals,L-Section and calculate the quantity of earth work in standard format of AutoCAD showing all layer of pavement components as applicable. . The Design will be carried out in accordance to latest design specification and to satisfaction of Engineer-in-charge. (D) Preparation of Detail project Report as per MORD/ MORTH guidelines of Bridge complete in all respect and Submission of draft copy & after getting approval from the competent authority the same may be fair out and be supplied in 6- sets (six sets) duly printed A-4 size, relevant drawing on A-2 & 3 size alongwith soft copy of DPR & Drawings in CD Format or USB Drive be submitted. | 1.000 | Job | | | Per job | |
| Total:- | | | | | | | |

Executive Engineer,
Bhujapur Division No. 2,
H.P.W.D., Bhujapur (H.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,59,600/-Only.

Earnest Money :- Rs.9,200/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Navgoan Beri road km 4/350 to 23/700 Providing and laying interlocking paver block at RD 13/210 to 13/270).

| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
|---------|--|----------|--------------|----------|--------|------------------|--------|
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All Kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 59.68 | cubic metre | | | Per cubic metre | |
| 2 | Granular sub-base/base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408 .including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 38.93 | Cubic metres | | | Per Cubic metre | |
| 3 | Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 80 mm (Eighty Millimeter) thick C.C. paver block of M-30 grade with approved color design and pattern. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 259.50 | Square metre | | | Per Square metre | |
| Total:- | | | | | | | |

Executive Engineer,
Bilaspur Division No. 2,
Bilaspur (H.P.).

| SCHEDULE OF QUANTITY. | | | | Estimated cost:- Rs.4,31,283/-Only. | | | |
|---|---|----------|-------------|-------------------------------------|--------|-----------------|--------|
| | | | | Earnest Money :- Rs.8,700/- | | | |
| | | | | Time:- Three Months. | | | |
| NAME OF WORK:-A/R & M/O Ghawandal to Ajnol km 0/00 to 4/765(SH:- Construction of R/wall at RD 2/225 to 2/233 & C/O V-shape drain at RD 2/180 to 2/310) | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. all kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 29.25 | cubic metre | | | Per cubic metre | |
| 2 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 19.84 | cubic metre | | | Per cubic metre | |
| 3 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 63.66 | Cubic metre | | | Per Cubic metre | |
| 4 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 20.48 | Cubic metre | | | Per Cubic Metre | |
| 5 | Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 19.92 | Cubic metre | | | Per Cubic Metre | |

| | | | | | | | |
|---------|--|-------|------|--|--|------|--|
| 6 | Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 28.00 | Nos. | | | Each | |
| Total:- | | | | | | | |


 Executive Engineer,
 Bhisspur Division No. 11
 HP PWD, Bhisspur (H.P.)

| SCHEDULE OF QUANTITY. | | Estimated cost:- Rs.4,43,582/-Only. | | | | | |
|---|--|-------------------------------------|-------------|----------|--------|-----------------|--------|
| | | Earnest Money :- Rs.8,900/- | | | | | |
| | | Time:- Three Months. | | | | | |
| NAME OF WORK:- A/R & M/O PWD Rest House at Swarghat , Teh Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- C/O Septic Tank at PWD Rest House) | | | | | | | |
| Sr No | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 61.42 | cubic metre | | | Per cubic metre | |
| 2 | Coursed rubble masonry (first sort) with hard stone in foundation and plinth with Cement mortar 1:6 (One cement : Six coarsesand)including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 16.90 | cubic metre | | | Per cubic metre | |
| 3 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:4:8 (one Cement : Four coarse sand : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 3.64 | Cubic Metre | | | Per Cubic Metre | |
| 4 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2.250 | Cubic metre | | | Per Cubic Metre | |
| 5 | Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement size) 1:1.5:3(One Cement one and half sand three graded stone aggregate 20 mm (Twenty Millimeter) noninal size). including carriage of materials ,within all leads and lifts and other incidentals as per direction of Engineer-in-Charge The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 3.31 | Cubic Metre | | | Per Cubic Metre | |

| | | | | | | |
|------|--|--------|---------------|--|--|--------------------|
| 6 | Providing form work with steel plates 3.15mm (Three point Fifteen milimetres) thick welded with angle iron in frame, 30 x 30 x 5 mm (Thirty into thirty into five milimetres) so as to give a fair finish including shuttering, strutting and propping etcetra with wooden battens and ballies upto any heights of propping and centaring below supporting floor to ceiling in all height and removal of the same for insitu reinforced cement concrete and plain concrete work including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | | | | |
| (i) | Flat surfaces such as soffits pf suspended floor roofs, landings and the like. | 16.00 | Square Meter. | | | Per Square Meter. |
| (ii) | Edge of slabs and breaks in floors and walls. | 17.60 | Running Meter | | | Per Running Meter |
| 7 | Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars Thermo-Mechanically Treated bars of grade Fe-500D or more including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 397.20 | Kilogram | | | Per Kilogram |
| 8 | Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:4 (one cement : Four coarse sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 9.60 | Square Meter | | | Per Square Meter |
| 10 | 20 mm(Twenty millimeter) cement plaster of mix 1:4 (One cement: Four fine sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 48.00 | Square Meter | | | Per Square Meter |
| 11 | Providing and fixing in vertical position in PVC pipe pinolex Type-B well including hire & labour charges, fittings & accessories etc all complete for all depths as per direction of Engineer-in-charge single socketed 110 mm (One Hundred ten millimeter) diameter Finiolex PVC pipe Type-B including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 110.00 | Running Meter | | | Per Running Meterr |

| | | | | | | | |
|---------|--|--------|---------------|--|--|--------------------|--|
| 12 | Providing and fixing in vertical position in PVC pipe pinolex Type-B well including hire & labour charges, fittings & accessories etc all complete for all depths as per direction of Engineer-in-charge Finiolex PVC pipe Type-B 150 mm (One Hundred Fifty millimeter) dia including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 130.00 | Running Meter | | | Per Running Meterr | |
| 13 | Constructing brick masonry manhole in cement mortar 1:4 (one cement : Four coarse sand) with R.C.C. top slab with 1:1.5:3 mix (One cement : one point Five coarse sand (zone- III) : Three graded stone aggregate 20 mm (Twenty millimeter) nominal size), foundation concrete 1:4:8 mix (one cement : Four coarse sand (zone- III) : Eight graded stone aggregate 40 mm (Forty millimeter) nominal size), inside plastering 12 mm (Twelve millimeter) thick with cement mortar 1:3 (One cement : Three coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (one cement : Two coarse sand : Four graded stone aggregate 20 mm (Twenty millimeter) nominal size) finished with a floating coat of neat cement complete as per standard design Inside size 90 (Ninety) x80 (Eighty) cm and 45 cm (Forty Five Millimeter) deep including C.I. cover with frame (light duty) 455x610 mm (Four hundred Fifty Five into Six Hundred Ten only) internal dimensions, total weight of cover and frame to be not less than 38 kg (Thirty Eight kilogram) (weight of cover 23 kg (Twenty Three kilogram) and weight of frame 15 kg (Fifteen kilogram) With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 8.00 | Nos. | | | Each | |
| 15 | Providing and fixing PVC Cowl 75 mm (Seventy Five millimeter) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | Nos. | | | Each | |
| Total:- | | | | | | | |

Executive Engineer,
Bilaspur Division No. 2,
H.P. P.W.D., Bilaspur (H.P.)

| | | | | | | | | | |
|---|---|--|--|-------------------------------------|--------------|----------|--------|-----------------|--------|
| SCHEDULE OF QUANTITY. | | | | Estimated cost:- Rs.2,98,546/-Only. | | | | | |
| | | | | Earnest Money :- Rs.6,000/- | | | | | |
| | | | | Time:- Three Months. | | | | | |
| NAME OF WORK:- Restoration of Rain Damages on link road Neri to Ashamajhari road km 0/00 to 1/600 (SH:- C/O V-shape drain at various RDs) | | | | | | | | | |
| Sr No. | Description of items. | | | Quantity | | Rates in | | Unit | Amount |
| 1 | 2 | | | 3 | | Figure. | Words. | | |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. all kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same | | | 68.00 | cubic metre | 4 | 5 | 6 | 7 |
| 4 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | | 59.50 | Cubic metre. | | | Per Cubic Metre | |
| Total:- | | | | | | | | | |


 Executive Engineer,
 Bhilaspur Division No. 2,
 H.P. P.W.D., Bhilaspur (H.P.)

(B)