



E-Mail id - ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 23/02/2024 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 22/02/2024 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be outrightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	Construction of Govt. Sr. Sec. School Makri in Distt. Bilaspur (HP) (SH:- C/o B/wall, U-Shape and Painting work etc.)	Rs. 4,67,306/-	Rs 9,400/-	Rs. 350/-	Three Month
2	Construction of link road from NH-205 to village Kattal Bagheri Km. 0/0 to 2/0 (SH:- C/o Subgrade, P/L Gr-I in Km. 1/800 to 2/015)	Rs. 4,96,886/-	Rs 10,000/-	Rs. 350/-	Three Month
3	Repair and Maintenance on Rajghat Sai Magazine Trivnighat road Km. 0/0 to 7/900 (SH:- Repair of Pot Holes in Km. 7/0 to 7/900)	Rs. 2,96,995/-	Rs 6,000/-	Rs. 350/-	Three Month
4	Repair and Maintenance on link road Niharkhan Basla Km. 0/0 to 0/900 (SH:- Repair of Pot Holes in Km. 0/0 to 0/900)	Rs. 2,81,265/-	Rs 5,700/-	Rs. 350/-	Three Month
5	Repair and Maintenance on link road from Khalota Mandir to Gutrahan road Km. 0/0 to 2/190 (SH:- Repair of Pot Holes in Km. 0/0 to 2/190)	Rs. 3,99,562/-	Rs 8,000/-	Rs. 350/-	Three Month
6	Repair and Maintenance on Thatch Sikroha Neri Jukhala road Km. 0/0 to 18/690 (SH:- Repair of Pot Holes in Km. 16/0 to 18/0)	Rs. 4,84,116/-	Rs 9,700/-	Rs. 350/-	Three Month
7	Construction of link road from NH-205 to village Kattal Bagheri Km. 0/0 to 2/0 (SH:- C/o Subgrade, P/L Gr-I in Km. 1/200 to 1/800)	Rs. 4,72,963/-	Rs 9,500/-	Rs. 350/-	Three Month
8	Restoration of road damages on Kutehla Kariyan Bagchhal road Km. 0/0 to 10/815 (SH:- Road widening from RD 10/784 to 10/787.50 on swarghat side approach of Bagchhal Bridge) Deposit work	Rs. 4,62,901/-	Rs 9,300/-	Rs. 350/-	Three Month
9	Restoration of Rain damages on link road to Harizen Basti Tiun Khas Km. 0/0 to 3/135 (SH:- C/o R/wall at RD 2/050 to 2/060)	Rs. 3,25,971/-	Rs 6,600/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

- The contractor should produce a copy of enlistment/renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
- The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

Dated:- 15/02/2024

No.PW/NBT/CB/Tender-State/EA-1/2023-

14223-32

Copy forwarded to the following for information and necessary action:-

- The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
- The Chief Engineer (HZ) HPPWD Hamirpur
- The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
- The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
- All the Assistant Engineers working under this Division.
- Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.

		Estimated cost:- Rs.4,67,306/-Only.			
		Earnest Money :- Rs.9,400/-			
		Time:- Three Months.			
NAME OF WORK:- Construction of Govt. Sr. Sec. School Makri in Distt. Bilaspur (HP) (SH:- C/o B/wall , U-shape drain and painting Work etc.)					
Sr No.	Description of items.	Quantity	Rates in		Amount
			Figure.	Words.	
1	2	3	4	5	6
1	Excavation work by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.98	Cubic Metre		Per Cubic Metre
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.95	cubic metre		Per cubic metre
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:4:8 (one Cement : Four coarse sand : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.32	Cubic Metre		Per Cubic Metre
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.85	Cubic metre.		Per Cubic Metre
5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.230	Cubic metre.		Per Cubic Metre

	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Nos.			Each	
7	Repairs to plaster of thickness 12 mm (Twelve millimeter) to 20 mm (Twenty millimeter) in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (one cement: Four coarse sand) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.02	Square meter			Per Square meter	
8	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : old work (one or more coats) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	657.76	Square meter			Per Square meter	
9	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	149.28	Square meter			Per Square meter	
10	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.18	Square meter			Per Square meter	
11	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	83.76	Square meter			Per Square meter	
12	Lettering with black japan paint of approved brand and manufacture including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	800.00	letter per cm			Per letter per cm	

	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (Ten millimeter) gap for thermal expansion, (i) Single socketed pipes 100 mm (One Hundred millimeter) diameter including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	36.00	Running Meter			Per Running Meter
14	Providing and fixing M.S. holder bat clamps of approved design to C.I. or S.C.I. rain water pipes embedded in and including cement concrete blocks 10x10x10 cm (Ten into Ten into Ten centimeter of 1:2:4 mix (one cement : Two coarse sand : Four graded stone aggregate 20 mm (Twenty millimeter) nominal size) and cost of cutting holes and making good the walls etc. 150 mm (One Hundred Fifty Millimeter) diameter including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Nos.			Each
15	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (Ten millimeter) gap for thermal expansion, including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
15.1	Coupler 110 mm (One Hundred Ten millimeter)	6.00	Nos.			Each
15.2	Bend	12.00	Nos.			Each
16	Making plinth protection 50mm (Fifty millimeter) thick of cement concrete 1:3:6 (one cement : three coarse sand : Six graded stone aggregate 20 mm (Twenty millimeter) nominal size) over 75mm (Seventy Five millimeter) thick bed of dry brick ballast 40 mm (Forty millimeter) nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth, including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.93	Square meter			Per Square meter
Total:-						

Executive Engineer,
Bilaspur Division No. 2,
Bilaspur, Sagar (H.P.)

SCHEDULE OF QUANTITY.									
Estimated cost:- Rs.4,96,886/-Only.									
Earnest Money :- Rs.10,000/-									
Time:-Three Months.									
NAME OF WORK:- Construction of link road from NH-205 to Village Kattal Bagheri km 0/00 to 2/00 (SH:- C/O U-Shape drain at Km1/700 to 1/793 & C/O Subgrade, P/L Gr-I.in KM 1/800 to 2/015)									
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount		
				Figure.	Words.				
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-Charge. All kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2	70.80	4	cubic metre	6	78	Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.		62.08		Cubic metre.			Per Cubic Metre	
3	Preparation of sub-grade by dressing to camber (Earth work) for the cutting involved for sub-grade to be measured and paid for separately depending upon the classification of soil completed as per HP.PWD, Specification as per direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals . The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.		756.26		Square metre.			Per Square metre.	
4	Consolidation of sub-grade with road roller including making good the undulation etcetra with earth or quarry soil etcetra and re-rolling the sub-grade completed as per HP.PWD, specification including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge . The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.		756.26		Square metre.			Per Square metre.	

viding, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 404. By Manual Means including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	75.62	Cubic metres			Per Cubic metre	
Total:-						

Executive Engineer,
 Pimpri Division No. 11
 P. W. D., Pimpri


SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.		Estimated cost:- Rs.2,96,995/-Only.				
		Earnest Money :- Rs.6,000/-				
		Time:- Three Months.				
NAME OF WORK:- Repair and Maintenance on Rajghat Sai Magazine Trivenighat road km 0/00 to 7/900 (SH:- Repair of Pot Holes in km 7/000 to 7/900)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification clause 1904.2.503 & 508.1 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, Malkana toll tax, goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	866.25	Square metre		Per Square metre.	
2	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and any key aggregate and rolling with a three wheel 80-100 kn static roller to achieve the desired degree of compaction as Technical Specification clause 506 50 mm thick (Fifty Millimetre) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, Malkana toll tax, goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	129.94	Square metre		Per Square metre.	
Total						


 Executive Engineer,
 Bilaspur Division No. 2,
 B.P.O. D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.2,81,265/-Only.	
							Earnest Money :- Rs.5,700/-	
							Time:- Three Months.	
NAME OF WORK:- Repair and Maintenance on link road Niharkhan Basla km 0/00 to 0/900 (SH:- Repair of Pot Holes in km 0/000 to 0/900)								
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount		
			Figure.	Words.				
		3	4	5	6	7		
1	2	850.00	Square metre		Per Square metre.			
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification clause 1904.2.503 & 508.1 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, Malkana toll tax ,goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.							
2	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and any key aggregate and rolling with a three wheel 80-100 kn static roller to achieve the desired degree of compaction as Technical Specification clause 506 50 mm thick (Fifty Millimetre)including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, Malkana toll tax ,goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	85.00	Square metre		Per Square metre.			
Total								

Executive Engineer,
Bilaspur Division No. 2,
P.O. Bilaspur, Bilaspur (H.P.)

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.3,99,562/-Only.		
							Earnest Money :- Rs.8,000/-		
							Time:- Three Months.		
NAME OF WORK:- Repair and Maintenance on link road from Khalota Mandir to Gutrahan road km 0/00 to 2/190 (SH:- Repair of Pot Holes in km 0/00 to 2/190)									
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount			
			Figure.	Words.					
		3	4	5	6	7			
1	2	1207.50	Square metre		Per Square metre.				
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification clause 1904.2.503 & 508.1 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, Malkana toll tax, goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same								
2	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and any key aggregate and rolling with a three wheel 80-100 kn static roller to achieve the desired degree of compaction as Technical Specification clause 506 50 mm thick (Fifty Millimetre)including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, Malkana toll tax, goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	120.75	Square metre		Per Square metre.				
Total									


 Engineer,
 Bilaspur Division No. 2,
 Bilaspur, Chhattisgarh (I.P.)


SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,84,116/-Only.
Earnest Money :- Rs.9,700/-
Time:- Three Months.

NAME OF WORK:- Repair and Maintenance on Thatch Sikroha Neri Jukhala road km 0/00 to 18/690 (SH:- Repair of Pot Holes in km 16/000 to 18/000)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification clause 1904.2.503 & 508.1 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, Malkana toll tax, goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 1463.03	4 Square metre	5 Per Square metre.	6 Per Square metre.	7 7
2	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and any key aggregate and rolling with a three wheel 80-100 kn static roller to achieve the desired degree of compaction as Technical Specification clause 506 50 mm thick (Fifty Millimetre) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, Malkana toll tax, goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	146.30	Square metre		Per Square metre.	
Total						

Executive Engineer,
Sikroha Division No. 2,
J.D. PWD., Bhatnagar (H.P.)
B

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,72,963/-Only.

Earnest Money :- Rs.9,500/-

Time:- Three Months.

P/L Gr-I in KM 1/200 to 1/800)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		3	4	Figure.	Words.		
1	Preparation of sub-grade by dressing to camber (Earth work) for the cutting involved for sub-grade to be measured and paid for separately depending upon the classification of soil completed as per HP.PWD. Specification as per direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2110.50	Square metre.			Per Square metre.	7
2	Consolidation of sub-grade with road roller including making good the undulation etcetra with earth or quarry soil etcetera and re-rolling the sub-grade completed as per HP.PWD. specification including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2110.50	Square metre.			Per Square metre.	
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 404. By Manual Means including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	211.05	Cubic metres			Per Cubic metre	
Total:-							

Executive Engineer,
Bilaspur Division No. 1
HP PWD, Bilaspur

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.4,62,901/-Only.	
							Earnest Money :- Rs. 9,300/- only	
							Time:- Three Months.	
NAME OF WORK:- Restoration of Road damages on Kutehla Kariyan Bagchhal Road Km 0/0 to 10/815 (SH:- Road widening from RD 10/784 to 10/787.50 on swarghat side approach of Bagchhal Bridge)(Deposit Work).								
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount		
			Figure.	Words.				
1	2 Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification, 2014 Clause 300, 302.3.5 & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber ,embankments for grade improvements and disposal of all useful /surplus materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and execution shall be absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases as per direction of Engineer-in-Charges including carriage of materials within all leads and lifts.The rate including octroi,royalty , Malkana , toll tax, sale tax, Goods services tax or other taxes imposed by the Govt. A recovery of useful stone for 184.39 Cum (one hundred Eighty Four point Thirty Nine). Cubic metre at the rate of Rs.300/- (Rs. Three hundred) only shall be done on pro-rate basis in each running bill for this item including carriage of materials in all leads lifts as per the direction of the Engineer-in-Charge.	3 553.18	4 Cubic Metre	5 Per Cubic Metre	6 7			
	Total:-							

Executive Engineer,
Bill/Spec Division No. 2,
M.P.W.D., Bhopal (M.P.)
B

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.3,25,971/-Only.						
Earnest Money :- Rs.6,600/-						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain Damages on link road to Harizan Basti Tiun Khas km 0/00 to 3/135 (SH:- C/o R/wall at RD 2/050 to 2/060)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge, ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.40	cubic metre		Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	65.70	Cubic metre		Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.30	Cubic metre.		Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Nos.		Each	
Total:-						

Executive Engineer,
Bilaspur Division No. 2,
B.P.O., Bilaspur (H.P.).