



E-Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 26/02/2024 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 23/02/2024 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be outrightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost form	of Time limit
1	Special repair to Ambulance/Jeepable road from Rajpura Chowk to NH-205 Nauni Brampukher road Km. 0/0 to 1/150 (SH:- Providing and laying stone soiling and Cement concrete 1:2:4 at RD 0/835 to 1/0)	Rs 4,20,704/-	Rs. 8,500/-	Rs. 350/-	Three Month
2	C/o link road Boh to Hambar Km. 0/0 to 1/500 (SH:- C/o 900 mm dia hume pipe culverts at RD 0/300 both side wing wall)	Rs 2,13,121/-	Rs. 4,300/-	Rs. 350/-	Three Month
3	A/R & M/O various roads under Sub-Division Namhol (SH:- Supplying and stacking at site of work crushed stone aggregate, 10mm to 12.5mm, 40mm nominal size and sand)	Rs 1,96,850/-	Rs. 4,000/-	Rs. 350/-	Three Month
4	Repair of PHC Building Behal Tehsil Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- C/o Boundary wall) Job No.1 Deposit work	Rs. 4,94,204/-	Rs. 10,000/-	Rs. 350/-	Three Month
5	A/R & M/O various roads under Sub-Division Swarghat (Swahan Section) (SH:- Supplying and stacking at site of work crushed stone aggregate, 10mm to 12.5mm, 40mm nominal size and sand)	Rs 2,73,070/-	Rs. 5,500/-	Rs. 350/-	Three Month
6	Restoration of Rain damages on link road Dolra to Bag Mehla Km., 0/0 to 3/810 (SH:- C/o R/wall at RD 3/175 to 3/207, 3/215 to 3/227 and 3/279 to 3/284) Deposit work	Rs 4,61,463/-	Rs. 9,300/-	Rs. 350/-	Three Month
7	Restoration of Rain damages on link road to village Bhuwai Km. 0/0 to 2/285 (SH:- C/o R/wall at RD 0/200 to 0/210)	Rs 2,67,705/-	Rs. 5,400/-	Rs. 350/-	Three Month
8	Construction of Balance work of Sub-Tehsil Namhol Distt. Bilaspur (HP) (SH:- Providing and fixing curtain)	Rs 1,44,867/-	Rs. 2,900/-	Rs. 350/-	Three Month
9	Repair of PHC Building Behal Tehsil Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- C/o Boundary wall) Job No.2 Deposit work	Rs. 2,18,281/-	Rs. 4,400/-	Rs. 350/-	Three Month
10	C/o Balance work of Neri to Ashamajari road Km. 0/0 to 1/600 (SH:- C/o Metalling and Tarring in Km. 0/890 to 1/030)	Rs. 3,54,717/-	Rs. 7,100/-	Rs. 350/-	Three Month
11	Restoration of Rain damages on Navgaon Beri road Km. 4/350 to 23/700 (SH:- C/o R/wall at RD 17/705 to 17/715.50)	Rs. 4,80,003/-	Rs. 9,600/-	Rs. 350/-	Three Month
12	Restoration of Rain damages on link road Dolra to Bag Mehla Km., 0/0 to 3/810 (SH:- C/o R/wall at RD 3/266 to 3/278.70) Deposit work	Rs 4,97,225/-	Rs. 10,000/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.

2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2023-

14313-22

Dated:-

17/02/2024

Copy forwarded to the following for information and necessary action:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur.
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.4,20,704/- Only.						
Earnest Money :- Rs.8,500/- Only						
Time:- Three Months.						
NAME OF WORK:- Special repair to Ambulance /Jeepable road from Rajpura Chowk to NH-205 Nauni Brahmputkhar Road km 0/00 to 1/150 (SH):- Providing and Laying Stone						
Sylling and Cement Concrete 1:2:4 at RD 0/835 to 1/000)						
Sl. No.	Description of items.	Quantity		Rates in		Unit
		Figure.	Words.	Figure.	Words.	
1	2	3		4	5	6
1	Preparation of sub-grade by dressing to camber (Earth work) for the cutting involved for sub-grade to be measured and paid for separately depending upon the classification of soil completed as per HP.PWD. Specification as per direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	485.10	Square metre.			Per Square metre.
2	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (One Hundred millimeter)spread thickness (finished work including materials and labour) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	55.79	Cubic metres			Per Cubic metre
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	59.55	Cubic metre.			Per Cubic Metre
Total						

Executive Engineer,
Bilaspur Division No. 2,
H.R. PWD, Bilaspur (H.P.).
B-1

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,13,121/-Only.

Earnest Money :- Rs 4,300/-

Time:- Three Months.

NAME OF WORK:- Construction of link road Boh to Hambar km 0/00 to 1/500 (SH:- Construction of 900 mm dia Hume pipe culverts at RD 0/300 Both side wing wall)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-Charge. The rates of carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 49.96		4 cubic metre	5 Per cubic metre	6 Per cubic metre	7 7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.90		Cubic metre		Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.28		Cubic Metre		Per Cubic Metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.99		Cubic metre.		Per Cubic Metre	
5	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50		Running Meter		Per Running Meter	

6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.58	Cubic metre.			Per Cubic Metre
7	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Nos.			Each
Total:-						


 Executive Engineer,
 Bilaspur Division No. 2,
 H.P.W.D., Bilaspur (H.P.)


Estimated cost:- Rs.1,96,850/- Only.

Earnest Money :- Rs.4,000/- Only

Time:- Three Months.

Work crushed stone aggregate, 10mm to 12.5mm, 40 mm

SCHEDULE OF QUANTITY.

NAME OF WORK:- A/R & M/O various roads under Sub-Division Namhol (SH:-Supplying and Stacking at site of work crushed stone aggregate, 10mm to 12.5mm, 40 mm nominal size and sand)		Description of items.	Quantity		Rates in		Unit	Amount
			Figure.	Words.	Figure.	Words.		
Sr No.								
1		2	3	5	4	6	7	
1		Supplying and stacking at site broken/ crushed stone aggregate of hard stone of following nominal size free from disintegrated, dataterious and orginic materials, stacking along road side uniform stacked including carriage of materials, with in all leads and lift as per direction by the Engineer in charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	100.00	Cubic Metre		Per Cubic Metre		
i)		10 mm (Ten millimeter) to 12.5 mm (Twelve point Five Millimeter) nominal size	10.00	Cubic Metre		Per cubic metre		
ii)		40 mm (forty millimeter) nominal size	25.00	Cubic Metre		Per cubic metre		
2		Supplying and stacking at site coarsed sand of approved quality (conforming to HPPWD specification 1990 Vol.- 1) clean and free from in jurcous soft and floty persion in proper stacks including carriage of materials, with in all leads and lift and as per direction by the Engineer in charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.						
Total:-								

Executive Engineer,
Bilaspur Division No. 2,
V.P.W.D., Bilaspur (H.P.).

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,94,204/-Only.

Earnest Money :- Rs.10,000/-

Time:- Three Months.

(Job-1) (Deposit Work)

NAME OF WORK:- Repair of PHC Buiding Behal Teh. Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- C/O Boundary wall)		Description of items.		Quantity		Rates in		Unit	Amount
Sr No.						Figure.	Words.		
			2		3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.38	cubic metre					Per cubic metre	
2	Providing and laying cement concrete, 1:6:12 (One cement : six Sand : twelve graded crushed stone aggregate, 40mm (Forty millimetres) nominal size) and curing complete excluding cost of centring and shuttering in foundation and plinth including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.10	cubic metre					Per cubic metre	
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:6 (one cement : six coarse sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	52.93	Cubic Metre					Per Cubic Metre	
4	15 mm (fifteen millimeter) cement plaster on rough side of single or half brick wall of mix 1:4 (one cement: four fine sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	427.00	Square Meter					Per Square Meter	
5	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	427.00	Square Meter					Per Square Meter	
Total:-									


 Executive Engineer,
 Bilaspur Division No. 2,
 D.O. PWD, Bilaspur (H.P.)


SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.2,73,070/- Only.						
Earnest Money :- Rs.5,500/- Only						
Time:- Three Months.						
NAME OF WORK:- A/R & M/O of various roads under HPPWD Sub-Division Swarghat (Swahan Section) (SH:-Supplying and Stacking at site of work crushed stone aggregate,10mm to 12.5mm,40 mm nominal size and sand)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Supplying and stacking at site broken/ crushed stone aggregate of hard stone of following nominal size free from disintegrated, dataterious and orginic materials, stacking along road side uniform stacked including carriage of materials, with in all leads and lift as per direction by the Engineer in charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
i)	10 mm (Ten millimeter) to 12.5 mm (Twelve point Five Millimeter) nominal size	70.00	Cubic Metre		Per Cubic Metre	
ii)	40 mm (forty millimeter) nominal size	20.00	Cubic Metre		Per cubic metre	
2	Supplying and stacking at site coarsed sand of approved quality (conforming to HPPWD specification 1990 Vol.- 1) clean and freee from in jurcous soft and floty persion in proper stacks including carriage of materials, with in all leads and lift and as per direction by the Engineer in charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.00	Cubic Metre		Per cubic metre	
		**				
Total:-						

Executive Engineer,
Ruralpur Division No. 2,
H.P.W.D., Balespur (H.P.)
(B4)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,61,463/-Only.

Earnest Money :- Rs.9,300/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on link road Dolra to Bag Mehla km 0/00 to 3/810 (SH:- C/o R/wall at RD 3/175 to 3/207, 3/215 to 3/227 and 3/279 to 3/284)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
		3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. The rates include carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates include octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.61		cubic metre	Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	93.05		Cubic metre	Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.45		Cubic metre.	Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates include octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	58.00		Nos.	Each	
Total:-						

Executive Engineer,
 Bilaspur Division No. 2,
 B.S. PWD, Bilaspur (H.P.)


SCHEDULE OF QUANTITY.


Estimated cost:- Rs.2,67,705/-Only.

Earnest Money :- Rs.5,400/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on link road to village Bhuwai km 0/00 to 2/285 (SH:- C/o R/wall at RD 0/200 to 0/210)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge, ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.00	cubic metre		Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	52.90	Cubic metre		Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.60	Cubic metre.		Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00	Nos.		Each	
Total:-						


 Executive Engineer,
 Bill/Spec Division No.2,
 P.W.D., Bikaner (H.F.)


SCHEDULE OF QUANTITY.		Estimated cost:- Rs.1,44,867/- Only.				
		Earnest Money :- Rs.2,900/- Only.				
		Time:- Three Months.				
NAME OF WORK:- Construction of Balance Work of Sub-Tehsil Namhol Distt. Bilaspur (HP) (SH:- Providing and fixing curtain)						
Sr	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Providing and fixing curtain including stitching and fixing in which curtain cloth & lining complete having size of 0.50 metre in width in all respect including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
1.1	9 feet curtain for door	18.00	No.		Each	
1.2	7 feet curtain for windows	40.00	No.		Each	
2	Providing and fixing steel curtain rod having wall thickness of 1.25 mm (One point Twenty Five Millimeter) with two steel brackets fixed with screws and PVC sleeves etc., wherever necessary complete including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	49.80	Running meter		Per Running meter	
Total:-						

Executive Engineer,
Bilaspur Division No. 2,
H.P.W.D., Bilaspur (H.P.)
B.S.

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,18,281/-Only.

Earnest Money :- Rs.4,400/-

Time:- Three Months.

NAME OF WORK:- Repair of PHC Buiding Behal Teh. Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- C/O Boundary wall) (Job-2) (Deposit Work)

Description of items.

Sr No.	Quantity	Unit	Amount	Rates in	
				Figure.	Words.
	3			4	5
1	3.40	cubic metre			6
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-Charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Per cubic metre	7		
2	Providing and laying cement concrete, 1:6:12 (One cement : six Sand : twelve graded crushed stone aggregate, 40mm (Forty millimetres) nominal size) and curing complete excluding cost of centring and shuttering in foundation and plinth including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Per cubic metre			
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:6 (one cement : six coarse sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Per Cubic Metre			
4	15 mm (fifteen millimeter) cement plaster on rough side of single or half brick wall of mix 1:4 (one cement: four fine sand) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Per Square Meter			
5	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Per Square Meter			
Total:-					

Executive Engineer,
Bilaspur Division No.2,
J.C. PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,54,717/-Only.

Earnest Money :- Rs.7,100/-

Time:- Three Months.

NAME OF WORK:- Construction of Balance work of Neri to Ashamajhari road km 0/00 to 1/600 (SH:- C/o Metallising and Tarring in km 0/890 to 1/030)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Providing & Laying, spreading and compacting stone aggregate alongwith Supplying and stacking at site of 90 mm (Ninety millimeter) to 45 mm (Forty Five Millimeter) size stone aggregate specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 49.25	4 Cubic metres	5	6 Per Cubic metre	7
2	Providing & Laying, spreading and compacting stone aggregate alongwith Supplying and stacking at site of 63 mm (Sixty Three to 45 mm (Forty Five Millimeter) size stone aggregate specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.63	Cubic metres		Per Cubic metre	
3	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	448.35	square metre		Per square metre	
4	Providing and applying tack coat using bitumen emulsion conforming to IS: 8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With rapid setting(RS-1) bituminous emulsion on bituminous surface @ 0.25 kg/ sqm (zero point twenty five kilogram per square meter) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	448.35	square metre		Per square metre	

5	2 cm (Two centimeter) premix carpet surfacing with 1.8 (One point Eight) cum and 0.90 (Zero point Ninety) cum of stone chippings of 13.2 mm (Thirteen point Two millimeter) size and 11.2 mm (Eleven point Two millimeter) size respectively per 100 (one Hundred) sqm and 52 (Fifty Two) kg and 56 (Fifty Six) kg of hot bitumen per cum of stone chippings of 13.2 mm (Thirteen point Two millimeter) and 11.2 mm (Eleven point Two millimeter) size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6 to 9 tonne capacity etc. complete (tack coat to be paid for separately). With paving Asphalt grade VG - 30 with no solvent including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	448.35	Square metre.		Per Square metre.
6	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm (Two point Thirty Six millimeter) and retained on 180 (One Hundred Eighty) micron sieve) with bitumen using 128 (One Twenty Eight) kg of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 (Zero point Sixty) cum of fine aggregate per 100 (One hundred) sqm of road surface including rolling and finishing with road roller all complete. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	448.35	Square metre		Per Square metre
Total:-					

Executive Engineer,
Bilaspur Division No. 2,
B.P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,80,003/-Only.

Earnest Money :- Rs.9,600/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Navgoan Beri road km 4/350 to 23/700 (SH:- C/o R/wall at RD 17/705 to 17/715.50)

Sl. No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All Kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.83	cubic metre		Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	97.02	Cubic metre		Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.38	Cubic metre		Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	48.00	Nos.		Each	
Total:-						

Executive Engineer,
Bulandshahr Division No. 2,
Bulandshahr, Uttar Pradesh (U.P.)
(B)

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.4,97,225/-Only.		
							Earnest Money :- Rs.10,000/-		
							Time:- Three Months.		
NAME OF WORK:- Restoration of Rain Damages on link road Dolra to Bag Mehla km 0/00 to 3/810 (SH:- C/o R/wall at RD 3/266 to 3/278.70) (Deposit Work)									
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount			
			Figure.	Words.					
1	2	3	4	5	6	7			
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge, ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.24	cubic metre		Per cubic metre	7			
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	101.09	Cubic metre		Per Cubic metre				
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.88	Cubic metre.		Per Cubic Metre				
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00	Nos.		Each				
Total:-									

Executive Engineer,
Bilaspur Division No. 2,
Bilaspur (M.P.)