



Office of
Executive Engineer HP.PWD. Division Baijnath
Himachal Pradesh Public Works Department
Phone No. 01894-263035 E-Mail:- ee-baij-hp@nic.in

“ Corrigendum “

The tenders called vide this office NIT letter No.**PWD/BD/TA/NIT/2023-24/17532-81** dated **07.02.2024** published in web site of “Public works Department Government of Himachal Pradesh” for the work appearing at Sr.No.6 “Balance work for C/O R/Wall and culvert at Govt. High School Sehla Distt. Kangra (SH: C/O R/Wall, culvert and P/L Hume Pipe culvert)” Estimated Cost. Rs.4,99,681/- Earnest Money Rs.10,000/- and Time limit. (One Month) may be substituted as “Construction of Dharer to Kandkosri Km 0/00 to 4/00 (SH: P/L C.C. Pavement at RD 2/060 to 2/120 & 1/680 to 1/720)” Estimated cost Rs.4,83,014/- Earnest Money Rs.9,700/- Time Limit (One Month)

Other terms and conditions of the N.I.T. will remain un-changed.

Executive Engineer
Baijnath Division,
HP.PWD., Baijnath.

NO:-PWD/BD/TA/NIT/2023-24/- | 7793-17804 Dated:-09.02.2024

- 1 Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction of Dharrer to Kandkosari km 0.00 to 4.00 .
(SH: P.T.C.C pavement at RD 2.060 to 2.120 & 1.680 to 1.720 .)

Estimate Cost: 4,00,00,000
Tendered Money: 9,700,000
Time Limit: One Month

SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT RS. P.
				Figures	Words	
1	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 k N static roller in stages to proper grade and camber, applying and brooming, stone screening type-43 of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer-in-Charge including hauling, carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	24.00	Per Cubic Metre			
2	Construction of un-reinforced, plain cement concrete pavement thickness as per design, over a prepared sub base with 43 grade cement or any other type as per Clause 1501.2.2 M20 (Grade), coarse and fine aggregates conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weight batcher using approved mix design, laid in approved fixed side formwork (steel) channel, laying and fixing of 1.25 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing spreading the concrete with shovels rakes compact using needle, screed and plate vibrator and finishing in continuous operation including construction joints, admixtures as approved, curing the concrete slab for 14 days using curing compound (where specified) and water finishing to lines and grade as per drawing and technical specification clause 1501. The rate shall be made from the quantity of stone aggregates supplies. The rate shall include all lead, lift and proper stacking complete in all respect as per the direction of the Engineer-in-charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	51.20	Per Cubic metre			
Total						

Exe
Br
H

201

201