

01899-240618, 292000
Fax No. 01899-240618

E-mail- ee-dal-hp@nic.in

No. PWD-Dal/TA/Tender /2023-24- **10472-74**

Dated: - **14-02-2024**

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

**Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.**


Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

**Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie**

Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2023-24:-10472-74 dated 14-2-2024 is emergent nature and in Public interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

“NOTICE INVITING TENDERS”

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- | | | |
|---|---|--|
| 1 | Date of receipt of application for the tender
Form a/w requisite documents:- | 15.02.2024 onward (between 2:00p.m. to 4:30p.m.) |
| 2 | Date of issued/sale of tender form against
Cash payment (non refundable). | 21.02.2024 |

The tender shall be received upto 3:00 PM on 22.02.2024 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 21.02.2024.

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Dismantling of existing Type-1 Residential building near HPPWD Rest House Dalhousie” including removal of serviceable/unserviceable material (making the site clear) all the dismantled serviceable and unserviceable material shall become the property of the successful bidder and he has to handover site to the department on. As it is and where it is basis” without having any claim on the material left out at site.	391659/-	10000/-	350/-	One month	Class-D & C
2.	Banikhet Dalhousie Khajjiar road k.m. 0/0 to 6/400 (SH:-Patch work of 25mm thick mix seal fur facing in k.m. 0/0 to 6/400 in various RDs (under MMSRRY)	478193/-	10000/-	350/-	Three month	Class-D & C
3	Patch work of 25mm thick mix seal surfacing of various roads under HPPWD Sub Division Dalhousie in various RDs (under MMSRRY)	489362/-	10000/-	350/-	Three month	Class-D & C
4	Restoration of Rain damage on Banikhet Dalhousie Khajjiar road k.m. 0/0 to 6/400 and 15/600 to 27/00 (SH:- removal of Slips/Snow on Banikhet Dalhousie Khajjiar road k.m. 0/0 to 6/400 and 15/600 to 27/00	247800/-	5000/-	350/-	Two month	Class-D & C
5	Restoration of Rain damage on various Roads under Dalhousie Sub Division Dalhousie (SH:- removal of Slips/Snow on Banikhet Dalhousie Khajjiar road k.m. 0/0 to 6/400 and 15/600 to 27/00 Dalhousie Jandrigat Chamba via kohleri road k.m. 0,0 to 11/040, Link road to village Ruliyani k.m. 0/0 to 3/0 & Link road to village Kathlog to Bharera k.m. 0/0 to 2/0180)	497700/-	10000/-	350/-	Two month	Class-D & C
6	A/R & M/O JE Quarter at Bathri (SH:- Painting work of JE Quarter at Bathri	68355/-	1500/-	350/-	Two month	D & C

- The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- The tender shall be issued to those contractor o who have not more than two works in hand.
- GST No./Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
- Application without all documents will not be entertained.
- Proxy application will not be entertained.

(Signature)
Executive Engineer,
Dalhousie Division,
HPPWD Dalhousie.


No. PWD/TA/Tender /2023-24-

10475-525

Dated: - 14-02-2024

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost :-	Rs.3,91,659.00
Earnest money :-	Rs. 10000.00
Time:-	Six Month

Name of Work:- Dismantling of existing Type -I Residential building near HPPWD Rest House Dalhousie" including removal of serviceable /unserviceable material (making the site clear) all the dismantled serviceable and unserviceable material shall become the property of the successful bidder and he has to handover site to the department on "As it is and Where it is basis" without having any claim on the material left out at site.

Sr. No	Description of items	Quantity	Unit	Rate		Amount	Amount in words
				In figure	In words		
1	Dismantling of existing Type -I Residential building near HPPWD Rest House Dalhousie" including removal of serviceable /unserviceable material (making the site clear) all the dismantled serviceable and unserviceable material shall become the property of the successful bidder and he has to handover site to the department on "As it is and Where it is basis" without having any claim on the material left out at site.	1.00	Job				
					Total:-	0.00	
	Quoted Rate in Figure (%)				To be quoted by contractor		
	Quoted Rate in Words%)				To be quoted by contractor		

Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Name of work: -A/R & M/O JE Quarter at Bathri (SH: - Painting work of JE Quarter at Bathri).

Estimated Cost: - Rs. 68333.00

Earnest Money :- Rs.1500.00

Time Limit :- Two Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and applying plaster of Paris Putty of 2mm (two millimeter) thickness over plastered surface to prepare the surface even and smooth complete as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	104.22			Per Square Metre	
2	Finishing with Deluxe Multi Surface paint system for interiors and exteriors using Primer Asain Paints/Nerolac Surksha Paints/Berger Paints/ Deluxe Paint or more coats applied on walls @ 1.25ltr/10 sqm (one point twenty five litre per ten square meter) over and including one coat of special primer applied @ 0.75 ltr/Sqm(Zero point sevey five liter per Suare meter) as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	345.18			Per Square Metre	
3	Painting one coat (excluding priming coat) of Asian paints/ Nerolac Surksha Paints/ Berger Paints/ Deluxe Paint on previously painted wood or wood based furface with enamel paint other than white to gave a even shade including cleaning of all dirt, dust other foreign matter sand papering and slopping within all leads and lift and as per direction of Engineer-In-Charge and other incidentals. The rate including the octori, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	60.69			Per Square Metre	
					Total: -	


 Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Qty.

Job No. 05 TS No. 74

Estimated Cost: - Rs.	497700.00
Earnest Money :- Rs.	10000.00
Time Limit :-	Two Month

Name of work: - Restoration of rain damage on various roads under Dalhousie Sub Division (SH:- removal of Slips/Snow on Banikhet Dalhousie Khajjar road Km. 0/0 to 6/400 & 15/600 to 27/00, Dalhousie Jandrightat Chamba via Kohlari road Km. 0/0 to 11/040, Link road to village Ruliyani Km. 0/0 to 3/0 & Link road to village Kathlog to Bharera Km. 0/0 to 2/180).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	474.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
P.P.W.D. Dept.

Schedule of Qty.

Job No. 04 TS No. 73

Estimated Cost: - Rs.	247800.00
Earnest Money :- Rs.	5000.00
Time Limit :-	Two Month

Name of work: - Restoration of rain damage on Banikhet Dalhousie Khajjiar road Km. 0/0 to 6/400 & 15/600 to 27/0 (SH:- removal of Slips/Snow on Banikhet Dalhousie Khajjiar road Km. 0/0 to 6/400 & 15/600 to 27/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	236.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.
 Note - 2) No deviation shall be allowed in any case.
 Note - 3) Subject of availbity of funds

Executive Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Qty.

Name of work: -Patch work of 25mm thick mix seal Surfacing of various roads under HP PWD Sub Division Dalhousie in various RD's under MMSRRY.

Job No. 03 TS 72
Estimated Cost: - Rs. 489362.00
Earnest Money :- Rs. 10000.00
Time Limit :- Three Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and applying Tack Coat with Bitumen emulsion (RS-1) using emulsions distributor at the rate of 0.25 to 0.30 (zero point twenty five to zero point thirty) kg per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 or as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana. toll tax, GST, sale tax or other taxes imposed by the Government.	1405.00			Per Squire Metre	
2	Providing, laying and rolling of close graded Mix seal surfacing surfacing material of 25mm (Twenty five millimeter) thickness composed of 11.2mm to 0.09mm (eleven point two millimeter to zero point nine millimeter) (Type-A) @ 0.338 Kg/10 sqm (Zero point three hundred thirty eight kilogram per ten square meter) aggregates using penetration grade bitumen @ 1.6 binders content @ 27.50 Kg/10 Sqm (Twenty seven point fifty Kilogram per sen square meter) or 5.11% by weight and minimum density of Mix seal surfacing should be 2.10gm/cc to required base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kn static roller and finishing to required level and grades as per Technical specification Clause 509 including leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. The rate including the octroi, royalty, Malkana. toll tax, GST, sale tax or other taxes imposed by	1405.00			Per Squire Metre	
					Total:-	

Executive Engineer
Dalhousie Division,
HP PWD, Dalhousie

Schedule of Qty.

Name of work: -Banikhet Dalhousie Khajjiar raod Km. 0/0 to 6/400 (SH: - Patch work of 25mm thick mix seal surfacing in Km. 0/0 to 6/400 in various RD's under MMSRRY).

Job No. 02 TS 71
Estimated Cost: - Rs. 478913.00
Earnest Money :- Rs. 10000.00
Time Limit :- Three Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and applying Tack Coat with Bitumen emulsion (RS-I) using emulsions distributor at the rate of 0.25 to 0.30 (zero point twenty five to zero point thirty) kg per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 or as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana. toll tax, GST, sale tax or other taxes imposed by the Government.	1375.00			Per Square Metre	
2	Providing, laying and rolling of close graded Mix seal surfacing surfacing material of 25mm (Twenty five millimeter) thickness composed of 11.2mm to 0.09mm (eleven point two millimeter to zero point nine millimeter) (Type-A) @ 0.338 Kg/10 sqm (Zero point three hundred thirty eight kilogram per ten square meter) aggregates using penetration grade bitumen @ 1.1% binders content @ 27.50 Kg/10 Sqm (Twenty seven point fifty Kilogram per ten square meter) or 5.11% by weight and minimum density of Mix seal surfacing should be 2.10gm/cc to required base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kn static roller and finishing to required level and grades as per Technical specification Clause 509 including leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	1375.00			Per Square Metre	
					Total: -	

Executive Engineer
Dalhousie Division,
Bilaspur, D.D. Dalhousie