



Office of
Executive Engineer B&R Division HP.PWD, Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@ncl.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P.) from the eligible contractors of the appropriate class registered in HP.PWD as per revised enrollment rules so as to reach in the office of under signed on 07-03-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of Intending contractors. The tender application will be received in this office on 5-03-2024 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 6-03-2024 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enrollment, GST Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction of Mela Ground at Joginder Nagar Distt. Mandi (H.P.) (SH:- Providing and Laying Ornamental Grill and Lighting System at Mela Ground RHS at RD. 0/040 to 0/085)	Rs.4,96,054/-	Rs.9,900/-	Rs.350/-	Class "D"	Three months
2	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SH:- Construction of Retaining wall at km. 31/015 to 31/030).	Rs.3,88,634/-	Rs.7,800/-	Rs.350/-	Class "D"	Three months
3	Restoration of Damages due to laying of OFC on Baijnath Lad Bharol Kandapattan road km. 0/00 to 46/00 (SH:- Constriction of U-shape drain in km. 31/390 to 31/485).	Rs.1,15,463/-	Rs.2,300/-	Rs.350/-	Class "D"	Three months
4	Construction of link road Ropri to Chandani Road km. 0/00 to 0/750 Under Deposit (SH:- Formation cutting in km. 0/150 to 0/530).	Rs.4,26,379/-	Rs.8,500/-	Rs.350/-	Class "D"	Three months
5	Restoration of Rain damages on Ladruhin Khalehal road km. 0/00 to 1/800 (SH:- C/o Wire Crate Retaining wall for protection of washed away portion at km. 1/675 to 1/680).	Rs.3,64,640/-	Rs.7,300/-	Rs.350/-	Class "D"	Three Months
6	Construction & M/T on Sandha Makan Kalan to Fagla road km. 0/00 to 4/500 (SH:- Formation cutting in km. 1/600 to 1/855).	Rs.4,99,303/-	Rs.10,000/-	Rs.350/-	Class "D"	Three Months
7	Restoration of Damages due to laying of OFC on Baijnath Lad Bharol Kandapattan road km. 0/00 to 46/00 (SH:- C/o wire Crate retaining wall along with Pusta at km. 42/150 to 42/166.25).	Rs.482,247/-	Rs.9,600/-	Rs.350/-	Class "D"	Three Months
8	Construction of Dhghon Salehra Fagla rod km. 0/00 to 1/500(SH:- Balnce work of 6.00 mtr. span RCC slab culvert at km. 0/400)	Rs.4,13,438/-	Rs.8,300/-	Rs.350/-	Class "D"	Three Months
9	Restoration of Rain Damages on Bhararu to Banaru Dom road km. 0/00 to 4/500(SH:- Construction of Breast wall at km. 3/885 to 3/900 to protect existing house).	Rs.1,93,896/-	Rs.3,900/-	Rs.350/-	Class "D"	Three Months
10	A/R & M/O Various Non Residential Buldings under Joginder Nagar Division HP PWD Joginder (SH:- C/o Edge wall, soling and Cement concrete in RHS Ground portion at JE Sectional office Bhararu).	Rs.1,82,450/-	Rs.3,600/-	Rs.350/-	Class "D"	Three Months
11	Restoration of Damages due to laying of OFC on Baijnath Jateher Golwan Draman Ahju Chowki Sainthal Dohag Joginder Nagar Garoru Majharnoo Bassi Kundani Manoh Kas Bhararu Bihun Nauhali Damela Padhar road km. 0/00 to 58/00 (Portion Dhelu Bhatehar) (SH:- Construction of Retaining Wall at km. 30/077 to 30/090)	Rs.2,22,749/-	Rs.4,500/-	Rs.350/-	Class "D"	Three Months
12	Restoration of Damages due to laying of OFC on Baijnath Jateher Golwan Draman Ahju Chowki Sainthal Dohag Joginder Nagar Garoru Majharnoo Bassi Kundani Manoh Kas Bhararu Bihun Nauhali Damela Padhar road km. 0/00 to 58/00 (Portion Dhelu Bhatehar) (SH:- Construction of Retaining Wall at km. 23/620 to 23/630)	Rs.1,34,314/-	Rs.2,700/-	Rs.350/-	Class "D"	Three Months
13	Special Repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (H.P.) (SH:- Painting work & P/F flushing cistern Door & Windows, Cupboard et. In 90 trainee boys Hostel).	Rs.4,36,799/-	Rs.8,700/-	Rs.350/-	Class "D"	Three Months
14	Restoration of damiages due to laying of OFC on Ladruhin Dohag rod (SH:- Construction of Retaining wall at km. 0/040 to 0/050).	Rs.2,23,146/-	Rs.4,500/-	Rs.350/-	Class "D"	Three Months
15	Construction of Mela Ground at Joginder Nagar Distt Mandi (H.P.) (SH:- Providing and Laying Ornamental Grill and Lighting System at Mela Ground RHS at RD. 0/085 to 0/110 & back Side at RD 0/0 to 0/020.)	Rs.4,96,054/-	Rs.9,900/-	Rs.350/-	Class "D"	Three months

16	Restoration of damages due to laying of OFC on Sandapattan Bharol Bagora Bagla Hard Roipari Kelang Triambli Basha Drubhal Charanj Banwar Kun Ka Tai Mandokhar Bhargoan Kotli road km. 0/00 to 80/00 (MDR-57) (SH:- Supplying and fixing road side open Gym/Garden Articles Near Outpur road at km. 1/500 and Near Bharan School at km. 4/000)	Rs.4,90,000/-	Rs.9,800/-	Rs.350/-	Class "D"	Three months
17	Construction & M/T on Salahan to Dugh road km. 0/00 to 4/000 (SH:- Widening of Curves and New Formation cutting in km. 0/720 to 1/075).	Rs.2,89,753/-	Rs.5,800/-	Rs.350/-	Class "D"	Three months
18	Restoration of damages due to laying of OFC on Joginder Ngar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SH:- Construction of Breast wall at km. 1/455 to 1/463).	Rs.99,922/-	Rs.2,000/-	Rs.350/-	Class "D"	Two months
19	Restoration of damages due to laying of OFC on Dholu Har to Sarkari Bagiha km. 0/00 to 1/000 (SH:- P/L WBM G-II and 20mm thick premix carpet at km. 0/270 to 0/324, 0/421 to 0/541 & 0/691 to 0/867).	Rs.4,16,038/-	Rs.8,300/-	Rs.350/-	Class "D"	Three Months
20	Construction of road from Kuthera Kurati to Banwar i/c Metalling Tarring km. 0/00 to 4/00 (SH:- Providing and laying WBM G-I at km. 1/400 to 1/675).	Rs.2,51,208/-	Rs.5,000/-	Rs.350/-	Class "D"	Three Months
21	Restoration of Rain Damages on Bagher to Bereu road km. 0/00 to 1/500 (SH:- Removal of Land Slide/ Slips at km. 0/410 to 0/530).	Rs.4,49,998/-	Rs.9,000/-	Rs.350/-	Class "D"	Three Months
22	Restoration of rain damages on link road from Ladwan to Mata Chatarbhuj Temple km. 0/0 to 2/0 (SH:- Formation cutting/ Removal of formation deficiency between km. 0/405 to 0/855).	Rs.4,92,343/-	Rs.9,800/-	Rs.350/-	Class "D"	Three Months
23	Construction of link road from Khuddi Gharloan to Nagaun Bhamori Mata Temple km. 0/0 to 4/0 under MNP (SH:- Providing and laying Kharanja Soling & Cement Concrete pavement at km. 3/660 to 3/760).	Rs.2,71,143/-	Rs.5,400/-	Rs.350/-	Class "D"	Three Months
24	Restoration of Rain Damages on Chanehar to Kufu Samoun road km. 0/00 to 2/00 (SH:- Construction of Retaining wall in km. 0/295 to 0/310).	Rs.2,67,534/-	Rs.5,400/-	Rs.350/-	Class "D"	Three Months
25	Construction & M/T Jhamehar Shanan Kunkar Nagn road in G.P. Dhar km. 0/00 to 2/500 (SH:- Formation cutting in km. 0/895 to 1/190).	Rs.4,90,298/-	Rs.9,800/-	Rs.350/-	Class "D"	Three Months
26	Restoration of Rain Damages on Kundani Kass road km. 0/00 to 6/795 (SH:- Construction of wire crate Breast wall for Protection of Existing House at km. 3/465 to 3/485).	Rs.1,99,302/-	Rs.4,000/-	Rs.350/-	Class "D"	Three Months
27	Construction & M/T Triambli Pplotu Chanchher road km. 0/00 to 4/00 under OTMNP (SH:- Construction of 900mm dia RCC Hume Pipe Culvert at km. 0/675, Providing and laying Kharanja Stone Soling at km. 0/650 to 0/850).	Rs.3,84,101/-	Rs.7,700/-	Rs.350/-	Class "D"	Three Months
28	Construction & M/T on Triambli Pplotu Chanchher road km. 0/00 to 4/00 (SH:- Construction of 900mm dia RCC Hume Pipe Culvert at km. 1/00)	Rs.2,70,464/-	Rs.5,400/-	Rs.350/-	Class "D"	Three Months
29	Construction & M/T of link road from Draman Galu to Village Batnahr km. 0/00 to 1/00 Under OTMNP (SH:- Improvement of Formation width by providing Retaining wall at km. 0/00 to 0/010).	Rs.4,16,514/-	Rs.8,300/-	Rs.350/-	Class "D"	Three Months
30	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SH:- Construction of Retaining wall at km. 12/180 to 12/190).	Rs.4,56,583/-	Rs.9,100/-	Rs.350/-	Class "D"	Three Months
31	Restoration of Damages due to laying of OFC on Baijnath Lad Bharol Kandapattan road km. 0/00 to 46/00 (SH:- Construction of Breast wall at km. 21/870 to 21/890).	Rs.3,58,435/-	Rs.7,200/-	Rs.350/-	Class "D"	Three Months
32	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SH:- Construction of Wire Crate Retaining wall at km. 30/910 to 30/922.50).	Rs.4,97,093/-	Rs.9,900/-	Rs.350/-	Class "D"	Three Months
33	Restoration of rain damages on Har Kass Patholu Ro km. 0/00 to 4/600 (SH:- Construction of Retaining wall at km. 2/240 to 0/248).	Rs.2,22,468/-	Rs.4,400/-	Rs.350/-	Class "D"	Three Months
34	Construction of Arthi Shanan Rod km. 0/00 to 3/00 under Deposit (SH:- Construction of Retaining wall at km. 0/370 to 0/385).	Rs.2,68,365/-	Rs.5,400/-	Rs.350/-	Class "D"	Three Months
35	Construction of link road from Jhalwan Palhoon road to Ex.MP House km. 0/00 to 0/300 under Deposit (SH:- Construction (SH:- Construction of Retaining wall for at km. 0/210 to 0/215.80)	Rs.2,88,642/-	Rs.5,800/-	Rs.350/-	Class "D"	Three Months
36	Restoration of rain damages on Joginder Nagar Sarkaghat Ghumarwin road km. 0/00 to 21/500 (SH:- Construction of Breast wall at km. 19/525 to 19/540)	Rs.1,93,993/-	Rs.3,900/-	Rs.350/-	Class "D"	Three Months
37	Restoration of Damages due to laying of OFC on Baijnath Lad Bharol Kandapattan road km. 0/00 to 46/00 (SH:- Construction of Retaining wall at km. 29/920 to 29/925)	Rs.2,13,644/-	Rs.4,300/-	Rs.350/-	Class "D"	Three Months
38	Restoration of Damages due to laying of OFC on Baijnath Lad Bharol Kandapattan road km. 0/00 to 46/00 (SH:- Construction of V-shape Drain in km. 41/00 to 41/400)	Rs.4,42,020/-	Rs.8,800/-	Rs.350/-	Class "D"	Three Months

39	Construction of Room at Health Sub Centro at Kas Kas Under BASP Deposit (SH:- Construction of room with Varendah).	Rs 3,23,419 /-	Rs 6,500/-	Rs 350/-	Class "D"	Three Months
40	Construction of Joginder Nagar Arthi rod to join with Syuri Majharnoo road & C/o Bridge over Nori Khad(SH:- Construction of Retaining wall at km. 0/700 to 0/710).	Rs 4,41,859 /-	Rs 8,800/-	Rs 350/-	Class "D"	Three Months
41	Construction of Ghatasani Bh ordhar road km. 0/00 to 3/500 G.P. Kadhar Under BASP Deposit (SH:- Providing and laying Kharanja Stone Soling and CC pavement at various reaches between km. 2/375)	Rs 4,25,671 /-	Rs 8,500/-	Rs 350/-	Class "D"	Three Months
42	Restoration of rain Damages on Draman Kun Ka Tar road km. 0/00 to 7/225 (SH:- Construction of Retaining wall at km. 4/4435 to 4/460)	Rs 3,35,148 /-	Rs 6,700/-	Rs 350/-	Class "D"	Three Months
43	Construction and Maintenance of road from Malai to Village Badan km. 0/00 to 4/00 (SH:- formation cutting in km. 0/00 to 0/249)	Rs 2,55,820 /-	Rs 5,100/-	Rs 350/-	Class "D"	Three Months
44	Restoration of Rain damages on Dhehu Bhatehar Road km. 0/00 to 13/400 (SH:- C/o Retaining wall at km. 10/420 to 10/435).	Rs 1,88,738 /-	Rs 3,800/-	Rs 350/-	Class "D"	Three Months
45	Construction of link road from Drubbal to Triambli Banoun road km. 0/00 to 2/700 (SH:- Providing and laying CC pavement at km. 0/720 to 0/860).	Rs 4,41,003 /-	Rs 8,800/-	Rs 350/-	Class "D"	Three Months
46	C/O various roads under Joginder Nagar Suyb Division (Harabag Section) Under Deposit (SH:- Providing and laying Wearing G-II and CC Pavement on Joginder Nagar Kathla Dul road at km. 1/368 to 1/465).	Rs 2,56,488 /-	Rs 5,100/-	Rs 350/-	Class "D"	Three Months
47	Restoration of damages due to laying of OFC on Dol Raktal Changehar road km. 0/00 to 8/660 (SH:- C/o R/Wall in km. 7/150 to 7/165).	Rs 2,63,679 /-	Rs 5,300/-	Rs 350/-	Class "D"	Three Months
48	Construction of Link road from Sanhali to Mangyal km. 0/00 to 1/00 under Deposit (SH:- Construction of Breast wall for protection of cow shed at km. 0/720 to 0/733).	Rs 3,52,393 /-	Rs 7,000/-	Rs 350/-	Class "D"	Three Months
49	C/O 180.00 Mtr. Span Bridge over River Beas at Sandha Tehsil Lad Bharol Distt. Mandi (SH:- Providing and laying cement concrete pavement in Approach road Sandha Side at km. 0/420 to 0/525)	Rs 4,96,128 /-	Rs 9,900/-	Rs 350/-	Class "D"	Three months
50	Restoration of rain damages on Machhyal Bhararu Bihun road km. 0/00 to 12/00 (SH:- Construction of Breast wall for protection of Patwar Khana Batari Bihun at km. 9/935)	Rs 1,89,308 /-	Rs 3,800/-	Rs 350/-	Class "D"	Three Months
51	Restoration of Rain Damages on Dhehu Bhatehar road km. 0/00 to 13/400 (SH:- Construction of Retaining wall at km. 10/520 to 10/530).	Rs 1,25,826 /-	Rs 2,500/-	Rs 350/-	Class "D"	Three Months
52	Periodical Maintenance of Various Roads under Annual maintenance Plan 2023-24 Lad Bharol Sub Division HP PWD, Lad Bharol (SH:- Providing and Applying Thermoplastic Strips, Side continue line and Zebra Crossing of Chobin Bander road km. 0/00 to 2/00, Baijnath Lad Bharol Kandapattan road km. 13/00 to 14/00 and Baijnath Padhar road km. 6/520 to 7/00).	Rs 4,99,539 /-	Rs 10,000/-	Rs 350/-	Class "D"	Three Months
53	Construction of Link road from Sanali to Mangyal km. 0/00 to 1/ under Deposit (SH:- Construction of Breast wall for protection of cow shed at km. 0/720 to 0/733).	Rs 4,58,112 /-	Rs 9,200/-	Rs 350/-	Class "D"	Three Months
54	Stock & storage under Sub Division HP PWD, Joginder Nagar (SH:- Providing and supplying of Sokkiya or equivalent Total Station (Model IM 55) 5 second machine battery 12 hrs alongwith stand, Prism Pole, Big Prism, Mini Prism).	Rs 4,75,000 /-	Rs 9,500/-	Rs 350/-	Class "D"	One Month
55	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SH:- Construction of Retaining wall at km. 16/015 to 16/024).	Rs 4,87,930 /-	Rs 9,800/-	Rs 350/-	Class "D"	Three Months
56	Restoration of damages Sandapattan Bharol Bagora Bagla Hard Ropari Kolang Triambli Bashai Drubbal Charonj Banwar Kun Ka Tar Mandokhar Bhargoan Kotli road (MDR-57) km. 0/00 to 80/00 (SH:- Construction of Breast wall at km. 40/330 to 40/350) OFC Deposit.	Rs 2,63,556 /-	Rs 5,300/-	Rs 350/-	Class "D"	Three Months
57	Restoation of Rain damages on Darkoti to Nichla Bhardyara road km. 0/00 to 8/600 (SH:- Construction of Retaining wall at km. 5/050 to 5/060).	Rs 1,84,959 /-	Rs 3,700 /-	Rs 350/-	Class "D"	Three Months
58	Restoration of Damages due to laying of OFC on Simus Gwaila rod km. 0/00 to 3/500(SH:- Removal of Slips at km. 1/775 to 2/240).	Rs 4,96,934 /-	Rs 9,900/-	Rs 350/-	Class "D"	Three months
59	Construction & M/T of rod from Banoun to Salang via Baba Ki Kutiya km. 0/00 to 2/00 (SH:- Construction of wing wall for Existing 3.00 mtr. span RCC Slab culvert at km. 1/675)	Rs 2,44,475 /-	Rs 4,900/-	Rs 350/-	Class "D"	Three months

60	Restoration of rain damages on Link road to Village Banog km. 0/00 to 1/500 (SH:- Construction of Breast wall for protection to the house of Sh. Bablu ram at km. 1/225 to 1/245)	Rs.2,51,650 /-	Rs.5,000/-	Rs.350/-	Class "D"	Three Months
61	Restoration of damages due to laying of OFC n Gagal Simus road km. 0/00 to 5/00 (SH:- Construction Retaining wall at km. 0/861 to 0/866).	Rs.1,43,110 /-	Rs.2,900/-	Rs.350/-	Class "D"	Three Months
62	Construction of Dhaghon Salehra Fagla road km. 0/00 to 1/500 (SH:- Widening of road by providing Retaining wall at km. 0/800 to 0/816).	Rs.4,88,424/-	Rs.9,800/-	Rs.350/-	Class "D"	Three Months
63	Construction of road from Majharnu Kufroo Kundnu km. 0/00 to 6/00 (SH:- Construction of wire crte retaining wall at km. 2/290 to 2/930).	Rs.2,06,286 /-	Rs.4,100/-	Rs.350/-	Class "D"	Three Months
64	Construction of link road from Balotu to Gwaila via Nugal Mahadev (SH:- Formation cutting in km. 3/625 to 3/675).	Rs.4,98,580 /-	Rs.10,000/-	Rs.350/-	Class "D"	Three Months
65	Construction of link road from Athrah to Kufro via Dogri Harizan Basti road km. 0/00 to 1/00 (SH:- Construction of Breast wall to protect Existing house at km. 0/495 to 0/503).	Rs.1,01,203 /-	Rs.2,000/-	Rs.350/-	Class "D"	Three Months
66	Construction & M/T on Sandha Makan Kalan to Fagla road km. 0/00 to 4/500 (SH:- Formation Cutting in km. 1/855 to 2/115).	Rs.4,92,979/-	Rs.9,900/-	Rs.350/-	Class "D"	Three Months
67	Construction of Dhaghon Salehar Fagla road km. 0/00 to 1/500 (SH:- Providing and laying Kharanja Soling and CC pavement at km. 0/500 to 0/608)	Rs.4,65,976/-	Rs.9,300/-	Rs.350/-	Class "D"	Three Months
68	Construction of road from Majharnu Kufro Kundnu km. 0/00 to 6/00 (SH:- Construction of wire crate retaining wall at km. 2/931 to 2/938.50).	Rs.1,54,734/-	Rs.3,100/-	Rs.350/-	Class "D"	Three Months
69	Construction of rain shelter on Joginder Nagar Sarkaghat Ghumarwin road (MDR-79) km. 0/00 to 34/300 at Kaunsal at km. 6/150).	Rs.2,34,342/-	Rs.4,700/-	Rs.350/-	Class "D"	Three Months
70	Construction of rain shelter on Joginder Nagar Sarkaghat Ghumarwin road (MDR-79) km. 0/00 to 34/300 at Khudar at km. 6/650).	Rs.2,34,342/-	Rs.4,700/-	Rs.350/-	Class "D"	Three Months
71	Construction of rain shelter on Baijnath Lad Bharol Kandapattan road MDR-43) km. 0/00 to 46/0 at Chakrog at km. 6/650).	Rs.2,34,400/-	Rs.4,700/-	Rs.350/-	Class "D"	Three Months
72	Construction of Chakka Jhamehar road upto Neri via Ali Pabo km. 5/00 to 10/00 (SH:- Formation cutting in km. 6/895 to 7/129).	Rs.4,61,633/-	Rs.9,200/-	Rs.350/-	Class "D"	Three Months
73	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SHG:- Construction of Retaining wall at km. 24/345 to 24/353).	Rs.3,65,365/-	Rs.7,300/-	Rs.350/-	Class "D"	Three Months
74	Construction of Harabag Bhatwari Lahla Malan Nakehar Kangwan road under Deposit (SH:- Widening of Road between km. 1/615 to 1/695).	Rs.3,09,444 /-	Rs.6,200/-	Rs.350/-	Class "D"	Three Months
75	(i)Construction of link rod from Village Bhagehar to Bhreau km. 0/00 to 1/479 (ii) Construction of link road from Guini to Prain km. 0/00 to 5/110 (SH:- Preparation of Digital Plan with including Online submission of Bhagehar to Bhreau road and Digital compensatory afforestation maps of Guini to Prain road under HP PWD. Division, Joginder Nagar	Rs.4,22,000/-	Rs.8,400/-	Rs.350/-	Class "D"	One year
76	Restoration of Damages due to laying of OFC on Baijnath Lad Bharol Kandapattan road km. 0/0 to 46/0 (SH:- Construction of Retaining wall at km. 42/405 to 42/419)	Rs.4,93,957 /-	Rs.9,900/-	Rs.350/-	Class "D"	Three Months
77	Construction and M/T of Link road Village Chanehar under SCSP (SH:- Providing and laying of Wearing G-II & Cement Concrete pavement at km. 2/040 to 2/090).	Rs.1,68,358 /-	Rs.3,400/-	Rs.350/-	Class "D"	Three Months
78	Special repair to Satate Revenue Training Institute at Joginder Nagar Distt. Mandi (H.P.) (SH:- Painting work, Tile work, Providing and fixing Wire Gauge Shutter & Repair of W.S. & S.I. In Dining /Canteen Hall)	Rs.1,85,687/-	Rs.3,700/-	Rs.350/-	Class "D"	Three Months
79	Construction & M/T on Jeepable link road Badoun to Almerah km. 0/00 to 1/00 (SH:- Improvement of Formation width by providing Breast wall at km. 0/485 to 0/500).	Rs.1,97,801/-	Rs.4,000/-	Rs.350/-	Class "D"	Three Months
80	Restoration of Rain damages on Petu Nallah to Guduhl road km. 0/00 to 1/500 (SH:- Construction of Retaining wall at km. 1/310 to 1/331).	Rs.4,96,272/-	Rs.9,900/-	Rs.350/-	Class "D"	Three Months
81	Restoration of rain damages on Basal Drubble road km. 0/00 to 8/00 (SH:- Repair of Pot Holes / Patch work at km. 0/00 to 8/00)	Rs.4,98,098/-	Rs.10,000/-	Rs.350/-	Class "D"	Three Months
82	Construction of Retaining wall at Bagdena road near house of Amar Singh Khadhiar under Deposit (SH:- Balance work of Retainign wall at km. 0/00 to 0/015).	Rs.1,21,722/-	Rs.2,400/-	Rs.350/-	Class "D"	Three Months
83	Restoration of rain Damages on Machhyal Bhararu Bihun km. 0/00 to 12/00 (SH:- Construction of Breast wall for protection of Existing house at km. 2/675 to 2/785)	Rs.4,68,674/-	Rs.9,400/-	Rs.350/-	Class "D"	Three Months

84 Restoration of Rain Damages on Petu Nallah to Rs.4,92,755/- Rs. 9,900/- Rs.350/- Class "D" Three Months
Guduhi road km. 0/00 to 1/500 (SH:- Providing and laying WBM G-II and CC Pavement at km. 1/090 to 1/210).

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2023-24-

36909-58

Dated:-

23-8-2024

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

SCHEDULE OF QUANTITY

Name of work : Construction of Mela Ground at Joginder Nagar Distt. Mandi H.P. (Sub Head:- Providing and Laying Ornamental Grill and Lighting System at Mela Ground RHS at RD 0/040 to 0/085)					Estimate Cost: 4,96,054.00 Earnest Money: 9,900.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is inclusive all taxes levy by the government time to time excluding GST	5.06	Per cubic metre			
2	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering strutting and propping etc. with wooden battens and ballies for all heights depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in foundation.. Footings bases of columns and mass concrete, including curing and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	27.00	Per square metre			
3	Providing and laying cement concrete work 1:2:4 (one Cement isto two Sand isto four graded stone aggregate twenty millimeter nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in Foundations, footings bases of columns and the like and mass concrete as per PW D specification including curing and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.55	Per cubic metre			
4	Providing and fixing grills of required pattern in steel frames of windows etc. with V.I.S. flats with round headed bolts and nuts or by screw, plain grill as per PW D specification complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	1576.80	Per Kilogramme			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Providing and fixing ornamental decorative lights pole with two nos solar LED (light emitting diod) lights including battery and all wiring and electrical component complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each			
	Total					


 Executive Engineer
 B & R Division HP, PWD.
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to laying of OFC on Joginder Ngar Sarkaghat Ghumarwin Road km 0/00 to 34/300 (SH: Construction of Retaining wall at km 31/015 to 31/030)				Estimate Cost: 3.88,634.00 Earnest Money: 7.800.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.35	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	22.73	Per cubic metre			

Description of work

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
3 Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls. in or under water complete including pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	27.00	Per cubic metre			
4 Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	70.29	Per Cubic metre			
5 Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	20.25	Per cubic metre			
Total					

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (Sub Head:- Construction of U-Shape Darin in km 31/390 to 31/485)				Estimate Cost: Earnest Money : Time Limit :			1.15.463.00 2.300.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Words	AMOUNT Rs. P
				Figures			
1	Earth work in excavation for structures in all depths as per drawing and M (O) R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, hailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost The rate is inclusive all taxes levy by the government time to time excluding GST.	37.05	Per cubic metre				
2	Providing concrete for plain-reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.06	Per cubic metre				
	Total						



 Engineer
 B & R Division H.P. P.W.D.
 Jalandhar

4 **SCHEDULE OF QUANTITY**

Name of Work: Construction of Link road Ropri to Chandani Road km 0/00 to 0/750 Under Deposit (Self-Formation Cutting in km 0/150 to 0/530)				Estimate Cost: Earnest Money: Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words Rs. P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling line dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 86.66 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	2166.45	Per cubic metre		
Total					


 Executive Engineer
 B & R Division IIP PWD.
 Baidar Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Ladruhin Khabhai road km 0/00 to 1/800 (SIP: Construction of wire Crate Retaining wall for protection of washed away portion at km 1/675 to 1/680)				Estimate Cost: 3,64,640.00 Earnest Money: 7,300.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1800 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with blasting and wedging out rock where blasting is prohibited. All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, timber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable materials in specified manner. filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.90	Per cubic metre		
2	Providing and laying of boulder apron laid in wire cranes with 4mm (four millimetre) diameter G.I wire conforming to IS-280 and IS-1826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	117.19	Per Cubic metre		
3	Filling earth in foundation trenches behind retaining breast wall with marshy soil as per drawing and technical specification clause 305.3.9 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	60.93	Per cubic metre		
	Total				


 Executive Engineer
 B & R Division H.P. PWD.
 Jodhpur

SCHEDULE OF QUANTITY

Name of Work: Construction & M/T on Sandha Makan Kalan to Fagla road km 0/00 to 4/500 (SFC: Formation Cutting in km 1/600 to 1/855)				Estimate Cost: Earnest Money: Time Limit :		4,99,303.00 10,000.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil inilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 153.96 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	2368.50	Per cubic metre			
Total						

Executive Engineer

B & R Division H.P.P.W.D.

For Under Officer

Jebrane - 7

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (SH: C construction of wire Crate retaining wall along with Pusta at km 42/150 to 42/166.25)					Estimate Cost: Earnest Money : Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Earth work in excavation for structures in all depths as per drawing and N.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) All earth work in cutting excavation including rock excavation shall be carried out due to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	27.62	Per cubic metre				
2	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203, Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	26.00	Per cubic metre				
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS - 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications clause 1201 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	85.93	Per Cubic metre				
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204, 3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	34.12	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M (O) R (D) technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	13.00	Each			
	Total					


 Executive Engineer
 B & R Division HP PW D.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of Dhaghon Salehra Fagla road km 0/00 to 1/500 (Sub Head:- Balance work of 6.00 mtr. Span RCC Slab Culvert at Km 0/400)				Estimate Cost: 4,13,438.00 Earnest Money: 8,300.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying Plain reinforced cement concrete in substructure complete as per drawings and technical specifications clause 802, 804,805,806,807,1202 & 1204. PCC Grade M-15 (nominal mix 1:2.5:5) upto 5m height and curing complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	67.06	Per Cubic metre			
	Total					

(Signature)
Executive Engineer

B & R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Bhararu to Banaru Dom road km 0/00 to 4/500 (SH: Construction of Breast wall at km 3/885 to 3/900 to protect existing house)				Estimate Cost: 1,93,896.00 Earnest Money: 3,900.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.70	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	17.25	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	35.31	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	24.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jdginder Nagar

SCHEDULE OF QUANTITY

Name of Work : A/R & M/O Various Non Residential Buildings under Joginder Nagar Division HPPWD Joginder Nagar (SH: Construction of Edge wall, Soling and Cement Concrete in RHS Ground Portion at JE Sectional Office Bhararu)				Estimate Cost: 1,82,450.00 Earnest Money: 3,600.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.20	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R.D technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.80	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Stone softing properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials minimum or earth etc. complete as per HP PWD specification, 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer-in-Charge including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.20	Per Cubic metre			
4	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.24	Per cubic metre			
5	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1(v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
6	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	39.00	Per cubic metre			
Total						


 Executive Engineer
 B & R Division HP, PWD,
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to laying of OFC on Baijnath Jatehar Golwan Draman Ahju Chowki Sainthal Dohag Joginder Nagar Garoru Majharnoo Bassi Kundani Manoh Kas Bhararu Bibun Naulhali Damela Padhar Road km 0/00 to 85/00 (Portion Dhelu Bhatehar) (SH: Construction of Retaining wall at km 30/077 to 30/090)				Estimate Cost: Earnest Money: Time Limit :		
				2,22,749.00 4,500.00 Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.60	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plumbs and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST	41.21	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.80	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	24.00	Each			
	Total					


 Jyoti Nagarkar
 B & R Division HP, PWD.
 Jyoti Nagarkar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to laying of OFC on Baijnath Jatchar Goltwan Draman Ahju Chowki Sainthal Dohag Joginder Nagar Garoru Majbaroon Bassi Kundani Manoh Kas Bhararu Bihun Nauhali Damela Padhar Road km 0/00 to 85/00 (Portion Dhelu Bhatchar) (SIH: Construction of Retaining wall at km 23/620 to 23/630)					Estimate Cost: 1,34,314.00 Earnest Money: 2,700.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	23.50	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads. lifts carriage of material and other incidentals; The rate is inclusive all taxes levy by the government time to time excluding GST.	9.90	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry (plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.00	Each			
	Total					


 B & R Division IIP PWD,
 Jolinder Nagar

SCHEDULE OF QUANTITY

Name of Work : Special Repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (HP)		Estimate Cost:		4,36,799.00	
(S.H. : Painting work & Providing and fixing flushing cistern, Door & Window, Cupboard etc. in 90 trainee Boys Hostel)		Earnest Money:		8,700.00	
		Time Limit :		Three Months	
Sl. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words
1	Applying Brush finished of Altek harmony of NCL altek and secular exterior paint containing pure acrylic binder of international standard good quality additives colour pigments with chemicals to resist algae and fungi to be applied in two coats directly on clean wall overall a coat of Altek primer or equivalent of approved shade to give final matter finish to the surface complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	872.19	Per square metre		
2	Providing and applying white cement based putty of average thickness 1 mm. (one millimeter) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	28.44	Per Square Metre		
3	Distemping (Two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on decorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2728.79	Per square metre		
4	White washing with lime (two coats) on undecorated wall ceiling surfaces two coats to give an even shade including thoroughly brooming the surface to remove all dirt dust mortar dirt and other foreign matter on ceiling and or sloping roofs. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST).	682.82	Per square metre		
				AMOUNT	
				Rs. P	

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Painting one coat (excluding priming coat) over previously painted steel and other metal surfaces with Aluminium paint, brushing to give an even shade. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	443.06	Per square metre			
6	Painting One coat (excluding priming coat) on previously painted steel & other metal surfaces with readymixed paint, brushing oil, grease to give an even shade including cleaning the surface of all dirt, dust and other foreign matter With white readymixed paint. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1420.11	Per square metre			
7	Painting two or more coats on G.I Sheets with readymix paint red shade of approved brand and manufacture on new work to give an even shade. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	641.98	Per square metre			
8	Providing and fixing controlled flush, 10 litre (full flush) capacity white low level cistern made of vitreous china with all fittings complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	21.00	Each			
9	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part 1) non-decorative type, core of black board construction with frame of 1st class hard wood and well matched commercial 3 (three) ply veneering with vertical grains or cross bands and face veneers on both faces of shutters 25 (twenty five) mm thick (for eupboard) including ISI marked nickel plated bright finished M.S. piano hinges with necessary screws. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.90	Per square metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Amount Rs. P
				Figures	Words	
10	Providing and fixing 35 mm (thirty five millimetre) panelled or panelled and glazed shutters with teak wood for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.85	Per Square Metre			
11	Providing and fixing 300x10mm (Three hundred by ten millimeter) size aluminium tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etc. complete as per PWD specification complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.00	Each			
12	Providing and fixing anodized aluminium handle anodized transparent or dyed to required shade or colour with necessary screws etcetera complete. 100 mm (one hundred millimeter) size as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer -In- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.00	Each			
Total						


 Executive Engineer
 B & R Division HP, PWD,
 Jalandhar Nagar

Job 14

SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to laying of OFC O on Ladrubin Dobag Road (SR: Construction of Retaining wall at km 0/040 to 0/050)				Estimate Cost: Earnest Money: Time Limit :			2,23,146.00 4,500.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.70	Per cubic metre					
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	41.50	Per cubic metre					

	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.90	Per cubic metre			
4	Providing weep holes in brick masonry, stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.00	Each			
Total						

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

SCHEDULE OF QUANTITY

(5)

Name of work : Construction of Mela Ground at Joginder Nagar Distt. Mandi H.P. (Sub Head:- Providing and Laying Ornamental Grill and Ligthning System at Mela Ground RHS at RD 0/085 to 0/110 & Back Side at RD 0/00 to 0/020)				Estimate Cost: Earnest Money: Time Limit :			4,96,054.00 9,900.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.06	Per cubic metre					
2	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and balhes for all heights depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in foundation, Footings bases of columns and mass concrete, including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	27.00	Per square metre					
3	Providing and laying cement concrete work 1:2:4 (one Cement isto two Sand isto four graded stone aggregate twenty millimeter nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in foundations, footings bases of columns and the like and mass concrete as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.55	Per cubic metre					
4	Providing and fixing grills of required pattern in steel frames of windows etc. with MS flats with round headed bolts and nuts or by screw plain grill as per PWD specification complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1576.80	Per Kilogramme					

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
iding and fixing ornamental decorative lights pole with two nos solar LED (light emitting diode) is including battery and all wiring and electrical component complete in all respect including haulage material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each			
Total					


 B & R Engineer
 B & R Division HP, PWD.
 Jodhpur, Rajasthan

SCHEDULE OF QUANTITIES

Name of work : Restoration of damages due to laying of OFC on Sandapattan Bharol Bagora Bagla Hard Ropari Kolang Triambli Bashai Drubbal Charonj Banwar Kun Ka Tar Mandokhar Bhargoon Kotli Road km 0/00 to 80/00 (MDR-57) (SH: Supplying and Fixing Road Side Open Gym/ Garden Articals Near Outpur School at km 1/500 and Near Bharan School at km 4/000)					Estimate Cost: Earnest Money : Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Supply and fixing of Concrete benches for garden of size 1000mm (one thousand millimeter) length X 350mm (three hundred millimeter) width X 50mm (fifty millimeter) thickness in terazzo or red colour finish (Curved). Overall Dimensions: Height of table: 780 mm. (seven hundred eighty millimeter) Height of benches: 450 mm (four hundred millimeter). All components are manufactured by using RCC M-30 grade of Concrete using vibro-compaction process. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	21.00	Each				
2	Supply and fixing Air waker, Leg Press, Seating Twister (four in One) for Outdoor fitness equipment having Size 2170 x 820 x 2070 mm (two thousand one hundred seventy by eight hundred twenty by two thousand seventy millimeter) made of GI Pipe / MS Pipe of different NB. Main Post made of 164 / 114 MM (one hundred sixty four / one hundred fourteen millimeter) Pipe. Main support diameter 80 / 60 / 40 MM (eighty / sixty / forty millimeter) The base plate made of 330 MM (three hundred thirt millimeter) diameter. Seating & Foot Hold is Plastic Alloy, UV protectable 3 (three) years and Lead free. Base Cover is Virgin LLDPE, 8 MM thick, UV protectable 3 years and Lead free. Powder Coated Pure Polyester Desired Color 110-150 (one hundred ten to one hundred fifty) microns, UV protectable for 3 (three) years and Lead free. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	4.00	Each				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Supply and fixing Chiest Press Chair (two in One) for Outdoor fitness equipment having Size 2170 X 820 X 2070 mm (two thousand one hundred seventy by eight hundred twenty by two thousand seventy millimeter) made of GI Pipe / MS Pipe of different NB. Main Post made of 164 / 114 MM (one hundred sixty four / one hundred fourteen millimeter) Pipe. Main support diameter 80 / 60 / 40 MM (eighty / sixty / forty millimeter) The base plate made of 330 MM (three hundred thirty millimeter) diameter Seating & Foot Hold is Plastic Alloy, UV protectable 3 (three) years and Lead free. Base Cover is Virgin LLDPE, 8 MM thick, UV protectable 3 years and Lead free. Powder Coated Pure Polyester Desired Color 110-150 (one hundred ten to one hundred fifty) microns, UV protectable for 3 (three) years and Lead free. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time and including GST.	2.00	Each			
4	Supply and fixing Stainless Steel 304 3016 grade benches for three person for garden of size 1750x450x450mm (One thousand seven hundred fifty by four hundred fifty by four hundred fifty millimeter) Bench & 1750x 300x 890mm (one thousand seven hundred fifty by three hundred by eight hundred ninety millimeter) back rest fixed with ground with base plate 400x120x8mm (four hundred by one hundred twenty by eight millimeter) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time and including GST.	4.00	Each			
Total						

Executive Engineer
B & R Division HP PW D.
Joginder Nagal

SCHEDULE OF QUANTITY

Name of Work: Construction & M/T on Salahan to Dugh road, km 0/00 to 4/000
(SII: Widening of Curves and New Formation cutting in km 0/720 to 1/075)

Name of Work: Construction & M/T on Salahan to Dugh road. km 0/00 to 4/000 (SH: Widening of Curves and New Formation cutting in km 0/720 to 1/075)				Estimate Cost: 2,89,753.00		
				Earnest Money: 5,800.00		
				Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 70.55 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	1411.02	Per cubic metre			
Total						


Executive Engineer
B & R Division HP PWD,
Jalandhar Nagar

19 SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumawin road km 0.00 to 34/300 (SH: Construction of Breast wall at km 1/455 to 1/463)					Estimate Cost: 99,922.00 Earnest Money: 2,000.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 A 500 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including hand load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machines, materials, tools equipments and safety measures. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	9.52	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 500 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc., and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines (grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and sale disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage or rain and other causes it shall be removed by suitable diversion, baling out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	6.16	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plumbs and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R.D. technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.88	Per cubic metre			
4	Providing weep holes in brick masonry (stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1(v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.00	Each			
Total						


 Jyotiinder Engineer
 B & R Division HP, P.W.D.
 Jyotiinder Nagar

SCHEDULE OF QUANTITIES

Name of Work : Restoration of damages due to laying of OFC on Dhela Har to Sarkari Bagicha km 0/00 to 1/000 (SH: P-I-WBNM G-11 and 20mm thick primix carpet at km 0/270 to 0/324, 0/421 to 0/541 & 0/691 to 0/867)

Estimate Cost: 4,16,038.00
Earnest Money: 8,300.00
Time Limit : Three Months

Sl. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 800-1000 KN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening, binding materials to fillup the interstices of coarse aggregate watering and compacting to the required density (Grading-3 (three) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	68.91	Per cubic metre		
2	Providing and applying primer tack with bituminous primer (A G-10) at the rate of 1.00 (one point zero zero) kilogram per square metre on existing WBNM (Water bound macadam) surface cleaned with mechanical brooms as per H.P. PW.D. MORD specification complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	918.75	Per square metre		
3	Providing, laying and rolling by mechanical means bitumen (A G-10) of open graded premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm to 5.0mm (thirteen point two millimetre to five point six millimetre) aggregates either using penetration grade bitumen at the rate of 1.46 (one point four six) kilogramme per square metre to required fine, grade and level to serve as wearing course on a previously prepared base including mixing in suitable plant, laying and rolling with a three wheel 800-1000 KN (eighty-hundred kilo newton) static roller capacity, finished to required level and grades to be followed by seal coat of Type-B as per technical specification clause 508 including all corrective measures such as patching pot holes, sealing of cracks including all profile correction for all depths and hauling of material with in all leads and lifts by all modes of transportation. The rate is inclusive all taxes levy by the government time to time excluding GST.	918.75	Per square metre		
4	Providing and laying seal coat Type-B by mechanical means sealing the voids in a bituminous surface laid to the specified levels, grade and crossfall using Bitumen (A G-10) at the rate of 0.68 (zero point six eight) kilogramme per square metre as per technical specification clause 510 including hauling of material with in all leads and lifts by all modes of transportation. The rate is inclusive all taxes levy by the government time to time excluding GST.	918.75	Per square metre		
Total					

Technical Engineer
B&R Division H.P. PW.D.
Jalandhar, Punjab


SCHEDULE OF QUANTITY

Name of Work : Construction of road from Kuthera Kurati to Banwar i/c Metalling Tarring km 0/00 to 4/00 (Sub Head:- Providing and laying WBM G-I at km 1/400 to 1/675)				Estimate Cost: Earnest Money: Time Limit :		2,51,208.00 5,000.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Preparation of sub grade by dressing to camber (earth work for cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HPPWD specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	924.00	Per square metre				
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and releveling the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	924.00	Per square metre				
3	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and blooming, stone screening, binding materials to fillup the interspaces of coarse aggregate watering and compacting to the required density Grading - I (one) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	92.40	Per cubic metre				
Total							


 Executive Engineer
 B & R Division HPPWD,
 Mandar Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Bagher to Bereu road km 0/00 to 1/500 (SH: Removal of Land slide / Slips at km 0/410 to 0/530)					Estimate Cost: 4,49,998.00 Earnest Money: 9,000.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per technical specification clause 302.3.5 and 1611. including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3035.40	Per cubic metre				
Total							


 Executive Engineer
 B & R Division HPJWD
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work: Restoration of rain damages on link road from Ladwan to Mata Chatarbhuja Temple km 0/00 to 2/00 (SH: Formation cutting / Removal of formation deficiency between km 0/405 to 0/855)				Estimate Cost: Earnest Money: Time Limit :		4,92,343.00 9,800.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate	Words	AMOUNT Rs. P
				Figures		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 119.88 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2397.58	Per cubic metre			
Total						

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

(22)

SCHEDULE OF QUANTITY

Name of Work : Construction of link road from Khuddi Charloan to Nagaun Bhamori Mata Temple km 0/0 to 4/0 Under MNP (S.H. : Providing and laying Kharanja Soling & Cement Concrete pavement at km 3/660 to 3/760)				Estimate Cost: Earnest Money: Time Limit :		2,71,143.00 5,400.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST	39.38	Per Cubic metre				
	Total						


 Executive Engineer
 B & R Division HP, PWD,
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Chanchar to Kufri Samoun road km 0/00 to 2/00 (Sl: Construction of Retaining wall in km 0/295 to 0/310)					Estimate Cost: Earnest Money: Time Limit :	2,67,534.00 5,400.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.43	Per cubic metre			
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material without all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.55	Per cubic metre			

60

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.68	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.C.R.D.technical specification clauses 614. 709 & 1206.6 and as per the directions of Engineer-in-charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	13.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work: Construction & M/T Jhamechar Shanan Kunkar Nagan road in GP Dhar km 0/00 to 2/500 (SH: Formation cutting in km 0/895 to 1/190)				Estimate Cost: Earnest Money: Time Limit :		4,90,298.00 9,800.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 99.63 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding C.S.L.	2491.48	Per cubic metre				
Total							


 Executive Engineer
 B & R Division HP, PWD.
 Joginder Natar

SCHEDULE OF QUANTITY

Name of Work: Restoration of Rain Damages on Kundani Kass road km 0/00 to 6/7/95 (S.H. : Construction of wire crate Breast wall for Protection of Existing House at km 3/465 to 3/485)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.90	Per cubic metre			
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	62.50	Per Cubic metre			
Total						


 Executive Engineer
 B & R Division HP.P.W.D.
 Jodhpur Nagar

27 SCHEDULE OF QUANTITY

Name of Work : Construction & M/T Triambli Paplotu Channelher road km 0/00 to 4/00 Under OTMNP (Sub Head:- Construction of 900mm dia RCC Hume Pipe Culvert at km 0/675, Providing and Laying Kharanja Stone Soling at km 0/650 to 0/850)					Estimate Cost:	3,84,101.00
					Earnest Money:	7,700.00
					Time Limit :	Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	66.92	Per cubic metre			
2	Providing and laying concrete for plain reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	3.71	Per cubic metre			
3	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	10.54	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing and laying concrete for plain reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803.1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	24.15	Per cubic metre			
5	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.49	Per cubic metre			
6	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.96	Per cubic metre			
7	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.50	Per running metre			
8	Providing weep hole in brick masonry, stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			

SCHEDULE OF QUANTITY

24

Name of Work : Construction & MT on Triambli Paplotu Chanchher road km 0/00 to 4/00 (Sub Head:- Construction of 900mm dia RCC Hume Pipe Culvert at km 1/00)		Estimate Cost: Earnest Money: Time Limit :			2,70,464,00 5,400,00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	40.20	Per cubic metre			
2	Providing and laying concrete for plain reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.43	Per cubic metre			
3	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.44	Per cubic metre			

Description of work		No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.49	Per cubic metre			
5	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.00	Per running metre			
6	Providing and laying concrete for plain reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	25.55	Per cubic metre			
7	Providing weep hole in brick masonry stone masonry plain reinforced concrete abutment wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
8	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.48	Per cubic metre			
Total						


 B & R Division I.P.P.W.D.
 Jyotinder Naggar

SCHEDULE OF QUANTITY

Name of Work : Construction & M/T of link road from Draman Galu to Village Batnaber km 0/00 to 1/00 Under OT MNP (SI): Improvement of Formation width by providing Retaining wall at km 0/00 to 0/010)				Estimate Cost: Earnest Money: Time Limit :		4,16,514.00 8,300.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner. filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	36.05	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R.D technical specifications section 800 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	52.90	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802. 803. 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads. lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.00	Per cubic metre			
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	17.70	Per cubic metre			
5	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614. 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

(30) SCHEDULE OF QUANTITY

Name of Work: Restoration of damages due to laying of OFC on Joginder Ngar Sarkaghat Ghumarwin Road km 0/00 to 34/300 (SIF: Construction of Retaining wall at km 12/180 to 12/190)				Estimate Cost: 4,56,583.00 Earnest Money: 9,100.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	31.40	Per cubic metre			
2	Providing and laying cement concrete 1:5:10 (one cement five sand ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plumbs and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R.D technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	79.80	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back Filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	21.60	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment. wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	46.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

31 **SCHEDULE OF QUANTITY**

Name of Work : Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (SH: Construction of Breast wall at km 21/870 to 21/890)				Estimate Cost: 3,58,435.00	
				Earnest Money: 7,200.00	
				Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words
				AMOUNT	
				Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and then intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1060 & 300) and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of surplus material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load of animals transport or mechanical means along with its leveling, fine dressing and hauling. Carriage of machines, materials, tools equipments and safety measures. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	40.00	Per cubic metre		
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines (grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.00	Per cubic metre		

(31)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding G.S.T.	66.00	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding G.S.T.	33.00	Each			
	Total					

Executive Engineer
B & R Division HP.PWD.
Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to laying of OFC on Joginder Ngar Sarkaghat Ghumarwin Road km 0/00 to 34/300 (SH: Construction of Wire Gate Retaining wall at km 30/910 to 30/922.50)				Estimate Cost: 4,97,093.00		
				Earnest Money: 9,900,00		
				Time Limit : Three Months		
Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification, section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	31.25	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.94	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	82.02	Per Cubic metre			
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	46.87	Per cubic metre			
	Total					

 Executive Engineer
 B & R Division HP.PWD.
 Jgginder Nagar

33

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Har Kass Patholu Road km 0/00 to 4/600 (SII: Construction of Retaining wall at km 0/240 to 0/248)				Estimate Cost: 2,22,468.00 Earnest Money: 4,400,000 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.40	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed, broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R.D technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST	39.04	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.92	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	21.00	Each			
	Total					

Executive Engineer
B & R Division H.P.P.W.D.
Joginder Nagar

SCHEDULE OF QUANTITIES

Name of Work : Construction of Arthi Shaban Road km 0.00 to 3.00 Under Deposit
 SRI Construction of Retaining wall at km 0.370 to 0.385

Estimate Cost : 2,68,365.00
 Earnest Money : 5,400.00
 Time Limit : Three Months

Sr. No.	Description of work	No. or QTY.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 500 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is exclusive of taxes levy by the government time to time excluding GST.	14.55	Per cubic metre				
2	Providing and laying cement concrete (1:3:10) one cement five sand ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plants and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R.D technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other details. The rate is inclusive of all taxes levy by the government time to time excluding GST.	47.55	Per cubic metre				

(35)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.45	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20 (H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	28.00	Each			
	Total					


 Engineer
 B & R Division IIP PWD,
 Jodhpur, Rajasthan

SCHEDULE OF QUANTITIES

Name of Work : Construction of link road from Jhalwan Palhoon road to Ex. M.P. House km 0.00 to 0.300 under Deposit (S.M.) Construction of Retaining wall for at km 0.210 to 0.215.80)					Estimate Cost: 2,88,642.00 Earnest Money: 5,800.00 Time Limit : Three Months		
Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Earthwork in excavation for structures in all depths as per drawing and MORD technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width of embankment super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be fully compensated by him at his own cost. The rate is inclusive of all taxes levy by the government time to time excluding GST.	14.00	Per cubic metre				
2	Providing and laying cement concrete 1:5:10 (one cement, five sand ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive of all taxes levy by the government time to time excluding GST.	52.90	Per cubic metre				

(35)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.15	Per cubic metre			
4	Providing weep holes in brick masonry plain or reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v) 20 (H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	30.00	Each			
Total						


 Engineer
 B & R Division HP PWID.
 Jodhpur Nagar

1006

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Joginder Nagar Sarkaghat Chummarwin road km 0/00 to 21/500 (SB: Construction of Breast wall at km 19/525 to 19/540)				Estimate Cost: Earnest Money: Time Limit :		1,93,993.00 3,900.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	20.40	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and A.L.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	11.55	Per cubic metre				

(3)

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. p
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement, five sand ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.25	Per cubic metre			
4	Providing weep holes in brick masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	14.00	Each			
	Total					

Executive Engineer
B & R Division HP, PWD,
Joginder Nagar

SCHEDULE OF QUANTITIES

Name of Work : Restoration of Damages due to Laying of OFC on Rajnath Lad Bharol Kandapattan Road km 0.00 to 46.00 (SHE Construction of Retaining wall at km 29.920 to 29.925)

Estimate Cost: 213,644.00
 Earnest Money: 4,300.00
 Time Limit : Three Months

Sl. No.	Description of work	No. or Qty.	Unit	Rate		Amount	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and MORD technical specification section 300 & 1400 including setting out, construction of shoring and bracing, removal of stumps and other detritious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge. Loading and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.05	Per cubic metre				
2	Providing and laying cement concrete 150mm cement five sand ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	39.90	Per cubic metre				
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.5.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.10	Per cubic metre				

(22)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing weep holes in brick masonry plain or reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 in 2000 towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	10.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD
 Jalandhar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (Sub Head:- Construction of V-Shape Darin in km 41/00 to 41/400)				Estimate Cost: Earnest Money: Time Limit :		
				4.42,020.00 8,800.00 Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 500 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deteeterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including and level as shown on the carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	108.00	Per cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time excluding GST.	63.00	Per cubic metre			
Total						


 Executive Engineer
 B & R Division H.P. P.W.D.
 Joginder Nagar

(39) SCHEDULE OF QUANTITY

Name of work : Construction of Room at Health Sub Centre at Kass Kass Under BASP Deposit (SHE: Construction of room with Varendah)				Estimate Cost: Earnest Money: Time Limit :		3,23,419.00 6,500.00 Three Months	
Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and AIO R D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and sale disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, baling out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.40	Per cubic metre				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level in 1:2:6 (one Cement to three coarse sand) to six graded stone aggregate 20 mm (twenty millimeter nominal size) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.22	Per cubic metre				
3	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.20	Per Square Meter				
4	Centering and shuttering including strutting, propping etc. and removal of form for Lintel, beams, plinth beams, girders, brusses and cantilevers. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	33.56	Per Square Meter				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Centering and shuttering including strutting, propping etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.50	Per Square Meter			
6	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	38.84	Per Square Meter			
7	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls under 20 cm (twenty centimeter) wide. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	25.20	Per running Meter			
8	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level in 1:1.5:3 (one cement to one part five coarse sand) to three graded stone aggregate 20 mm (twenty millimeter) nominal size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.05	Per cubic metre			
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.07	Per cubic metre			
10	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillers, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement in 1:1.5:3 (one cement to one part five coarse sand) to three graded stone aggregate 20 mm (twenty millimeter) nominal size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.12	Per cubic metre			

Description of work

Sl. No.	Description of work	No. or Qty.	Unit	Rate		Amount Rs. P
				Figures	Words	
11	Supply and laying of 10 mm dia. wire including straightening, cutting, bending, placing in position and binding all complete upto photo level. Hard drawn steel wire. The rates are inclusive of cost and carriage of materials within all leads, lifts and other incidents @ Rs. per sq. foot for erection and extra provision of Engineer. In Charge. The rate is inclusive of all taxes levied by the governing authority to time including C.S.T.	1200.00	Sq. Metre			
12	12 inch work with common burnt clay 10 x 8 inch modular bricks of class designation 7.5 in superstructure above photo level up to floor level, including all shapes and sizes of cement mortar 1:3 using cement (40 to 50 coarse sand) and bricks are in place. The rate is inclusive of all taxes levied by the governing authority to time including C.S.T.	8.66	Per cubic metre			
Total						


 R. A. R. Division HP DWD
 Engineer

SCHEDULE OF QUANTITY

Name of Work : Construction of Joginder Nagar Arthi road to join with Syuri Majharnoo road & C/O bridge over Neri Khad. (SH: Construction of Retaining wall at km 0/700 to 0/710)				Estimate Cost: Earnest Money: Time Limit :		4,41,859.00 2800.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner. Filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	24.90	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORID technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	79.60	Per cubic metre				

(40)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	25.50	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment. wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	36.00	Each			
Total						


 Executive Engineer
 B & R Division HP PWD.
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of Ghatasani Bhoradhar Road km 0/00 to 3/500 G.P. Kadhar Under BASP Deposit (SI: Providing and Laying Kharanja Stone Soling and CC Pavement at various reaches between km 2/250 to 2/375)				Estimate Cost: Earnest Money: Time Limit :		4,25,671.00. 8,500.00. Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	56.25	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	46.88	Per Cubic metre			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

(42)

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain Damages on Drainage Kun Ka Tar road km 0/00 to 7/225 (S16: Construction of Retaining wall at Km 4/435 to 4/460)					Estimate Cost: 3,35,148.00 Earnest Money: 6,700.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and XI O R D technical specification section 360 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines (grades, side slopes, width, camber, super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	17.75	Per cubic metre			
2	Providing and laying cement concrete 1:5:10 (one cement five sand ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MOED technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	58.75	Per cubic metre			

42

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST	28.50	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v) 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	20.00	Each			
Total						

Executive Engineer
B & R Division H.P.P.W.D.
Kagadur Nagar

SCHEDULE OF QUANTITY

Name of Work: Construction of and Maintenance of road from Malan to Village Badan km 0/00 to 4/00 (Sl: Formation cutting in km 0/00 to 0/249)				Estimate Cost: Earnest Money: Time Limit :		2,55,820.00 5,100.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, culvert, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling line dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 104.74 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	1136.17	Per cubic metre			
Total						


 Executive Engineer
 B & R Division HP.P.W.D.
 Jalandhar

SCHEDULE OF QUANTITY

Name of Work: Restoration of Rain Damages on Dhelu Bhatehar Road km 0/00 to 13/400 (S11: Construction of Retaining wall at km 10/420 to 10/435)				Estimate Cost: 1,88,738.00 Earnest Money: 3,800.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures at all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated as chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes width, camber super elevation and level as shown in the drawings or as directed by the Engineer in-charge handling and stacking of materials useful for construction at suitable sites and safe disposal of disposable materials in specified manner. Filling of unevenness and finishing the road to specified dimensions or as directed by the Engineer in Charge. If the foundation of the structure is to be excavated when it is not in good condition due to spring due to spring seepage, rain and other causes it is to be removed or suitable diversion, baring out or dumping of material and maintenance of the foundation or whatever shall be kept dry. Any loss to the blocks or property, injury during this process of excavation shall be the whole responsibility of the contractor who shall have to be fully compensated by him at his own cost. The rates including all taxes, cesses, the governing labor rates, etc. shall be in RS.	12.60	Per cubic metre			
2	Providing and laying cement concrete (1:3:6) (Dome cement) 100 mm and ten graded crushed broken stone aggregate 40 mm or 45 mm nominal size, 150 mm sand and curing completely including the cost of form work in Retaining walls, Backfill walls, etc. etc. to the complete including pumping or hauling out water, dewatering removal of water, repaired or any which may arise at the time of laying grade, when complete for all heights, 100 mm, including cost of form work as per drawings and M.O.R.D technical specification section 800, 900, 1200 & 1600 not as per the direction of Engineer in Charge including carriage of material within 40' leads and lifts and other negotiable. The rate is inclusive of taxes less by the 10% and 200 time for 10% including GST	15.25	Per cubic metre			

90

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.75	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 in 20 (10 towards drainage face complete as per drawing and M.O.R.D technical specification clauses 6' 1, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST)	15.00	Each			
Total		21.75				

Executive Engineer
B & R Division H.P. P.W.D.
Bhader Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of link road from Drubhal to Triambli Banoun road km 0/00 to 2/700 (Sub Head:- Providing and Laying CC Pavement at km 0/720 to 0/860)					Estimate Cost: 4,41,003.00 Earnest Money: 8,800.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	64.05	Per Cubic metre				
		Total					


 B & R Division HP.PW.D.
 Jalandhar

SCHEDULE OF QUANTITY

Name of Work : Construction of various roads under Joginder Nagar Sub Division (Harabag Section) Under Deposit (Sub Head:- Providing and Laying Wearing C-11 and CC Pavement on Joginder Nagar Kathla Dul road at km 1/368 to 1-465)				Estimate Cost: 2,56,488.00 Earnest Money: 5,100.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo new-ton) static roller in stages to proper grade and camber applying and brooming, stone screening, binding materials to fillup the interstices of coarse aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete in all respect including baulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.39	Per cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates, an entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.16	Per Cubic metre			
Total						

Executive Engineer
B & R Division HP, PW
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to laying of OFC on Dol Raktal Changehar Road km 0/00 to 8/660 (SIL: Construction of Retaining wall at km 7/150 to 7/165)					Estimate Cost: Earnest Money: Time Limit :		2,63,679.00 5,300,000 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Figures	AMOUNT	
				Words	Words		Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc, and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, embank super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, handling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.65	Per cubic metre					
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R.D technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST	47.55	Per cubic metre					

47

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.5.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.00	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment. wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C pipe extending through the full width of the structures with slope of 1 in 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge The rate is inclusive all taxes levy by the government time to time excluding GST	24.00	Each			
	Total					


 Executive Engineer
 B & R Division IIP PWD,
 Jodhpur Nagar

48

SCHEDULE OF QUANTITY

Name of Work : Construction of Link road from Sanhali to Mangyal km 0/00 to 1/00 under Deposit (SR) Construction of Breast wall for protection of cow shed at km 0/720 to 0/733)					Estimate Cost: 3,52,393.00 Earnest Money: 7,000.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M O R D technical specification section 1600 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	11.80	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M O R D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	8.10	Per cubic metre			

48

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M1-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	32.00	Per cubic metre			
4	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	29.40	Per cubic metre			
5	Providing weep holes in brick masonry, stone masonry, plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.00	Each			
Total						

Executive Engineer
B & R Division H.P. PWD.
Jodhpur Nagar

(47)

SCHEDULE OF QUANTITY

Name of Work : Construction of 180.00 Mtr. Span Bridge over River Beas at Sandha Tehsil Lad Bharol Distt. Mandi (H.P.) (S.H. : Providing and laying Cement Concrete pavement in Approach road Sandha Side at km 0/420 to 0/525)				Estimate Cost: 4,96,128.00 Earnest Money: 9,900.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 4.5 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	74.42	Per Cubic metre			
Total						


 Executive Engineer
 B & R Division H.P.W.D.
 Janginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Machhwal Bhararu Bihun Road km 0/00 to 12/00 (SH) Construction of Breast wall for protection of Patwar Khana Bafari Bihun at km 9/920 to 9/935)				Estimate Cost: Earnest Money: Time Limit :		1,89,308.00 3,800.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling, line dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	24.75	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.65	Per cubic metre			

50

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement, five sand ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.25	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v), 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.00	Each			
Total						


Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

5

SCHEDULE OF QUANTITIES

Name of Work : Restoration of Rain Damages on Dhelu Bhatebar Road km 0/00 to 13/400 (SHE : Construction of Retaining wall at km 10/520 to 10/530)				Estimate Cost : 1,25,826,000 Earnest Money : 2,500,000 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earthwork in excavation for structures in all depths as per drawing and MORD technical specification section 500 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock where blasting is prohibited. All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber, super elevation and level as shown on the drawings or as directed by the Engineer-in-charge handling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner. Filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to bearing settlement, etc. and other causes it shall be removed by suitable diversion, hauling out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rates to be given for taxes levied by the government time to time excluding GST.	8.40	Per cubic metre			
2	Providing and laying cement concrete 1:5:10 (one cement, five sand ten graded crushed broken stone aggregate 40 mm thirty millimeters nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or hauling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the provision of Engineer-in-charge including carriage of material within all leads and lifts and other incidents. The rates inclusive all taxes levied by the government time to time excluding GST.	23.50	Per cubic metre			

51

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads. lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.50	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment. wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1(x): 20(y) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	10.00	Each			
	Total	2.00				

B & R Division 111' PVA 13

12/11/19

Executive Engineer

Joginder Narar

SCHEDULE OF QUANTITIES

Name of Work : Construction of Link road from Sanhali to Mangyal km 0/00 to 1/00 under Deposit (SH: Construction of Breast wall for protection of cow shed at km 0/720 to 0/733)										Estimate Cost: 4,58,112.00	Earnest Money: 9,200.00	Time Limit : Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOI NI		Rs.	P			
				Figures	Words							
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and then intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M O R D technical specification section 1000 & 300 and setting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling, line dressing and hauling, carriage of machineries, materials, tools equipments and safety measures. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	15.34	Per cubic metre									
2	Earth work in excavation for structures in all depths as per drawing and M O R D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in all areas with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, hauling out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	10.53	Per cubic metre									

(54)

Schedule of Quantity

Estimated Cost:- Rs. 475000.00
Earnest Money :- Rs. 15000.00
Time:- One Month

Work:- Storage under Sub Division HPPWD, Jodhpur Nagar.

Sub Head :- Provision and Supplying of Sokkiya or equivalent Total Station (Model IM 55) 5 second machine battery 12 hrs. alongwith stand, Prism pole, Big Prism, Mini Prism

Sl. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Provision and Supplying of Sokkiya or equivalent Total Station (Model IM 55) 5 (five) second machine battery 12(twelve) hours alongwith stand, Prism pole, Big Prism, Mini Prism complete set including entire carriage of materials with in all leads lifts and as per entire satisfaction of Engineer-in-Charge including all incidentals. The rate shall be including Octroi, Royalty, Malkana, Toll tax, Sale tax and all other taxes imposed by the Government time to time but excluding GST	1.00			Each	

Executive Engineer
B&R Division, HPPWD
Jodhpur Nagar

55

SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Chumaw in road km 0.06 to 34.300 (SH: C construction of Retaining wall at km 16/015 to 16/024)					Estimate Cost: Earnest Money: Time Limit :		4,87,930.00 9,800.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT		Rs.	P
					Figures	Words		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D (technical specification section 500 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	47.48	Per cubic metre					
2	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals, The rate is inclusive all taxes levy by the government time to time excluding GST	10.00	Per cubic metre					

SCHEDULE OF QUANTITY

Name of Work : Restoration of road damages Sandapattan Bharola Bagora Bagla Hard Ropari Kolang Triambli Bashai Drubhal Charonj Banwar Kun Ka Tar Mandokhar Bhargoon Kotli Road (MDR-57) km 0/00 to 80/00 (SH: Construction of Breast wall at km 40/330 to 40/350) (P.F. 2445.1)				Estimate Cost: Earnest Money: Time Limit :		
Description of work				Rate		
Sr. No.	No.	Unit	Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load of animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	30.30	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.00	Per cubic metre			

2.63,556.00

5,300.00

Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.20	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 in 1, 20 (11) towards drainage face complete as per drawing and M.O.R.D technical specifications clauses 614, 709 & 1206 6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	32.00	Each			
Total						


 Executive Engineer
 B & R Division HP.P.W.D.
 Jodhpur, Rajasthan

SCHEDULE OF QUANTITIES

Name of Work : Restoration of Rain Damages on Darkoti to Nidhi Bhadyara road km 0/00 to 8/600 (SII: C construction of Retaining wall at km 5/050 to 5/060)				Estimate Cost: 1,84,959.00 Earnest Money: 3,700.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth Work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 500 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.75	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R.D technical specifications section 800, 900, 1200 & 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidents. The rate is inclusive all taxes levy by the government time to time excluding GST.	31.70	Per cubic metre			

57

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	14.70	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment. Wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.00	Each			
Total						


 Engineer
 B & R Division HP.PWD.
 Jalandhar

57

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3.	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	14.70	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment. Wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(h) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge The rate is inclusive all taxes levy by the government time to time excluding GST.	15.00	Each			
Total						


 Engineer
 B & R Division H.P. P.W.D.
 Jodhpur, Rajasthan

(58)

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to laying of OFC on Simus Gwaila road-km-0/00 to 3/500 (SIH: Removal of Slips at km 1/775 to 2/240)					Estimate Cost: Earnest Money: Time Limit :		4,96,934.00 9,900,000 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT		Rs.	P
					Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per technical specification clause 302.3.5 and 1611, including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	3352.00	Per cubic metre					
Total								


Executive Engineer
B & R Division H.P. PWD.
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction & M.T. of road from Banoun to Salang via Baba ki Kutiya km 0/00 to 2/00 (S.H. Construction of Wing wall for 1 existing 3.00 mtr. Span RCC Slab Culvert at km 1/675)				Estimate Cost: Earnest Money: Time Limit : 2,44,475.00 4,900.00 Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.Detailed specification section 800 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, cambers, etc. excavation and level as shown on the drawings or as directed by the Engineer-in-Charge. Ready to use materials useful for construction at suitable sites and safe disposal of unserviceable materials in specified manner. Filling of unevenness and finishing the road to specified cross section as directed by the Engineer-in-Charge. If the foundation of the structure is in contact with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be fully compensated by him at his own cost. The rate is inclusive all taxes levy by the government upto time excluding GST.	18.48	Per cubic metre			
2	Providing and laying cement concrete 1:5:10 (one cement five sand ten graded crushed broken stone aggregate 10 mm thirty millimeter) nominal size) plans and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings of M.O.R.Detailed specification section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material without cart, loads and lifts and other incidents. The work is to be done by the 2:30:10:100 time rate excluding GST.	44.38	Per cubic metre			

	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 of similar material complete within all leads. Lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST	13.44	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment wing wall, return wall with minimum one hundred millimeter dia P.V.C. pipe extending through the full width of the structures with slope of 1 in 20 (1:20) towards drainage face complete as per drawing and M.O.R. Detailed specification clauses 6.1.1, 7.09 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	24.00	Each			
	Total					

Executive Engineer
B & R Division HP, PWID,
Joginder Nagar.

Job no - 5

SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to falling of OGC on Gagal Simus road km 0.00 to 5.00 (SHE: Construction of Retaining wall at km 0.861 to 0.866)			Estimate Cost: 1,43,110.00 Earnest Money: 2,900.00 Time Limit : Three Months			
Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and MORD technical specification section 300 & 6000 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and scaling out rock (where blasting is prohibited). All earth work in cutting excavation including back excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge. handling and stacking of materials used for construction of suitable sites and safe disposal of unsuitable cut materials in specified manner. Filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive of taxes levy by the Government time to time excluding GST	15.00	Per cubic metre			
2	Providing and laying cement concrete 1:5 (One cement five sand ten graded crushed broken stone aggregate 40 mm forty millimeters nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls in or under water complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800 900 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive of all taxes levy by the government time to time excluding GST	26.45	Per cubic metre			

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads. lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.00	Per cubic metre			
4 Providing weep holes in brick masonry plain or reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.00	Each			
Total					


 B. & R. Div. Sd/- Engineer
 Hyderabad Nagar

Job No-6

(12)

SCHEDULE OF QUANTITY

Name of Work : Construction of Dhaghon Salehra Fagla road km 0/00 to 1/500 (SII: Widening of road by providing Retaining wall at km 0/800 to 0/816)		Estimate Cost: 4,88,424.00 Earnest Money: 9,800.00 Time Limit : Three Months				
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-charge handling and stacking of materials as per construction at suitable sites and safe disposal of unsuitable cut materials in specified manner. Filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	38.00	Per cubic metre			
2	Providing and laying cement concrete 1:5:10 (one cement, five sand ten graded crushed broken stone aggregate 40 mm (four millimeters nominal size) plums and curing complete including the cost of form work in Retaining walls, Breast walls, in or under water complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete, for all heights depths including cost of form work as per drawings and M.O.R.D technical specifications, 800 (800) 1200 & 1600 and as per the direction of Engineer in-charge including carriage of material within all leads and lifts and other particulars. The rate is inclusive all taxes levy by the government time to time excluding GST.	84.64	Per cubic metre			

	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST	30.00	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C pipe extending through the full width of the structures with slope of 1 in 20(1) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	34.00	Each			
	Total					


 Jyoti K. Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

Job No - 62

63

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITIES						Estimate Cost: 2,06,286.00	
Name of Work : Construction of road from Majharanu Kufro Kundnu Km 0/00 to 6/00						Earnest Money: 4,100.00	
SHT: Construction of wire C rate retaining wall at km 2/920 to 2/930)						Time Limit :	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.20	Per cubic metre				
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.L. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	62.50	Per Cubic metre				

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Back filling-behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	17.70	Per cubic metre			
Total					


 Executive Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

(64)

Jobne - 8

SCHEDULE OF QUANTITIES

Name of Work: Construction of Link road from Balotu to Gwila via Nugal Mahade

sl: Formation cutting in km 3625 to 3675)

[illegible]

REG. MAIL ENGINEER
BANK DIVISION HP PWD
TELEPHONE: NAGAR

706NO-19

(15)

SCHEDULE OF QUANTITY

Name of Work : Construction of link road from Athrah to Kufra via Dogri Harizan Basti road km 0/00 to 1/00 (Slq: Construction of Breast wall to protect Existing house at km 0/495 to 0/503)				Estimate Cost: 1,01,203.00 Earnest Money: 2,000.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in fully area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and then intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M O R D technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling, line dressing and hauling, carriage of machineries, materials, tools equipments and safety measures. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	14.56	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M O R D technical specification section 300 & 1000 including setting out, construction of shooting and backing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated. Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, hauling out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	4.08	Per cubic metre			

Description of work		No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement, five sand, ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.80	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 in 20 (H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.00	Each			
Total						


 Executive Engineer
 B & R Division HP, PWD.
 Jodhpur Nagaur

00
.00
ths

SCHEDULE OF QUANTITY

Name of Work : Construction of Dhagbon Salehra Fagla road km 0/00 to 1/500 (SH: Providing and Laying Kharanja Soling and CC Pavement at km 0/500 to 0/608)				Estimate Cost: Earnest Money: Time Limit :		4,65,976.00 9,300.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate			AMOUNT Rs. P
				Figures	Words		
1	Preparation of sub grade by dressing to camber (Earth work for cutting involved for sub grade to paid for separately depending upon the classification of soil) completed as per IIPPWD specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	348.87	Per square metre				
2	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per IIP PWD specification. 100 mm (one hundred millimeter) spread thickness finished work including materials and labour) and to the entire satisfaction and direction of Engineer-in-Charge including carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect The rate is inclusive all taxes levy by the government time to time excluding GST.	51.88	Per Cubic metre				
3	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 45 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge The rate is inclusive all taxes levy by the government time to time excluding GST	51.88	Per Cubic metre				
Total							

Executive Engineer
B & R Division IIP PW D,
Bardhaman

SCHEDULE OF QUANTITY

Name of Work: Construction of road from Majharan Kufro Kundur Km 0/00 to 6/00
(SHE: Construction of wire Gate retaining wall at km 2/931 to 2/938.50)

Estimate Cost: 1,54,734.00
Earnest Money: 3,100.00
Time Limit: Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Amount	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 500 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	7.65	Per cubic metre				
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST	46.88	Per Cubic metre				

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST	13.28	Per cubic metre			
	Total					


 Executive Engineer
 B & R Division HP PWD,
 Jalandhar Nagar

(69) Jobate 14

SCHEDULE OF QUANTITY

Name of Work : Construction of rain shelter on Jogindernagar Sarkaghat Ghumarwam road (MDR- 79) km 0/0 to 34/300 at Kaonsal at Km. 6/150				Estimate Cost: Earnest Money: Time Limit :		2,34,342.00 4,700,000 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick nipper work, blasting work, soft or hard rocks including chiseling wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm fifteen centimeters thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is inclusive all taxes levy by the government time to time excluding GST	2.49	Per Cubic Meter				
2	Supplying and filling of hard stone for under floor thick at site. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	0.98	Per Cubic Meter				
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:8 (one Cement isto four coarse sand) isto eight graded stone aggregate 40 mm (fourty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	0.42	Per Cubic Meter				
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement Concrete 1:6:12 (one cement isto six coarse sand isto twelve graded stone aggregate 20 mm (twenty millimeter) nominal size) upto plinth level with Cement mortar 1:6 (one cement isto six coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	2.49	Per Cubic Meter				

	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1:5 (one cement to one part fine sand to three graded stone aggregate 20 mm (twenty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.66	Per Cubic Meter			
6	Centering and shuttering including strutting, propping etc. and removal of form for all heights in Lintel, Beams, Plinth beams, Girders, Cantilever etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.54	Per Square Meter			
7	Cement concrete flooring 1:2:4 (one cement to two coarse sand to four graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm (forty millimeter) thick with 20 mm (twenty millimeter) nominal size stone aggregate. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.81	Per Square Meter			
8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	875.60	Per Kilogramme			
9	Steel work welded in built up sections, framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in girders, frames, guard bar, ladder, railings, brackets, gates and similar works. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	420.80	Per Kilogramme			
10	Providing and fixing 0.6mm (zero point six zero millimeter) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester 5 (five) microns over 5 (five) microns primer coating including fixing with screws pre-painted iron 1 or 1.1 hooks, bolts and nuts 6mm (six millimeter) diameter with pre-painted flange and rubber washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.38	Per Square Meter			

	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
	Providing and fixing ridges or hips 60cm (sixty centimetre) overall with 0.63mm (zero point six three millimetre) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (twenty) microns over 5 (five) microns primer coating plus back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with screws pre-painted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with pre-painted GI limpet and bitumen washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST	24.00	Per Running Meter			
12	Providing and fixing MS BP sheet 1.6mm to 2mm (one point six six millimetre to two millimetre) thick in eaves board fascia soffits ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-In-Charge (Base members of steel work shall be measured & paid separately) including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST	6.14	Each			
13	Painting on Steel work with two or more coat applied @ 0.09 litre / 10 sqm (zero point nine liter per ten square meter) over an under coat of primer applied @ 0.80 litre / 10 sqm (zero point eight liter per ten square meter) of approved brand and manufacture with Deluxe Multi Surface Paint to give an even shade complete including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST	9.35	Per Cubic metre			
Total						


 B & R Division HP PWD
 Jodhpur Nagar

Job No - 15

(72)

SCHEDULE OF QUANTITY

Name of Work : Construction of rain shelter on Jogindernagar Sarkaghat Ghumarwin road (MDR- 79) km 0/0 to 34/300 at Khudar at Km 6/650				Estimate Cost: Earnest Money: Time Limit :		2,34,342.00 4,700.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is inclusive all taxes levy by the government time to time excluding GST	2.49	Per Cubic Meter			
2	Supplying and filling of hard stone for under floor thick at site. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	0.98	Per Cubic Meter			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. - All work up to plinth level 1:1.8 tone Cement (isto four coarse sand) isto eight graded stone aggregate 40 mm (forty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	0.42	Per Cubic Meter			
4	Random rubble masonry with hand stone in foundation and plinth including levelling up with cement concrete 1:6:12 tone cement (isto six coarse sand) isto twelve graded stone aggregate 20 mm (twenty millimeter) nominal size) upto plinth level with Cement mortar 1:6 tone cement (isto six coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	2.49	Per Cubic Meter			

	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (one cement : one part fine sand : two parts graded stone aggregate 20 mm (twenty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.66	Per Cubic Meter			
6	Centering and shuttering including strutting, propping etc. and removal of form for all heights in 1:1:1. Beams, Plinth beams, Girders, Cantilever etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.54	Per Square Meter			
7	Cement concrete flooring 1:2:4 (one cement : two coarse sand : two four graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm (fourty millimeter) thick with 20 mm (twenty millimeter) nominal size stone aggregate. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.81	Per Square Meter			
8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	875.60	Per Kilogramme			
9	Steel work welded in built up sections, framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	420.80	Per Kilogramme			
10	Providing and fixing 0.60mm (zero point six zero millimetre) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester 5 (five) microns over 5 (five) microns primer coating including fixing with screws pre-painted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with pre-painted impact and rubber washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	29.38	Per Square Meter			

Description of work		No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
12	Providing and fixing ridges or hips 60cm (sixty centimetres) overall with 0.6mm (zero point six three millimetre) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (twenty) microns over 5 (five) microns primer coating plus back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with screws pre-painted iron 1 or 1.1 hooks, bolts and nuts 6mm (six millimetre) diameter with pre-painted Gal Impet and bitumen washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	24.00	Per Running Meter			
13	Providing and fixing MS BP sheet 1.66mm to 2mm (one point six six millimetre to two millimetre) thick in eaves board fascia/soffits ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-In-Charge (Base members of steel work shall be measured & paid separately) including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.14	Each			
13	Painting on Steel work with two or more coat applied at 0.90 litre 10 sqm (zero point nine liter per ten square meter) over an under coat of primer applied at 0.80 litre 10 sqm (zero point eight liter per ten square meter) of approved brand and manufactured with Deluxe Multi Surface Paint to give an even shade complete including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.35	Per Cubic metre			
Total						


 B & R Division HP.PWD.
 Joginder Nagar

342.00
 700.00
 months
 T
 P

Job No - 16

SCHEDULE OF QUANTITY

Name of Work : Construction of rain shelter on Baijnath Lad-Bharol Kandapattan road (MDR-43) km 0/0 to 46/0 at Chakrog at Km. 6/650

Name of Work : Construction of rain shelter on Baijnath Lad-Bharol Kandapattan road (MDR-43) km 0/0 to 46/0 at Chakrog at Km. 6/650							Estimate Cost: Earnest Money: Time Limit :	2,34,404.00 4,700.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.49	Per Cubic Meter					
2	Supplying and filling of hard stone for under floor thick at site. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.98	Per Cubic Meter					
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level 1:4.8 (one Cement isto four coarse sand) isto eight graded stone aggregate 40 mm (forty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.42	Per Cubic Meter					
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6.12 (one cement isto six coarse sand isto twelve graded stone aggregate 20 mm (twenty millimeter) nominal size) upto plinth level with . Cement mortar 1:6 (one cement isto six coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.49	Per Cubic Meter					

	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (one cement : one part fine sand : two parts graded stone aggregate 20 mm (twenty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.66	Per Cubic Meter			
6	Centering and shuttering including strutting, propping etc. and removal of form for all heights in 1 Intel. Beams, Plinth beams, Girders, Cantilever etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.54	Per Square Meter			
7	Cement concrete flooring 1:2:4 (one cement : two coarse sand : two four graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm (fourty millimeter) thick with 20 mm (twenty millimeter) nominal size stone aggregate. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.81	Per Square Meter			
8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	875.60	Per Kilogramme			
9	Steel work welded in built up sections, framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	420.80	Per Kilogramme			
10	Providing and fixing 0.6mm (zero point six zero millimeter) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester 5 (five) microns over 5 (five) microns primer coating including fixing with screws prepainted non 1 or 1 hooks, bolts and nuts 6mm (six millimeter) diameter with prepainted Impet and rubber washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	29.38	Per Square Meter			

Description of work

	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Providing and fixing ridges of laps 60cm (sixty centimetre) overall with 0.63mm (zero point six three millimetre) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (twenty) microns over 5 (five) microns primer coating plus back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with screws pre-painted iron 1 or 1.1 hooks, bolts and nuts 6mm (six millimetre) diameter with pre-painted GI limpet and bitumen washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time excluding GST	2.4 00	Per Running Meter			
12 Providing and fixing A/S BP sheet 1.60mm to 2mm (one point six six millimetre to two millimetre) thick in eaves board fascia soffits ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-In-Charge (Base members of steel work shall be measured & paid separately) including carriage of materials within all leads, lifts and other incidental charges The rate is inclusive all taxes levy by the government time to time excluding GST	6 14	Each			
13 Painting on Steel work with two or more coat applied @ 0.90 litre 10 sqm (zero point nine liter per ten square meter) over an under coat of primer applied @ 0.80 litre 10 sqm (zero point eight liter per ten square meter) of approved brand and manufacture with Deluxe Multi Surface Paint to give an even shade complete including carriage of materials within all leads, lifts and other incidental charges The rate is inclusive all taxes levy by the government time to time excluding GST	9 35	Per Cubic metre			
Total					


 Executive Engineer
 B & R Division HP, PW D.
 Jodinder Nagar

ENo. 990.

(72)

1652

DNII DRAFT SCHEDULE OF QUANTITY

Name of Work: Construction of Chakka Jhamechar road upto Neri Via Ali Pabo km 0/00 to 10/00 (Silt Formed Cutting in km 6/895 to 7/129)				Estimate Cost: 4,61,633.00 Earnest Money: 9,200.00 Time Limit: Three Months	
Sl. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words
206	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 163.28 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quantity of cutting in earth work executed Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2155.05	Per cubic metre	214.21	Rupees Two Hundred Fourteen And Paise Twenty One Only
Total					4,61,633.00

Draft schedule of quantity checked and
approved for 4,61,633.00/- (at four last digits are
thousand six hundred thirty three) only

 Executive Engineer

B & R Division HP, PWD.

Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to laying of OFC on Joginder Ngar Sarkaghat Ghumarwin Road km 0/00 to 34/300 (SH: Construction of Retaining wall at km 24/345 to 24/353)				Estimate Cost: Earnest Money: Time Limit :		3,65,365.00 7,300.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	15.84	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	68.08	Per cubic metre			

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads. lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.56	Per cubic metre			
5 Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	22.00	Each			
Total	0.00				


 J. Recurve Engineer
 B & R Division HP, PWD,
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work: Construction of Harabag Bhatwari Lahla Malan Nakehar Kangwan road under Deposit
(SH): Widening of Road between km 1/615 to 1/695)

Estimate Cost: 3,09,444.00
Earnest Money: 6,200.00
Time Limit: Three Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
206	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 95.41 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	1467.88	Per cubic metre			
Total						


 Engineer
 B & R Division HP, PWD,
 Joginder Nagar

675

SCHEDULE OF QUANTITY

Estimated Cost: Rs 422000 00
Earnes Money: Rs 8400 00
Time: One year

Name of work:- (i) Construction of Link Road from village Bhagehar to Bhreau Km. 0/00 to 1/479. (ii) Construction of Link Road from Guini To Prain Km. 0/0 To 5/110. (SH):- Preparation of Digital Plan with including Online Submission of Bhagehar to Bhreau road, and Digital Compensatory afforestation maps of Guini To Prain road under HPPWD Division Joginder Nagar .

S.N Q.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Preparation of plan Geo reference/Digital map and Digital Toposheet Map and Digital Compensatory afforestation maps Global Positioning System Coordinaters collection from site including preparation of KMLs files, with printing and scanning of all papers in PDF files as per requirement and as per direction of Engineer-in-charge. The rate is included all taxes excluding GST levy by the Govt time to time.	1.00			Job	
					Total	


Executive Engineer
B&R Division, HP PWD
Joginder nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to laying of OFC on Rajinath Lad Bharol Kandapattan road km 0/00 to 46/00 (SH: Construction of Retaining wall at km 42/405 to 42/419)				Estimate Cost: Earnest Money : Time Limit :			4,93,957.00 9,900.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 500 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, hauling out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST	14.42	Per cubic metre					
2	Providing and laying cement concrete 1:4:10 (one cement, five sand ten graded crushed broken stone aggregate, 40 mm forty millimeter nominal size) plums and curing complete including the cost of form work in Retaining walls, Breast walls, in or under water complete including, pumping or hauling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work, as per drawings and M.O.R.D technical specifications section 800, 900, 1000 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST	92.26	Per cubic metre					

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204 & 8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.50	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P V C pipe extending through the full width of the structures with slope of 1 (v) : 20 (H) towards drainage face complete as per drawing and M O R D technical specification clauses 614, 709 & 1206 6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals, and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	49.00	Each			
	Total					


 Executive Engineer
 B & R Division HP, PWD
 Jalandhar

SCHEDULE OF QUANTITY

Name of Work : Construction and M/T of Link road Village Chanchar Under SCSP (S.H. : Providing and laying of Wearing (G-II & Cement Concrete pavement at km 2/040 to 2/090)					Estimate Cost: Earnest Money: Time Limit :		1,68,358.00 3,400.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit		Rate		AMOUNT	
					Figures	Words	Rs.	P
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening, binding materials to fillup the interstices of coarse aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause -405 complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.01	Per cubic metre					
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.01	Per Cubic metre					
Total								


 Executive Engineer
 B & R Division HP PWD,
 Jangrider

SCHEDULE OF QUANTITY

(78)

Name of work : Special repair to State Revenue Training Institute at Joginder Nagar Distt. Mandi (H.P.) (S/L: Painting work, Tile work Providing and Fixing Wire Gauge Shutter & Repair of W.S. & S.L. in Dining/ Canteen Hall)					Estimate Cost: Earnest Money: Time Limit:			1,85,687.00 3,700.00 Two Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate	Amount		Rs.	P
					Figures	Words		
1	Painting one coat (excluding priming coat) over previously painted steel and other metal surfaces with Aluminium paint, brushing to give an even shade. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	42.45	Per square metre					
2	Painting one coat (excluding priming coat) over previously painted wood and wood based surfaces with enamel paint to given an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping With white enamel paint. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	511.83	Per square metre					
3	Providing and fixing 40 mm (forty millimetre) thick second class Deodar wood wire gauge shutters using galvanised MS wire gauge of 18 gauge designation 85G) with wire of dia 0.56 mm (Zero decimal five six millimetre) for doors, windows and cleanstory windows including bright finished black enamelled iron hinges with necessary screws as per PWD specification complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.88	Per Square Metre					
4	Wall painting (two coats) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for making the surface. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	217.64	Per square metre					

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Amount Rs. p
				Figures	Words	
5	Finishing wall with weather proof exterior grade emulsion of approved design (Apexuluma) or its equivalent on undecorated wall surfaces (three coats) to give an even shade and final after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	110.82	Per square metre			
6	Painting two or more coats on G.I Sheets with readymix paint of approved brand and manufacture on new work to give an even shade. Readymixed paint green shade. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	665.44	Per square metre			
7	Providing and fixing 10 mm (ten millimeter) thick acid and or alkali resistant tiles of approved make and colour using acid and or alkali resisting mortar bedding, and joints filled with acid and or alkali resisting cement as per IS - 4457, complete as per the direction of Engineer-in- Charge. In dado skirting on 12 mm thick mortar 1:4 (one acid proof cement isto four coarse sand) Acid and alkali resistant tile. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	31.31	Per square metre			
8	Providing and fixing controlled flush, low level cistern made of vitreous china with all fittings complete. 10 (Ten) litre (full flush) capacity-white. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.00	Each			
9	Providing and fixing 75mm (seventy five millimeter) diameter high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc, complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.00	Each			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
10	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm (hundred millimeter) sand cast iron P or S trap, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required. White Vitreous china Orissa pattern W.C. pan of size 580x440 mm (five hundred eighty by four hundred forty millimeter) with integral type foot rests complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	1.00	Each			
Total						


 Executive Engineer
 B & R Division HP, PWID,
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction & M.T on Jeepable link road Badoun to Almerah km 0/00 to 1/00
(SH: Improvement of Formation width by providing Breast wall at km 0/485 to 0/500)

Estimate Cost: 1,97,801.00
Earnest Money: 4,000.00
Time Limit: Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts as acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.13	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1000 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.25	Per cubic metre				


Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5 (one cement five sand ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST	35.40	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P V C pipe extending through the full width of the structures with slope of 1 (v) 20(H) towards drainage face complete as per drawing and MORD technical specification clauses 614, 709 & 1206 6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	28.00	Each			
Total						


 Executive Engineer
 B & R Division HP PWD,
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Petu Nallah to Gudubhi road km 0/00 to 1/500 (SFI: Construction of Retaining wall at km 1/310 to 1/331)					Estimate Cost: 4,96,272,300 Earnest Money: 9,900,000 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of mounds and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.07	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement, five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R D technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	87.57	Per cubic metre			

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	30.87	Per cubic metre			
4	Providing weep-holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C pipe extending through the full width of the structures with slope of 1 in 20 (1 in 20) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST	40.00	Each			
	Total					


 Executive Engineer
 B & R Division HP/PWD,
 Jalandhar Nagar

(81)

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Bashai Drubblle road km 0/00 to 8/00 (S.I:Repair of Pot holes / Patch work at km 0/00 to 8/00)							Estimate Cost: Earnest Money: Time Limit :	4,98,098.00 10,000.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 0.30 kg (zero point three kilogramme) per Sqm. 20 mm thick pre-mix carpet with Bitumen VG-10 @ 1.46 kg (One point four six kilogramme) per Sqm. and seal coat type B with bitumen VG-10 @ 0.68 kg (zero point six eight kilogramme) per Sqm. as per technical specification clause 1904.2, 503 and 508.1 The rate including hauling, carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST	1637.94	Per Square metre					
Total								


Executive Engineer
B & R Division HP PWD.
Ajmer Nagar

(82)

SCHEDULE OF QUANTITY

Name of Work : Construction of Retaining wall at Bagdena road near house of Amar Singh Khadhia under Deposit (Sub Head:- Balance work of Retaining wall at km 0/00 to 0/015)				Estimate Cost: 1,21,722.00 Earnest Money: 2,40,000 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying cement concrete 1:5 (forty millimeters) nominal size 1) plans and curing complete including the cost of form work in Retaining walls, Breast walls, in or under water complete including, pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and AFORED technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	21.60	Per cubic metre			
2	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.5.8 Circular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.80	Per cubic metre			
3	Providing weep holes in brick masonry, stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drainage face complete as per drawing and AFORED technical specifications clause 14, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.00	Each			
Total						

Executive Engineer
B & R Division J.P. P.W.D.
Jharkhand

SCHEDULE OF QUANTITIES

Name of Work : Restoration of rain Damages on Macehval Bharan Bihun km 0/00 to 12/00
 Estimate Cost: 4,68,674.00
 Earnest Money: 9,400.00
 Time Limit : Three Months

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling wedging out of rock where blasting is prohibited) and then intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.20	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 500 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines of grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, haulage and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes shall be removed by suitable version, bailing out or pumping as directed and the area of the foundation or bankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	25.20	Per cubic metre			

S. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P.
1	Providing and laying concrete 1:2:4 (one cement five sand & graded crushed broken stone aggregate) in 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 in 200 towards drainage face complete as per drawings and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. This rate is inclusive of taxes levied by the government time to time excluding GST.	87.00	Per cubic meter			
2	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 in 200 towards drainage face complete as per drawings and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive of taxes levied by the government time to time excluding GST.	54.00	Each			
	Total					


 Executive Engineer
 B & R Division HP, PW D.
 Hyderabad

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Petu Nallah to Guduh road km 0.60 to 1.500
(Sub Head:- Providing and Laying WBM G-II and C C Pavement at km 1.090 to 1.210)

Estimate Cost: 4,92,755.00
Earnest Money: 9,000.00
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and blooming, stone screening, binding materials to fillup the interstices of coarse aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	30.24	Per cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS-383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST	60.48	Per Cubic metre			
Total						


Executive Engineer
B & R Division HP PW D.
Jodhpur Nagar