



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG PH:**

01907-222229 Fax: 222229, e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2023-

14275

Dated:- 22-2-2024

To


The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :-

Regarding publication of Tender on departmental site.

Enclosed please find herewith the copies of Notice Inviting Tender for the loading on departmental web-site before 22.02.2024 as per notification issued by the Pr. Secy.(PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16th July, 2021. It is further intimated that all the works mentioned are of urgent nature.

Encl:- As above.


Executive Engineer,
B&R Division,
HP PWD Karsog



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229, E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division, HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **29.02.2024 upto 11.00 AM** and shall be opened on the same day at **12:00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 28.02.2024** for which the application should reach in this office **upto 1.00 PM 28.02.2024**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Kotlu to Nanj road Km. 0/00 to 6/120 (SH:- C/o R/wall at RD 3/606 to 3/615) Deposit Work/SDF/2023/381	1,08,887/-	2,200/-	One month	350/-
2	R/R damages on Mamail Mehendi road Km. 0/00 to 19/00 (SH:- C/o R/wall at RD 3/648 and 11/645 to 11/549.05) Balance work	2,51,060/-	5,100/-	One month	350/-
3	A/R & M/O various roads under Churag Section Sub Division Churag (SH:- Repair to pot holes at various RDs)	2,99,450/-	6,000/-	One month	350/-
4	A/R & M/O various roads under Churag Sub Division Tattapani Section (SH:- Repair of pot holes in Shimla Mandi via Tattapani road Km. 55/00 to 61/00 and Tattapani to Shakra road Km. 0/00 to 5/00 and Link road to New Bridge at Thalli Km. 0/00 to 0/250 and link road to Harizan Basti upper Balh Km. 0/00 to 0/500)	2,96,599/-	6,000/-	One month	350/-
5	A/R & M/O Shimla Mandi road Km. 60/00 to 80/00 and Chamonalla to Bagshar road km. 0/00 to 3/00 (SH:- Repair of pot holes at various RDs)	1,38,145/-	2,800/-	One month	350/-
6	A/R & M/O Kheel Pangna road Km. 0/00 to 11/600 (SH:- P/L G-III and repair of pot holes in Km. 0/00 to 5/500)	4,95,417/-	9,900/-	One month	350/-
7	A/R & M/O link road to PWD Rest House Pangna Km. 0/00 to 0/225 (SH:- C/o R/wall at RD 0/120 to 0/126)	2,88,190/-	5,800/-	One month	350/-
8	A/R & M/O Shimla Mandi via Tattapani road Km. 90/00 to 115/00 (SH:- P/L G-III and repair of pot holes in Km. 99/00 to 100/00 & 109/00 to 110/00)	4,89,666/-	9,800/-	One month	350/-


9	R/R damages on Karsog Kanda road km. 0/00 to 5/00 (SH:- C/o B/wall at RD 3/420 to 3/445)	4,37,846/-	8,800/-	One month	350/-
10	R/R damages on Thakutthana to Delag road km. 0/00 to 7/100 (SH:- C/o B/wall at RD 2/405 to 2/425)	4,43,228/-	8,900/-	One month	350/-
11	R/R damages on Thakutthana to Delag road km. 0/00 to 7/00 (SH:- C/o R/wall at RD 2/075 to 2/093)	4,67,930/-	9,400/-	One Month	350/-
12	Repair and maintenance of road from Ralla to Saryogi Mandir Mohal Km. 0/00 to 3/00 (SH:- Removal of slips and maintenance of berms at various RDs) Deposit VKV/2023/1191	1,49,692/-	3,000/-	One month	350/-
13	Construction of Chajodi to Gharena road in Gram Panchayat Kao Development Block Karsog Distt. Mandi (SH:- Widening of road in Km. 0/00 to 0/075) MP Lad Deposit Sr. No. 5 dated 15.01.2024	98,573/-	2,000/-	One month	350/-
14	Construction of Ambulance road from Choa Dhar to Paroseri km. 0/00 to 2/00 (SH:- F/C 3/5 mtr wide road in Km. 1/765 to 2/00) DC Deposit/SDP/2022/586	4,14,537/-	8,300/-	One month	350/-
15	Construction of road from Kevidhar to Kotlu via Porla Km. 0/00 to 8/00 (SH:- Widening of road in Km. 0/490 to 0/640)DC Deposit/SDP/2023/1123	3,18,439/-	6,400/-	One month	350/-
16	Constructio of link road from Dateha to Harizan Basti Chova via Kehu road km. 0/00 to 3/470 (SH:- C/o 900mm dia RCC Pipe culvert & wing wall at RD 0/250)	3,32,015/-	9,400/-	One month	350/-
17	C/o & M/T on Alsindi Badeyog via Dhundan road including portion Chanyana to Jassal road km. 0/00 to 11/00 (SH:- Preparation of DPR) NABARD	3,24,500/-	7,000/-	Two Months	350/-
18	R/R damages on Rangan Handpump to Kutaldhar Tatmo Bag road km. 0/00 to 7/00 (SH:- C/o R/wall at RD 0/275 to 0/300) DC Deposit. NDF/2023/1304	4,99,305/-	10,000/-	One month	350/-
19	R/R damages on Tattapani Khanderi Lamshar road Km. 0/00 to 6/500 (SH:- C/o B/wall at RD 6/075 to 6/095) DC Deposit NDF/2023/1303	3,53,501/-	7,100/-	One month	350/-
20	C/o link road from Batoni Gali to Manshanidhar Km. 0/00 to 0/900 (SH:- Widening of road Km. 0/00 to 1/165)	3,72,616/-	7,400/-	One month	350/-
21	Construction of link road Kelodhar to Govt. Degree College Karsog Km. 0/00 to 1/500 (Sub-Head:- Providing and laying 20mm premix carpet in km. 0/00 to 0/750) Under SCDP	4,83,4987 /-	9,700/-	Two Months	350/-
22	Construction of link road Kelodhar to Govt. Degree College Karsog Km. 0/00 to 1/500 (Sub-Head:- Providing and laying 20mm premix carpet in km. 0/750 to 0/500) Under SCDP	4,83,498 /-	9,700/-	Two Months	350/-
23	R/R damags on Salana to Mehandi via Noga Tikri road Km. 0/00 to 4/500 (SH:- Removal of slips at various RDs)	2,66,798/-	5,400/-	One month	350/-
24	R/R damages on Kelodhar Chhatri road km. 0/00 to 19/00 (SH:- C/o R/wall at RD 6/117.50 to 6/121)	2,01,454/-	4,100/-	One month	350/-
25	Repair of road Panvi to Kanyog 0/00 to 3/00 (SH:- Removal of slips at various RDs) DC Deposit NDF/2023/750)	1,80,130/-	3,700/-	One month	350/-

26	Repair of road Chamri to Chakhana km. 0/00 to 3/00 (SH:- Removal of slips at various Rds)DC DepositNDF/2023/751	1,79,825/-	3,600/-	One month	350/-
27	C/o Alsindi Tattapani via Dhundan Km. 0/00 to 5/00 (SH:- C/o 900mm dia RCC Hume pipe culvert at RD 4/00)	2,25,710/-	4,600/-	One month	350/-
28	R/R damages on Mahota Bagshar road Km. 0/00 to 17/00 (SH:- C/o B/wall at RD 9/735 to 9/755)	2,63,297/-	5,300/-	One month	350/-
29	Construction of Salana to Mehendi via Noga Tikri in GP Mehendi road km. 0/00 to 4/500 (SH:- Widening of road in Km. 2/510 to 2/885)	4,66,948/-	9,400/-	One month	350/-
30	Construction of Salana to Mehendi via Noga Tikri in GP Mehendi road km. 0/00 to 4/500 (SH:- Widening of road in Km. 3/480 to 3/750) under SCDP)	4,90,635/-	9,000/-	One month	350/-
31	Construction of link road from Dateha to Harizan Basti Chova via Kehu road km. 0/00 to 3/470 (SH:- Widening of road in Km. 1/150 to 1/600) under SCDP	4,96,846/-	10,000/-	One month	350/-
32	Construction of link road from Dateha to Harizan Basti Chova via Kehu road km. 0/00 to 3/470 (SH:- Widening of road in Km. 1/615 to 1/885) under SCDP	4,99,861/-	10,000/-	One month	350/-
33	Construction of link road from Dateha to Harizan Basti Chova via Kehu road km. 0/00 to 3/470 (SH:- Widening of road in Km. 1/900 to 2/195) under SCDP	4,89,567/-	9,800/-	One month	350/-
34	Construction of Sapnot to Bldonala road Km. 0/00 to 1/00 (SH:- P/L 20mm premix carpet in Km. 0/00 to 0/400) D.C. Deposit	4,05,949/-	8,200/-	Three months	350/-
35	Restoration of rain damages on Tattapani Shakra road Km. 0/00 to 10/00 (SH:-Hiring of JCB for removal of slips)	97,750/-	2,100/-	One month	350/-
36	R/R damages on Tattapani to Shakra road km. 0/00 to 10/00 (SH:- C/o B/wall at RD 2/195 to 2/210)	2,24,886/-	9,900/-	One month	350/-
37	Construction of Salana to Mehendi via Noga Tikri in GP Mehendi road km. 0/00 to 4/500 (SH:- Widening of road in Km. 3/210 to 3/480) under SCDP)	4,98,082/-	10,000/-	One month	350/-
38	R/R damages on Sanarli Karsog road Km. 0/00 to 3/300 (SH:- C/o B/wall at RD 3/035 to 3/050)	1,76,717/-	3,600/-	One month	350/-
39	Restoration of rain damages on Tattapani Shakra road Km. 0/00 to 10/00 (SH:-Hiring of JCB for removal of slips)	97,750/-	2,100/-	One month	350/-
40	Construction of Punni to Naswar road Km. 0/00 to 3/00 (SH:- P/L Kharanja stone soling in Km. 0/200 to 0/615)	4,95,977/-	10,000/-	One month	350/-
41	R/R damages on Makneri to Tharli road Km. 0/00 to 3/00 (SH:- removal of slips at various RDs) Deposit work SDP/2020/404	81,332/-	1,700/-	One month	350/-
42	R/R damages on Kelodhar Sainj road km. 0/00 to 19/00 (SH:- C/o R/wall at RD 15/245 to 15/257)	3,35,699/-	6,800/-	One month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.


3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.


Executive Engineer
B&R Division
HPPWD Karsog,
Distt. Mandi(HP)

No. PW-E-Tender-NIT/23-

Dated:- 

1. Copy to the Director , Information & Publications Department, HP Shimla for favour of publication in one Regional Newspaper and one National Newspaper.
2. Copy to the Superintending Engineer, 1st Circle, HP,PWD, Mandi for information please.
3. The Sub-Divisional Officer (Civil) Karsog, Tehsil Karsog Distt. Mandi HP.
4. The Block Development Officer Karsog , Tehsil Karsog Distt. Mandi HP.
5. All the Assistant Engineers, working under this Division.
6. Copy to Drawing & Account Branch.
7. Notice board of this office.


Executive Engineer,
B&R Division,
HP PWD Karsog



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG PH:**

01907-222229 Fax: 222229, e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2023-
To

14275

Dated:- 22-2-2024


The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :-

Regarding publication of Tender on departmental site.

Enclosed please find herewith the copies of Notice Inviting Tender for the loading on departmental web-site before 22.02.2024 as per notification issued by the Pr. Secy.(PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16th July, 2021. It is further intimated that all the works mentioned are of urgent nature.

Encl:- As above.


Executive Engineer,
B&R Division,
HP PWD Karsog



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division, HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **29.02.2024 upto 11.00 AM** and shall be opened on the same day at **12:00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 28.02.2024** for which the application should reach in this office **upto 1.00 PM 28.02.2024**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Kotlu to Nanj road Km. 0/00 to 6/120 (SH:- C/o R/wall at RD 3/606 to 3/615) Deposit Work/SDF/2023/381	1,08,887/-	2,200/-	One month	350/-
2	R/R damages on Mamail Mehandi road Km. 0/00 to 19/00 (SH:- C/o R/wall at RD 3/648 and 11/645 to 11/549.05) Balance work	2,51,060/-	5,100/-	One month	350/-
3	A/R & M/O various roads under Churag Section Sub Division Churag (SH:- Repair to pot holes at various RDs)	2,99,450/-	6,000/-	One month	350/-
4	A/R & M/O various roads under Churag Sub Division Tattapani Section (SH:- Repair of pot holes in Shimla Mandi via Tattapani road Km. 55/00 to 61/00 and Tattapani to Shakra road Km. 0/00 to 5/00 and Link road to New Bridge at Thalli Km. 0/00 to 0/250 and link road to Harizan Basti upper Balh Km. 0/00 to 0/500)	2,96,599/-	6,000/-	One month	350/-
5	A/R & M/O Shimla Mandi road Km. 60/00 to 80/00 and Chamonalla to Bagshar road km. 0/00 to 3/00 (SH:- Repair of pot holes at various RDs)	1,38,145/-	2,800/-	One month	350/-
6	A/R & M/O Kheel Pangna road Km. 0/00 to 11/600 (SH:- P/L G-III and repair of pot holes in Km. 0/00 to 5/500)	4,95,417/-	9,900/-	One month	350/-
7	A/R & M/O link road to PWD Rest House Pangna Km. 0/00 to 0/225 (SH:- C/o R/wall at RD 0/120 to 0/126)	2,88,190/-	5,800/-	One month	350/-
8	A/R & M/O Shimla Mandi via Tattapani road Km. 90/00 to 115/00 (SH:- P/L G-III and repair of pot holes in Km. 99/00 to 100/00 & 109/00 to 110/00)	4,89,666/-	9,800/-	One month	350/-

9	R/R damages on Karsog Kanda road km. 0/00 to 5/00 (SH:- C/o B/wall at RD 3/420 to 3/445)	4,37,846/-	8,800/-	One month	350/-
10	R/R damages on Thakutthana to Delag road km. 0/00 to 7/100 (SH:- C/o B/wall at RD 2/405 to 2/425)	4,43,228/-	8,900/-	One month	350/-
11	R/R damages on Thakutthana to Delag road km. 0/00 to 7/00 (SH:- C/o R/wall at RD 2/075 to 2/093)	4,67,930/-	9,400/-	One Month	350/-
12	Repair and maintenance of road from Ralla to Saryogi Mandir Mohal Km. 0/00 to 3/00 (SH:- Removal of slips and maintenance of berms at various RDs) Deposit VKV/2023/1191	1,49,692/-	3,000/-	One month	350/-
13	Construction of Chajodi to Gharena road in Gram Panchayat Kao Development Block Karsog Distt. Mandi (SH:- Widening of road in Km. 0/00 to 0/075) MP Lad Deposit Sr. No. 5 dated 15.01.2024	98,573/-	2,000/-	One month	350/-
14	Construction of Ambulance road from Choa Dhar to Paroseri km. 0/00 to 2/00 (SH:- F/C 3/5 mtr wide road in Km. 1/765 to 2/00) DC Deposit/SDP/2022/586	4,14,537/-	8,300/-	One month	350/-
15	Construction of road from Kevidhar to Kotlu via Porla Km. 0/00 to 8/00 (SH:- Widening of road in Km. 0/490 to 0/640)DC Deposit/SDP/2023/1123	3,18,439/-	6,400/-	One month	350/-
16	Constructio of link road from Dateha to Harizan Basti Chova via Kehu road km. 0/00 to 3/470 (SH:- C/o 900mm dia RCC Pipe culvert & wing wall at RD 0/250)	3,32,015/-	9,400/-	One month	350/-
17	C/o & M/T on Alsindi Badeyog via Dhundan road including portion Chanyana to Jassal road km. 0/00 to 11/00 (SH:- Preparation of DPR) NABARD	3,24,500/-	7,000/-	Two Months	350/-
18	R/R damages on Rangan Handpump to Kutaldhar Tatmo Bag road km. 0/00 to 7/00 (SH:- C/o R/wall at RD 0/275 to 0/300) DC Deposit. NDF/2023/1304	4,99,305/-	10,000/-	One month	350/-
19	R/R damages on Tattapani Khanderi Lamshar road Km. 0/00 to 6/500 (SH:- C/o B/wall at RD 6/075 to 6/095) DC Deposit NDF/2023/1303	3,53,501/-	7,100/-	One month	350/-
20	C/o link road from Batoni Gali to Manshanidhar Km. 0/00 to 0/900 (SH:- Widening of road Km. 0/00 to 1/165)	3,72,616/-	7,400/-	One month	350/-
21	Construction of link road Kelodhar to Govt. Degree College Karsog Km. 0/00 to 1/500 (Sub-Head:- Providing and laying 20mm premix carpet in km. 0/00 to 0/750) Under SCDP	4,83,4987 /-	9,700/-	Two Months	350/-
22	Construction of link road Kelodhar to Govt. Degree College Karsog Km. 0/00 to 1/500 (Sub-Head:- Providing and laying 20mm premix carpet in km. 0/750 to 0/500) Under SCDP	4,83,498 /-	9,700/-	Two Months	350/-
23	R/R damags on Salana to Mehandi via Noga Tikri road Km. 0/00 to 4/500 (SH:- Removal of slips at various RDs)	2,66,798/-	5,400/-	One month	350/-
24	R/R damages on Kelodhar Chhatri road km. 0/00 to 19/00 (SH:- C/o R/wall at RD 6/117.50 to 6/121)	2,01,454/-	4,100/-	One month	350/-
25	Repair of road Panvi to Kanyog 0/00 to 3/00 (SH:- Removal of slips at various RDs) DC Deposit NDF/2023/750)	1,80,130/-	3,700/-	One month	350/-


26	Repair of road Chamri to Chakhana km. 0/00 to 3/00 (SH:- Removal of slips at various Rds)DC DepositNDF/2023/751	1,79,825/-	3,600/-	One month	350/-
27	C/o Alsindi Tattapani via Dhundan Km. 0/00 to 5/00 (SH:- C/o 900mm dia RCC Hume pipe culvert at RD 4/00)	2,25,710/-	4,600/-	One month	350/-
28	R/R damages on Mahota Bagshar road Km. 0/00 to 17/00 (SH:- C/o B/wall at RD 9/735 to 9/755)	2,63,297/-	5,300/-	One month	350/-
29	Construction of Salana to Mehendi via Noga Tikri in GP Mehendi road km. 0/00 to 4/500 (SH:- Widening of road in Km. 2/510 to 2/885)	4,66,948/-	9,400/-	One month	350/-
30	Construction of Salana to Mehendi via Noga Tikri in GP Mehendi road km. 0/00 to 4/500 (SH:- Widening of road in Km. 3/480 to 3/750) under SCDP)	4,90,635/-	9,000/-	One month	350/-
31	Construction of link road from Dateha to Harizan Basti Chova via Kehu road km. 0/00 to 3/470 (SH:- Widening of road in Km. 1/150 to 1/600) under SCDP	4,96,846/-	10,000/-	One month	350/-
32	Construction of link road from Dateha to Harizan Basti Chova via Kehu road km. 0/00 to 3/470 (SH:- Widening of road in Km. 1/615 to 1/885) under SCDP	4,99,861/-	10,000/-	One month	350/-
33	Construction of link road from Dateha to Harizan Basti Chova via Kehu road km. 0/00 to 3/470 (SH:- Widening of road in Km. 1/900 to 2/195) under SCDP	4,89,567/-	9,800/-	One month	350/-
34	Construction of Sapnot to Bldonala road Km. 0/00 to 1/00 (SH:- P/L 20mm premix carpet in Km. 0/00 to 0/400) D.C. Deposit	4,05,949/-	8,200/-	Three months	350/-
35	Restoration of rain damages on Tattapani Shakra road Km. 0/00 to 10/00 (SH:-Hiring of JCB for removal of slips)	97,750/-	2,100/-	One month	350/-
36	R/R damages on Tattapani to Shakra road km. 0/00 to 10/00 (SH:- C/o B/wall at RD 2/195 to 2/210)	2,24,886/-	9,900/-	One month	350/-
37	Construction of Salana to Mehendi via Noga Tikri in GP Mehendi road km. 0/00 to 4/500 (SH:- Widening of road in Km. 3/210 to 3/480) under SCDP)	4,98,082/-	10,000/-	One month	350/-
38	R/R damages on Sanarli Karsog road Km. 0/00 to 3/300 (SH:- C/o B/wall at RD 3/035 to 3/050)	1,76,717/-	3,600/-	One month	350/-
39	Restoration of rain damages on Tattapani Shakra road Km. 0/00 to 10/00 (SH:-Hiring of JCB for removal of slips)	97,750/-	2,100/-	One month	350/-
40	Construction of Punni to Naswar road Km. 0/00 to 3/00 (SH:- P/L Kharanja stone soling in Km. 0/200 to 0/615)	4,95,977/-	10,000/-	One month	350/-
41	R/R damages on Makneri to Tharli road Km. 0/00 to 3/00 (SH:- removal of slips at various RDs) Deposit work SDP/2020/404	81,332/-	1,700/-	One month	350/-
42	R/R damages on Kelodhar Sainj road km. 0/00 to 19/00 (SH:- C/o R/wall at RD 15/245 to 15/257)	3,35,699/-	6,800/-	One month	350/-
43	Preparation of Forest Case under FCA, Act 1980 for the construction of Mandpa Gali (Kelodhar) to Shojha via Samsothi, Richhani, Jatho, Kamehri Km. 0/00 to 16/00)	1,94,400/-	4,000/-	Six months	350/-

44	R/R damages on Chouridhar to Kotlu road Km. 0/00 to 7/00(Sh:- Removal of slips at various RDS) Section Kelodhar.	2,13,639/-	4,300/-	One month	350/-
----	--	------------	---------	-----------	-------

TERMS & CONDITIONS:-


1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.


Executive Engineer
B&R Division
HPPWD Karsog,
Distt. Mandi(HP)

Dated:- 

No. PW-E-Tender-NIT/23-

1. Copy to the Director , Information & Publications Department, HP Shimla for favour of publication in one Regional Newspaper and one National Newspaper.
2. Copy to the Superintending Engineer, 1st Circle, HP,PWD, Mandi for information please.
3. The Sub-Divisional Officer (Civil) Karsog, Tehsil Karsog Distt. Mandi HP.
4. The Block Development Officer Karsog , Tehsil Karsog Distt. Mandi HP.
5. All the Assistant Engineers, working under this Division.
6. Copy to Drawing & Account Branch.
7. Notice board of this office.


Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Schedule Of Quantity

Estimated Cost 108887
Earnest Money 2200
Time One Month

Name of Work:- R/R Damages on Kottu to Nainj road km 0/00 to 06/120 (SH:- C/O R/Wall at RD 3/606 to 3/615) Deposit Work SDF /2023/381

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	8.55	Per Cubic Meter	379.90	3248	Rupees Three Thousand Two Hundred Forty Eight and Paise Fourteen Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	18.63	Per Cubic Meter	5140.40	95766	Rupees Ninety Five Thousand Seven Hundred Sixty Five and Paise Sixty Five Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3,8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	5.40	Per Cubic Meter	1277.55	6899	Rupees Six Thousand Eight Hundred Ninety Eight and Paise Seventy Seven Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	8.00	Each	371.75	2974	Rupees Two Thousand Nine Hundred Seventy Four and Paise Zero Only
Total in Figures					108887	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HP PWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Marnail to mehandi road Km.0/00 to 19/00 (SH:- C/O R/Wall at RD 3/648 and 11/645 to 11/649.05) Balance Work

Estimated Cost 251060
Earnest Money 5100
Time One Month

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	32.24	Per Cubic Meter	379.90	12248	Rupees Twelve Thousand Two Hundred Forty Seven and Paise Ninety Seven Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	45.59	Per Cubic Meter	5140.40	234351	Rupees Two Lakhs Thirty Four Thousand Three Hundred Fifty and Paise Eighty Three Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	12.00	Each	371.75	4461	Rupees Four Thousand Four Hundred Sixty One and Paise Zero Only
Total in Figures					251060	
Quoted Rate in Figures					0.00	
Quoted Rate in Words			Select			


Executive Engineer,
Karsog Division,
HPPWD/Karsog.

Percentage Schedule Of Quantity

Estimated Cost 239450
Earnest Money 6000
Time One Month

Name of Work:- A/R & M/O Various roads under Churag Section (Sub- Division Churag (SH: - Repair to Pot Holes at Various RD's)

Sl. No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Repair to Pot Holes and removal of fail material, trimming the side to vertical and leveling the bottom, cleaning the same with compressed air or any appropriate method filled with 75 mm B.M Applying bitumen emulsion prime coat at the bottom and bitumen emulsion tack coat on side and on bottom as per technical specification clauses 502, 503, and 504 as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals	820.41	Per Cubic Meter	365.00	239450	Rupees Two Lakhs Ninety Nine Thousand Four Hundred Forty Nine and Paise Sixty Five Only
Total In Figures					239450	
Quoted Rate In Figures			Select		0.00	
Quoted Rate In Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

21

Percentage Schedule Of Quantity

Estimated Cost 296599
Earnest Money 6000
Time One Month

Name of Work:- A/R & M/O Various road under Churrag Sub- Division Tattapani section (SH : - Repair to Pot Holes in Shimla Mandi Via Tattapani road km. 55/00 to 61/00 and Tattapani to Shakra road km 0/00 to 5/00 and Link road to New Bridges at Thalli km 0/00 to 0/250 and Link road to Harizan Basti upper Balh km 0/00 to 0/500)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Repair to Pot Holes and removal of fail material, inriming the side to vertical and leveling the bottom, cleaning the same with compressed air or any appropriate method filled with 75 mm B.M Applying bitumen emulsion prime coat at the bottom and bitumen emulsion Yack coat on side and on bottom as per technical specification clauses 502, 503, and 504 as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and otehr incidentals	812.60	Per Square Meter	365.00	296599	Rupees Two Lakhs Ninety Six Thousand Five Hundred Ninety Nine and Paise Zero Only
Total in Figures					296599	
Quoted Rate in Figures					0.00	
Quoted Rate in Words						


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 138145
Earnest Money 2800
Time One Month

Name of Work:- A/R & M/O Shimla Mandi road km 60/00 to 80/00 and Chamonnalla to Bagshar road km 0/00 to 3/00 (SH: - Repair to Pot Holes at Various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Repair to Pot Holes and removal of fail material,trimming the side to vertical and leveling the bottom, cleaning the same with compressed air or any appropriate method filled with 75 mm B. M. Applying bitumen emulsion prime coat at the bottom and bitumen emulsion (yack coat on side and on bottom as per technical specification clauses 502, 503, and 504 as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and othr incidentals	378.48	Per Cubic Meter	365.00	138145	Rupees One Lakh Thirty Eight Thousand One Hundred Forty Five and Paise Twenty Only
Total in Figures					138145	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- A/R & M/O Kheel Pangna road km. 0/00 to 11/600 (SH:- P/L G-III and repair pot holes in km. 0/00 to 5/500)

Estimated Cost 495417
Earnest Money 9900
Time One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Providing, laying spreading and compacting stone aggregates of specific sizes to water bond macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 Kn in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices to coarse aggregate, watering and compacting to the required density grading 3 as per technical specification clause 405 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	6.20	Per Cubic Meter	3212.41	19917	Rupees Nineteen Thousand Nine Hundred Sixteen and Paise Ninety Four Only
2	Repair to Pot Holes and removal of loose material, trimming the side to vertical and leveling the bottom, cleaning of surface by providing tack coat 20mm thick premix carpet and seal coat type B specification clause 1904.2.503 and 508.1 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals	1365.79	Per Square Meter	348.15	475500	Rupees Four Lakhs Seventy Five Thousand Four Hundred Ninety Nine and Paise Seventy Eight Only
Total in Figures					495417	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 288190
Earnest Money 5800
Time One Month

Name of Work:- A/R & M/O link road to PWD Rest House km 0/00 to 0/225 (SH:- C/O R/Wall at RD 0/120 TO 0/126)

Page 9

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Excavation in soil in hilly area by mechanical mean including cutting and trimming of side slope and disposing of excavated earth with any lift and any lead as per technical specification clause 1603.1 as per direction of engineer in charge with in all lead and lift As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	10.8	Per Cubic Meter	207.20	2238	Rupees Two Thousand Two Hundred Thirty Seven and Paise Seventy Six Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.50	Per Cubic Meter	379.90	6268	Rupees Six Thousand Two Hundred Sixty Eight and Paise Thirty Five Only
3	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	50.64	Per Cubic Meter	5140.40	260310	Rupees Two Lakhs Sixty Thousand Three Hundred Nine and Paise Eighty Five Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	15.00	Per Cubic Meter	371.75	5576	Rupees Five Thousand Five Hundred Seventy Six and Paise Twenty Five Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.80	Per Cubic Meter	1277.55	13798	Rupees Thirteen Thousand Seven Hundred Ninety Seven and Paise Fifty Four Only
Total in Figures					288190	
Quoted Rate in Figures					0.00	
Quoted Rate in Words		Select				


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 489666
Earnest Money 9800
Time One Month

Name of Work:- A/R & M/O Shimla Mandi Via Tattapani road km. 90/00 to 115/00 (SH:- P/L G-II and repair pot holes in km. 99/00 to 100/00 & 109/00 to 110/00)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Providing, laying spreading and compacting stone aggregates of specific sizes to water bond macadam specification uncluding spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kn in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices to coarse aggregate, watering and compacting to the required density grading 3 as per technical specification clause 405 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	33.51	Per Cubic Meter	3212.41	107648	Rupees One Lakh Seven Thousand Six Hundred Forty Seven and Paise Eighty Five Only
2	Repair to Pot Holes and removal of loose material trimming the side to vertical and leveling the bottom, cleaning of surface bu providing tack coat 20mm thick premix carpet and sealn coat type B sepcification clause 1904 2.503 and 508.1 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals	1097.28	Per Square Meter	348.15	382018	Rupees Three Lakhs Eighty Two Thousand Eighteen and Paise Three Only
Total in Figures					489666	
Quoted Rate in Figures					0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Karsog Kanda road km. 0/00 to 5/00 (SH:- C/O B/Wall at RD 3/420 TO 3/445)

Estimated Cost 437846
Earnest Money 8800
Time One Month

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Excavation in soil in hilly area by mechanical mean including cutting and trimming of side slope and disposing of excavated earth with a lift upto 1.5 mtrs and a lead upto 20 mtrs. as per technical specification clause 1603.1 as per direction of engineer in charge with in all lead and lift As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	63.00	Per Cubic Meter	207.20	13054	Rupees Thirteen Thousand Fifty Three and Paise Sixty Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	80.83	Per Cubic Meter	5140.40	415499	Rupees Four Lakhs Fifteen Thousand Four Hundred Ninety Eight and Paise Fifty Three Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	25.00	Each	371.75	9294	Rupees Nine Thousand Two Hundred Ninety Three and Paise Seventy Five Only
Total in Figures					437846	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						



Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Thakurthana to Delag road km 0/00 to 7/100 (SH:- C/O B/Mail at RD 2/405 to 2/425)

Estimated Cost 443228
Earnest Money 8900
Time One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	52.40	Per Cubic Meter	379.90	19907	Rupees Nineteen Thousand Nine Hundred Six and Paise Seventy Six Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Noimnal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	81.05	Per Cubic Meter	5140.40	416629	Rupees Four Lakhs Sixteen Thousand Six Hundred Twenty Nine and Paise Forty Two Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	18.00	Each	371.75	6692	Rupees Six Thousand Six Hundred Ninety One and Paise Fifty Only
Total in Figures					443228	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Thakurthana to Delay road km 0/00 to 7/00 (SH:- C/O R/Wall at RD 2/075 TO 2/093)

Estimated Cost
Earnest Money
Time

467930
9400
One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305, 1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	52.20	Per Cubic Meter	379.90	19831	Rupees Nineteen Thousand Eight Hundred Thirty and Paise Seventy Eight Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	81.95	Per Cubic Meter	5140.40	421256	Rupees Four Lakhs Twenty One Thousand Two Hundred Fifty Five and Paise Seventy Eight Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	32.00	Each	371.75	11896	Rupees Eleven Thousand Eight Hundred Ninety Six and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3,8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	11.70	Per Cubic Meter	1277.55	14947	Rupees Fourteen Thousand Nine Hundred Forty Seven and Paise Thirty Three Only
Total in Figures					467930	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	


 Executive Engineer,
 Karsog Division,
 HPPMD, Karsog.

Percentage Schedule Of Quantity

Name of Work : Repair and Maintenance of road from Raila to Saryogi Mandir Mohal km. 0/00 to 3/00 (SH:- Removal of slips and maintenance of berms at Various RD's) Deposit VKV/2023/191

Estimated Cost 149692
Earnest Money 3000
Time One Month

Sr No	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals	1320.00	Per Running Meter	21.60	28512	Rupees Twenty Eight Thousand Five Hundred Twelve and Paise Zero Only
2	Removal of land slide slip clearance -Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	881.95	Per Square Meter	137.40	121180	Rupees One Lakh Twenty One Thousand One Hundred Seventy Nine and Paise Ninety Three Only
Total in Figures					149692	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPMD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98573
Earnest Money 2000
Time One Month

Name of Work:- Construction of Chajodi to Gharena road in Gram Panchayat Kao Developmental Block Karsog Distt. Mandi (SH:- Widening of road in km 0/00 to 0/075)
MPLAD Deposit Sr. No. 5 Dated - 15.01.2024

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 23.75 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.7124/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	405.92	Per Cubic Meter	242.84	98573.00	Ruppes Nirety Eight Thousand Five Hundred Seventy Three and Paise Zero Only
Total in Figures					98573.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPWMD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost Rs.
Earnest Money cost Rs.
Time

414537
8300
One Month

Name of Work:- Construction of Ambulance road from Choa Dhar to Paroseri km 0/00 to 2/00 (SH:- F/C 3/5 Mtr wide road in km 01/765 to 02/00) DC Deposit /SDP/2022/586

Sr.No.	Description Work	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 171.24 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 51373/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1317.25	Per Cubic Meter	314.70	414537.00	Rupees Four Lakhs Fourteen Thousand Five Hundred Thirty Seven and Paise Zero Only
Total in Figures					414537.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPRMD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost Rs.
Earnest Money cost Rs.
Time

318439
6400
One Month

Name of Work:- Construction of road from Kevidhar to Kotlu Via Porta km 0/00 to 8/00 (SH:- Widening of road in km. 00/490 to 00/640) DC Deposit/SDP/2023/1123

Sr.No.	Description Work	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 113.35 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 34006/- only, shall be done on pro rata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1062.68	Per Cubic Meter	299.66	318439.00	Rupees Three Lakhs Eighteen Thousand Four Hundred Thirty Nine and Paise Zero Only
Total in Figures					318439.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money

332015
9400

Time

One Month

Name of Work:- Construction of link road from Dateha to Harizan Basti Chova Via Kahu road km. 0/0 to 03/470 (SH:- C/O 900mm Dia RCC Pipe Culvert & Wing Wall at RD 00250)

Sr.No	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals	51.16	Per Cubic Meter	379.50	19436	Rupees Nineteen Thousand Four Hundred Thirty Five and Paise Sixty Eight Only
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 Nominal mix 1:6:12 (one cement, six sand, twelve graded stone aggregate 40mm (four millimeter) nominal size as per direction of engineer in charge including cartage of materials within all lead and lifts and other incidentals As per direction of Engineer-in-Charge including cartage of materials within all leads and lifts and other incidentals	2.02	Per Cubic Meter	4832.00	9761	Rupees Nine Thousand Seven Hundred Sixty and Paise Sixty Four Only
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 Nominal mix 1:5:10 (one cement, five sand, ten graded stone aggregate 40mm (four millimeter) nominal size as per direction of engineer in charge including cartage of materials within all lead and lifts and other incidentals as per direction of Engineer-in-Charge including cartage of materials within all leads and lifts and other incidentals	47.93	Per Cubic Meter	5140.40	246379	Rupees Two Lakhs Forty Six Thousand Three Hundred Seventy Nine and Paise Thirty Seven Only
4	Providing and laying reinforced concrete pipe NP2 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per clause 1106as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Meter	5437.60	40782	Rupees Forty Thousand Seven Hundred Eighty Two and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	7.60	Per Cubic Meter	1277.55	9709	Rupees Nine Thousand Seven Hundred Nine and Paise Thirty Eight Only
6	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of (1v):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including cartage of materials within all leads and lifts and other incidentals.	16.00	Each	371.75	5948	Rupees Five Thousand Nine Hundred Forty Eight and Paise Zero Only
Total in Figures					332015	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Secudule Of Quantity

Name of Work:- C/O & MT on Alsindi Badeyog via Dhundhan road including Portion Chanyana to Jassal Road km 0/00 to 11/00(SH:-Preparation of DPR) Under UABR

Estimated Cost 324500
Earnest Money 7000
Time Two Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Total Amount with all taxes	Total Amount with all taxes
1	Surveying and investigation for Preparation of menscript copy of detailed Estimate i.c Cross-sections, plan, Preparation of Detailed Estimate in the Shape of menscript copy duly approved from the Cricle Office & Chief office. Preparation of approved copies of Detailed estimate along with relevant working drawings(Five sets of DPRs and five additional sets of working drawing complete) and soft copies in the form of compact Disc (C.D) of blew mentioned works including Estimate and Drawings)	11.00	Per kilo meter	29500.00	324500	Rupees Three Lakhs Twenty Four Thousand Five Hundred and Paise Zero Only
Total In Figures					324500.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			



Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 499305
Earnest Money 10000
Time One Month

Name of Work:- R/R damages on Rangan Handpump to Kutal Dhar Tatmo Bag road km. 0/00 to 7/00 (SH:- C/O R/Wall at Rd 0/275 TO 0/300) DC Deposit :NDF/2023/1304

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to any lead dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto any depth or as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	34.75	Per Cubic Meter	379.90	13202	Rupees Thirteen Thousand Two Hundred One and Paise Fifty Two Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including cartage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	88.50	Per Cubic Meter	5140.40	454925	Rupees Four Lakhs Fifty Four Thousand Nine Hundred Twenty Five and Paise Forty Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	17.13	Per Cubic Meter	1277.55	21884	Rupees Twenty One Thousand Eight Hundred Eighty Four and Paise Forty Three Only
4.	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	25.00	Each	371.75	9294	Rupees Nine Thousand Two Hundred Ninety Three and Paise Seventy Five Only
Total in Figures					499305	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HRPMD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money

353501
7100

Time

One Month

Name of Work:- R/R damages on Tattapani Khanderi Lamshar soad km 0/00 to 6/500 (SH:- C/O B/Wall at Rd 6/075 to 6/095) DC Deposit .NDF/2023/1303

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation by mechanical means(hydraulic excavator)/manual means in foundation trenches of drain (not exceeding 1.5 meter in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, life upto 1.5 m, including gaffing out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m, with in all lead and lift As per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	49	Per Cubic Meter	195.00	9555	Rupees Nine Thousand Five Hundred Fifty Five and Paise Zero Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305, 1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to any lead dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto any depth or as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	15.00	Per Cubic Meter	379.90	5699	Rupees Five Thousand Six Hundred Ninety Eight and Paise Fifty Only
3	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including cartage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	64.50	Per Cubic Meter	5140.40	331556	Rupees Three Lakhs Thirty One Thousand Five Hundred Fifty Five and Paise Eighty Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	18.00	Each	371.75	6692	Rupees Six Thousand Six Hundred Ninety One and Paise Fifty Only
Total in Figures					353501	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	


Executive Engineer,
Karsog Division,
MPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 372616
Earnest Money 7400
Time One Month

Name of Work:- C/O Link road from Batoni Gali to Manshanidhar km 0/00 to 0/900(SH:-Widening of road km 0/00 to 1/165)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 132.63 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 39789/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1243.47	Per Cubic Meter	299.66	372616	Rupees Three Lakhs Seventy Two Thousand Six Hundred Sixteen and Paise Zero Only
Total in Figures					372616	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPPWD, Karsog.
47

Tender Inviting Authority: Executive Engineer, HP.PWD, Division Karsog

Percentage Schedule of Quantity

Name of Work: Construction of link road Kelodhar to Govt. Degree College Karsog Km. 0/00 to 1/500 (Sub Head:- Providing and laying 20 mm premix carpet in Km. 0/00 to 0/750) under SCDP

Contract No:

Name of the Bidder/
Bidding Firm /
Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	RATE with all taxes including GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST In Words
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
1	Providing, laying and rolling or open-graded premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm to 5.6mm (Thirteen point two millimeter to five point six millimeter) aggregates either using penetration grade bitumen VG-10/S-90 previously prepared base, including mixing in a suitable plant, laying and rolling with three wheel 80-100KN static roller capacity, finished to required level and grades to be followed by seal coat of either Type-B as per technical specification clause 508 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	4	5	6	53	55
		2401.88	Per Square Meter	201.30	483498.44	INR Four Lakh Eighty Three Thousand Four Hundred & Ninety Eight and Paise Forty Four Only
Total in Figures					483498.44	#VALUE!
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only

Estimate of cost :- 483,498/-
Earned money :- 9700/-
Time :- two months


Executive Engineer
Karsog Division
HP PWD Karsog

Tender Inviting Authority: Executive Engineer, HP.PWD. Division Karsog

Name of Work: Construction of link road Kelodhar to Govt. Degree College Karsog Km. 0/00 to 1/500 (Sub Head:- Providing and laying 20 mm premix carpet in Km. 0/750 to 1/500) under SCDP

Contract No:

Name of the Bidder/ Bidding Firm / Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	RATE with all taxes including GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST In Words
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
1	1	4	5	6	53	55
1	Providing, laying and rolling or open-graded premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm to 5.6mm (Thirteen point two millimeter to five point six millimeter) aggregates either using penetration grade bitumen VG-10/S-90 previously prepared base, including mixing in a suitable plant, laying and rolling with three wheel 80-100KN static roller capacity, finished to required level and grades to be followed by seal coat of either Type-B as per technical specification clause 508 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	2401.88	Per Square Meter	201.30	483498.44	INR Four Lakh Eighty Three Thousand Four Hundred & Ninety Eight and Paise Forty Four Only
Total in Figures					483498.44	#VALUE!
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	

Percentage Schedule of Quantity

Estimate cost:- 4,83,498
Garnest money :- 9700
time :- two months

Executive Engineer
Karsog Division
HPPWD Karsog

Percentage Schedule Of Quantity

Estimated Cost 266798
Earnest Money 5400
Time One Month

Name of Work:- R/R damages on Salana to Mehandi Via Noga Tikri road km 0/00 to 4/500 (SH:- Removal of slips at Varios RD's)

Sl. No.	Sub-Head and items of works.	No. Of Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	2110.74	Per Cubic Meter	126.40	266798	Rupees Two Lakhs Sixty Six Thousand Seven Hundred Ninety Seven and Paise Fifty Three Only
Total in Figures					266798	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 201454
Earnest Money 4100
Time One Month

Name of Work:- R/R Damages on Kelodhar Chhatri road km 0/00 to 19/00 (SH:- C/O R/Wall at RD 6/117.50 to 6/121)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.70	Per Cubic Meter	379.90	5964.00	Rupees Five Thousand Nine Hundred Sixty Four and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	35.42	Per Cubic Meter	5140.40	182073.00	Rupees One Lakh Eighty Two Thousand Seventy Three and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of (1/1) 20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	8.00	Each	371.75	2974.00	Rupees Two Thousand Nine Hundred Seventy Four and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204, 3, 8 or as per direction of engineer in charge including carriage of materials within in all lead and lifts and other incidentals.	7.56	Per Cubic Meter	1381.34	10443.00	Rupees Ten Thousand Four Hundred Forty Three and Paise Zero Only
Total in Figures					201454.00	
Quoted Rate In Figures					0.00	
Quoted Rate In Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 180130
Earnest Money 3700
Time One Month

Name of Work:- Repair of road Panvi to Kanyog 0/00 to 3/00 (SH:- Removal of slips at various RD's) DC Deposit NDF/2023/750

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1425.08	Per Cubic Meter	126.40	180130.00	Rupees One Lakh Eighty Thousand One Hundred Thirty and Paise Zero Only
Total in Figures					180130.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words		Zero and Paise Zero Only				


Executive Engineer,
Karsog Division,
HRPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 179825
Earnest Money 3600
Time One Month

Name of Work:- Repair of road Chamri to Chakhana km 0/00 to 3/00 (SH:- Removal of slips at various RD's) DC Deposit NDF/2023/751

Sr No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 16.1.1 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1422.67	Per Cubic Meter	126.40	179825.00	Rupees One Lakh Seventy Nine Thousand Eight Hundred Twenty Five and Paise Zero Only
Total in Figures					179825.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Schedule of Quantity

Estimated Cost
Earnest Money
Time

225710
4600
One month

Name of Work:-C/O Aisindi Tattapani via Dhundhan Km. 0/00 to 5/00 (SH:- C/O 900 mm dia RCC Hume Pipe culvert at RD 4/00)

Sr.No.	Sub-Head and Items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	In words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	49.33			Per Cubic Meter	
2	Providing and laying concrete for pain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	27.76			Per Cubic Meter	
3	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per clause 1106as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50			Running Metre	
4	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	12.00			Each	
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.91			Per Cubic Meter	
	Total :-					


 Executive Engineer,
 Karsog Division,
 HBPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 263297
Earnest Money 5300
Time One Month

Name of Work:- R/R Damages on Mahota Bagshar road km 0/00 to 17/00 (SH:- C/O B/Wall at RD 9/735 to 9/755)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in upot any lead and technical specification clause 1603.1 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	33.60	Per Cubic Meter	208.15	6994	Rupees Six Thousand Nine Hundred Ninety Three and Paise Eighty Four Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	8.60	Per Cubic Meter	379.90	3267	Rupees Three Thousand Two Hundred Sixty Seven and Paise Fourteen Only
3	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	47.20	Per Cubic Meter	5140.40	242627	Rupees Two Lakhs Forty Two Thousand Six Hundred Twenty Six and Paise Eighty Eight Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (h) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	28.00	Each	371.75	10409	Rupees Ten Thousand Four Hundred Nine and Paise Zero Only
Total in Figures					263297	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost Rs. 466948
 Earnest Money cost Rs. 9400
 Time One Month

Name of Work:- Construction of Salana to Mehandi Via Noga Tikri In G.P. Mehandi road km 0/00 to 4/500 (SH:- Widening of road in km. 2/510 to 2/885) under SCDP

Sr.No.	Description Work	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in Rupees Four Lakhs Sixty Six Thousand Nine Hundred Forty Eight and Paise Zero Only
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 189.18 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 56753/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1736.64	Per Cubic Meter	268.88	466948.00	
Total in Figures					466948.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule of Quantity

Name of Work:- Construction of Salana to Mehandi Via Noga Tikri in G.P. Mehandi road km 0/00 to 4/500 (SH:- Widening of road in km. 3/480 to 3/750) under SCDP

Estimated Cost Rs.
Earnest Money cost Rs.
Time

490635
9900
One Month

Sr.No.	Description Work	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 214.36cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 64308/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1740.95	Per Cubic Meter	281.82	490635.00	Rupees Four Lakhs Ninety Thousand Six Hundred Thirty Five and Paise Zero Only
Total in Figures					490635.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 J.P.P.W.D., Karsog.

Percentage Schedule of Quantity

Estimated Cost Rs.
Earnest Money cost Rs.
Time

496846
10000
One Month

Name of Work:- Construction of link road from Dateha to Harizan Basti Chova Via Kethu road Km. 0/00 to 03/470 (SH:- Widening of road in Km. 1/150 to 1/600) under SCDP

Sr.No.	Description Work	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in Rupees Four Lakhs Ninety Six Thousand Eight Hundred Forty Six and Paise Zero Only
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 242.12 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 72636/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2342.84	Per Cubic Meter	212.07	496846.00	
Total in Figures					496846.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPMD, Karsog.

Percentage Schedule of Quantity

Estimated Cost Rs. 499861
Earnest Money cost Rs. 10000
Time One Month

Name of Work:- Construction of link road from Dateha to Harizan Basti Chova Via Kahu road Km. 0/00 to 03/470 (SH:- Widening of road in km. 1/615 to 1/885) under SCDP

Sr.No.	Description Work	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 249.17 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 74751/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2337.00	Per Cubic Meter	213.89	499861.00	Rupees Four Lakhs Ninety Nine Thousand Eight Hundred Sixty One and Paise Zero Only
Total in Figures					499861.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost Rs.
Earnest Money cost Rs.
Time

489567
9800
One Month

Name of Work:- Construction of link road from Dateha to Harizan Basti Chova Via Kahu road Km. 0/00 to 03/470 (SH:- Widening of road in km. 1/900 to 2/195) under SCDP					
Sr.No.	Description Work	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 244.11 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 73234/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2288.55	Per Cubic Meter	213.92	489567.00
Total in Figures					489567.00
Quoted Rate in Figures			Select		0.00
Quoted Rate in Words					


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 405949
Earnest Money 8200
Time Three Months

Name of Work :- Construction of Sapnot to Baldonalia road Km. 0/00 to 1/00 (SH:- P/L 20 mm premix carpet in Km. 0/00 to 0/400) D.C. Deposit

Sl.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Providing and applying primer coat with paving bitumen of VG-10 grade conforming to IS:73 to be applied by heating in oil fired & self propelled or towed bitumen boiler and spraying the material uniformly 0.70 to 1.00 Kg per sqm (zero point seven zero to one point zero Kilogram per squaremetre) on the prepared bituminous surface cleared with hydraulic broom or as per direction of Engineer-in-Charge including cartage of material within all leads, lifts and other incidentals.	1281.00	Per Square Meter	48.70	62385.00	Rupees Fourteen thousand four hundred sixty five only
2	Providing, laying and rolling or open-graded premix carpet of 20mm (Twenty millimeter) thickness composed of 13.2 mm to 5.6 mm (thirteen point two millimeter to five point six millimeter) aggregates either using penetration grade bitumen VG-10/S-90 previously prepared base, including mixing in a suitable plant, laying and rolling with three wheel 80-100 KN static roller capacity, finished to required level and grades to be followed by seal coat of either Type-B as per technical specification clause 508 or as per direction of Engineer-in-Charge including cartage of material within all leads, lifts and other incidentals.	1281.00	Per Square Meter	196.35	251524.00	Rupees Two Lakhs Fifty One Thousand Five Hundred Twenty Four and Paise Zero Only
3	Providing, laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type-B as per technical specification clause-510 or as per direction of Engineer-in-Charge including cartage of material within all leads, lifts and other incidentals.	1281.00	Per Square Meter	71.85	92040.00	Rupees Ninety Two Thousand Forty and Paise Zero Only
Total In Figures			Select		405949.00	
Quoted Rate In Figures					0.00	
Quoted Rate In Words						


Executive Engineer,
Karsog Division,
HRPWD, Karsog.

Schedule Of Quantity

Name of work: <i>K.R. Damages on Link road to Village Parlog km. 12 to 24</i> <i>Chamkema to Masal road km. 10 to 24</i> <i>(SH - Hiring of JCB for removal of slips)</i>							
						Estimated Cost:- 97,750.00	
						Earnest Money:- 2,100.00	
						Time allowed : One Months	
S.No	Description of Work	No. of Qty.	Rate		Unit	Amount	
			In figures	In words			
1		3	4	5	6	7	8
1.00	Hiring of JCB/excavator for removal of slips road side berms, katcha drain and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction and entire satisfactions of Engineer in Charge. any loss to the public/private property and accident etc. the contractor is fully responsible during the execution of work. the fuel and operation staff for the machine and repair charges of machinery during the execution of work shall be borne by the contractor. the useful materials shall be stacked along the road side as per the direction of Engineer in charge.	85.00	hours	1150.00	Rupees One thousand one hundred fifty and paise nil only.	per hour	97750.00
Amount Quoted by the Contractor in percentage						Rs.	97750
Conditions:- (i) All the materials will be procured by the contractor himself and bills will be submitted.							

[Signature]

[Signature]

Assistant Engineer
Churag Sub Division
HPPWD Churag

[Signature]


Executive Engineer
Karsog Division
HPPWD Karsog

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time
224886
9900
One Month

Name of Work :- R/R Damages on Tattapani to Shakra road Km. 0/00 to 10/00 (SH:- C/O BMail at RD 2/195 to 2/210)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Excavation in soil in hilly area by mechanical mean including cutting and trimming of side slope and disposing of excavated earth with any lift and any lead as per mechanical specification clause 1603.1 as per direction of engineer in charge with in all lead and lift As per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	14.25	Per Cubic Meter	208.15	2966	Rupees Fourteen thousand four hundred sixty five only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shooting and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in- Charge including cartage of material within all leads and lifts and other incidentals.	14.55	Per Cubic Meter	379.90	5528	Rupees Five thousand Five Hundred Twenty Eight and Paise Zero Only
3	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including cartage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	40.55	Per Cubic Meter	5140.40	208957	Rupees Two Lakhs Eight Thousand Nine Hundred Fifty Seven and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only
Total In Figures					224886	
Quoted Rate In Figures					0.00	
Quoted Rate In Words						


 Executive Engineer,
 Karsog Division,
 HPBW, Karsog.

Percentage Schedule of Quantity

Estimated Cost Rs.
Earnest Money cost Rs.
Time

498082
10000
One Month

Name of Work:- Construction of Salana to Mehandi Via Noga Tikri in G.P. Mehandi road km 0/00 to 4/500 (SH:- Widening of road in km. 3/210 to 3/480) under SCDP						
Sr.No.	Description Work	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in Rupees Four Lakhs Ninety Eight Thousand Eighty Two and Paise Zero Only
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 186.34 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 55902/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1834.42	Per Cubic Meter	271.52	498082.00	
Total in Figures					498082.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 176717
Earnest Money 3600
Time One Month

Name of Work :- R/R Damages on Sanarli Karsog road Km. 0/00 to 3/300 (SH:- C/O B/Wall at RD 3/035 to 3/050)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	18.00	Per Cubic Meter	379.90	6838	Rupees Six Thousand Eight Hundred Thirty Eight and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including cartage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in-Charge including cartage of materials within all leads and lifts and other incidentals.	32.18	Per Cubic Meter	5140.40	165418	Rupees One Lakh Sixty Five Thousand Four Hundred Eighteen and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including cartage of materials within all leads and lifts and other incidentals.	12.00	Each	371.75	4461	Rupees Four Thousand Four Hundred Sixty One and Paise Zero Only
Total In Figures					176717	
Quoted Rate In Figures					0.00	
Quoted Rate In Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Schedule Of Quantity

Name of work:- *Restoration of drain Damages on Tattapani Shakra road Km. 0 to 14*
(Sfr- Hiring of JCB for removal of Slips)

Estimated Cost:- 97,750.00
 Earnest Money:- 2,100.00

Time allowed : One Months

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1.00	Hiring of JCB/excavator for removal of slips road side berms, katcha drain and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction and entire satisfactions of Engineer in Charge. any loss to the public/private property and accident etc. the contractor is fully responsible during the execution of work. the fuel and operation staff for the machine and repair charges of machinery during the execution of work will be borne by the contractor. the useful materials shall be stacked along the road side as per the direction of Engineer in charge.	85.00	hours	1150.00	Rupees One thousand hundred fifty and paise nil only	per hour	97750.00
	Amount Quated by the Conctrator in percentage					Rs.	97750
	Conditions:- (i) All the materials will be procured by the contractor himself and bills will be submitted.						

Junior Engineer
H.P.P.W.D.
Section - Tattapani

Executive Engineer
Karsog Division
HPPWD, Karsog

Percentage Schedule Of Quantity

Name of Work:- Construction of Punni to Naswar road km 0/00 to 3/00 (SH:- P/L Kharanja Stone Soling in km 0/200 to 0/615)

Estimated Cost
Earnest Money
Time
495977
10000
One Month

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	218.96	Per Cubic Meter	379.90	83183	Rupees Eighty Three Thousand One Hundred Eighty Two and Paise Ninety Only
2	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for sub-graded to be paid for separately depending upon the classification of Engineer-in-Charge within all leads and lifts and other incidentals.	1459.76	Per Square Meter	1.91	2788	Rupees Two Thousand Seven Hundred Eighty Eight and Paise Fourteen Only
3	Consolidation of sub-grade with road roller including making good the undulation etc. with earth or quarry soil etc. and re-rolling the sub-grade completed as per HP.PWD. Specifications as per direction of Engineer-in-Charge within all leads and lifts and other incidentals.	1459.76	Per Square Meter	2.59	3781	Rupees Three Thousand Seven Hundred Eighty and Paise Seventy Seven Only
4	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidations with power road roller to the requested gradient and corber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HPPWD specification. 100 mm (one hundred millimetre) spread thickness (finished work including materials and labour) within all leads and lifts and other incidentals as per direction of Engineer-in-Charge within all leads and lifts and other incidentals.	218.93	Per Cubic Meter	1855.50	406225	Rupees Four Lakhs Six Thousand Two Hundred Twenty Four and Paise Sixty One Only
Total in Figures					495977	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time
81332
1700
One Month

Name of Work:- R/R Damages on Makneri to Tharli road km 0/00 to 3/00 (SH:- Removal of slips at various Rd's) Deposit work SDP/2020/404

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance.-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals.	643.45	Per Cubic Meter	126.40	81332.00	Rupees Eighty One Thousand Three Hundred Thirty Two and Paise Zero Only
Total in Figures					81332.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

335699
6800
One Month

Name of Work:- R/R Damages on Kelodhar Saini road km 0/00 to 19/00 (SH:-C/O R/Wall at RD-15/245 to 15/257)

Sr No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals	23.70	Per Cubic Meter	379.90	9004	Rupees Nine Thousand Three and Paise Sixty Three Only
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 Nominal mix 1:5:10 (one cement, five sand, ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	57.10	Per Cubic Meter	5140.40	293517	Rupees Two Lakhs Ninety Three Thousand Five Hundred Sixteen and Paise Eighty Four Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	21.00	Each	371.75	7807	Rupees Seven Thousand Eight Hundred Six and Paise Seventy Five Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	19.86	Per Cubic Meter	1277.55	25372	
Total in Figures					335699	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	
				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPMD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 194400
Earnest Money 4000
Time Six month

Name of Work:- Preparation of Forest Diversion Case under FCA, Act 1980 for the Construction of Mandpa Gali (Kelodhar) to Shoja via Samsothi, Richhani, Jatho, Kamehri KM 0/00 to 16/00

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes
1	Preparation of Forest Diversion case under Forest Conservation Act, 1980 including preparation of revenue papers of land falling on the road alignment and collection of the other field data. All relevant documents/ formats mandatory required would be attached with the case as per latest requirement of Ministry of Environment and Forest conservation Govt. of India after getting the joint inspection/site including computer typing in six copies, binding complete and getting it through from HPPWD, Sub - Division Karsog, HPPWD Division Karsog, Office of concern Range Officer, Office of Divisional Forest Officer Karsog. Including attending all the observation, if raised, at any time by any above mentioned office and to prepare the same by neatly and accurately filling in all the formats/ Documents complete in all respect as per direction and complete satisfaction of HPPWD and Forest Department.	16.00	Per kilo meter	12150.00	194400	Rupees One Lakh Ninety Four Thousand Four Hundred and Paise Zero Only
Total in Figures					194400.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

44

Percentage Bill Of Quantity

Estimated Cost 213639
Earnest Money 4300
Time One Month

Name of Work:- R/R Damages on Chouridhar to Kotlu road km. 0/00 to 7/00 (SH:- Removal of slips at various Rd's) Section Kelodhar

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:- Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of stops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1690.18	Per Cubic Meter	126.40	213639.00	Rupees Two Lakhs Thirteen Thousand Six Hundred Thirty Nine and Paise Zero Only
Total in Figures					213639.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			

Bill of Quantity approved for Rs. 213639 /- only.
Sr. No. 823 for Years 2023-24

Executive Engineer,
Karsog Division,
HPPWD, Karsog.