

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(Padhar)E-Tender-NIT/2023-24- 23745-47

Dated:- 23/2/24

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: -

Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR
Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive
Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and
further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 04.03.2024 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 02.03.2024 upto 12:00 Noon.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Construction of Bhiuli Chipnu road Km 0/0 to 4/0. (SH:- Construction of Retaining wall at R.D. 3/780 to 3/792.20)	3,27,848.20	6,600/-	350/-	One month
2	Restoration of damages due to laying of O.F.C. by Indian Army N.F.S. on Neri Duhuki Behindhar Gharan Road Km 0/0 to 17/810. (SH:- Construction of Retaining wall at R.D. 2/140 to 2/160)	3,36,595.06	8,700/-	350/-	One month
3	Restoration of rain damages on Pakhari Galu Baragaon road Km 0/0 to 5/800. (SH:- Construction of Breast wall at R.D. 0/482 to 0/489)	4,11,352.54	8,200/-	350/-	One month
4	Restoration of rain damages on Kufri Nihon road Km 0/0 to 5/500. (SH:- Construction of Retaining wall at R.D. 3/120 to 3/135)	2,87,504.76	5,700/-	350/-	One month
5	Restoration of rain damages on Kufri Kheel Lohra road at Km 0/0 to 7/0. (SH:- Construction of Retaining wall at R.D. 2/225 to 2/235)	2,78,915.42	5,600/-	350/-	One month
6	Restoration of rain damages on Pali Baragaon road Km 0/0 to 11/0. (SH:- Construction of Breast wall at R.D. 3/585 to 3/605)	3,75,831.00	3,000/-	350/-	One month
7	Restoration of rain damages on Padhar Nahuli road Km 0/0 to 14/500. (SH:- Construction of Retaining wall at R.D. 13/240 to 13/250)	4,49,510.00	9,000/-	350/-	One month
8	Restoration of rain damages on Urla Nousa road Km 0/0 to 5/630. (SH:- Construction of toe wall for protection of slab culvert alongwith wing wall at R.D. 3/345)	3,25,209.00	6,500/-	350/-	One month
9	Restoration of rain damages on Balh to Ropa road km 0/0 to 5/0 (SH:- Construction of Retaining wall from Km 3/015 to 3/023)	4,40,088.06	8,800/-	350/-	One month
10	Restoration of rain damages on Tikkan Silhbudhani road Km 0/0 to 16/110. (SH:- Construction of Breast wall at R.D. 6/900 to 6/915)	3,20,033.00	6,400/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh


PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 327848.20
 Earnest Money Rs:- 6600.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- Construction of Bhiuli Chipnu road Km.0/00 to 4/00. (Sub Head: - Construction of Retaining wall at R.D. 3/780 to 3/792.80).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	46.13	Per cubic metre	461.00	21265.93	Rupees Twenty Thousand Sixty Five and Paise Ninety Three Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	64.52	Per cubic metre	4461.00	287823.72	Rupees Two Lakh Eighty Seven Thousand Eight Hundred Twenty Three and Paise Seventy Two Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.35	Per cubic metre	1433.00	13398.55	Rupees Thirteen Thousand Three Hundred Ninety Eight and Paise Fifty Five Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	268.00	5360.00	Rupees Five Thousand Three Hundred Sixty Only
Total in figure :					327848.20	Rupees Three Lakh Twenty Seven Thousand Eight Hundred Forty Eight and Paise Twenty
Total in Words :		Rupees Three Lakh Twenty Seven Thousand Eight Hundred Forty Eight and Paise Twenty Only				

Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 436595.06
 Earnest Money Rs:- 8700.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
Name of work :- Restoration of Damages due to laying of OFC by Indain Army N.F.S. on Neri Duhuki Behindhar Gharan Road Km. 0/00 to 17/810. (Sub Head: - Construction of Retaining wall at R.D. 2/140 to 2/160).
Contract No. :
Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	61.40	Per cubic metre	461.00	28305.40	Rupees Twenty Thousand Three Hundred Five and Paise Forty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	85.19	Per cubic metre	4430.40	377425.78	Rupees Three Lakh Seventy Seven Thousand Four Hundred Twenty Five and Paise Seventy Eight Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	14.40	Per cubic metre	1433.20	20638.08	Rupees Twenty Thousand Six Hundred Thirty Eight and Paise Eight Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	38.00	Each	269.10	10225.80	Rupees Ten Thousand Two Hundred Twenty Five and Paise Eighty Only
Total in figure :					436595.06	Rupees Four Lakh Thirty Six Thousand Five Hundred Ninety Five and Paise Six Only
Total in Words :		Rupees Four Lakh Thirty Six Thousand Five Hundred Ninety Five and Paise Six Only				

Chg
 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 411352.54
Earnest Money Rs:- 8200.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.


Name of work :- Restoration of rain damages on Pakhari Galu Baragaon road Km. 0/0 to 5/800. (Sub Head:- Construction of Breast wall at R.D. 0/482 to 0/489).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	98.42	Per cubic metre	461.00	45371.62	Rupees Forty Five Thousand Three Hundred Seventy One and Paise Sixty Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	78.61	Per cubic metre	4572.00	359404.92	Rupees Three Lakh Fifty Nine Thousand Four Hundred Four and Paise Ninety Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.00	Each	274.00	6576.00	Rupees Six Thousand Five Hundred Seventy Six Only
Total in figure :					411352.54	Rupees Four Lakh Eleven Thousand Three Hundred Fifty Two and Paise Fifty Four Only
Total in Words :					Rupees Four Lakh Eleven Thousand Three Hundred Fifty Two and Paise Fifty Four Only	


Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 287504.76
Earnest Money Rs:- 5700.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Kufri Nihon road Km. 0/00 to 5/500. (Sub Head:- Construction of Retaining wall at R.D. 3/120 to 3/135).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	32.10	Per cubic metre	461.00	14798.10	Rupees Fourteen Thousand Seven Hundred Ninety Eight and Paise Ten Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	54.00	Per cubic metre	4729.90	255414.60	Rupees Two Lakh Fifty Five Thousand Four Hundred Fourteen and Paise Sixty Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.00	Each	279.90	5038.20	Rupees Five Thousand Thirty Eight and Paise Twenty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.55	Per cubic metre	1433.20	12253.86	Rupees Twelve Thousand Two Hundred Fifty Three and Paise Eighty Six Only
Total in figure :					287504.76	Rupees Two Lakh Eighty Seven Thousand Five Hundred Four and Paise Seventy Six Only
Total in Words :					Rupees Two Lakh Eighty Seven Thousand Five Hundred Four and Paise Seventy Six Only	


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 278915.42
 Earnest Money Rs:- 5600.00
 Time One month


Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- Restoration of Damages rain damages on Kufri Kheel Lohra road at Km. 0/00 to 7/00. (Sub Head: - Construction of Retaining wall at R.D. 2/225 to 2/235).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	31.10	Per cubic metre	461.00	14337.10	Rupees Fourteen Thousand Three Hundred Thirty Seven and Paise Ten Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	50.05	Per cubic metre	5020.70	251286.04	Rupees Two Lakh Fifty One Thousand Two Hundred Eighty Six and Paise Four Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.90	Per cubic metre	1433.20	9889.08	Rupees Nine Thousand Eight Hundred Eighty Nine and Paise Eight Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	283.60	3403.20	Rupees Three Thousand Four Hundred Three and Paise Twenty Only
Total in figure :					278915.42	Rupees Two Lakh Seventy Eight Thousand Nine Hundred and Paise Forty Two Only
Total in Words :		Rupees Two Lakh Seventy Eight Thousand Nine Hundred and Paise Forty Two Only				


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 375831.00
 Earnest Money Rs:- 3000.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain Damages on Pali Baragaon road Km. 0/0 to 11/00. (Sub Head:- Construction of Breast wall at R.D.3/585 to 3/605).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	66.20	Per cubic metre	461.00	30518.00	Rupees Thirty Thousand Five Hundred Eighteen Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre) into one hundred millimetre mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	156.25	Per cubic metre	2210.00	345313.00	Rupees Three Lakh Forty Five Thousand Three Hundred Thirteen Only
Total in figure :					375831.00	Rupees Three Lakh Seventy Five Thousand Eight Hundred Thirty One Only
Total in Words :		Rupees Three Lakh Seventy Five Thousand Eight Hundred Thirty One Only				


 Executive Engineer,
 Mandi Division No. I,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 449510.00
Earnest Money Rs:- 9000.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.						
Name of work :- Restoration of Rain damages on Padhar Nahuli road km. 0/0 to 14/500 (S.H.-C/O Retaining wall at R.D. 13/240 to 13/250.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	38.40	Per cubic metre	461.00	17702.00	Rupees Seventeen Thousand Seven Hundred Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	83.41	Per cubic metre	4960.40	413747.00	Rupees Four Lakh Thirteen Thousand Seven Hundred Forty Seven Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	16.00	Each	282.30	4517.00	Rupees Four Thousand Hundred Seventeen Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.45	Per cubic metre	1433.20	13544.00	Rupees Thirteen Thousand Four Hundred Only
Total in figure :					449510.00	Rupees Four Lakh Forty Nine Thousand Five Hundred Ten Only
Total in Words :		Rupees Four Lakh Forty Nine Thousand Five Hundred Ten Only				


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 325209.00

Earnest Money Rs:- 6500.00

Time :- One months

Tender Inviting Authority: Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work:- Restoration of Rain Damages on Urfi Nousa road Km. 0/0 to 5/630. (Sub Head:- Construction of toe wall for protection of slab culvert alongwith wing wall at R.D. 3/345.)

Contract No.:-

Name of Bidder/Bidding Firm/ Company:-


SCHEDULE OF WORKS						
Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	28.50	Per cubic metre	461.00	13139.00	Rupees Thirteen Thousand One Hundred Thirty Nine Only
2	Providing and laying concrete mechanically mixed and vibrated mix 1:4:8 (one cement: four sand: eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	49.27	Per cubic metre	5106.90	251617.00	Rupees Two Lakh Fifty One Thousand Six Hundred Seventeen Only
3	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	7.28	Per cubic metre	5314.70	38691.00	Rupees Thirty Eight Thousand Six Hundred Ninety One Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	24.00	Each	279.70	6713.00	Rupees Six Thousand Seven Hundred Thirteen Only
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	10.50	Per cubic metre	1433.20	15049.00	Rupees Fifteen Thousand Nine Only
Total in Figure					325209.00	Rupees Three Lakh Twenty Five Thousand Two Hundred Nine Only
Quoted Rate in Words		Rupees Three Lakh Twenty Five Thousand Two Hundred Nine Only				


 Executive Engineer,
 Mandi Division No. 1
 HP.PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 440088.06
Earnest Money Rs:- 8800.00
One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.						
Name of work :- Restoration of damages on Balh to Ropa road km.0/00 to 5/00. (Sub Head:- Construction of Retaining wall from km. 3/015 to 3/023).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	34.32	Per cubic metre	461.00	15821.52	Rupees Fifteen Thousand Eight Hundred Twenty One and Paise Fifty Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	80.35	Per cubic metre	5079.20	408113.72	Rupees Four Lakh Eight Thousand One Hundred Thirteen and Paise Seventy Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	285.50	3426.00	Rupees Three Thousand Four Hundred Twenty Six Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.88	Per cubic metre	1433.20	12726.82	Rupees Twelve Thousand Seven Hundred Twenty Six and Paise Eighty Two Only
Total in figure :					440088.06	Rupees Four Lakh Forty Thousand Eighty Eight and Paise Six Only
Total in Words :		Rupees Four Lakh Forty Thousand Eighty Eight and Paise Six Only				


 Executive Engineer,
 Mandi Division No. I,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 320033.00
Earnest Money Rs:- 6400.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Tikkan Silhbudhani road Km. 0/0 to 16/110. (Sub Head:- Construction of Breast wall at R.D. 6/900 to 6/915).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	31.40	Per cubic metre	461.00	14475.40	Rupees Fourteen Thousand Four Hundred Seventy Five and Paise Forty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	56.50	Per cubic metre	5151.00	291031.50	Rupees Two Lakh Ninety One Thousand Thirty One and Paise Fifty Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.00	Each	289.00	6358.00	Rupees Six Thousand Three Hundred Fifty Eight Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.70	Per cubic metre	1433.00	8168.10	Rupees Eight Thousand One Hundred Sixty Eight and Paise Ten Only
Total in figure :					320033.00	Rupees Three Lakh Twenty Thousand Three Hundred Thirty Three Only
Total in Words :		Rupees Three Lakh Twenty Thousand Thirty Three Only				

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.