

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited on Form No.7 &8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works 06-03-2024 upto 11:00 A.M and shall be opened on the same day on 11:30 P.M. in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.


The earnest money in the shape of National Saving Certificate, FDRs/TDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

S.N	Tender Schedule				
1	Last date for tender receipt of application for tender form	04-03-2024 up to 4:00 PM			
2	Last date of sale of tender forms	05-03-2024 up to 4:00 PM			
3	Date of receipt of tender forms	06-03-2024 up to 11:00 P.M			
4	Date of opening of tenders	06-03-2024 at 11:30 PM			
Sr. No	Name of Work	Estimat ed cost	Earnest Money	Time Limit	Cost of Form
1	C/O Mari Ka Ghat Jaganji Ki Ser road Km 0/0 to 8/00 (SH:- C/O PCC R/wall at RD 0/885 to 0/912) Under MMSY	489273/	10000/-	Two Month	350/-
2	R/R Damages on Jaman Ki Ser Harkaghat upto Galanaghat road Km 0/0 to 11/450 (SH:- C/O wire crate at RD 9/140 to 9/152)	301924/	6000/-	One Month	350/-
3	R/R damages on Dungaghat Bagthan road Km 0/0 to 12/480 (SH:- C/O PCC R/wall at Rd 1/375 to 1/390) Height 3.65 mtr	346125/	7000/-	One Month	350/-
4	R/R damages on Dungaghat Kila Klanch road Km 0/0 to 22/00 (SH:- C/O R/wall at Rd 10/660 to 10/675) length 15mtr height	193479/	4000/-	One Month	350/-
5	R/R Damages on Banalag Dhemesha Panchpeer road 0/0 to 8/450 (SH:- C/O B/wall at Rd 2/330 to 2/345) Height 2.44 mtr , R/Wall at RD 5/900 to 5/915 height 3.44 m	482806/	10000	One Month	350/-
6	R/R damages on Deed Gluth road km 0/0 to 4/00 (SH;- C/O PCC R/wall at RD 1/216 to 1/234) length 18 mter ,height 4 mtr	488637/	10000	One Month	350/-
7	C/o link road to village Gandhal Km 0/0 to 7/00 (SH;- Improvement of curve at various RD 5/443 to 5/475, 5/585 to 5/615, 5/770 to 5/820, 6/00 to 6/30 to 6/170 to 6/310) MNP	462259/	9500/-	One Month	350/-

Certificate:-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
4. Conditional and telegraphic tender will not be accepted and rejected straightway. Tender received after due date and time shall not entertained.
5. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
6. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
7. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
8. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.


Executive Engineer
HPPWD Division Sarahan

P.T.O

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Shimla-171002.
2. The Chief Engineer (South) HP.PWD, Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. 7. All Intending Bidders/Contractors.
8. Notice Board.



Executive Engineer
HPPWD Division Sarahan
District Shimla (HP)

SCHEDULE OF QUANTITY

Estimated cost:-Rs.4,89,273/-
Earnest money:- Rs. 10000/-
Time Limit:- Two Month.

Name of work:- C/O Mari ka ghat Chando Jaganji ki ser road 0/0 to 8/00 (SH:- C/O PCC B/Wall at RD 0/885 to 0/912) Under MMSY

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	53.73	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	10424.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	96.66	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	455965.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	22.000	Each	270.30	Rupees. Two Hundred seventy and paise thirty only. ✓	5947.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	22.95	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only. ✓	16937.00
						489273.00


Executive Engineer
Saraha Division
HP, PWD, Saraha

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Jaman ki ser Harkaghat upto Galanaghat road km 0/0 to 11/450 (SH:- C/O wire crate at RD 9/140 to 9/152),

Estimated cost:- Rs. 3,01,924/-

Earnest money:- Rs. 6000/-

Time Limit:- one Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	25.20✓	Per Cubic Metre.	194.00✓	Rupees one hundred ninety four and paise zero only.✓	4889.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints, laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	99.75✓	Per Cubic Metre.	2846.40✓	Rupees Two thousand Eight hundred forty six and paise forty only.✓	283928.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	17.76✓	Per Cubic Metre.	738.00✓	Rupees seven Hundred thirty eight and paise zero Only.✓	13107.00
						301924.00


Executive Engineer
K. Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Estimated cost-Rs.346125/-
Earnest money: - Rs. 7000/-
Time Limit: - One Months.

Name of work:- R/R Damages on Dunga ghat Bagthan Road km 0/0 to 12/480 (SH:- C/O PCC R/Wall at RD 1/375 to 1/390 Height 3.65

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	14.82	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.✓	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	70.02	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only.✓	330298.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	24.000	Each	270.30	Rupees. Two Hundred seventy and paise thirty only.✓	6487.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	8.76	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.✓	6465.00
						346125.00

Executive Engineer
K. Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Dunga ghat Kila kalandh Road km 0/0 to 22/00 (SH:- C/O R/Wall at RD 10/660 to 10/675 Length 15 m Height 2.44

Estimated cost:-Rs.193479/-

Earnest money:- Rs. 4000/-

Time Limit:- One Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	17.75	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only, ✓	3444.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	37.65	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only, ✓	177603.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	12.000	Each	270.30	Rupees, Two Hundred seventy and paise thirty only, ✓	3244.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	12.45	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only. ✓	9188.00
						193479.00


 Executive Engineer
 K/Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- -R/R Damages on Banalag Dhamesha Punchpeer Road 0/0 to 8/450 (SH:- C/O B/Wall at RD 2/330 to 2/345 Height 2.44 m, R/Wall at RD 5/900 to 5/915 Height 3.44 m

Estimated cost:-Rs.482806/-

Earnest money:- Rs. 10000/-

Time Limit:- One Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	21.97	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.	4262.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	97.41	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only.	459502.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	29.000	Each	270.30	Rupees. Two Hundred seventy and paise thirty only.	7839.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	15.18	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	11203.00
						482806.00

Executive Engineer
K. Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Deed Galuth road km 0/0 to 4/00 (SH:- C/O PCC R/Wall at RD 1/216 to 1/234) Length 18mtr Hieght 4 mtr

Estimated cost:-Rs.488637/-
 Earnest money:- Rs. 10000/-
 Time Limit:- One Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	53.10	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.✓	10301.00✓
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	95.47	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only.✓	450351.00✓
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	48.000	Each	270.30	Rupees. Two Hundred seventy and paise thirty only.✓	12974✓
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	20.34	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.✓	15011.00✓
						488637.00


 KS Sarahan
 Executive Engineer
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- -C/O Link Road to village Gandal km 0/0 to 7/00 (SH)- Improvement of curve at various RD,s 5/443 to 5/475, 5/585 to 5/615,5/770 to 5/820,6/00 to6/30 to 6/170 to 6/310 (MNP)

Estimated cost:-Rs.4,62,259/-

Earnest money:- Rs. 9500/-

Time Limit:- one Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). and there intermediate classification of soil including,dewatering wherever requiried,setting out to required lines, levels as shown on the drawing and directed by the Engineer-in-Charge at site . according to the HPPWD. specification and sorting out useful and un-useful material and transporation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer -in-Charge through all modes of transporation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools, equipment and safety measures to complete the work (if required) any loss to the public and private property during the course of execution and					
2	Pick Work					
		Cum	211.59	159.00	Rupees one hundred fifty nine and paise nil only ✓	33643.00
3	Jamper Work					
		Cum	211.59	159.00	Rupees one hundred fifty nine and paise nil only ✓	33643.00
	Blastic work					
		Cum	1692.68	263.80	Rupees two hundred sixty three and paise eighty only ✓	446529.00
	Recovery for usefull stones, =]W =211.59/10= BW=1692.68 m3/6=303.27m3@Rs.170/-	Cum	303.27	170.00		462259.00

Executive Engineer
Sarahan Division
HP, PWD, Sarahan