

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited on Form No.7 &8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works 04-03-2024 upto 11:00 A.M and shall be opened on the same day on 11:30 P.M. in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.

The earnest money in the shape of National Saving Certificate, FDRs/TDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

S N	Tender Schedule				
1	Last date for tender receipt of application for tender form	01-03-2024 up to 4:00 PM			
2	Last date of sale of tender forms	02-03-2024 up to 4:00 PM			
3	Date of receipt of tender forms	04-03-2024 up to 11:00 P.M			
4	Date of opening of tenders	04-03-2024 at 11:30 PM			
Sr. No	Name of Work	Estimat ed cost	Earnest Money	Time Limit	Cost of Form
1	R/R Damages on Jaman Ki Ser Harkaghat upto Galanaghat road Km 0/0 to 11/450 (SH:- C/O wire crate at RD 4/765 to 4/777, 9/125 to 9/130 & 9/110 to 9/118).	431672/-	9000/-	One Month	350/-
2	R/R damages on Kanyon Shirla Anji km 0/0 to 6/480 (SH:- Providing and paying interlocking tiles in Km 6/360 to 6/460)	496535/-	10000	One Month	350/-
3	R/R damages on Tindu Kharimoo Mehal Preet Nagar road Km 0/0 to 5/555 (SH:- P/L G-II & G-III in damaged portion of Km 5/00 to 5/555)	421636/-	8500/-	One Month	350/-
4	R/R damages on Prem Nagar Chandog road Km 0/0 to 15/00 (SH:- C/o PCC R/wall at Rd 10/810 to 10/830)	470822/-	9500/-	One Month	350/-
5	C/O Naina Tikker Chadiyar road Km 0/0 to 2/300 (SH:- ROFD in Km 0/310 to 0/390) SCSP	497627/-	10000/-	One Month	350/-
6	R/R damages on Lawassa Chowki Preet Nagar road Km 0/0 to 42/00(SH:- C/O PCC R/wall at Rd 27/140 to 27/150) height 3.04 mtr	182234/-	4000/-	One Month	350/-
7	R/R damages on Dungaghat Bagthan road Km 0/0 to 12/450 (SH:- C/O R/wall at Rd 6/495 to 6/510) height 5 mtr	380065/-	8000/-	One Month	350/-

Certificate:-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
4. Conditional and telegraphic tender will not be accepted and rejected straightway. Tender received after due date and time shall not entertained.
5. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
6. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
7. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
8. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.

Executive Engineer
HPPWD Division Sarahan

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Shimla-171002.
2. The Chief Engineer (South) HP.PWD, Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. 7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer
HPPWD Division Sarahan
District Sirmour (HP)

Name of work:- R/R Damages on Jaman ki ser Harkaghat upto Galanaghat road km 0/0 to 11/450 (SH:- C/O wire crate at RD 4/765 to 4/777.9/125 to 9/130 & 9/110 to 9/118)

Estimated cost: Rs. 4,31,672/-

Earnest money: - Rs. 9000/-

Time Limit: - one Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3	Per Cubic Metre.	194.00 ✓	Rupees one hundred ninety four and paise zero only. ✓	7857.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	142.19 ✓	Per Cubic Metre.	2846.40 ✓	Rupees Two thousand Eight hundred forty six and paise fourty only. ✓	404730.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	25.86 ✓	Per Cubic Metre.	738.00 ✓	Rupees seven Hundred thirty eight and paise zero Only. ✓	19085.00
						431672.00

Executive Engineer
K. Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Kanyon Shiria-Anji (SH:- Providing and laying interlocking tiles in 6/360 to 6/460

Estimated cost:- Rs. 4,96,535/-
Earnest money:- Rs. 10,000/-
Time Limit:- one Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	1552.00
2	Providing and laying concrete PCC M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20 (Twenty millimeter) nominal size for plain/ reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802,803,1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer -in Charge	8.00	Per Cubic Meter.	5819.60	Rupees Five thousand Eight hundred nineteen and paise sixty only. ✓	46557.00
3	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504. including carriage of all labour equipments and materials to various location through all modes of transportations in all leads and lift to the entire satisfaction as per direction of Engineer-in Charge	374.00	Per Square meter.	1199.00	Rupees one thousand one Hundred ninety nine and paise zero Only. ✓	448426.00
						496535.00


Executive Engineer
Ks Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Tindu kharimoo Mehal Preet Nagar Road Km 0/0 to 5/555 (SH:- Providing and laying G-II & G-III in Damaged portion of km 5/00 to 5/555

Estimated cost:-Rs.421636/-

Earnest money:- Rs. 8500/-

Time Limit:- One Months.

Sr. No		Description Items of work	Qty.	Unit	Time Limit: - One Months.		Amount
					Rate		
					in figures.	in words	
1	1	2	3	4	5	6	7
	1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading -II (63 mm to 45 mm) as per HPPWD Technical Specification Clause 405.by Manual means	Cum	78.023	2252.13	Rupees two thousand two hundred fifty two and paise thirteen only , ✓	175718.00
	2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density 55mm to 25mm size Grading -III as per Technical Specification Clause 405.by Manual means	Cum	98.604	2494.00	Rupees two thousand four hundred ninety four and paise nil only . ✓	245918.00
							421636.00


 Executive Engineer
 K. Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Premnagar Chandog Road km 0/00 to 15/00 (SH:-C/O PCC R/Wall at RD 10/810 to 10/830

Estimated cost:-Rs.470822/✓
Earnest money:- Rs. 9500/✓
Time Limit:- One Months.

Sr. No	Description Items of work	Qty.	Unit	in figures.	Rate		Amount
					in words	in words	
1	2	3	4	5	6	7	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	36.40	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.✓	7	7062.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	92.40	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓		435869.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	18.000	Each	270.30	Rupees. Two Hundred seventy and paise thirty only.✓		4865.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	31.20	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only. ✓		23026.00
							470822.00


Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Naina Tikker Chadyar road km. 0/0 to 2/300 (SH:- ROFD in km RD 0/310 to 0/390)SCSP

Estimated cost:-Rs.497627/-
Earnest money:- Rs. 10000/-

Time Limit:- One Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2 Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 297.27 cum (two hundred ninety seven point twenty seven) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	3	4	5	6	7
2	Blastic work	Cum	1783.61	279.00	Rupees two hundred seventy nine and paise nil only	497627.00
	Recovery for usefull stones, =1783.61 m3/6=297.27m3@Rs.170/-	Cum	297.27	170.00	Rupees one hundred seventy and paise nil only	
						497627.00


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Lawassa chowki Preet Nagar road km 0/0 to 42/00 (SH:- C/O PCC R/Wall at RD 27/140 to 27/150 Height 3.04 mm)

Estimated cost:- Rs.182234/- ✓

Earnest money:- Rs. 4000/- ✓
Time Limit:- One Months.

Sr. No	Description Items of work	Qty.	Unit	in figures.	Rate		Amount
					in words		
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	3	4	5	6	7	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.64	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	1676.00	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement: Four Sand: Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	35.79	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	168829.00	
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven))including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	15.000	Each	270.30	Rupees. Two Hundred seventy and paise thirty only. ✓	4054.00	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	10.40	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only. ✓	7675.00	
							182234.00


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY


Name of work:- R/R Damages on Dunga ghat Bagthan Road Km 0/0 to 12/450 (SH:-C/O wire crate at RD 6/495 to 6/510 Height 5 mtr

Estimated cost:-Rs.380065/-
Earnest money:- Rs. 8000/-
Time Limit:- one Months.

Sr. No		Description Items of work	Qty.	Unit	Rate		Amount
					in figures.	in words	
1	1	2 Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	3	4 Per Cubic Metre.	5 194.00	6 Rupees one hundred ninety four and paise zero only. ✓	7 5193.00
2	2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	124.70	Per Cubic Metre.	2846.40	Rupees Two thousand Eight hundred forty six and paise fourty only. ✓	354946.00
3	3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	27.00	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only. ✓	19926.00
							380065.00

Time Limit: - one Months.

Earnest money: - Rs. 8000. ✓


Executive Engineer
Saraha Division
HP, PWD, Saraha