



OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811

E-MAIL:- ee-sol-hp@nic.com

No.PW-SD/CB-Tender/-2023-24- 14820-24.

Dated:- 09⁰⁹/₂₀₂₄.


To

✓ The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID:cc-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.


Executive Engineer,
B&R Division,
HP.PWD, Solan

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.


Executive Engineer,
B&R Division,
HP.PWD, Solan.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Exigency

Scaled item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD, Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	15.02.2024	Upto 3.00 P.M.
2	The last date sale of tender forms.	16.02.2024	Upto 4.00 P.M.
3	The date for receipt of tender forms.	17.02.2024	Upto 10.30 P.M.
4	The date of opening of tender	17.02.2024	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 17.02.2024 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs.)	Time	Cost of Form
1.	Annual repair and maintenance of Anu Dharon Ki Dhar road km 0/0 to 4/625 (SH: Providing and laying BC in patch work at RD 0/0 to 1/0 and construction of PCC R./wall at RD 0/0 to 0/018)	Rs. 476711/-	Rs. 9600/-	One month	Rs.350/-
2.	Restoration of rain damages on link road to Jatoli Mandir km 0/0 to 0/750 (SH: C/o PCC R/wall at RD 0/119.50 to 0/128.70)	Rs. 492530/-	Rs. 9900/-	One month	Rs.350/-
3.	Restoration of rain damages on link road to Jatoli Mandir km 0/0 to 0/750 (SH: C/o PCC R/wall at RD 0/110 to 0/119.50)	Rs. 493255/-	Rs. 9900/-	One month	Rs.350/-
4.	Annual repair and maintenance of foot bridge at Katal (SH: Providing protection work for abutment and laying concrete in approach path)	Rs. 499135/-	Rs. 10000/-	Two months	Rs.350/-
5.	Renovation of Holy Shoolini Mata Mandir at Solan (SH: Architectural upgradation of idol worship place of the temple by P/L plastering, stone and tile work etc.)(Deposit work)	Rs. 492044/-	Rs. 9900/-	Two months	Rs.350/-
6.	Renovation of Holy Shoolini Mata Mandir at Solan (SH: Architectural upgradation of idol worship place of the temple by P/L Teak wood work and steel work etc.)(Deposit work)	Rs. 492044/-	Rs. 9900/-	Two months	Rs.350/-
7.	Construction of indoor auditorium for cultural programmes at Jatoli Distt. Solan (SH: Providing and fixing furnishing articles)(Deposit work)	Rs. 497200/-	Rs. 10000/-	Two months	Rs.350/-

8.	A/R & M/O various road under Oachghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips)	Rs. 499700/-	Rs. 10000/-	Two months	Rs.350/-
9.	Construction of Public gate at Ram Lok Rudha Mandir starting point on Kehlog Basha road at RD 0/0 (Deposit work)	Rs. 427290/-	Rs. 8600/-	Two months	Rs.350/-
10.	Repair and maintenance of HPPWD Circuit House near old bus stand Solan (SH: Dismantling of CGI Sheet and P/F steel work etc.)(Deposit work)	Rs. 499907/-	Rs. 10000/-	Two months	Rs.350/-
11.	Repair and maintenance of HPPWD Circuit House near old bus stand Solan (SH: Providing and fixing prepainted steel sheet in the roof)(Deposit work)	Rs. 499405/-	Rs. 10000/-	Two months	Rs.350/-

TERMS & CONDITIONS:-


1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.

N. N. Tiwari
Executive Engineer
Solan B & R Division
H.P.P.W.D. Solan

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :-				Estimated Cost :-		476711.00
				Earnest Money :-		9600.00
				Time limit :-		One Month
Name of Work :- Annual Repair and Maintenance of Annu Dharon Ki Dhar road Km.0/00 to 4/625 (SH:- Providing and laying BC in patch work at Rd.0/00 to 1/00 and Construction of PCC R/wall at Rd.0/00 to 0/018)						
1	Providing and applying tack coat with rapid setting (RS-1) bitumen emulsion using emulsion distributor at the rate of 0.275 kg (point two seven five kilogramme) per square meter on the prepared dry and hungry granular bituminous surface treated with primer cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lift and other incidental charges.	525.00	Per Square meter	19.93	Rupees Nineteen and Paise Ninety Three Only	10463.00
2	Providing and laying bituminous concrete 30mm (Thirty milimetres) thick with 100-120 (one hundred to one hundred twenty) TPH batch type hot mix plant producing an average output of 75 (seventy five) tonnes per hour using crushed stone aggregates of specified grading, premixed with bituminous binder @ 5.5% (five point five percent) of total weight of mix, aggregate Grading II (thirteen milimetres nominal size) i.e. 13.2 - 10 mm 30% (thirty percent), 10 - 5 mm 25% (twenty five percent), 5 mm and below 43% (forty two per cent) of volume of aggregate and filler @ 2% (two percent) by weight of Aggregate, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 (five zero nine) complete in all respects and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead, lift and other incidental charges.	15.75	Per Cubic Meter	13349.29	Rupees Thirteen Thousand Three Hundred Forty Nine and Paise Twenty Nine Only	210251.00

3	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited). Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	32.94	Per Cubic Meter	387.00	Rupees Three Hundred Eighty Seven Only	12748.00
4	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	56.70	Per Cubic Meter	4229.00	Rupees Four Thousand Two Hundred Twenty Nine Only	239784.00
5	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	15.00	Each	231.00	Rupees Two Hundred Thirty One Only	3465.00
Total:-						476711.00
Rupees Four Lakhs Seventy Six Thousand Seven Hundred Eleven Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			


T/S No. 279 for the 2023-24.
Sr. No. 418 for the year 2023-24


Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 92				Estimated Cost :-		492530.00
				Earnest Money :-		9900.00
				Time limit :-		One month
Name of Work :- Restoration of Rain damages on link road to Jatoli Mandir Km.0/00 to 0/750 (SH: - Construction of PCC Retaining wall at Rd.0/119.50 to 0/128.70)						
1	removal of disposal of excavated soil material/ debris to the dumping site as per much management plan including loading, unloading stacking etc. by mechanical transport including carriage of material, within all leads and lifts as per directions of Engineer-in-Charge.	90.89	Per Cubic Meter	161.00	Rupees One Hundred Sixty One Only	14633.00
2	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chesling / wedging out rocks (where blasting is prohibited), Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	42.41	Per Cubic Meter	387.00	Rupees Three Hundred Eighty Seven Only	16413.00
3	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	102.76	Per Cubic Meter	4229.00	Rupees Four Thousand Two Hundred Twenty Nine Only	434572.00

4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle (sto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	36.00	Each	231.00	Rupees Two Hundred Thirty One Only	8316.00
5	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	17.66	Per Cubic Meter	1053.00	Rupees One Thousand Fifty Three Only	18596.00
Total:-						492530.00
Rupees Four Lakhs Ninety Two Thousand Five Hundred Thirty Only						
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

T/S No.278 for the 2023-24.
Sr. No. 417 for the year 2023-24



Executive Engineer
B&R Division, HP.PWD. Solan.


Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 5				Estimated Cost :-		493255.00
				Earnest Money :-		9900.00
				Time limit :-		One month
Name of Work :- Restoration of Rain damages on link road to Jatoli Mandir Km.0/00 to 0/750 (SH: - Construction of PCC Retaining wall at Rd.0/110 to 0/119.50)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited). Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	43.80	Per Cubic Meter	387.00	Rupees Three Hundred Eighty Seven Only	16951.00
2	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	106.12	Per Cubic Meter	4229.00	Rupees Four Thousand Two Hundred Twenty Nine Only	448781.00
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	36.00	Each	231.00	Rupees Two Hundred Thirty One Only	8316.00

4	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	18.24	Per Cubic Meter	1053.00	Rupees One Thousand Fifty Three Only	19207.00
Total:-						493255.00
Rupees Four Lakhs Ninety Three Thousand Two Hundred Fifty Five Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.277 for the 2023-24.

Sr. No.416 for the year 2023-24



Executive Engineer
B&R Division, HP.PWD. Solan.


Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 4				Estimated Cost: -		499135.00
				Earnest Money: -		10000.00
				Time limit : -		Two months
Name of Work :- Annual repair and maintenance of Foot Bridge Katal (SH:- Providing protection work for abutment, Piers and laying concrete in approach path)						
1	Providing and laying cement concrete 1:1.5:3 (one cement into one point five Sand into three graded stone aggregate 20 mm (twenty millimeters) nominal size in foundation and plinth and curing complete excluding cost of form work as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	35.05	Per Cubic Meter	7800.00	Rupees Seven Thousand Eight Hundred Only	273390.00
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) of specified grade excluding the cost of centering and shuttering all work up to plinth level as per H.P.PWD. Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	4.50	Per Cubic Meter	6281.00	Rupees Six Thousand Two Hundred Eighty One Only	28265.00
3	Centering and shuttering including strutting, propping etc. and removal of form work as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.					0.00
a	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	77.88	Per Square Meter	585.85	Rupees Five Hundred Eighty Five and Paise Eighty Five Only	45626.00
4	Providing for Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level as per structural drawing in all floors up to all heights and levels, direction of Engineer-in-Charge and as per HP.PWD. Specification 1990 volume-I, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	635.86	Per Killogram m	109.00	Rupees One Hundred Nine Only	69309.00
5	Providing laying 20 mm thick cement plaster 1:4 (1 Cement:4Coarse Sand) as required dosage as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	64.98	Per Square Meter	342.05	Rupees Three Hundred Forty Two and Paise Five Only	22226.00

6	Finishing walls with textured exterior paint of required shade. New work Two or more coats applied 3.28 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20kg/10 sqm as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	64.98	Per Square Meter	196.05	Rupees One Hundred Ninety Six and Paise Five Only	12739.00
7	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	396.50	Per Square Meter	120.00	Rupees One Hundred Twenty Only	47580.00
Total:-						499135.00
Rupees Four Lakhs Ninety Nine Thousand One Hundred Thirty Five Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.280 for the 2023-24.

Sr. No. 419 for the year 2023-24



Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 5				Estimated Cost: -		492044.00
				Earnest Money: -		9900.00
				Time limit :-		Two months
Name of Work :- Renovation of Holy Shoolini Mata Mandir Solan (SH:- Architectural upgradation of Idol worship place of the temple by P/L plastering, Stone & Tile work etc.) (Deposit work)						
1	Providing and fixing Red sand stone jali 40 mm thick (Forty Millimetre) throughout in cement mortar 1:3 (1 cement : 3 coarse sand), including pointing in white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment, matching the stone shade, jali slab without any chamfers etc. as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	44.43	Per Square Meter	6517.50	Rupees Six Thousand Five Hundred Seventeen and Paise Fifty Only	289573.00
2	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position Sal wood with necessary stainless steel screws etc.as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	0.50	Per Cubic Meter	91310.90	Rupees Ninety One Thousand Three Hundred Ten and Paise Ninety Only	45655.00
3	Providing and fixing 12mm thick (Twelve Millimetre) fire retardant plywood conforming to IS:5509, in ceiling with necessary nails etc. complete (frame work to be paid separately) as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	13.66	Per square meter.	1524.00	Rupees One Thousand Five Hundred Twenty Four Only	20818.00
4	Providing and laying vitrified floor tiles in different sizes of tile 1000x1000 mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	55.89	Per square meter.	2359.45	Rupees Two Thousand Three Hundred Fifty Nine and Paise Forty Five Only	131870.00

5	Providing laying 20mm thick (Twenty Millimetre) cement plaster 1:3 (1 Cement:3 Coarse Sand) finished with a floating coat of neat cement and including water proofing material from the approved manufacturer as required dosage as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	10.98	Per Square Meter	376.00	Rupees Three Hundred Seventy Six Only	4128.00
	Total:-					492044.00
	Rupees Four Lakhs Ninety Two Thousand Forty Four Only					
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No.260 for the 2023-24.


Sr. No. 414 for the year 2023-24


Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 6				Estimated Cost: -		498360.00
				Earnest Money: -		10000.00
				Time limit: -		Two months
Name of Work :- Renovation of Holy Shoolini Mata Mandir Solan (SH: - Architectural upgradation of Idol worship place of the temple by P/L Teak wood work and steel work etc.) (Deposit work)						
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	1548.79	Per Killogramme	111.00	Rupees One Hundred Eleven Only	171916.00
2	Providing and fixing shutter of Superior class Teak wood such as Dandeh, Balarshah of Malabar in planks in ceiling with necessary nails etc. complete (frame work to be paid separately) as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	51.91	Per square meter.	6252.00	Rupees Six Thousand Two Hundred Fifty Two Only	324541.00
3	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	10.98	Per square meter.	135.90	Rupees One Hundred Thirty Five and Paise Ninety Only	1492.00
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	10.98	Per Square Meter	37.40	Rupees Thirty Seven and Paise Forty Only	411.00
Total:-						498360.00
Rupees Four Lakhs Ninety Eight Thousand Three Hundred Sixty Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.261 for the 2023-24.

Sr. No. 415 for the year 2023-24



Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 7				Estimated Cost: -		497200.00
				Earnest Money: -		10000.00
				Time limit: -		Two months
Name of Work :- Construction of Indoor Auditorium for cultural programmes at Jatoli, Distt. Solan (SH:- Providing and Fixing furnishing articles) (Deposit work)						
1	Supplying and fixing Bed comforter made of high quality cloth and filled with superior quality of conjugated fiber sheet of size 70" x 100" inches complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	50.00	Each	2600.00	Rupees Two Thousand Six Hundred Only	130000.00
2	Supplying and fixing Bed blanket made of high quality cloth made up of mink complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	80.00	Each	1500.00	Rupees One Thousand Five Hundred Only	120000.00
3	Supplying and fixing Pillow of superior quality of size 17x 27" filled with conjugated fiber complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	80.00	Each	500.00	Rupees Five Hundred Only	40000.00
4	Supplying and fixing Double bed sheet made up of superior quality of silky cotton along with two set of pillow cover made up of same quality of cloth complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	2.00	Each	1900.00	Rupees One Thousand Nine Hundred Only	3800.00
5	Supplying and fixing cover for Bed comforter made of high quality cloth and filled with superior quality of conjugated fiber sheet of size 70" x 100" inches complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	81.00	Each	1400.00	Rupees One Thousand Four Hundred Only	113400.00

6	Supplying and fixing Single bed sheet made up of superior quality of silky cotton along with two set of pillow cover made up of same quality of cloth complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	120.00	Each	750.00	Rupees Seven Hundred Fifty Only	90000.00
Total:-						497200.00
Rupees Four Lakhs Ninety Seven Thousand Two Hundred Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			


T/S No.250 for the 2023-24.

Sr. No. 413 for the year 2023-24


Executive Engineer
B&R Division, HP.PWD. Solan.


SCHEDULE OF QUANTITY.				Earnest Money :-		Time Limit :-		Two Months.	
Job No. 2									
Name of work: A/R and M/O on various roads under Oachghat Sub- Division (SH) :- Hiring of JCB + loader cum-excavator for removal of slips (Under Oachghat Sub-Division)									
Sno.	Description of items	Quantity	Unit	Rate in figure.	Rate in Words	Amount			
1	2	3.00	4	5	6	7			
1	Hiring of JCB + loader cum-excavator .	526.00	Per hour.	950.00	Rupees nine hundred fifty & paise nil only.	499700.00			
Terms and Conditions :-									
(a)	Hire charges should include expenses on account of establishment, POI, Major and minor repairs /over hauling and replacement of tyres and batteries if reqd								
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.								
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.								
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.								
(e)	Minimum work as per PWD norms must be executed by the machinery hired.								
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .								
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour								
						Total:-		499700.00	
Total in words.				Rupees-Four lacs Ninety Nine thousand seven hundred only.					
Quoted Percentage rate upto Three Digits :-				(+) / (-)					

Sr. No. 420 for the year 2023-24.


Executive Engineer,
Solan B&R Division,
H.P.P.W.D; Solan.


Schedule of Quantity

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 9				Estimated Cost: -		427290.00
				Earnest Money:-		8600.00
				Time limit :-		Two months
Name of Work :- Construction of Public Gate at Ram Lok Rudha Mandir starting point on Kehlog Basha Road at Rd.0/00 (Deposit work)						
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in All kinds of soil, foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	0.864	Per Cubic meter.	222.90	Rupees Two Hundred Twenty Two and Paise Ninety Only	193.00
2	Providing and laying in position cement concrete 1:2:4 (1 Cement :2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering all work up to plinth level as per H.P.PWD.Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	0.720	Per Cubic meter.	8692.50	Rupees Eight Thousand Six Hundred Ninety Two and Paise Fifty Only	6259.00
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering all work up to plinth level as per H.P.PWD.Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	0.144	Per Cubic meter.	6615.30	Rupees Six Thousand Six Hundred Fifteen and Paise Thirty Only	953.00
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works in position and applying a priming coat of approved steel primer using structural steel etc. as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	2210.700	Per Killogram m	126.40	Rupees One Hundred Twenty Six and Paise Forty Only	279432.00
5	Providing and fixing M.S. BP Sheet 1.66mm to 2mm thick in eaves board/ fascia/ soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	34.675	Per square meter.	1906.20	Rupees One Thousand Nine Hundred Six and Paise Twenty Only	66097.00

6	Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester(RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating fixing with prepainted iron J or L hooks, bolts and nuts 6mm diameter with prepainted limpet and rubber washers complete with all accessories as per H.P.PWD. Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	39.240	Per square meter.	1417.20	Rupees One Thousand Four Hundred Seventeen and Paise Twenty Only	55611.00
7	Providing and fixing ridges or hips 60cm (sixty centimeter) overall with 0.60mm(zero point sixty millimeter) thick pre-painted steel sheets in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (twenty) microns over 5 (five) microns primer coating + back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts & nuts 6mm dia & pre-painted G.I. limpet and bitumen washers complete with all accessories as required as per HP.PWD. specification 1990 (One thousand Nine hundred Ninety) Volume-I (One),including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges	21.700	Per running Meter	741.65	Rupees Seven Hundred Forty One and Paise Sixty Five Only	16094.00
8	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	23.753	Per Square Meter	111.60	Rupees One Hundred Eleven and Paise Sixty Only	2651.00
Total:-						427290.00
Rupees Four Lakhs Twenty Seven Thousand Two Hundred Ninety Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.291 for the 2023-24.


Sr. No. 423 for the year 2023-24


Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 10				Estimated Cost: -		499907.00
				Earnest Money: -		10000.00
				Time limit: -		Two months
Name of Work :- Repair and Maintenance of HPPWD Circuit House near Old Bus Stand Solan (SH:- Dismantling of CGI Sheet and P/F Steel work etc.) (Deposit work)						
1	Dismantling of G.S. Sheet roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	513.00	Per square meter.	69.80	Rupees Sixty Nine and Paise Eighty Only	35807.00
2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.	4550.00	Per Killogramme	102.00	Rupees One Hundred Two Only	464100.00
Total:-						499907.00
Rupees Four Lakhs Ninety Nine Thousand Nine Hundred Seven Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.289 for the 2023-24.


Sr. No. 421 for the year 2023-24


Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- / /				Estimated Cost: -		499405.00
				Earnest Money: -		10000.00
				Time limit :-		Two months
Name of Work :- Repair and Maintenance of HPPWD Circuit House near Old Bus Stand Solan (SH:- Providing and fixing Prepainted steel sheet in the Roof) (Deposit work)						
1	Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester(RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating fixing with prepainted iron J or L hooks, bolts and nuts 6mm diameter with prepainted limpet and rubber washers complete with all accessories as per H.P.PWD. Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	339.50	Per square meter.	1471.00	Rupees One Thousand Four Hundred Seventy One Only	499405.00
Total:-						499405.00
Rupees Four Lakhs Ninety Nine Thousand Four Hundred Five Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.290 for the 2023-24.

Sr. No. 422 for the year 2023-24


Executive Engineer
B&R Division, HP.PWD. Solan.

Exigency Certificate

It is certified that the tenders which were invited vide this office
NIT No.PW-SD/CB-Tender/2023-24- 14820-24 , Dated: 09.02.2024 are of emergent nature
of work and in public interest.

Dated:- 09.02.2024

Place:- Solan


Executive Engineer
B&R Division
HPPWD, Solan

