

Himachal Pradesh
Public Works Department

NO.PW.THD/CB-tender/2023-24 - 16861-72
To

Dated:- 27-2-2024

The Executive Engineer, (IT Cell)
O/O Engineer-in- Chief,
H.P.P.W.D., Nirmal Bhawan, Shimla-2

Subject:- Publication of Tender notice

Sir,

I am enclosing herewith Notice Inviting Tender for the various work typed in English for uploading the same on department website in view of Principal Secretary (PW) to the Government of Himachal Pradesh Notification No. PBW (B) A (3) 1/2020 dated 16th July 2021.

As the work mentioned in the tender notice are urgent in nature and in public interest.


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog.

Copy forwarded to the following a/w copy of tender notice for information:-

- 1 The Deputy Commissioner, Shimla Distt. Shimla H.P
- 2 The Superintending Engineer, 4th circle H.P.P.W.D , Shimla-3
- 3 The Sub-divisional officer© Theog.
- 4 The municipal Council Theog.
- 5 Block development officer, Theog block.
- 6 All the Assistant Engineer working under this division
- 7 Superintendent Gr-II(Estt.) in this division.
- 8 Drawing branch in this office.
- 9 Notice Board


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER

Sealed percentage rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP. for the following works from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on or before 06/03/2024 up to 11:00 PM. and the same shall be opened on the same day at 11:30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on 05/03/2024 up to 11:00 A.M. and the application for issue of tender form shall be received on 04/03/2024 up to 4:00 P.M.

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD. Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 45 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.

Sr. No	Name of work	Estimated cost(Rs.)	Earnest money (Rs.)	Cost of form (Rs)	Time allowed for completion
1	2	3	4	5	6
1	R/R Damages on Patinal Malari Road Km 0/0 to 6/500 (SH:- C/O R/wall at RD 1/123 to 1/128.) Balance work	134380	2700	350	One Month
2	A/R & M/O Rest House at Sainj (SH:- C/O septic tank and C/O edging R/wall)	431963	8700	350	One Month
3	R/R Damages on Tihana to Pargeya Road Km 0/0 to 4/285 (SH:- C/O PCC R/wall at RD 2/870 to 2/880)	498258	10000	350	One Month
4	C/O Kargoli Deha Road Km 0/0 to 6/500 (SH:- Re-Construction of R/wall at Rd 2/840 to 2/846)	99698	3250	350	One Month
5	R/R Damages approach Road to PWD Store Theog Km 0/0 to 5/0 (SH:- C/O PCC R/wall at RD 0/081 to 0/102)	455275	9200	350	One Month
6	C/O Sarion Gawai Road via Bhalech Jadeog Km 0/0 to 5/0 (SH:- Re-Construction PCC B/wall at RD 2/030 to 2/058)	482643	9700	350	One Month
7	C/O Mohari to Patinal Via Maleri Road Km 0/0 to 6/500 (SH:- Re-Constriction of B/wall at RD 0/600 to 0/620.) Protect of house Sh. Amar Singh	231081	4700	350	One Month
8	R/R of Rain Damages on Sainj Deha Chopal Road Km 0/0 to 20/740 (SH:- C/O PCC R/wall at RD 5/135 to 5/148.)	468788	9400	350	One Month
9	R/R Damages on Forest Colony to Chikhar Pump House Km 0/0 to 6/400 (SH:- Hiring of JCB for removal of slips)	301550	6050	350	One Month
10	R/R Damages on Forest Colony to Chikhar Pump House Km 0/0 to 6/400 (SH:- C/O wire crate for the protection of slabculvert at RD 5/650 left and right)	186903	1720	350	One Month

11	R/R Damages on jai to Palana Road Km 0/0 to 6/765 (SH:- C/O PCC R/wall at RD 0/390 to 0/402)	391105	7900	350	One Month
12	C/O Kiari to Talin Road Km 0/0 to 3/0 (SH:- C/O wire crate R/wall in at RD 0/557.50 to 0/560)	86015	1720	350	One Month
13	C/O Kiari to Talin Road Km 0/0 to 2/540 (SH:- Formation cutting in earth work 5/7 mtr . Wide Km 1/360 to 1/555.)	236747	4750	350	One Month
14	C/O Dhatti to Manlog Teer Km 0/0 to 5/0 (SH:- C/O PCC B/wall at RD 0/660 to 0/695)	489714	9800	350	One Month
15	C/O Dhhatti to Manlog Teer Km 0/0 to 5/0 (SH:- C/O PCC B/wall at RD 0/960 to 0/995)	495751	10000	350	One Month
16	R/R Damages on Devgarh Jarai Manlog Road Km 0/0 to 6/500 (SH:- C/O PCC B/wall at Rd 5/570 to 5/5820)	240683	4800	350	One Month
17	C/O Dhatti to Manlog Teer Km 0/0 to 5/0 (SH:- C/O PCC B/wall at RD 0/885 to 0/920)	493669	9900	350	One Month
18	R/R Damages on jai to Palana Road Km 0/0 to 6/765 (SH:- C/O PCC B/wall at RD 5/450 to 5/480)	453500	9070	350	One Month
19	R/R Damages on jai to Palana Road Km 0/0 to 6/765 (SH:- C/O PCC R/wall at RD 0/180 to 0/193)	461696	9300	350	One Month
20	R/R Damages on Runkali to Chikhar Road Km 0/0 to 6/500 (SH:- C/O R/wall at Rd 1/175 to 1/182.50)	495737	10000	350	One Month
21	R/R Damages on Runkali to Chikhar Road Km 0/0 to 6/500 (SH:- C/O B/wall at Rd 0/600 to 0/620.)	273025	5500	350	One Month
22	Consultancy Service for Flood Damages Report of MDR -74, MDR-73 (SH:- Prepration of Detailed Project Report for flood Damages Portion.)-	170762	5500	350	One Month
23	Land Mitigation work consultancy for construction of Rahighat to Kiartoo (SH:- Geotechnical Investigation Km 0/00 to 0/045)	365000	7300	350	One Month
24	Land Mitigation work consultancy for construction of Raighat to Kiartoo (SH:- Geotechnical Investigation and Topographical Survey from 0/00 to Km 0/045)	405000	8100	350	One Month
25	C/O Road Basa Mahog Road to Delogar Road in District Shimla (H.P.) (SH:- Preparation of Detailed Project Report.)	211750	4300	350	One Month
26	C/O Kargoli Nallah to Deha Road Km 0/0 to 8/0 (SH:- Re-Construction PCC B/wall at Rd 2/655 to 2/667)	204756	5000	350	One Month
27	R/R Damages on Various Road under Sainj Sub-Division (SH:- Removal of land slide and clearance.)	99700	2000	350	One Month
28	A/R & M/o varioous Road under matiana Sub-Division 0/0 to 8/0 (SH:- Removal of land slide in hill side under Matiana	99750	2000	350	One Month

	-Section)				
29	C/O Balghar Tihana Dhar Kalna Road Km 0/0 to 24/0 (SH:- formation Cutting at RD 3/302 to 3/505.)	475263	9600	350	One Month
30	C/O Balghar Tihana Dhar Kalna Road Km 0/0 to 24/0 (SH:- formation Cutting at RD 3/060 to 3/165.)	492783	10000	350	One Month
31	R/R Damages on Various Road under sainj Sub-Division (Sainj)-Section) (SH:- Hiring of Tipper for carriage of debries /stone)	150000	3000	350	One Month
32	R/R Damages on Various Road under Sainj Sub-Division (Sainj)-Section) (SH:- Hiring of Tipper for carriage of debries /stone)	150000	3000	350	One Month
33	R/R Damages on Various Road under Sainj Sub-Division (Sainj)-Section) (SH:- Hiring of JCB for removal of slips)	267750	5355	350	One Month
34	Restoration of snow/Rain damages on Various Road under Theog Sub-Division (SH:- Supplying and Stacking at site crusher sand in various Road & Various RDs)	99750	2000	350	One Month
35	R/R Damages on Rahighat to Kiartoo Road Km 0/0 to 9/0 (SH:- C/O B/wall at RD Km 3/980 to 4/010)	491138	7850	350	One Month

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

Following documents should accompany the application for tenders: -

- (1) The contractors are required to be produce a copy of their PAN No.GST. NO and should produce a copy of enlistment /renewal letter.
- (2) Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected.
- (3) The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act 1952 (EPF number) within a month from award of work/contract. Failure to observe this condition shall render the tender of contractor liable to summary rejection.
- (4) The bidder are advised to quote rates inclusive of G.S.T. as applicable notified vide Additional Chief Secretary (PW) to the Govt. of H.P. letter No. PBW(B)C(17)2/2012 dated 07/08/2018 ,G.S.T. shall not be paid extra.
- (5) Contractors are allowed to bid only two works, if he bids for more than two works only the first two works in sequence will be considered.

On Behalf of Governor of Himachal Pradesh


Executive Engineer,
Theog Division, H&R,
H.P.P.W.D, Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 134380
 Earnest Money: 2700.00
 Time: one Months

R/R Damages on Patinal Malari Road Km 0/0 to 6/500 (SH:- C/O R/wall at RD 1/123 to 1/128.) Balance work						
Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Amount
				Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	19.45	214.10	Rupees Two Hundred Fourteen and Paise Ten Only		4164.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203 . (1:4:8) 40 mm Agg including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	28.22	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only		123558.00
3	Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 110 mm dia (4 Kg Cm2 pressure) PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	8.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only		1937.00
4	Stone filling behind the retaining wall, B/wall and wing wall complete as per drawing and technical specification clauses 1204, 3.8. granular material including all leads and lift as per directions of the Engineer - in Charge.	3.75	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only		4720.00
Total						134380.00
				Quoted rate in figer+/-		
				Quoted rate in words		

Executive Engineer,
 Theog Division,
 HP PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs - 431963
 Earnest Money 8700.00
 Time: one Months

A/R & M/O Rest House at Sainj (SH:- C/O septic tank and C/O edging R/wall)						
Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Amount
				Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	82.65	214.10	Rupees Two Hundred Fourteen and Paise Ten Only		17695.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203 . (1:4:8.) 25 mm Agg including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	44.13	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only		193219.00
3	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 and 1204 Random rubble masonry in cement mortar 1:5 including all leads and lifts or as per the direction of Engineer - in Charge	27.14	3365.00	Rupees Three Thousand Three Hundred Sixty Five Only		91326.00
4	Cement concrete flooring 1:2: 4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement , including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm thick with 20 mm nominal size stone aggregate including carriage of material within all leads and lifts or as per the direction of Engineer - in Charge	27.14	467.40	Rupees Four Hundred Sixty Seven and Paise Forty Only		12685.00
5	Providing from work with steel plates 3.15 (Three point on five millimetre) thick welded with angle iron in frame 30X30x5mm (Thirty into thirty into five millimeter) so as to give a fair finish including centering , shuttering, strutting and propping etcetra with wooden battens and ballies for all height of propping and centering below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in all leads and lifts as per direction of the Engineer -in-Charge in foundation.	27.14	628.50	Rupees Six Hundred Twenty Eight and Paise Fifty Only		17057.00
5.01	Centering and shuttering including strutting , propping etc. and removal of from edges of slab and breaks in floors and walls under 20 cm wide upto all floor levels complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	18.00	455.00	Rupees Four Hundred Fifty Five Only		8190.00

6	Reinforced cement concrete work in beams, suspended floors landings, balconies, shelves, chajjas, lintels, bands, plain window sills, above plinth level up to floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement 1.5 coarse sand) . 3 graded stone aggregates 20 mm nominal size) upto all floor level complete including carriage of material in all leads and lifts as per direction of the Engineer-in-charge.	2.40	9114.35	Rupees Nine Thousand One Hundred Fourteen and Paise Thirty Five Only	Per Cum meter	21874.00
7	Providing Tor steel reinforcement for RCC work including bending and placing in position including cost of binding wire complete including all leads and lifts as per direction of the Engineer-in-Charge.	288.00	102.00	Rupees One Hundred Two Only	per kilo gram	29376.00
8	Half Brick masonry in 2nd class common burnt clay building bricks in cement mortar 1:4 (one cement: four sand) complete including all leads and lifts as per direction of the Engineer-in-Charge.	4.95	1089.30	Rupees One Thousand Eighty Nine and Paise Thirty Only	Per square meter	5392.00
9	Providing and fixing PVC waste soil and vent pipes including fixing with approved adhesive complete including carriage of materials all leads and lifts > 110 mm dia.	5.00	1056.10	Rupees One Thousand Fifty Six and Paise Ten Only	Each	5281.00
10	Providing and fixing weapholes in bricks masonry/stone masonry plain RCC abument, B/wall R/wall with 110 mm dia (4Kg Cm2 pressure) PVC pipe i/c all leads and lifts. As per direction of the Engineer-in-Charge.	26.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	6296.00
11	Supplying Cast Iron cover without frame for manholes. For frame of 600 mm internal dia meter C.L cover (medium duty) the weight of cover to be less than 58 kg i/c all leads and lifts as per Engineer-in-charge.	2.00	4800.00	Rupees Four Thousand Eight Hundred Only	Each	9600.00
12	Stone filling behind retaining walls complete including carriage of material in all leads and lifts as per direction of the Engineer-in-charge.	11.10	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per Cum meter	13971.00
Total						431963.00
			Quoted rate in figer+/(%-----)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs - 498258
 Earnest Money 10000.00
 Time: one Months

R/R Damages on Tihana to Pargaya Road Km 0/0 to 4/285 (SH:- C/O PCC R/wall at RD 2/870 to 2/880)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	48.30	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum meter	10341.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203 . (1:4:8.) 40 mm Agg.including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	104.42	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per Cum meter	457193.00
3	Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 110 mm dia (4 Kg Cm2 pressure) PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	38.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	9202.00
4	Stone filling behind the retaining wall. B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lift as per directions of the Engineer - in Charge.	17.10	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per Cum meter	21523.00
Total						498258.00
			Quoted rate in figer+/-{%------}			
			Quoted rate in words			

Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 99698

Earnest Money 3250.00

Time: one Months

C/O Kargoli Deha Road Km 0/0 to 6/500 (SH:- Re-Construction of R/wall at Rd 2/840 to 2/846)							
Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
				Rate in words			
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	5.70	214.10	Rupees Two Hundred Fourteen and Paise Ten Only		Per Cum meter	1220.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203 . (1:4:8) 40 mm Agg.including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	20.50	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only		Per Cum meter	89757.00
3	Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 110 mm dia (4 Kg Cm2 pressure) PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	12.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only		Each	2906.00
4	Stone filling behind the retaining wall. B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lift as per directions of the Engineer - in Charge.	4.62	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only		Per Cum meter	5815.00
	Total						99698.00
			Quoted rate in figer+/-(%-----)				
			Quoted rate in words				

Executive Engineer
Theog Division
HP PWD, Theog.

Estimated Cost Rs - 455275
 Earnest Money 9200 00
 Time one Months

R/R Damages approach Road to PWD Store Theog Km 0/0 to 5/0 (SH:- C/O PCC R/wall at RD 0/081 to 0/102)						
Sr. No.	Description of item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and lead upto 20 mtr. as per technical specification clause 1603 1 with in all leads and lift as per the direction of engineer in charge	28.56	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	Per Cum	4248.00
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	32.13	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum meter	6879.00
3	Providing and laying concrete for plain / reinforced concrete 1:4:8 (1 cement 4 sand 8 graded stone agg. 25mm nominal size) in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203 . (1:4:8.) 40 mm Agg including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	91.98	4492.40	Rupees Four Thousand Four Hundred Ninety Two and Paise Forty Only	Per Cum meter	413211.00
4	Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 110 mm dia (4 Kg Cm2 pressure) PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	54.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	13076.00
5	Stone filling behind the retaining wall. B/wall and wing wall complete as per drawing and technical specification clauses 1204 3.8. granular material including all leads and lift as per directions of the Engineer - in Charge.	14.19	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per Cum meter	17860.00
Total						455275.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			

Executive Engineer,
 Theog Division,
 HP.PWD Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 482643

Earnest Money 9700.00

Time: one Months

C/O Serion Gawai Road via Bhalech Jadeog Km 0/0 to 5/0 (SH:- Re-Construction PCC B/wall at RD 2/030 to 2/058)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and lead upto 20 mtr. as per technical specification clause 1603.1 with in all leads and lift as per the diraction of engineer in charge	56	84.95	Rupees Eighty Four and Paise Ninety Five Only	Per Cum	4757.00
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	38.36	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum meter	8213.00
3	Stoe masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	92.23	4597.00	Rupees Four Thousand Five Hundred Ninety Seven Only	Per Cum meter	423981.00
4	Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 110 mm dia (4 Kg Cm2 pressure) PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	52.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	12592.00
5	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203. (1:4:8) 40 mm Agg including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	7.56	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per Cum meter	33101.00
Total						482644.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 231081
Earnest Money 4700.00
Time: one Months

C/O Mohri to Patinal Via Maleri Road Km 0/0 to 6/500 (SH:- Re-Constriction of B/wall at RD 0/600 to 0/620.) Protect of house Sh. Amar Singh						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopess and disposing of excavated earth with a lift upto 1.5 mtr. and lead upto 20 mtr. as per technical specification clause 1603.1 with in all leads and lift as per the diraction of engineer in charge.	39.80	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	Per Cum meter	5920.00
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	18.40	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum meter	3939.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1204 Agg.including all leads and lifts or as per the direction of Engineer - in Charge (1:4:8) 40 mm	49.53	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per Cum meter	216862.00
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1204 Agg.including all leads and lifts or as per the direction of Engineer - in Charge (1:4:8) 40 mm	18.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	4359.00
Total						231080.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 468788
Earnest Money 9400.00

Time: one Months

R/R of Rain Damages on Sainj Deha Chopal Road Km 0/0 to 20/740 (SH:- C/O PCC R/wall at RD 5/135 to 5/148.)						
Sr. No.	Description of Item	QTY	Rate in fig.	Rate	Unit	Amount
				Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and lead upto 20 mtr. as per technical specification clause 1603.1 with in all leads and lift as per the direction of engineer in charge.	26.52	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum meter	5678.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1204 Agg including all leads and lifts or as per the direction of Engineer - in Charge (1:4:8:) 40 mm	102.70	4178.40	Rupees Four Thousand One Hundred Seventy Eight and Paise Forty	Per Cum meter	429122.00
3	Providing and fixing weapholes in brick masonry Stone / masonry plain RCC abutment , B/wall & R/wall with 100 mmm dia PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge	39.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	9444.00
4	Stone filling behind the retaining wall. B/wall all leads and lifts as per directions of the Engineer - in Charge	19.50	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per Cum meter	24544.00
Total						468788.00
				Quoted rate in figer+/-(%-----)		
				Quoted rate in words		

Executive Engineer,
Theog Division,
HP PWD, Theog

Estimated Cost	Rs - 301550
Earnest Money:	6050.00
Time: one Months	

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 186903
Earnest Money: 1720.00

Time: one Months

R/R Damages on Forest Colenny to Chikhar Pump House Km 0/0 to 6/400 (SH:- C/O wire crate for the protection of slabculvert at RD 5/650 left and right)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	42.18	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum meter	9031.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100mm X100 mm mesh (Woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification Clauses 1301 including all leads and lifts or as per the direction of Engineer - in Charge	54.73	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per Cum meter	177873.00
Total						186903.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost

Rs :- 391105

Earnest Money:

7900.00

Time: one Months

R/R Damages on jai to Palana Road Km 0/0 to 6/765 (SH:- C/O PCC R/wall at RD 0/390 to 0/402)						
Sr. No.	Description of Item	QTY	Rate in fig.	Rate	Unit	Amount
				Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	63.00	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum meter	13488.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203 (1:4:8:) 40 mm Agg including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	79.08	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per Cum meter	346244.00
3	Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 110 mm dia (4 Kg Cm2 pressure) PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	36.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	8717.00
4	Stone filling behind the retaining wall. B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lift as per directions of the Engineer - in Charge.	18.00	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per Cum meter	22656.00
Total						391105.00
				Quoted rate in figer+/-(%-----)		
				Quoted rate in words		

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs. -236747
Earnest Money 4750 00
Time one Months

C/O Kiari to Talin Road Km 0/0 to 2/540 (SH:- Formation cutting in earth work 5/7 mtr . Wide Km 1/360 to 1/555.)					
Sr. No.	Description of Item	QTY	Rate		Amount
			Rate in fig.	Rate in words	
1	Cutting in earth work in all depths and heights in all kinds of soils including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock, with chiseling and wedging out of rock. (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required setting out true to the required lines grades side slopes, trimming of bottoms and levels as shown on the drawing and as directed by the Engineer-in charge at site, according to the HP.PWD. specification of 1990 volume-1 and sorting of useful and un useful materials and stacking the same in all lead and left and transportation of the un useful materiel for filling in road way embankments for grade improvement and leveling to required grades and then disposing of surplus excavated materials in acquired width of the road or on approved dumping site/sites through all modes of transportation including head loads, animals loads or mechanical means along with its leveling and fine dressing and carriage of all labour, machinery, materials tools, equipments and safety measures and other incidental necessary to completes the work by mechanical means and /or labour (if any required complete as per directions of Engineer-in Charge) All useful materials, such as stones, shingles, 177.90cum useful stone during the course of execution shall be made @ 300/- cum on prorata basis. Any loss to the public and private property during the courses of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respect. including all leads and lifts as per direction of the Engineer-in-Charge	2563.80	92.34	Rupees Ninety Two and Paise Thirty Four Only	236747.00
					236747.00
			Quoted rate in figer+/-(%-----)		
			Quoted rate in words		

Executive Engineer,
Theog Division,
HP.PWD Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.489714

Earnest Money: 9800/

Time: One months

Name of work:- C/O Dhhattli to Manlog Teer Jai Palana km 0/0 to 5/0(SH):- C/O PCC B/wall at RD 0/660 to 0/695)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	96.25	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	Per cubic meter	14317
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge (Ordinary Soil)	44.10	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	9442
3	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	102.55	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	449005
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure,PVC pipe 1/c all leads and lifts as per direction of the Engineer -in -Charge.	70.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	16951
						489714
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.495751
Earnest Money: 10000/
Time: One months

Name of work:- C/O Dhhatti to Manlog Teer km 0/0 to 5/0(SH):- C/O PCC B/wall at RD0/960 to 0/995)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	132.30	148.75	Rupees One Hundred Forty Eight and Paise Five Only	Per cubic meter	19680
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	47.25	214 10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	10116
3	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	102.55	4378 40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	449005
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	70.00	242 15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	16951
						495751
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.240683
Earnest Money: 4600/-
Time: One months

Name of work:- R/R Dampers on Dargah Jarai Manlog m km 6/0 to 6/500(SH:- C/O PCC B/wall at RD5/570 TO 5/5820

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	42.24	148.75	Rupees One Hundred Forty Eight and Paise Five Only	Per cubic meter	6283
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 1605.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m. dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	19.80	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	4239
3	Providing and Laying concrete for plain/reinforced concrete: 1:4:8 (1 cement 4 sand 8 graded stone agg. 40 mm nominal size) in open foundations complete as per drawing and technical specifications, clauses 802, 803, 1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge	51.24	4378.40	Rupees Four Thousand Three Hundred Eight and Paise Forty Only	Per cubic meter	224349
4	Providing and fixing weapholes in brick masonry/stone masonry plain, RCC abument B/wall R/wall with 1:10 mm. grt (w/ Ke-Cm2 pressure) PVC pipe i/c all leads and lifts as per direction of the Engineer-in-Charge.	24.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	5812
				Quoted rate in fig +/- (%.....)		240683
				Quoted rate in words		


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.493669

Earnest Money: 9900/

Time: One months

Name of work:- C/O Dhhatti to Manlog Teer Jai Patana km 0/0 to 5/0(SH):- C/O PCC Biwall at RD 0/885 to 0/920)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	118.30	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	Per cubic meter	17597
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	47.25	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	10116
3	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge	102.55	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	449005
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument, Biwall R/wall with 110 mm dia (4 KgCm2 pressure) PVC pipe etc all leads and lifts as per direction of the Engineer -in -Charge.	70.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	16951
						493669
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			



 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.453500
Earnest Money. 9070/
Time: One months

Name of work:- R/R Darnages on Jai Palana km 0/0 to 6/765(SH:- C/O PCC B/wall at RD5/450 to 5/480)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	95.70	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	Per cubic meter	14235
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	39.00	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	8350
3	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge	95.10	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	416386
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe 1/c all leads and lifts,as per direction of the Engineer-in -Charge.	60.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	14529
						453500
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP, PWD Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.461696
Earnest Money 9300/
Time: One months

Name of Work : R/R Damages on Jai to Palana road km 0/0 to 6/765 (SH- C/O PCC Rivali at RD 0/180 to 0/193)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	76.05	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	16282
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	94.64	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	414372
3	Stone filling behind the retaining wall B/wall and wing wall complete as per drawing and technical specification clauses 1204.3 8. granular material including all leads and lifts as per direction of the Engineer -in -Charge.	17.16	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per cubic meter	21598
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	39.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	9444
						461696
			Quoted rate in figer +/- (%).....			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs - 495737

Earnest Money: 10000 00

Time: one Months

R/R Damages on Runkali to Chikhar Road Km 0/0 to 6/500 (SH:- C/O R/wall at Rd 1/175 to 1/182.50)						
Sr. No.	Description of Item.	QTY	Rate in fig.	Rate		Amount
				Rate in words	Unit	
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	40.73	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum meter	8719.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203 . (1:4:8:) 25 mm Agg including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	106.38	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per Cum meter	465774.00
3	Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 110 mm dia (4 Kg Cm2 pressure) PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	35.10	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Per Cum meter	8499.00
4	Stone filling behind the retaining wall. B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8, granular material including all leads and lift as per directions of the Engineer - in Charge.	10.13	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per Cum meter	12744.00
						495737.00
				Quoted rate in figert+ /{%-.....}		
				Quoted rate in words		


Executive Engineer
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 273025
Earnest Money: 5500.00
Time: one Months

R/R Damages on Runkali to Chikhar Road Km 0/0 to 6/500 (SH:- C/O B/wall at Rd 0/600 to 0/620.)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slope and disposing of excavated earth with in lift upto 1.5 mtr. and a lead upto 20 mtr as per technical specification clause 1603.1 including all leads and lifts or as per the direction of Engineer - in Charge.	50.00	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	Per Cum meter	7438.00
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	30.00	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum meter	6423.00
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts or as per the direction of Engineer - in Charge 1:6:12	6.00	3503.65	Rupees Three Thousand Five Hundred Three and Paise Sixty Five Only	Per Cum meter	21022.00
4	R/R masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 Random rubble masonry in cement mortar 1:6 including all leads and lifts or as per the direction of Engineer - in Charge)	70.76	3365.5	Rupees Three Thousand Three Hundred Sixty Five and Paise Fifty Only	each	238143.00
						273025.00
			Quoted rate in figer+/- (%-----)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 170762
 Earnest Money: 5500 00
 Time: Three Months

Consultancy Service for Flood Damages Report of MDR -74, MDR-73 (SH:- Prepration of Detailed Project Report for flood Damages Portion.)-							
Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
				Rate in words			
1	Prepration of detailed Project report for Flood Damages on Sainj Deha Chopal Road Km 0/000 to 27/740 (MDR-74) , Chhaila Sainj Neripul Yashwent nager Solan Km 0/000 to 18/435 (MDR-73) complete in all respect and submission of the same to higher office for approval, if any correspondance /ammendment has desired by this office as well as by head office, the same may be rectified as desired and directed by Engineer-in-charge in all respect. after approval the same should be submitted in five set of fair copy of DPR complete. The detail is as under :- TOTAL AMOUNT =Rs 68304883.9	68304883.90	0.25	Rupees NIL and Paise Twenty Five Only		Rupees	170762.00
							170762.00


 Executive Engineer,
 Theog Division,
 HP.PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 365000
 Earnest Money: 7300.00
 Time: 30 Days

Land Mitigation work consultancy for construction of Raighat to Kiartoo (SH:- Geotechnical Investigation Km 0/00 to 0/045)						
Sr. No.	Description of item	QTY	Rate in fig.	Rate	Unit	Amount
				Rate in words		
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75mm dia h for investigation and de-mobilization for drilling . shifting of machinery to bore site and water arrangement for drilling . The scope of work includes relevant tests and submission of geotechnical report of comlex site of work including carriage of materials within all leads and lift as per the direction of Engineer-in-Charge.	50.00	7300.00	Rupees Seven Thousand Three Hundred Only	Running meter	365000.00
						365000.00


 Executive Engineer,
 Theog Division,
 HP.PWD Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 405000
 Earnest Money: 8100.00
 Time:- 30 Days

Land Mitigation work consultancy for construction of Raighat to Kiaroo (SH:- Geotechnical Investigation and Topographical Survey from 0/00 to Km 0/045)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia h for investigation of soil rock conditions at site of work, two no bores of 25.0 mt each including mobilization and demobilization for drilling shifting or machinery to bore site and water arrangement for drilling the scope of work including carriage of materials within all leads and lift as per the direction of Engineer-in-charge.	50.00	7300.00	Rupees Seven Thousand Three Hundred Only	per running meter	365000.00
2	Preparation of Digital Contour survey plan and drawings in all respect and submission of the higher office for approval. If any amendment has desired by the head office, the same may be corrected and directed by Engineer -in-Charge in akk respect. After the same should be submitted in two no set of fair draing again if any amendment as desired by head office.	1.00	40000.00	Rupees Forty Thousand Only	no	40000.00
						405000.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP, PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 211750
 Earnest Money: 4300.00
 Time:- 30 Days

C/O Road Basa Mahog Road to Delogar Road in District Shimla (H.P.) (SH:- Preparation of Detailed Project Report.)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Preparation of Detailed Project Report which includes following provision as mentioned below:- i) Topography survey by digital total station with two second accuracy showing all features on survey plan like tress, culvert, bridges, electric poles, telephone poles, hand pumps, school, habitants villages etc. ii) Draw cross-section at 15 m intervals, L-section and calculate the quantity of earth work in standard format of autocad showing all layers of pavement components as applicable. iii) Preparation of survey plan showing all details as per MORD guidelines and specifications. if any correction/amendment will be desired by the office the same may be corrected as desired and directed by the Engineer-In-Charge complete in all respect. after approval of the same from the head office the same should be submitted in three fair copies and soft copy as per the requirement of this office and upto entire satisfaction of Engineer-In-Charge including all type of incidental charges.	7.070	25000.00	Rupees Twenty Five Thousand Only	Km	176750.00
2	CBR test including gain size analysis , afterberbs limil. proctor compaction and CBR value upto the entire satisfaction of Engineer-In-Charge including all type of incidental charges.	14 00	2500.00	Rupees Two Thousand Five Hundred Only	Sample	35000.00
						211750.00
			Quoted rate in figer+/-{%-}-----}			
			Quoted rate in words			

Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 204755
Earnest Money: 5000.00
Time: one Months

C/O Kargoli Nallah to Deha Road Km 0/0 to 8/0 (SH:- Re-Construction PCC B/wall at Rd 2/655 to 2/667)						
Sr. No.	Description of Item	QTY	Rate in fig.	Rate	Unit	Amount
				Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	46.60	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum meter	9977.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203 . (1:4:8.) 25 mm Agg including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	4.87	4492.40	Rupees Four Thousand Four Hundred Ninety Two and Paise Forty Only	Per Cum meter	21878.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 including all leads and lifts or as per the direction of Engineer - in Charge.	42.85	3865.50	Rupees Three Thousand Eight Hundred Sixty Five and Paise Fifty Only	Per Cum meter	165637.00
4	Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 100 mmm dia PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	30.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	7265.00
	Total					204756.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP PWD Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.99700
Earnest Money:1000/
Time: one month

Name of Work : R/R damages on various road under Sainj Sub- Division (SH:- Removal of land slide and clearance)

Sr. No.	Description of Item.	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	1329.33	75.00	Rupees Seventy Five Only	Per cubic meter	99700
			Quoted rate in figer +/- (%.....)			99700
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 99750

Earnest Money: 2000.00

Time: one Months

A/R & M/o varoious Road under matiana Sub-Division 0/0 to 8/0 (SH:- Removal of land slide in hill side under Matiana -Section)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Removal of landslides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 mtr and land upto 1000 meter as per technical specification 302.3.5 and 1611	1330.00	75.00	Rupees Seventy Five Only	Per Cum meter	99750.00
						99750.00
			Quoted rate in figer+/(%-----)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 475263

Earnest Money: 9600.00

Time: one Month

C/O Balghar Tihana Dhar Kalna Road Km 0/0 to 24/0 (SH:- formation Cutting at RD 3/302 to 3/505.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Cutting in earth work in all depths and heights in all kinds of soils including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock, with chiseling and wedging out of rock. (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required setting out true to the required lines grades side slopes, trimming of bottoms and levels as shown on the drawing and as directed by the Engineer-in charge at site, according to the HP PWD. specification of 1990 volume-1 and sorting of useful and un useful materials and stacking the same in all lead and left and transportation of the un useful material for filling in road way embankments for grade improvement and leveling to required grades and then disposing of surplus excavated materials in acquired width of the road or on approved dumping site/sites through all modes of transportation including head loads, animals loads or mechanical means along with its leveling and fine dressing and carriage of all labour, machinery, materials tools, equipments and safety measures and other incidental necessary to completes the work by mechanical means and /or labour (if any required complete as per directions of Engineer-in Charge) All useful materials, such as stones, shingles, 360 93cum useful stone during the course of execution shall be made @ 300/- cum on prorate basis. Any loss to the public and private property during the courses of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respect. including all leads and lifts as per direction of the Engineer-in-Charge.	2308.89	205.84	Rupees Two Hundred Five and Paise Eighty Four Only	Per Cum	475263.00
						475263.00
			Quoted rate in figer+/-{%-}-----}			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 492783

Earnest Money: 10000.00

Time: one Months

C/O Balghar Tihana Dhar Kalna Road Km 0/0 to 24/0 (SH:- formation Cutting at RD 3/060 to 3/165.)					
Sr. No.	Description of Item	QTY	Rate		Amount
			Rate In fig.	Rate in words	
1	Cutting in earth work in all depths and heights in all kinds of soils including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock, with chiseling and wedging out of rock. (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required setting out true to the required lines grades side slopes, trimming of bottoms and levels as shown on the drawing and as directed by the Engineer-in charge at site, according to the HP.PWD specification of 1990, volume-1 and sorting of useful and un useful materials and stacking the same in all lead and left and transportation of the un useful material for filling in road way embankments for grade improvement and leveling to required grades and then disposing of surplus excavated materials in acquired width of the road or on approved dumping site/sites through all modes of transportation including head loads, animals loads or mechanical means along with its leveling and fine dressing and carriage of all labour, machinery, materials tools, equipments and safety measures and other incidental necessary to completes the work by mechanical means and /or labour (if any required complete as per directions of Engineer-in Charge) All useful materials, such as stones, shingles, 398.13cum useful stone during the course of execution shall be made @ 300/- cum on prorate basis. Any loss to the public and private property during the courses of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respect. including all leads and lifts as per direction of the Engineer-in-Charge.	2127.68	231.61	Rupees Two Hundred Thirty One and Paise Sixty One Only	492783.00
					492783.00
			Quoted rate in figer+ / (%-----)		
			Quoted rate in words		

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 150000

Earnest Money: 30000.00

Time: one Month

R/R Damages on Various Road under sainj Sub-Division (Sainj-Section) (SH:- Hiring of Tipper for carriage of debris /stone)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate In fig.	Rate in words		
1	Hiring of full size tipper 5.50 cum/10 tonne capacity to be deployed for disposing /carrying of material like earth kanker, moorum shingle and boulders etc. including cost of fuel, oil lubricant and wages of operational staff, any repair breakage during operation will be carried out by the owner at his own risk and cost including shifting of vehicle from one place to other at required location, actual working hours will be accounted for the payment and six hours per day working will be required . having of front end loading capacity 1.00 cum i/c all leads and lifts as per the direction of the Engineer-in-charge.	30.00	5000.00	Rupees Five Thousand Only	Per/Hour	150000.00
						150000.00
			Quoted rate in fig+/-(%-----)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 150000

Earnest Money: 30000.00

Time: one Months

R/R Damages on Various Road under sainj Sub-Division (Sainj-Section) (SH:- Hiring of Tipper for carriage of debris /stone)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of full size tipper 5.50 cum/10 tonne capacity to be deployed for disposing /carrying of material like earth kanker, moorum shingle and boulders etc. including cost of fuel, oil lubricant and wages of operational staff, any repair breakage during operation will be carried out by the owner at his own risk and cost including shifting of vehicle from one place to other at required location, actual working hours will be accounted for the payment and six hours per day working will be required. Having of front end loading capacity 1.00 cum i/c all leads and lifts as per the direction of the Engineer-in-charge.	30.00	5000.00	Rupees Five Thousand Only	Per /Hour	150000.00
						150000.00
			Quoted rate in figer+/- (-----)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 267750

Earnest Money: 5355.00

Time: one Months

R/R Damages on Various Road under sainj Sub-Division (Sainj-Section) (SH:- Hiring of JCB for removal of slips)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB excavator to be deployed for removal of slip i/c cost of fuel oil, lubricant, wages of operational staffs any repair package during operation will be carried out at his risk and cost including carrying of machinery from one place to another at required location, actual working hour will be accounted for payment and proper disposal slip/ snow by the contractor will be insured and i/c all leads and lifts as per the direction of the Engineer-in-Charge.	255.00	1050.00	Rupees One Thousand Fifty Only	Per /Hour	267750.00
						267750.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.:- 99750/-

Earnest Money 2000.00

Time: one Months

Restoration of snow/Rain damages on Various Road under Theog Sub-Division (SH:- Supplying and Stacking at site crusher sand in various Road & Various RDs)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Supply and stacking at site of work crusher sand clean and free from adherent coating and organic matter and shall not contain any appreciable amount of nayclay bails pills etc.in all leads and lifts as per the direction of the Engineer-in-Charge.	105.00	950.00	Rupees Nine Hundred Fifty Only	Per/cum	99750.00
						99750.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			



Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 491138
 Earnest Money: 7850.00
 Time: one Months

R/R Damages on Rahighat to Kiartoo Road Km 0/0 to 9/0 (SH:- C/O B/wall at RD Km 3/980 to 4/010)						
Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Amount
				Rate in words	Unit	
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slope and disposing of excavated earth with in lift upto 15 mtr. and a lead upto 20 mtr as per technical specification clause 1603.1 including all leads and lifts or as per the direction of Engineer - in Charge.	66.00	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	Per Cum meter	9818.00
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	33.00	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum meter	7065.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203 . (1:4:8.) 40 mm Agg.including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	105.22	4378.4C	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per Cum meter	460695.00
4	Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 110 mm dia (4 Kg Cm2 pressure) PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	56.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	13560.00
						491138.00
			Quoted rate in figer+/-(%-----)			
				Quoted rate in words		


 Executive Engineer,
 (B&R) Division,
 H.P.P.W.D., Theog