



E-Mail id - ee-bil2-hp@nic.in
Phone No, 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 14/02/2024 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 13/02/2024 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	Restoration of Rain damages on link road to Deoth Dabbar road Km. 0/0 to 10/960 (SH:- C/o R/wall at RD 4/075 to 4/080 and 4/090 to 4/095).	Rs. 1,60,558/-	Rs. 3,300/-	Rs. 350/-	Three Month
2	Restoration of Rain damages on Navgaon Beri road Km. 4/350 to 23/700 (SH:- C/o R/wall at RD 13/135 to 13/145)	Rs. 2,54,638/-	Rs. 5,100/-	Rs. 350/-	Three Month
3	Restoration of Rain damages on Laraghat Bathoh Bholi road Km. 0/0 to 10/500 (SH:- C/o R/wall at RD 0/300 to 0/306)	Rs. 2,28,561/-	Rs. 4,600/-	Rs. 350/-	Three Month
4	Restoration of Rain damages on Deoth Lagghat Jamli road Km. 0/0 to 13/180 (SH:- C/o R/wall at RD 3/385 to 3/393 and 3/432 to 3/441)	Rs. 4,79,433/-	Rs. 9,600/-	Rs. 350/-	Three Month
5	Construction of link road Neri to Ashamajari Km. 0/0 to 1/600 (SH:- Construction of 900mm dia hume pipe culverts at RD 0/975)	Rs. 2,27,629/-	Rs. 4,600/-	Rs. 350/-	Three Month
6	Restoration of Rain damages on Deoth Dabber road Km. 0/0 to 10/980 (SH:- C/o R/wall at RD 7/840 to 7/855)	Rs. 4,73,503/-	Rs. 9,500/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

SH
Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2023-

13644-53

Dated:- 06-02-2024

Copy forwarded to the following for information and necessary action:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

LD
Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.									
Estimated cost:- Rs.1,60,558/-Only.									
Earnest Money :- Rs.3,300/-									
Time:- Three Months.									
NAME OF WORK:- Restoration of Rain Damages on link road to Deoth Dabbar road km 0/00 to 10/960 (SH:- C/o R/wall at RD 4/075 to 4/080 and 4/090 to 4/095)									
Sr No.	Description of Items.	Quantity		Rates in		Unit	Amount		
				Figure.	Words.				
1	2	3	4	5	6	7			
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.75	cubic metre			Per cubic metre			7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.50	Cubic metre			Per Cubic metre			
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.15	Cubic metre.			Per Cubic Metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00	Nos.			Each			
Total:-									

Executive Engineer,
Bilaspur Division No.2,
Bilaspur (M.P.)
P.W.D., Bilaspur (M.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,54,638/-Only.

Earnest Money :- Rs.5,100/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Navgoan Beri road km 4/350 to 23/700 (SH:- C/o R/wall at RD 13/135 to 13/145)

Description of items.

Description of items.					
Sr No.	Quantity	Rates in		Unit	Amount
		Figure.	Words..		
1	3	4	5	6	7
1	24.30	cubic metre		Per cubic metre	
Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge, ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	52.90	Cubic metre		Per Cubic metre	
Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
3	12.00	Cubic metre.		Per Cubic Metre	
Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204, 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
4	24.00	Nos.		Each	
Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
Total:-					

Executive Engineer,
 Bilaspur Division No. 2,
 P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.			Estimated cost:- Rs.2,28,561/-Only.			
			Earnest Money :- Rs.4,600/-			
			Time:- Three Months.			
NAME OF WORK:- Restoration of Rain Damages on Laraghat Bathoh Bholi road km 0/00 to 10/500 (SH:- C/O R/wall at RD 0/300 to 0/306)						
Sl No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 27.66	4 cubic metre	5 Per cubic metre	6 Per cubic metre	7 7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 76	Cubic metre		Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.64	Cubic metre.		Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.		Each	
Total:-						

Executive Engineer.
Batespur Division No. 11
P.W.D., Bhisopur (H.P.)

SCHEDULE OF QUANTITY.						Estimated cost:- Rs.4,79,433/-Only.	
						Earnest Money :- Rs.9,600/-	
						Time:- Three Months.	
NAME OF WORK:- Restoration of Rain Damages on Deoth Lagghat Jamli road 0/00 to 13/180 (SH:- C/o R/wall at RD 3/385 to 3/393 & 3/432 to 3/441)							
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount	
			Figure.	Words.			
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.47	cubic metre		Per cubic metre		
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	96.66	Cubic metre		Per Cubic metre		
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.79	Cubic metre.		Per Cubic Metre		
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.00	Nos.		Each		
Total:-							

Executive Engineer:
Bilaspur Division No. 1
P.W.D., Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,27,629/-Only.

Earnest Money :- Rs 4,600/-

Time:- Three Months.

NAME OF WORK:- Construction of link road Neri to Ashamajhari km 0/00 to 1/600 (SH:- Construction of 900 mm dia Hume pipe culverts at RD 0/975)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	46.45	cubic metre		Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.90	Cubic metre		Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.90	Cubic Metre		Per Cubic Metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.47	Cubic metre.		Per Cubic Metre	
5	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Running Meter		Per Running Meter	

6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.88	Cubic metre.			Per Cubic Metre
7	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Nos.			Each
Total:-						


 Engineer,
 Bilaspur Division No. 2,
 H.P. Field, Bilaspur (H.P.).

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.4,73,503/-Only.						
Earnest Money :- Rs.9,500/-						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain Damages on Deoth Dabber road km 0/00 to 10/980 (SH:- C/o R/wall at Rd 7/840 to 7/855)						
Sr No.	Description of items.	Quantity		Rates in		Unit
				Figure.	Words.	
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 44.40	cubic metre	4	5 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	99.00	Cubic metre			
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.35	Cubic metre.			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	36.00	Nos.			
Total:-						

Executive Engineer,
Bilaspur Division No. 11
Bilaspur, M.P.
11/11/2019