



Office of
EXECUTIVE ENGINEER (KULLU DIVISION)
H.P. PUBLIC WORKS DEPARTMENT, KULLU-175101
FAX: 01902-222571, E.mail. ee-kul2-hp@nic.in

No.PW/KD/TA/Tender/2023-2024- **25182-89**

Dated:- **3-2-2024**


To

The Executive Engineer, I.T. Cell,
Nigam Bihar Shimla-2.

Subject:- Publishing of Notice inviting tender.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website 13.02.2024 as per notification issued by Secretary (PW) to the Govt. of HP Shimla vide letter No.PBW(S)A(3)1/2020 dated 16.07.2021. As per works mentioned in the Tender Notice is urgent nature of work in the public interest.


DA/As above.


**Executive Engineer,
Kullu Division,
HP. PWD, Kullu.**

Copy alongwith notice inviting tender is forwarded to the following for information and necessary action.

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. Supdt./DAO/HDM of this office.
5. Notice Board.

DA/Nil.


**Executive Engineer,
Kullu Division,
HP. PWD, Kullu.**

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

The Executive Engineer, Kullu Division HP.PWD, Kullu on behalf of the Government of Himachal Pradesh invites the **offline tender i.e. on percentage rates** for the following works from the eligible contractors/Firms registered with HP.PWD, department, so as to reach in the office as per time schedule given below:-

1	Date of receipt of application for tender form.		12.02.2024 upto 4:00 PM		
2	Date of issue/sale of tender form.		12.02.2024 upto 4:00 PM		
3	Date of receipt of tender.		13.02.2024 upto 10:30 AM		
4	Date of opening tender.		13.02.2024 upto 11:00 AM		
Sr. No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	2	3	4	5	6
1	C/O Ambulance road from Bhutti Chowk to Chamunda Naggar Km. 0/00 to 0/200 (SH:- Providing and laying paver block flooring and fixing of metal beam).	3,79,053/-	7,600/-	Two months	350/-
2	C/O Ambulance road from Bhutti Chowk to Chamunda Naggar Km. 0/00 to 0/200 (SH:- Construction of PCC retaining wall at RD 0/110 to 0/120).	4,23,478/-	8,600/-	Two months	350/-
3	C/O Ambulance road from Bhutti Chowk to Chamunda Naggar Km. 0/00 to 0/200 (SH:- Construction of PCC pushta at RD 0/110 to 0/120).	4,78,323/-	9,800/-	Two month	350/-
4	Improvement of Black Spot by providing corrective measures on Kullu Karon road Km. 0/00 to 15/000 (SH:- Providing and fixing "W" metal beam railing between Km. 7/360 to 7/470).	4,77,642/-	9,600/-	Two months	350/-
5	Improvement of Black Spot by providing corrective measures on Kullu Karon road (SH:- Providing and fixing "W" metal beam railing between Km. 11/650 to 11/750).	4,34,089/-	8,800/-	Two months	350/-
6	Improvement of Black Spot by providing corrective measures on Kullu Karon road (SH:- Providing and fixing "W" metal beam railing between Km. 13/900 to 14/010).	4,77,642/-	9,600/-	Two months	350/-
7	Improvement of Black Spot by providing corrective measures on Kullu Karon road (SH:- Providing and fixing "W" metal beam railing between Km. 11/550 to 11/650).	4,34,089/-	8,800/-	Two months	350/-
8	Flash flood on Sainik Chowk (Bhunter) to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of RCC retaining wall between RD 0/865 to 0/870).	4,90,880/-	10,000/-	Two months	350/-
9	Flash flood on Sainik Chowk (Bhunter) to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of RCC retaining wall between RD 0/870 to 0/875).	4,90,880/-	10,000/-	Two months	350/-
10	Flash flood on Sainik Chowk (Bhunter) to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of RCC retaining wall between RD 0/875 to 0/880).	4,69,633/-	9,500/-	Two months	350/-
11	Flash flood on Sainik Chowk (Bhunter) to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of RCC retaining wall between RD 0/880 to 0/885).	4,69,633/-	9,500/-	Two months	350/-
12	Flash flood on Sainik Chowk (Bhunter) to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of RCC retaining wall between RD 0/885 to 0/890).	4,69,633/-	9,500/-	Two months	350/-

13	Flash flood on Sainik Chowk (Bhunter) to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of RCC retaining wall between RD 0/890 to 0/895).	4,69,633/-	9,500/-	Two months	350/-
14	Flash flood on Sainik Chowk (Bhunter) to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of RCC retaining wall between RD 0/895 to 0/900).	4,69,633/-	9,500/-	Two months	350/-
15	Flash flood on Sainik Chowk (Bhunter) to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of RCC retaining wall between RD 0/900 to 0/905).	4,69,633/-	9,500/-	Two months	350/-

The tender documents shall be issued only to those contractor/firm who fulfill the following documents with the application.

1	The valid enlistment/Registration of contractor in Appropriate Class.
2	Permanent account No. (PAN No.).
3	G.S.T. No.
4	Earnest Money in the shape of National Saving certificate/time deposit account in the any of the post office in HP F.D.R. from any Nationalized Bank duly pleaded in favour of the Executive Engineer, Kullu Division HP.PWD, Kullu.
5	The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6	The offer of the tender shall remain valid upto 90 days after the opening of tender.
7	Ambiguous/telephonic conditional tenders of tender by fax/E-mail not be considered and will be summarily be rejected.
8	Executive Engineer, reserve the right to reject or cancel any or all tenders without assigning any reasons.
9	If the date given above happens to be holiday the same shall be processed on next working day.
10	The contractor/firm must quote their rates in words as well as in figures failing which XEN reserve the right to accept/reject any or all tenders.
11	The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12	One contractor shall not have more than two major works in hand at a time.
13	Work should be completed by the contractor within stipulated period.
14	The rates beyond over +5% will be rejected, besides this the Additional Performance security will have to borne @ 20% & 30% for unbalanced bid in case rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively. The tender beyond the limit of -30% will also be excepted.


Executive Engineer,
Kullu Division,
HP.PWD, Kullu.

No.PW/KD/TA/2023-2024-

25190-280

Dated:- 3-2-24

Copy is forwarded to the following for information and necessary action:-

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. All the Executive Engineers, in HP.PWD,.
5. All the Assistant Engineers, working under this Division.
6. All the registered contractors, in HP.PWD.
7. Supdt./DA/HDM of this office.
8. Notice Board.


Executive Engineer,
Kullu Division,
HP.PWD, Kullu.

13/9/24

(2)

SCHEDULE OF QUANTITY

Name of work:- C/o Ambulance road from Bhutti chowk to Chamunda Nagar Km 0/00 to 0/200 .
(SH:- Providing and laying paver block flooring and fixing of Metal beam).

Estimated cost:- Rs. 3,79,053.00
Earnest money :- Rs. 7,600.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Providing and laying heavy duty precast cement concrete inter locking paver blocks vibro compacted upto M- 50 (Fifty grade including border or kurb block grey or coloured over sub-base of concrete with 25mm (Twenty five millimetre) thick average thickness of cement mortar 1:4 (One cement : Four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing & polishing complete (Sub base concrete floor to be paid for 80mm thick inter locking blocks within all leads and lifts including carriage of material in all respect and as per direction of Engineer-in-charge.	152.00	1480.40	Rupees One thousand four hundred eighty and paise forty only.	Per Square metre	225021.00
2	Providing and erecting a "W" Metal Beam crash barrier comprising of 3 mm (Three millimetre) thick corrugated sheet metal beam rail 70 cm (Seventy centimetre) above ground level fixed of ISMC series channel vertical row post 150*75*5 mm (One hundred fifty x Seventy five x Five millimetre) spaced 2.00 m (Two metre) C/C 1.80 m (One point eighty metre) height, 1.10 m (One point ten metre) below ground level all steel post and filaments to be galvanized hot dip process and fittings to confirm to IS 1367 and 1364 metal beam rail to be fixed on the vertical post with a spacer of channels section 150*75*5 mm, (One hundred fifty x Seventy five x Five millimetre) 330 cm (Three hundred thirty centimetre) long compion as per clause 810 within all leads and lift of materials and as per direction of Engineer-in- charge.	40.00	3850.80	Rupees Three thousand eight hundred fifty and paise eighty only.	Per running metre	154032.00
	Total					379053.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

2

SCHEDULE OF QUANTITY

Name of work:- C/o Ambulance road from Bhutti chowk to Chamunda Nagar Km 0/00 to 0/200 .
(SH:- Construction of P.C.C. Retaining wall at RD 0/110 to 0/120)

Estimated cost:- Rs. 4,23,478.00
Earnest money :- Rs. 8,600.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	64.40	5944.15	Rupees Five thousand nine hundred forty four and paise fifteen only.	Per cubic metre	382803.00
2	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	15.60	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	25037.00
3	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	40.00	390.95	Rupees Three hundred ninety and paise ninety five only.	Each	15638.00
	Total					423478.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- C/o Ambulance road from Bhutti chowk to Chamunda Nagar Km 0/00 to 0/200 .
(SH:- Construction of P.C.C. Pushpa at RD 0/110 to 0/120)

Estimated cost:- Rs. 4,78,323.00
Earnest money :- Rs. 9,800.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	48.75	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	17811.00
2	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	75.50	5944.15	Rupees Five thousand nine hundred forty four and paise fifteen only.	Per cubic metre	448783.00
3	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	30.00	390.95	Rupees Three hundred ninety and paise ninety five only.	Each	11729.00
	Total					478323.00

Executive Engineer,
Kullu Division,
HP, PWD Kullu

(4)

SCHEDULE OF QUANTITY

Name of work:- Improvement of Black Spot by providing corrective measures on Kullu Karon road Km 0/00 to 15/000
(SH:- Providing and fixing "V" metal beam railing between Km 7/360 to 7/470).

Estimated cost:- Rs. 4,77,642.00
Earnest money:- Rs. 9,600.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	8.27	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	3021.00
2	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 PCC grade M-10 for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	8.18	6250.50	Rupees Six thousand two hundred fifty and paise fifty only.	Per cubic metre	51121.00
3	Providing and erecting a 'W' Metal Beam crash barrier comprising of 3 mm (Three millimetre) thick corrugated sheet metal beam rail 70 cm (Seventy centimetre) above ground level fixed of ISMC series channel vertical row post 150x75x5 mm (One hundred fifty x Seventy five x Five millimetre) spaced 2.00 m (Two metre) C/C 1.50 m (One point fifty metre) height, 0.80 m (Zero point eighty metre) below ground level all steel post and fittings to be galvanized hot dip process and fittings to confirm to IS 5986 or 10748 or 2062 or equivalent and metal beam rail to be fixed on the vertical post with a spacer of channels section 150x75x5 mm, (One hundred fifty x Seventy five x Five millimetre) 330 mm (Three hundred thirty millimetre) long compion as per clause 810 within all leads and lift of materials and as per direction of Engineer-in-charge.	110.00	3850.00	Rupees Three thousand eight hundred fifty only.	Per running metre	423500.00
	Total					477642.00

Executive Engineer,
 Kullu Division
 HP.PWD Kullu

3

SCHEDULE OF QUANTITY

Name of work:- Improvement of Black Spot by providing corrective measures on Kullu Karon road
(SH:- Providing and fixing "W" metal beam railing between Km 11/650 to 11/750).

Estimated cost:- Rs. 4,34,089.00
Earnest money :- Rs. 8,800.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	7.50	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	2739.00
2	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 PCC grade M-10 for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	7.42	6250.50	Rupees Six thousand two hundred fifty and paise fifty only.	Per cubic metre	46350.00
3	Providing and erecting a 'W' Metal Beam crash barrier comprising of 3 mm (Three millimetre) thick corrugated sheet metal beam rail 70 cm (Seventy centimetre) above ground level fixed of ISMC series channel vertical row post 150x75x5 mm (One hundred fifty x Seventy five x Five millimetre) spaced 2.00 m (Two metre) C/C 1.50 m (One point fifty metre) height, 0.80 m (Zero point eighty metre) below ground level all steel post and fittings to be galvanized hot dip process and fittings to confirm to IS 5986 or 10748 or 2062 or equivalent and metal beam rail to be fixed on the vertical post with a spacer of channels section 150x75x5 mm, (One hundred fifty x Seventy five x Five millimetre) 330 mm (Three hundred thirty millimetre) long complian as per clause 810 within all leads and lift of materials and as per direction of Engineer-in-charge.	100.00	3850.00	Rupees Three thousand eight hundred fifty only.	Per running metre	385000.00
	Total					434089.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

6

SCHEDULE OF QUANTITY

Name of work:- Improvement of Black Spot by providing corrective measures on Kullu Karon road.
(SH:- Providing and fixing "W" metal beam railing between Km 13/900 to 14/010).

Estimated cost:- Rs. 4,77,642.00
Earnest money :- Rs. 9,600.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	8.27	365.35	Rupees Three hundred sixty five and paisa thirty five only	Per cubic metre	3021.00
2	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 PCC grade M-10 for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	8.18	6250.50	Rupees Six thousand two hundred fifty and paise fifty only.	Per cubic metre	51121.00
3	Providing and erecting a "W" Metal Beam crash barrier comprising of 3 mm (Three millimetre) thick corrugated sheet metal beam rail 70 cm (Seventy centimetre) above ground level fixed of ISMC series channel vertical row post 150x75x5 mm (One hundred fifty x Seventy five x Five millimetre) spaced 2.00 m (Two metre) C/C 1.50 m (One point fifty metre) height, 0.80 m (Zero point eighty metre) below ground level all steel post and fittings to be galvanized hot dip process and fittings to confirm to IS 5986 or 10748 or 2062 or equivalent and metal beam rail to be fixed on the vertical post with a spacer of channels section 150x75x5 mm, (One hundred fifty x Seventy five x Five millimetre) 330 mm (Three hundred thirty millimetre) long compion as per clause 810 within all leads and lift of materials and as per direction of Engineer-in-charge.	110.00	3850.00	Rupees Three thousand eight hundred fifty only.	Per running metre	423500.00
	Total					477642.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

7

SCHEDULE OF QUANTITY

Name of work:- Improvement of Black Spot by providing corrective measures on Kullu Karon road.
(SH:- Providing and fixing "W" metal beam railing between Km 11/550 to 11/650).

Estimated cost:- Rs. 4,34,089.00
Earnest money :- Rs. 8,800.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary soil within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	7.50	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	2739.00
2	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 PCC grade M-10 for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	7.42	6250.50	Rupees Six thousand two hundred fifty and paise fifty only.	Per cubic metre	46350.00
3	Providing and erecting a "W" Metal Beam crash barrier comprising of 3 mm (Three millimetre) thick corrugated sheet metal beam rail 70 cm (Seventy centimetre) above ground level fixed of ISMC series channel vertical row post 150x75x5 mm (One hundred fifty x Seventy five x Five millimetre) spaced 2.00 m (Two metre) C/C 1.50 m (One point fifty metre) height, 0.80 m (Zero point eighty metre) below ground level all steel post and fittings to be galvanized hot dip process and fittings to confirm to IS 5986 or 10748 or 2062 or equivalent and metal beam rail to be fixed on the vertical post with a spacer of channels section 150x75x5 mm, (One hundred fifty x Seventy five x Five millimetre) 330 mm (Three hundred thirty millimetre) long compition as per clause 810 within all leads and lift of materials and as per direction of Engineer-in-charge.	100.00	3850.00	Rupees Three thousand eight hundred fifty only.	Per running metre	385000.00
	Total					434089.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Flash Flood on Sainik Chowk (Bhuntar) to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850.

Estimated cost:- Rs. 4,90,880.00
Earnest money :- Rs. 10,000.00

(SH:- Construction of RCC Retaining wall between RD 0/865 to 0/870).

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	37.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13701.00
2	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	561.64	132.83	Rupees One hundred thirty two and paise eighty three only	Per cubic metre	74603.00
3	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate nominal mix in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	46.50	8472.58	Rupees Eight thousand four hundred seventy two and paise fifty eight only.	Per cubic metre	393975.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (One hundred millimetre) dia PVC pipe extending through the full with of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204,3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	22	390.95	Rupees Three hundred ninety and paise ninety five only	Each	8601.00
	Total					490880.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Flash Flood on Sainik Chowk (Bhuntar) to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850 .

Estimated cost:- Rs. 4,90,880.00
Earnest money :- Rs. 10,000.00

Time :- Two months.

(SH:- Construction of RCC Retaining wall between RD 0/870 to 0/875)

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	37.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13701.00
2	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	561.64	132.83	Rupees One hundred thirty two and paise eighty three only	Per cubic metre	74603.00
3	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate nominal mix in open foundations complete as per drawing and technical specification clause 802.803, 1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	46.50	8472.58	Rupees Eight thousand four hundred seventy two and paise fifty eight only.	Per cubic metre	393975.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	22	390.95	Rupees Three hundred ninety and paise ninety five only	Each	8601.00
	Total					490880.00

Executive Engineer,
Kullu Division ,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Flash Flood on Sainik Chowk (Bhuntar) to Manikaran Chowk (Hatnithan) road Km 0/00 to 1/850 .

Estimated cost:- Rs. 4,69,633.00
Earnest money :- Rs. 9,500.00

(SH:- Construction of RCC Retaining wall between RD 0/875 to 0/880).

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	37.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13701.00
2	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	561.64	95.00	Rupees Ninety five and paise zero only	Per cubic metre	53356.00
3	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate nominal mix in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	46.50	8472.58	Rupees Eight thousand four hundred seventy two and paise fifty eight only.	Per cubic metre	393975.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (One hundred millimetre) dia PVC pipe extending through the full with of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204,3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	22	390.95	Rupees Three hundred ninety and paise ninety five only	Each	8601.00
	Total					469633.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Flash Flood on Sainik Chowk (Bhuntar) to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850 .

Estimated cost:- Rs. 4,69,633.00
Earnest money :- Rs. 9,500.00

(SH:- Construction of RCC Retaining wall between RD 0/880 to 0/885).

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	37.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13701.00
2	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	561.64	95.00	Rupees Ninety five and paise zero only	Per cubic metre	53356.00
3	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate nominal mix in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	46.50	8472.58	Rupees Eight thousand four hundred seventy two and paise fifty eight only.	Per cubic metre	393975.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (One hundred millimetre) dia PVC pipe extending through the full with of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in- charge.	22	390.95	Rupees Three hundred ninety and paise ninety five only	Each	8601.00
	Total					469633.00


Executive Engineer,
Kullu Division ,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Flash Flood on Sainik Chowk (Bhuntar) to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850 .

Estimated cost:- Rs. 4,69,633.00
Earnest money :- Rs. 9,500.00

(SH:- Construction of RCC Retaining wall between RD 0/885 to 0/890).

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	37.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13701.00
2	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	561.64	95.00	Rupees Ninety five and paise zero only	Per cubic metre	53356.00
3	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate nominal mix in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	46.50	8472.58	Rupees Eight thousand four hundred seventy two and paise fifty eight only.	Per cubic metre	393975.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (One hundred millimetre) dia PVC pipe extending through the full with of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in- charge.	22	390.95	Rupees Three hundred ninety and paise ninety five only	Each	8601.00
	Total					469633.00


Executive Engineer,
Kullu Division ,
HP.PWD/Kullu

SCHEDULE OF QUANTITY

Name of work:- Flash Flood on Sainik Chowk (Bhuntar) to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850.

Estimated cost:- Rs. 4,69,633.00
Earnest money :- Rs. 9,500.00

(SH:- Construction of RCC Retaining wall between RD 0/890 to 0/895).

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	37.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13701.00
2	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	561.64	95.00	Rupees Ninety five and paise zero only	Per cubic metre	53356.00
3	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate nominal mix in open foundations complete as per drawing and technical specification clause 802.803, 1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	46.50	8472.58	Rupees Eight thousand four hundred seventy two and paise fifty eight only.	Per cubic metre	393975.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	22	390.95	Rupees Three hundred ninety and paise ninety five only	Each	8601.00
	Total					469633.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Flash Flood on Sainik Chowk (Bhuntar) to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850 .

Estimated cost:- Rs. 4,69,633.00
Earnest money :- Rs. 9,500.00

Time :- Two months.

(SH:- Construction of RCC Retaining wall between RD 0/895 to 0/900) .

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	37.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13701.00
2	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	561.64	95.00	Rupees Ninety five and paise zero only	Per cubic metre	53356.00
3	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate nominal mix in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	46.50	8472.58	Rupees Eight thousand four hundred seventy two and paise fifty eight only.	Per cubic metre	393975.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full with of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204,3.7. within all leads and lift of materials and as per direction of Engineer-in- charge.	22.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	8601.00
	Total					469633.00


Executive Engineer,
Kullu Division
HP,PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Flash Flood on Sainik Chowk (Bhuntar) to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850 .

Estimated cost:- Rs. 4,69,633.00
Earnest money :- Rs. 9,500.00

(SH:- Construction of RCC Retaining wall between RD 0/900 to 0/905).

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	37.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13701.00
2	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	561.64	95.00	Rupees Ninety five and paise zero only	Per cubic metre	53356.00
3	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate nominal mix in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	46.50	8472.58	Rupees Eight thousand four hundred seventy two and paise fifty eight only.	Per cubic metre	393875.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in- charge.	22	390.95	Rupees Three hundred ninety and paise ninety five only	Each	8601.00
	Total					469633.00

Executive Engineer,
Kullu Division ,
HP.PWD Kullu