

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(Padhar)E-Tender-NIT/2023-24- 24464-66 Dated:- 28/2/24

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 11.03.2024 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 07.03.2024 upto 1.00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Construction of Kufri Nihon Kheel Damela road Km 0/0 to 8/100. (SH:- Construction of Breast wall at RD 5/840 to 5/855)	2,92,900.00	5,900/-	350/-	One month
2	Construction of Kufri Kheel Damela road Km 0/0 to 8/100. (SH:- Construction of 900 mm dia Hume pipe culvert alongwith wing walls at R.D. 6/135)	2,71,244.00	5,400/-	350/-	One month
3	Restoration of rain damages on Balh to Ropa road Km 0/0 to 5/100. (SH:- Construction of Retaining wall from Km 3/023 to 3/030)	3,85,473.55	7,700/-	350/-	One month
4	Restoration of rain damages on Thaltukhod Graman Panjound road Km 0/0 to 4/500. (SH:- Construction of retaining wall at R.D. 0/570 to 0/585)	4,17,440.09	8,300/-	350/-	One month
5	Construction of Tandoo Mathaneul Shadla road Km 0/0 to 4/500. (SH:- Construction of Retaining wall at R.D. 0/350 to 3/360)	3,97,175.47	7,900/-	350/-	One month
6	Construction of Tandoo Mathaneul Shadla Trambli road Km 0/0 to 4/750. (SH:- Construction of Retaining wall at R.D. 4/510 to 4/530)	3,56,358.65	7,100/-	350/-	One month
7	Construction of Link road Ropa Khad Harizan Basti Ropru to Nasloh Road Km 0/0 to 3/450. (SH:- Construction of Retaining wall at R.D. 0/105 to 0/113)	2,45,983.16	4,900/-	350/-	One month
8	Construction of Bijani to Labandhi road Km 0/0 to 3/0. (SH:- Construction of 900mm dia R.C.C. Hume pipe culvert at R.D. 1/465)	2,39,512.89	4,800/-	350/-	One month
9	Construction of Bijani to Labandhi road Km 0/0 to 3/0. (SH:- Construction of 900mm dia R.C.C. Hume pipe culvert at R.D. 1/300)	2,36,781.89	4,700/-	350/-	One month
10	Restoration of rain damages on Shegali Prasher Road Km 0/0 to 22/510. (SH:- Construction of Retaining wall at R.D. 5/405 to 5/427)	2,69,175.84	5,400/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.

2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh


PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 292900.00
Earnest Money Rs:- 5900.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP PWD, at Padhar.						
Name of work :- Construction of Kufri Nihon Kheel Damela road Km. 0/0 to 8/100 (Sub Head:- Construction of Breast wall at R.D. 5/840 to 5/855).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	42.75	Per cubic metre	461.00	19708.00	Rupees Nineteen Thousand Seven Hundred Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	52.80	Per cubic metre	5065.90	267480.00	Rupees Two Lakh Sixty Seven Thousand Four Hundred Eighty Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	285.60	5712.00	Rupees Five Thousand Seven Hundred Twelve Only
Total in figure :					292900.00	Rupees Two Lakh Ninety Two Thousand Nine Hundred Only
Total in Words :					Rupees Two Lakh Ninety Two Thousand Nine Hundred Only	

Executive Engineer,
Mandi Division No.I,
HP, PWD, at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 271244.00
 Earnest Money Rs:- 5400.00
 Time :- One months


Tender Inviting Authority: Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work:- Construction of Kufri Kheel Damela road Km. 0/00 to 8/100 (Sub Head:- Construction of 900 mm dia Hume Pipe culvert along with wing walls at R.D. 6/135).						
Contract No.:						
Name of Bidder/Bidding Firm/ Company:						
SCHEDULE OF WORKS						
Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including settling out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sites and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	45.97	Per cubic metre	461.00	21192.00	Rupees Twenty One Thousand One Hundred Ninety Two Only
2	Providing and laying concrete Mechanically mixed and vibrated mix 1:5:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	0.90	Per cubic metre	4906.50	4416.00	Rupees Four Thousand Four Hundred Sixteen Only
3	Providing concrete for plain reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement: three sand: twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.05	Per cubic metre	5614.30	50809.00	Rupees Fifty Thousand Eight Hundred Nine Only
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement: five sand: Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	32.78	Per cubic metre	5065.90	166060.00	Rupees One Lakh Sixty Six Thousand Sixty Only
5	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	5.00	Per running metre	3465.50	17328.00	Rupees Seventeen Thousand Three Hundred Twenty Eight Only
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	5.59	Per cubic metre	1433.20	8012.00	Rupees Eight Thousand Twelve Only
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	12.00	Each	285.60	3427.00	Rupees Three Thousand Four Hundred Twenty Seven Only
Total In Figure					271244.00	Rupees Two Lakh Seventy One Thousand Two Hundred Forty Four Only
Rate in Words						Rupees Two Lakh Seventy One Thousand Two Hundred Forty Four Only

Executive Engineer,
 Mandi Division No. 1,
 HP.PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 385473.55
Earnest Money Rs:- ~~7400.00~~
One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- Restoration of damages on Balh to Ropa road km.0/00 to 5/100. (Sub Head:- Construction of Retaining wall from km. 3/023 to 3/030).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	30.03	Per cubic metre	461.00	13843.83	Rupees Thirteen Thousand Eight Hundred Forty Three and Paise Eighty Three Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	70.30	Per cubic metre	5079.20	357067.76	Rupees Three Lakh Fifty Seven Thousand Sixty Seven and Paise Seventy Six Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	285.50	3426.00	Rupees Three Thousand Four Hundred Twenty Six Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	7.77	Per cubic metre	1433.20	11135.96	Rupees Eleven Thousand One Hundred Thirty Five and Paise Ninety Six Only
Total in figure :					385473.55	Rupees Three Lakh Eighty Five Thousand Four Hundred and Paise Fifty Five Only
Total in Words :		Rupees Three Lakh Eighty Five Thousand Four Hundred Seventy Three and Paise Fifty Five Only				


Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 417440.09
Earnest Money Rs:- 8300.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I H.P.P.W.D. at Padhar.						
Name of work :- Restoration of rain damages on Thaltukhod Graman Panjoundroad Km. 0/0 to 4/500. (Sub Head:- Construction of retaining wall at R.D. 0/570 to 0/585.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	33.79	Per cubic metre	461.00	15577.19	Rupees Fifteen Thousand Five Hundred Seventy Seven and Paise Nineteen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	66.70	Per cubic metre	5491.00	366249.70	Rupees Three Lakh Sixty Six Thousand Two Hundred Forty Nine and Paise Seventy Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.40	Per cubic metre	1433.00	29233.20	Rupees Twenty Nine Thousand Two Hundred Thirty Three and Paise Twenty Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.00	Each	290.00	6380.00	Rupees Six Thousand Three Hundred Eighty Only
Total in figure :					417440.09	Rupees Four Lakh Seventeen Thousand Four Hundred Nine Only
Total in Words :		Rupees Four Lakh Seventeen Thousand Four Hundred			Forty and Paise Nine	Only


 Executive Engineer
 Mandi Division No.1
 H.P.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 397175.47
 Earnest Money Rs:- 7900.00
 Time :- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Construction of Tando Mathaneut Shadla Road Km. 0/00 to 4/500. (Sub Head: - Construction of Retaining wall at R.D. 0/350 to 0/360).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of Items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	29.70	Per cubic metre	461.00	13691.70	Rupees Thirteen Thousand Six Hundred Ninety One and Paise Seventy Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	78.83	Per cubic metre	4535.00	357494.05	Rupees Three Lakh Fifty Seven Thousand Four Hundred Ninety Four and Paise Five Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	45.00	Each	271.80	12231.00	Rupees Twelve Thousand Two Hundred Thirty One Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.60	Per cubic metre	1433.20	13758.72	Rupees Thirteen Thousand Seven Hundred Fifty Eight and Paise Seventy Two Only
Total in figure :					397175.47	Rupees Three Lakh Ninety Seven Thousand One Hundred Seventy Five and Paise Forty Seven Only
Total in Words :		Rupees Three Lakh Ninety Seven Thousand One Hundred Seventy Five and Paise Forty Seven Only				


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 356358.65
 Earnest Money Rs:- 7400.00
 Time :- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP PWD. at Padhar.						
Name of work :- Construction of Tandoo Mathaneul Shadla Trambli Road Km. 0/00 to 4/750. (Sub Head: - Construction of Retaining wall at R.D. 4/510 to 4/530).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	46.40	Per cubic metre	461.00	21390.40	Rupees Twenty One Thousand Three Hundred Ninety and Paise Forty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	68.55	Per cubic metre	4551.00	311971.05	Rupees Three Lakh Eleven Thousand Nine Hundred Seventy One and Paise Five Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	40.00	Each	274.00	10960.00	Rupees Ten Thousand Nine Hundred Sixty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.40	Per cubic metre	1433.00	12037.20	Rupees Twelve Thousand Thirty Seven and Paise Twenty Only
Total in figure :					356358.65	Rupees Three Lakh Fifty Six Thousand Three Hundred Fifty Eight and Paise Five Only
Total in Words :					Rupees Three Lakh Fifty Six Thousand Three Hundred Fifty Eight and Paise Sixty Five Only	

Executive Engineer,
 Mandi Division No. I,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 245983.16
 Earnest Money Rs:- 49000.00
 Time :- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD. at Padhar.						
Name of work :- Construction of Link Road Ropa Khad Harizan Basti Ropru to Nasloah Road Km. 0/00 to 3/450. (Sub Head: - Construction of Retaining wall at R.D. 0/105 to 0/113)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.96	Per cubic metre	461.00	10584.56	Rupees Ten Thousand Five Hundred Eighty Four and Paise Fifty Six Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	50.36	Per cubic metre	4476.00	225411.36	Rupees Two Lakh Twenty Five Thousand Four Hundred Eleven and Paise Thirty Six Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.00	Each	269.00	2421.00	Rupees Two Thousand Four Hundred Twenty One Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.28	Per cubic metre	1433.00	7566.24	Rupees Seven Thousand Five Hundred Sixty Six and Paise Twenty Four Only
Total in figure :					245983.16	Rupees Two Lakh Forty Five Thousand Nine Hundred Eighty Three and Paise Sixteen Only
Total in Words :		Rupees Two Lakh Forty Five Thousand Nine Hundred Eighty Three and Paise Sixteen Only				

Executive Engineer,
 Mandi Division No.1,
 HP, PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 239512.89
Earnest Money Rs:- 4800.00
Time :- Three months

Tender Inviting Authority: Executive Engineer, Mandi Division No. I HP PWD, at Padhar.									
Name of work:- Construction of Bijani to Labandhii road in Km 0/00 to 3/00. (Sub Head:- Construction of 900mm Dia R.C.C. Hume Pipe culvert at R.D. 1/465).									
Contract No.:-									
Name of Bidder/Bidding Firm/ Company:-									
SCHEDULE OF WORKS									
Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in	TOTAL AMOUNT with all Taxes excluding GST in	7	8	9
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including settling out, construction of shoring and bracing, removal of slumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	3	4	5	6	7	8	9	10
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including settling out, construction of shoring and bracing, removal of slumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	45.83	Per cubic metre	461.00	21127.63	Rupees Thousand One Hundred Twenty Seven and Paise Sixty Three Only			
2	Providing and laying concrete Mechanically mixed and vibrated mix 1:6:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.68	Per cubic metre	4383.40	7364.11	Rupees Seven Thousand Three Hundred Sixty Four and Paise Eleven Only			
3	Providing and laying concrete mechanically mixed and vibrated mix 1:4:8 (one cement: four sand: eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	22.75	Per cubic metre	4836.20	110023.55	Rupees One Lakh Ten Thousand Twenty Three and Paise Fifty Five Only			
4	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.73	Per cubic metre	5015.10	48796.92	Rupees Forty Seven Hundred Ninety Six and Paise Ninety Two Only			
5	Providing and laying concrete mechanically mixed and vibrated mix 1:5:10 (one cement: five sand: ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	0.97	Per cubic metre	4534.30	4398.27	Rupees Four Thousand Three Hundred Ninety Eight and Paise Twenty Seven Only			
6	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00	Per running metre	3462.90	24240.30	Rupees Twenty Four Thousand Two Hundred Forty and Paise Thirty Only			
7	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303. Rubble stone laid in cement mortar 1:3 (one cement : three sand) (Excavation for preparation of bed and cement concrete bedding to be measured and paid for separately) including curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	0.49	Per cubic metre	5148.60	2522.81	Rupees Two Thousand Five Hundred Twenty Two and Paise Eighty One Only			
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	18.00	Each	273.10	4915.80	Rupees Four Thousand Nine Hundred Fifteen and Paise Eighty Only			

9	Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	11.25	Per cubic metre	1433.20	16123.50	Rupees Sixteen Thousand One Hundred Twenty Three and Paise Fifty Only
Total in Figure					239512.89	Rupees Two Lakh Thirty Nine Thousand Five Hundred and Paise Eighty Nine Only
Quoted Rate in Words					Rupees Two Lakh Thirty Nine Thousand Five Hundred Nine Only	Twelve and Paise Eighty



 Executive Engineer,
 Mandi Division No. 1,
 HP.PWD. at Padhaur

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 236781.89
Earnest Money Rs:- 4700.00
Time :- Three months

Tender Inviting Authority: Executive Engineer, Mandi Division No. 1 HP PWD, at Padhar.

Name of work:- Construction of Bijani to Labandhi road in Km 0/00 to 3/00. (Sub Head:- Construction of R.C.C. Hume Pipe culvert at R.D. 1/300).

Contract No.:

Name of Bidder/Bidding Firm/ Company:

SCHEDULE OF WORKS

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including settling out, construction of shoring and bracing, removal of slumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	45.83	Per cubic metre	461.00	21127.63	Rupees Twenty One Hundred Twenty Seven and Paise Sixty Three Only
2	Providing and laying concrete Mechanically mixed and vibrated mix 1:6:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.68	Per cubic metre	4383.40	7364.11	Rupees Seven Thousand Three Hundred Sixty Four and Paise Eleven Only
3	Providing and laying concrete mechanically mixed and vibrated mix 1:4:8 (one cement: four sand: eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	22.75	Per cubic metre	4836.20	110023.55	Rupees One Lakh Ten Thousand Twenty Three and Paise Fifty Five Only
4	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.73	Per cubic metre	5015.10	48796.92	Rupees Forty Seven Hundred Ninety Six and Paise Ninety Two Only
5	Providing and laying concrete mechanically mixed and vibrated mix 1:5:10 (one cement: five sand: ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	0.97	Per cubic metre	4534.30	4398.27	Rupees Four Thousand Three Hundred Ninety Eight and Paise Twenty Seven Only
6	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2, as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00	Per running metre	3462.90	24240.30	Rupees Twenty Four Thousand Forty and Paise Thirty Only
7	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303. Rubble stone laid in cement mortar 1:3 (one cement : three sand) (Excavation for preparation of bed and cement concrete bedding to be measured and paid for separately) including curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	0.49	Per cubic metre	5148.60	2522.81	Rupees Two Thousand Five Hundred Twenty Two and Paise Eighty One Only
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical iso twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	8.00	Each	273.10	2184.80	Rupees Two Thousand One Hundred Eighty Four and Paise Eighty Only

9	Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	11.25	Per cubic metre	1433.20	16123.50	Rupees Sixteen Thousand One Hundred Twenty Three and Paise Fifty Only
Total in Figure					236781.89	Rupees Two Lakh Thirty Six Thousand Seven Hundred Eighty One and Paise
Quoted Rate in Words						Rupees Two Lakh Thirty Six Thousand Seven Hundred Eighty One and Paise


 Executive Engineer,
 Markit Division No. 1,
 HP.PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 269175.84
 Earnest Money Rs:- 5400.00
 Time :- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.						
Name of work :- Restoration of rain Damages on Shegali Prasher Road Km. 0/00 to 22/510. (Sub Head: - Construction of Retaining wall at R.D. 5/405 to 5/427).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	55.44	Per cubic metre	4494.00	249147.36	Rupees Two Lakh Forty Nine Thousand One Hundred Forty Seven and Paise Thirty Six Only
2	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.00	Each	272.00	4896.00	Rupees Four Thousand Eight Hundred Ninety Six Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.56	Per cubic metre	1433.00	15132.48	Rupees Fifteen Thousand One Hundred Thirty Two and Paise Forty Eight Only
Total in figure :					269175.84	Rupees Two Lakh Sixty Nine Thousand One Hundred Seventy Five and Paise Eighty Four Only
Total in Words :					Rupees Two Lakh Sixty Nine Thousand One Hundred Seventy Five and Paise Eighty Four Only	


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar