

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(Padhar)E-Tender-NIT/2023-24- 21956-58 Dated:- 7/2/24

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 16.02.2024 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 15.02.2024 upto 1:00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Improvement of Back spot on Kataula Batheri Arang road in Km 0/0 to 15/285. (SH:- Construction of Retaining wall at R.D. 1/870 to 1/880)	4,71,376.97	9,400/-	350/-	One month
2	BSP/2023/872, C/O (Construction of) Restoration of Malwara Batheri road Km 1/230 to 1/840. (SH:- Construction of wire crated Retaining wall on dumping site D/S of Bridge, (RHS, LHS and front side at R.D. 0/00 to 0/005, 0/00 to 0/008) (Job No. 1)	4,67,826.00	9,400/-	350/-	One month
3	BSP/2023/872, C/O (Construction of) Restoration of Malwara Batheri road Km 1/230 to 1/840. (SH:- Construction of wire crated Retaining wall on dumping site D/S of Bridge, front side at R.D. 0/010 to 0/040) (Job No. 2)	4,75,916.00	9,500/-	350/-	One month
4	BSP/2023/872, C/O (Construction of) Restoration of Malwara Batheri road Km 1/230 to 1/840. (SH:- Construction of wire crated Retaining wall on dumping site D/S of Bridge, along the khad Kuthar side at R.D. 0/00 to 0/041) (Job No. 3)	4,95,953.00	9,900/-	350/-	One month
5	BSP/2023/872, C/O (Construction of) Restoration of Malwara Batheri road Km 1/230 to 1/840. (SH:- Construction of wire crated Retaining wall on dumping site D/S of Bridge, along the khad Kuthar side at R.D. 0/041 to 0/071) (Job No. 4)	3,68,935.00	7,400/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.


3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh


PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 471376.97
 Earnest Money Rs:- 9400.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. IHP.PWD. at Padhar.						
Name of work :- Improvement of Black Spot on Katauia Batheri Arang road in Km. 0/00 to 15/2&5. (Sub Head:- Construction of Retaining wall at R.D. 1/870 to 1/880).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	49.80	Per cubic metre	461.00	22957.80	Rupees Twenty Two Thousand Nine Hundred Fifty Seven and Paise Eighty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	96.53	Per cubic metre	4421.90	426846.01	Rupees Four Lakh Twenty Six Thousand Eight Hundred Forty Six and Paise One Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	11.30	Per cubic metre	1433.20	16195.16	Rupees Sixteen Thousand One Hundred Ninety Five and Paise Sixteen Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	268.90	5378.00	Rupees Five Thousand Three Hundred Seventy Eight Only
Total in figure :					471376.97	Rupees Four Lakh Seventy One Thousand Three Hundred Seventy Six and Paise Ninety
Total in Words :		Rupees Four Lakh Seventy One Thousand Three Hundred Seventy Six and Paise Ninety Seven Only				


 Executive Engineer
 Mandi Division No.1
 H.P.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 467826.00
Earnest Money Rs:- 9400.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.
Name of work :- BSP/2023/872, C/O (Construction of) Restoration of rain damages on Malawara Bathari road Km. 1/230 to 1/840. (Sub Head:- Construction of Wire crated Retaining wall on dumping site D/S of Bridge, (RHS, LHS and front side at RD. 0/00 to 0/005, 0/00 to 0/008). (Job No. 1)
Contract No. :
Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures: for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	90.73	Per cubic metre	485.30	44031.00	Rupees Forty Thousand Thirty One Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	182.16	Per cubic metre	2326.50	423795.00	Rupees Four Lakh Twenty Three Thousand Seven Hundred Ninety Five Only
Total in figure :					467826.00	Rupees Four Lakh Sixty Seven Thousand Eight Hundred Only
Total in Words :						Rupees Four Lakh Sixty Seven Thousand Eight Hundred Twenty Six Only


Executive Engineer
Mandi Division No.1
H.P.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 475916.00
 Earnest Money Rs:- 9500.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- BSP/2023/872, C/O (Construction of) Restoration of rain damages on Malawara Batheri road Km. 1/230 to 1/840. (Sub Head:- Construction of Wire crated Retaining wall on dumping site D/S of Bridge, front side at RD. 0/010 to 0/040). (Job No. 2)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	107.40	Per cubic metre	485.30	52121.00	Rupees Fifty Two Thousand One Hundred Twenty One Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	182.16	Per cubic metre	2326.50	423795.00	Rupees Four Lakh Twenty Three Thousand Seven Hundred Ninety Five Only
Total in figure :					475916.00	Rupees Four Lakh Seventy Five Thousand Nine Hundred Sixteen Only
Total in Words :		Rupees Four Lakh Seventy Five Thousand Nine Hundred Sixteen Only				


 Executive Engineer
 Mandi Division No.1
 H.P.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 495953.00
 Earnest Money Rs:- 9900.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- BSP/2023/872, C/O (Construction of) Restoration of rain damages on Malawara Batheri road Km. 1/230 to 1/840. (Sub Head:- Construction of Wire crated Retaining wall on dumping site D/S of Bridge, along the khad kuthar side at RD. 0/00 to 0/041). (Job No. 3)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	102.09	Per cubic metre	485.30	49544.00	Rupees Forty Thousand Five Hundred Forty Four Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	191.88	Per cubic metre	2326.50	446409.00	Rupees Four Lakh Forty Six Thousand Four Hundred Nine Only
Total in figure :					495953.00	Rupees Four Lakh Ninety Five Thousand Nine Hundred Fifty Three Only
Total in Words :		Rupees Four Lakh Ninety Five Thousand Nine Hundred Fifty Three Only				

Executive Engineer
 Mandi Division No. 1
 H.P.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 368935.00
 Earnest Money Rs:- 7400.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I H.P.P.W.D. at Padhar.

Name of work :- BSP/2023/872, C/O (Construction of) Restoration of rain damages on Malawara Batheri road Km. 1/230 to 1/840. (Sub Head:- Construction of Wire crated Retaining wall on dumping site D/S of Bridge, along the khad kuthar side at RD. 0/041 to 0/071). (Job No. 4)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	87.15	Per cubic metre	485.30	42294.00	Rupees Forty Thousand Two Hundred Ninety Four Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	140.40	Per cubic metre	2326.50	326641.00	Rupees Three Lakh Twenty Six Thousand Six Hundred Forty One Only
Total in figure :					368935.00	Rupees Three Lakh Sixty Eight Thousand Nine Hundred Thirty Five Only
Total in Words :		Rupees Three Lakh Sixty Eight Thousand Nine Hundred Thirty Five Only				


Executive Engineer
Mandi Division No.1
H.P.P.W.D. at Padhar