

Himachal Pradesh
Public Works Department

NOTICE INVITING TENDER

Sealed percentage rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP. for the following works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on or before **17/02/2024 up to 11:00 AM.** and the same shall be opened on the same day at 11:30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on **16/02/2024 up to 11:00 A.M.** and the application for issue of tender form shall be received on **15/02/2024 up to 4:00 P.M.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD. Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 45 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.

Sr. No	Name of work	Estimated cost(Rs.)	Earnest money (Rs.)	Cost of form (Rs)	Time allowed for completion
1	2	3	4	5	6
1	C/O Chailla Ghoond road km. 0/0 to 16/00 (SSH- Re-construction of PCCR/at Rd 12/840 to 12/855)	1,33,386	2700	350	one month
2	C/O Roni Karyali road km. 0/0 to 55/130 (SH:- C/O B/wll in wire crate at RD 1/240 to 1/260)	4,44,967	9000	350	one month
3	A/R & M/O to HPPWD Rest House at Theog (SH:- repair of furniture's)	1,12,350	2250	350	one month
4	A/R & M/O to HPPWD Rest house at Fagu (SH:- Repair of furnitures)	49,550	1000	350	one month
5	R/R damages on Kargoli Nallah to Deha road km. 0/0 to 8/0 (SH:- Removal of slip at RD 0/0 to 8/0)	4,99,950	10000	350	one month
6	C/O Ghorna Deothi road km. 0/0 to 5/435 (SH:- Re-construction off R/ wall at Rd. 0/390 to 0/405)	2,83,774	5700	350	one month
7	R/R damages on various road under Sainj Sub-division (SH:- Hiring of Tipper for carriage of debries/ stone)	1,50,000	3000	350	one month
8	C/O Sainj Deha Chopal road km. 0/0 to 20/700 (SH:- Re construction of PCC R/wll at Rd. 4/740 to 4/753)	4,84,356	9700	350	one month
9	C/O Sainj Deha Chopal road km. 0/0 to 20/700 (SH:- Re-construction of B/wll at Rd 7/0 to 7/037)	4,99,954	10000	350	one month
10	C/O Chailla Ghoond road km. 0/0 to 16/0 (SH:- Re-construction of PCC R/wall at Rd 2/240 to 2/247)	1,58,169	3200	350	one month
11	C/O Katudi Nallah to Harijan road km. 0/0 to 4/930 (SH:- Re-construction of R/wall at RD 0/640 to 0/650.50)	4,61,118	9300	350	one month
12	S/R Civil Hospital at Theog (SH:- S/R of old bldg.. at Theog all minor work)	2,88,424	5800	350	one month
13	R/R damages on Powach Dharmai Koti road km. 0/0 to 8/400 (SH:- C/O R/wall at Rd 8/120 to 8/132)	4,83,959	9700	350	one month

14	R/R damages on Dhalli Chouri Sainj road km. 0/0 to 6/500 (SH:- Demolishing of concrete C/O R/wall at Rd 5/240 to 5/250) protection of house of Sh. Dila Ram .	4,93,226	9900	350	One month
15	Imp. Of black spot on Black spot on Balghar Tihanadhar Kalna road km. 0/0 to 24/0 (SH:- ROFD in km. 3/075 to 3/345)	4,76,055	9600	350	One month
16	R/R damages on various road under Sainj Sub-Division(Sainj Section) (SH:- Hiring of Tipp-er for carriage of debris/stone)	1,50,000	3000	350	one month
17	A/R and M/O to HPPWD Rest House Mtiana (SH:- Repair of furniture's and Dry cleaning of rest house furnitures)	2,09,100	4200	350	one month
18	C/O Shilaroo Rachhan road km. 0/0 to 2/3350 (SH:- C/O 900mm dia Hume pip-e culvert at Rd 1/390 and 2/385)	2,65,680	5400	350	one month
19	C/o Runkali to Chikhar road km. 0/0 to 6/500 (SH:- Re-construction of R/wall at Rd 0/450 to 0/456).	1,60,864	3250	350	One month
20	C/O Bhagat to Kopper road km. 0/0 to 1/500 (SH:- Re-construction of B/wll aatt Rd 0/380 to 0/400)	3,44,092	6900	350	One month
21	R/R damages on Meha to Dandi road km. 2/700 to 5/00 (SH:- Hiring of JCB for removal of slips)	99,500	2000	350	One month
22	R/R damages on Meha to Danoad km. 2/700 to 5/00 (in Deha section) (SH:- Hiring of Tipper for carriage of debris/stone)	99,000	2000	350	One month
23	A/R and M/O Chailla Mohari Narkanda road km. 0/0 to 10/500 (SH:- curve cutting in earth work 11/014 to 10250 to 1/275 to 3/030 to 3/065)	97,930	1960	350	One month
24	R/R damages on Matiana Baragoan ro. 0/0 281 (SH:- C/PCC R/wall at RD 0/415 to 0/445)	4,97,273	10000	350	One month
25	A/R and M/O Ghorna Deothi road (Deha Section) (SH:- hiring of JCB for removal of slips i/c dressing of ground)	49000	1000	350	One month
26	R/R damages on Matiana Baragoan road km. 0/0 to 25/810 (SH:- C/O PCC B/wall at Rd 16/770 to 16/785)	2,13,399	43000	350	One month
27	R/R damages on Runkali to Chikhar road km. 0/0 to 6/500 (SH:- C/O R/wall at Rd 1/182.50 to 1/190)	4,95,737	10000	350	One month
28	R/R damages on Rahighat Kiartyoo road km. 0/0 to 5/0 (SH:- C/O B/wall at Rd 0/175 to 0/200)	3,95,434	7950	350	One month
29	R/R damages on Tiyaali Mandir Manla Maipul road km. 0/0 to 8/0 (SH:- C/O R/wall at Rd 4/840 to 4/885)	4,91,445	9850	350	One month
30	R/R damages on Harog to Chair road km. 0/0 to 5/0 (SH:- C/O PCC R/wall at Rd 0/740.95 to 0/747.05)	2,30,801	4620	350	One month
31	R/R damages on Matiana Mohari via Kalzar road km. 0/0 to 16/0 (SH:- C/O B/wall at Rd 0/215 to 0/232.50)	1,87,781	3800	350	One month
32	R/R. damages on Devgarh Jarai Man log road km. 0/0 to 6/5500 (SH:- C/O PCC B/wall at RD 4/850 to 4/875)	3,91,145	7850	350	One month
33	R/R damages on Jabal Sabal Deothi Bagri Dasana Kenchi road km. 0/0 to 8/900 (SH:- C/O PCC B/wall at Rd 5/378 to 5/390)	1,99,019	4000		One month

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

Following documents should accompany the application for tenders: -

- (1) The contractors are required to be produce a copy of their PAN No.GST. No. and should produce a copy of enlistment /renewal letter.
- (2) Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected
- (3) The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act 1952 (EPF number) within a month from award of work/contract. Failure to observe this condition shall render the tender of contractor liable to summary rejection.
- (4) The bidder are advised to quote rates inclusive of G.S.T. as applicable notified vide Additional Chief Secretary (PW) to the Govt. of H.P. letter No. PBW(B)C(17)2/2012 dated 07/08/2018 ,G.S.T. shall not be paid extra.
- (5) Contractors are allowed to bid only two works, if he bids for more than two works only the first two works in sequence will be considered.

On Behalf of Governor of Himachal Pradesh


Executive Engineer,
Theog Division,B&R,
H.P.P.W.D., Theog

"Exigency Certificate"

It is certified that the tenders for various works as called for
vide this office letter No. PW.THD/CB-tender/2024-16010-21..... dated
07/02/2024.....are of emergent nature in exigency of public interest.

Dated: 7th February, 2024

Place: Theog


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog


SCHEDULE OF QUANTITY

Estimated Cost Rs:-133386/-
Earnest Money:-2700/-

Time: One month

Name of Work : - C/O Chhaila Ghoond Road km 0/0 to 16/00(SH-.Re-construction PCC R/Wall at RD 12/840 to 12/855)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	13.50	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	per cubic meter	2890
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 25 mm	25.65	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	112306
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	26.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Per running meter	6296
4	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	9.45	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per cubic metre	11894
						133386
			Quoted Rate in figer+/- (-----)			
			Quoted Rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.-444967/-
Earnest Money.-9000/-
Time: One month

Name of Work : - C/O Roni Karyali Road km 0/0 to 5/130 (SH.- C/O B/Wall in wire crate at RD 1/240 to 1/260)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 20 mtr. As per technical specification clause 1603. 1 including all leads and lifts as per direction of the Engineer-in-Charge	134.00	179.7	Rupees One Hundred Seventy Nine and Paise Seventy Only	per cubic meter	24080
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	31.20	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	per cubic meter	6680
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 25 mm	93.75	2950.00	Rupees Two Thousand Nine Hundred Fifty Only	Per cubic meter	276563
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	30.00	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per running meter	131352
5	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	5.00	1258.65	Rupees One Thousand Hundred Fifty Eight and Paise Sixty Five Only	Per cubic metre	6293
						444968
		Quoted Rate in figer+/- (-----)				
		Quoted Rate inwards				


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs112350
Earnest Money:2250/
Time: one month

Name of Work :- A/R and M/O to HPPWD Rest house at Theog (SH:- Repair of furnitures .

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Up holsering reshiffing of sofa set /seats/using 2 thick sleep well (32 density) with quality foam sheets nad back fixing padding with calla and latest with superior quality trans cloth in proper position including cost of stitching material and sets sleeps well 40 density size 500555 100 including necessary repair of wood polishing complete as per HPPWD specification including carriage of material with all leads and lift and other incidents sofa set repair including all leads and lifts as per direction of the Engineer-in-Charge	3.00	5200.00	Rupees Five Thousand Two Hundred Only	Each	15600
2	Up holsering reshiffing of sofa set /seats/using 2 thick sleep well (32 density) with quality foam sheets nad back fixing padding with cala and latest with superior quality trans cloth in proper position including cost of stitching material and sets sleeps well 40 density size 500555100 including necessary repair of wood polishing complete as per HPPWD specification including carriage of material with all leads and lift and other incidents sofa set repair including all leads and lifts as per direction of the Engineer-in-Charge Sofa Seats cover	22.00	2750.00	Rupees Two Thousand Seven Hundred Fifty Only	Each	60500
(i)	Sofa seats chair cover	16.00	2200.00	Rupees Two Thousand Two Hundred Only	Each	35200
(ii)	Dressing stool	1.00	1050.00	Rupees One Thousand Fifty Only	Each	1050
						112350
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs49550
Earnest Money:1000/
Time: one month

Name of Work :- A/R and M/O to HPPWD Rest house at (SH:- Repair of furnitures)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Up holserling reshffing of sofa set /seats/using 2 thick sleep well (32 density) with quality foam sheets nad back fixing padding with calla and latest with superior quality trans cloth in proper position including cost of stitching material and sets sleeps well 40 density size 500555 100 intulcung necessary repair of wood polishing complete as per HPPWD specification including carriage of material with all leads and lift and other incidents sofa set repair including all leads and lifts as per direction of the Engineer-in-Charge	5.00	5200.00	Rupees Five Thousand Two Hundred Only	Each	26000
2	Up holserling sofa Chair and back with making of lapestry cloth cutting to shape and fixing etc. including properly scrring spenings in position wiyh twins U hooks and cane stick etc.Fixing coin and cotton/latest foam rubber of approved quality in the sheet and back all complete including carriage of material with all leads and lifts as per direction of the Engineer in-Charge					
(i)	Sofa chair Chair	2.00	2700.00	Rupees Two Thousand Seven Hundred Only	Each	5400
3	Up holserling reshffing of sofa set /seats/using 2 thick sleep well (32 density) with quality foam sheets nad back fixing padding with cala and latest with superior quality trams cloth in proper position including cost of stitching material and sets sleeps well 40 density size 500555100 intulcung necessary repair of wood polishing complete as per HPPWD specification including carriage of material with all leads and lift and other incidents sofa set repair including all leads and lifts as per direction of the Engineer-in-Charge Sofa Seats cover	5.00	2750.00	Rupees Two Thousand Seven Hundred Fifty Only	Each	13750
(i)	Sofa chair cover	2.00	2200.00	Rupees Two Thousand Two Hundred Only	Each	4400
						49550
		Quoted rate in figer +/- (%.....)				
		Quoted rate in words				

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.499950
Earnest Money 10000/
Time: one month

Name of Work : R/R damages on Kargoli Nallah Deha road km 0/0 to 8/0 (SH:- Removal of slip at RD 0/0 to 8/0)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	6666	75.00	Rupees Seventy Five Only	Per cubic meter	499950
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			
						499950


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.283774
Earnest Money:5700/
Time: One month

Name of Work : C/O Gherna Deothi road Km 0/0 to 5/435 (SH)- Re-construction of R/wall at RD 0/390 to 0/405.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	51.90	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	11112
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 25mm	54.90	4378.40	Rupees Four Thousand Three Hundred Eight and Paise Forty Only	Per cubic meter	240374
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	39.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Per running meter	9444
4	Back filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	18.15	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per cubic meter	22844
						283774
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

Estimated Cost Rs.150000
Earnest Money:3000/
Time: one month

Name of Work : R/R damages on various road under Sainj Sub-Division (SH:- Hiring of

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of full size Tipper 5.50cum/10 tones capacity to be deployed , for disposing /carrying of material like earth ,kankar moorum , shingles and boulder etc.including cost of fuel , oil lubricants and wages of operational staff , any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of vehicle from one place to other ataccounted for the paymentand six hours per days working will be required having of front and loading capacity 1.00 Cum i/c all leads and lifts as per direction of the Engineer-in-Charge	30.00	5000.00	Rupees Five Thousand Only	per day	150000
					Total	150000
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.484356/
Earnest Money:9700
Time: One Months

Name of Work : C/O Sainj Deha Chopal road km 0/0 to 20/700 (SH:- Re-Construction of R/wall at RD 4/740 to 4/753.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	49.79	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	per cubic meter	10660
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 25 mm	101.66	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	445108
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts as per direction of the Engineer -in -Charge.	39.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	9444
4	Stone filling behind the retaining wall.B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer -in -Charge.	15.21	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	per cubic meter	19144
						484356
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			



 Executive Engineer,
 Theog Division,
 HP,PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.499954/
Earnest Money:10000
Time: One Months

Name of Work : C/O Sainj Deha Chopal road km 0/0 to 20700 (SH:- Re-Construction of B/wall at RD7/0 to 7/037.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	35.77	214.10	Rupees Two Hundred Fourteen and Paise Only	per cubic meter	7658
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 25 mm	108.40	4378.40	Rupees Four Thousand Three Hundred Eight and Paise Forty Only	Per cubic meter	474619
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	73.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	17677
						499954
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.158169/
Earnest Money:3200
Time: One Months

Name of Work : C/O Chhaila Ghoond road km 0/0 to 16/0 (SH:- Re-Construction of PCC R/wall at RD2/240 TO 2/247.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	16.24	214.10	Rupees Two Hundred and Paise Ten Only	per cubic meter	3477
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 25 mm	32.69	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	143130
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument.B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	15.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	3632
4	Stone filling behind the retaining wall.B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer -in -Charge.	6.30	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	per cubic meter	7929
						158169
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.461118
Earnest Money.9300/
Time: One months

Name of work:- C/O Katudi Nallah to Harijan Road km 0/0 to 4/930 (SH:- Re-construction R/wall at RD 0/640 to 0/650.50)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	57.96	148.75	Rupees One Hundred Forty Eight and Paise Five Only	Per cubic meter	8622
2	Providing and Laying concrete for plain reinforced concrete 1:4:8 (1 cement 4 sand : 8 graded stone agg. 25 mm nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge	96.08	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	420677
3	Stone filling behind the retaining wall B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer-in-Charge.	19.22	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per cubic meter	24191
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	31.50	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	7628
						461118
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.288428
Earnest Money:5800/
Time: One months

Name of Work : S/R Civil Hospital at Theog (SH- S/R of old building at Theog all miner work)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Dismantling tiled floors and roof laid in mortar including stacking materials within 50 metres lead thickness 10 to 25mm including in all leads and lifts as per direction of Engineer-in-Charge.	29.70	41.00	Rupees Forty One Only	Per square meter	1218
2	Dismantling doors, windows and clerestory windows, ventilators etc. (wood or steel) shutters including chowkhats, architraves, hold fasts and other attachments etc. complete including in all leads and lifts as per direction of Engineer-in-Charge.	3.00	214.80	Rupees Two Hundred Fourteen and Paise Eighty Only	each	644
3	Dismantling W.C.pan wash basin and sink of all size including disposal of etc. complete including in all leads and lifts as per direction of Engineer-in-Charge.	6.00	73.40	Rupees Seventy Three and Paise Forty Only	each	440
4	Demolition cement conc.1:2:4 manually /by mechanical means including disposal of materials in 50 metres lead . including in all leads and lifts as per direction of Engineer-in-Charge.	2.24	813.00	Rupees Eight Hundred Thirteen Only	Per square meter	1821
5	Providing woodwork in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position including in all leads and lifts as per direction of Engineer-in-Charge. 2nd class deodar wood	0.213	99718.70	Rupees Ninety Nine Thousand Seven Hundred Eighteen and Paise Seventy Only	Per cubic meter	21240
6	Providing and fixing panelled glazed or panelled and glazed. shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws complete . including in all leads and lifts as per direction of Engineer-in-Charge.	6.40	4412.20	Rupees Four Thousand Four Hundred Twelve and Paise Twenty Only	each	28238
7	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure in : Cement mortar 1:4 (1 cement : 4 coarse sand) complete including carriage of material in all leads and lifts as per direction of the Engineer - in - Charge.	12.60	891.00	Rupees Eight Hundred Ninety One Only	Per square metre	11227.00
8	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	22.40	247.90	Rupees Two Hundred Forty Seven and Paise Ninety Only	Per square metre	5553

9	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: i) 1:1.5:3 (1 cement : 1.5 coarse sand); 3 graded stone aggregate 20 mm nominal size) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	0.168	6845.18	Rupees Six Thousand Eight Hundred Forty Five and Paise Eighteen Only	Per cubic metre	1150
10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars complete including carriage of material in all leads and lifts as per direction of the Engineer - in - Charge.	20.16	95.00	Rupees Ninety Five Only	Per kilogramme	1915
11	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete . including in all leads and lifts as per direction of Engineer-in-Charge.	71.97	96.25	Rupees Ninety Six and Paise Twenty Five Only	Per square meter	6927
12	Wall painting with syntetic enamel approved brand and manufacture including in all leads and lifts as per direction of Engineer-in-Charge.	71.97	99.00	Rupees Ninety Nine Only	Per square meter	7125
13	Applying priming coat with ready mixed pink and grey primer of approved brand manufacture on wood work hard and soft wood including in all leads and lifts as per direction of Engineer-in-Charge.	40.16	51.65	Rupees Fifty One and Paise Sixty Five Only	Per square meter	2074
14	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping. including in all leads and lifts as per direction of Engineer-in-Charge. With enamel paint other than white	40.16	97.20	Rupees Ninety Seven and Paise Twenty Only	Per square meter	3904
15	Painting two coats (excluding priming coat) on new steel and other metal surface under coat with ready mixed paint brushing to give an even shade including cleaning the surface all dirt,dust and other foreign matter. including in all leads and lifts as per direction of Engineer-in-Charge.	252.90	124.00	Rupees One Hundred Twenty Four Only	Per square meter	31360
16	Providing and laying spartic ceramic glazed tiles of flooring (300 x300mm. size) including to be in cement mortar 1:4(1cement: 4 sand) finished with flush pointing in white cement including in all leads and lifts as per direction of Engineer-in-Charge.	27.81	1200.00	Rupees One Thousand Two Hundred Only	Per square meter	33372
17	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1866) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. :125mm.	6.00	48.00	Rupees Forty Eight Only	each	288

18	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. : 250mm x 10mm.	3.00	83.00	Rupees Eighty Three Only	each	249
19	Providing and fixing aluminium sliding door bolts (Barrel type) anodized transparent or dyed to required shade and colour with bolts and nuts etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.:300 X 16 mm	3.00	369.00	Rupees Hundred Sixty Nine Only	Each	1107.00
20	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) No. 20012 with seat and lid, 10 litre low level white P.V.C. flushing cistern, No. 21001 including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	2.00	6937.00	Rupees Six Thousand Nine Hundred Thirty Seven Only	Each	13874.00
21	Providing and fixing wash basin with C.I Brackets 15 mm C.P pillar tap 32 MM C.P. Brass waste of standard pattern including painting of fitting and brackets cutting and making good the walls wherever required white vitreous china wash basin size 430x 450 mm with a pair of 15 mm cp brass pillar tap including carriage of material in all leads and lifts as per direction of the Engineer in Charge. :-32mm dia	2.00	3562.00	Rupees Thousand Hundred Sixty Two Only	Each	7124.00
22	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	2.00	1330.00	Rupees One Thousand Three Hundred Thirty Only	Each	2660.00
23	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge :-610x460 mm bowl depth 200mm.	3.00	3267.00	Rupees Thousand Hundred Sixty Seven Only	Each	9801.00
24	Providing and fixing PVC. waste pipe for sink or wash basin including waste filling complete carriage of material in all leads and lifts as per direction of the Engineer in Charge.:- 32 mm dia	5.00	90.00	Rupees Ninety Only	Each	450.00

25	Providing and fixing 600mm x 450mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	1.00	1011.95	Rupees Thousand Eleven and Paise Ninety Five Only	One Each	1012.00
26	Providing and fixing charomium plated toilet paper holder complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	1.00	585.80	Rupees Five Hundred Eighty Five and Paise Eighty Only	Each	586.00
27	Providing and fixing charomium plated brass soap dish with C.P. brass brackets fixed to wooden cleats with C.P. brass screws complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	1.00	150.00	Rupees One Hundred Fifty Only	Each	150.00
28	Providing and fixing 600mm X 20mm size C.P. brass towel rail (heavy duty ISI marked IS:8931 & 8934) complete with C.P. brass brackets fixed to wooden plugs with C.P. brass screws complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	1.00	624.00	Rupees Six Hundred Twenty Four Only	Each	624.00
29	Providing and fixing C.P. brass angle cock with wash basin complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	1174.85	Rupees Thousand Hundred Seventy Four and Paise Eighty Five Only	Each	4699.00
30	Providing and fixing PVC. Connection pipe with basin union 45 cm long including complete carriage of material in all leads and lifts as per direction of the Engineer in Charge.	6.00	203.55	Rupees Two Hundred Three and Paise Fifty Five Only	Each	1221.00
31	Providing and fixing 19 mm thick commercial board water proof shutter for cup boards including fixing with nickel plated piano hinges with screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	23.30	2244.80	Rupees Thousand Hundred Forty Four and Paise Eighty Only	Per square metre	52304.00
32	Providing and fixing 6mm thick ply wood lining with butt jointing and nails (frame work and cover fillets to be measured and paid for separately complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	15.25	917.70	Rupees Nine Hundred Seventeen and Paise Seventy Only	Per square metre	13995.00

33	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Raj Nagar Plain white marble/ Udaipur green marble/ Zebra black marble Area of slab upto 0.50 sqm complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	6.27	2728.15	Rupees Thousand Hundred Twenty Eight and Paise Fifteen Only	Two Seven metre	17106.00
34	Providing and fixing glass panes with putty and glazing chips in steel door windows and clearstory windows all complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	3.50	847.55	Rupees Eight Hundred Forty Seven and Paise Fifty Five Only	Per square metre	2966.00
						288424
		Quoted rate in figer +/- (%.....)				
		Quoted rate in words				


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.483959/
Earnest Money:9700
Time: One Months

Name of Work : R/R damages on Powach Dharmai Koti road km 0/0 to 8/400 (SH:- C/O R/wall at RD 8/120 to 8/132.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	58.92	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	per cubic meter	12615
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8)25 mm	100.61	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	440511
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	45.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	10897
4	Stone filling behind the retaining wall.B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer -in -Charge.	15.84	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	per cubic meter	19937
						483959
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.493225/
Earnest Money:9900
Time: One Months

Name of Work : R/R damages on Dhali Chouri Sainj road km 0/0 to 6/500 (SH:- Demolishing of concrete C/O R/wall at RD5/240 to 5/250.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge Nominal concrete 1:4:8	108.99	813.70	Rupees Eight Hundred Thirteen and Paise Seventy Only	per cubic meter	88685
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	45.50	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	per cubic meter	9742
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8)25 mm	83.80	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	366910
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts as per direction of the Engineer -in -Charge.	45.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	10897
5	Stone filling behind the retaining wall.B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer -in -Charge.	13.50	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	per cubic meter	16992
						493225
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 476055
 Earnest Money:9600/
 Time: one month

Name of Work :- Imp of black spot on Balghar Tihanadhar Kalna road km 0/0 to 24/500 (SH:-ROFD in km3/075 to 3/345 .)

Sr. No.	Description of item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Cutting in earth work in all depths and heights in all kinds of soils including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock, with chiseling and wedging out of rock. (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required setting out true to the required lines grades side slopes, trimming of bottoms and levels as shown on the drawing and as directed by the Engineer-in charge at site, according to the HP.PWD. specification of 1990 volume-1 and sorting of useful and un useful materials and stacking the same in all lead and lifts and transportation of the un useful material for filling in road way embankments for grade improvement and leveling to required grades and then disposing of surplus excavated materials in acquired width of the road or on approved dumping site/sites through all modes of transportation including head loads, animals loads or mechanical means along with its leveling and fine dressing and carriage of all labour, machinery, materials tools, equipments and safety measures and other incidental necessary to completes the work by mechanical means and /or labour (if any required complete as per directions of Engineer-in Charge) All useful materials, such as stones, shingles347.80cum useful stone during the course of execution shall be made @ 300/- cum on prorata basis. Any loss to the public and private property during the courses of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respect. including all leads and lifts as per direction of the Engineer-in-Charge.	2056.06	231.54	Rupees Two Hundred Thirty One and Paise Fifty Four Only	Per cubic meter	476055
						476055
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.150000

Earnest Money:3000/

Time: one month

Name of Work : R/R damages on various road under Sainj Sub- Division (Section Sainj) (SH:- Hiring of full size Tipper for carriage of debris / stone)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of full size Tipper 5.50cum/10 tones capacity to be deployed , for disposing /carring of material like earth ,kankar moorum , shingles and boulder etc.including cost of fuel , oil lubricants and wages of operational staff , any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of vehicle from one place to other ataccounted for the paymentand six hours per days working will be required having of front and loading capacity 1.00 Cum i/c all leads and lifts as per direction of the Engineer-in-Charge	30.00	5000.00	Rupees Five Thousand Only	per day	150000
					Total	150000
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs209100

Earnest Money:4200/

Time: one month

Name of Work :- A/R and M/O to HPPWD Rest house at Matiana (SH):- Repair of furnitures and Drycleaning of rest house furnitures)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Up holserling reshiffing of sofa set /seats/using 2 thick sleep well (32 density) with quality foam sheets nad back fixing padding with calia and latest with superior quality trans cloth in proper position including cost of stitching material and sets sleeps well 40 density size 500555 100 including necessary repair of wood polishing complete as per HPPWD specification including carriage of material with all leads and lift and other incidents sofa set repair including all leads and lifts as per direction of the Engineer-in-Charge	5.00	5200.00	Rupees Five Thousand Two Hundred Only	Each	26000
2	Up holserling sofa Chair and back with making of lapestry cloth cutting to shape and fixing etc. including properly scrring spenings in position wiyh twins U hooks and cane stick etc.Fixing coin and cotton/latest foam rubber of approved quality in the sheet and back all complete including carriage of material with all leads and lifts as per direction of the Engineer in-Charge					
(i)	Sofa Chair	16.00	2700.00	Rupees Two Thousand Seven Hundred Only	Each	43200
(ii)	dressing stool	3.00	1500.00	Rupees One Thousand Five Hundred Only	Each	4500
(iii)	Room Chair	8.00	1050.00	Rupees One Thousand Fifty Only	Each	8400
3	Up holserling reshiffing of sofa set /seats/using 2 thick sleep well (32 density) with quality foam sheets nad back fixing padding with cala and latest with superior quality trans cloth in proper position including cost of stitching material and sets sleeps well 40 density size 500555100 including necessary repair of wood polishing complete as per HPPWD specification including carriage of material with all leads and lift and other incidents sofa set repair including all leads and lifts as per direction of the Engineer-in-Charge Sofa Seats cover	34.00	2750.00	Rupees Two Thousand Seven Hundred Fifty Only	Each	93500
(i)	Sofa seats chair cover	14.00	2200.00	Rupees Two Thousand Two Hundred Only	Each	30800
4	Drycleaning of various materials including all leads and lifts as per direction of the Engineer-in-Charge					

(i)	Sofa seats		5.00	300.00	Rupees Three Hundred Only	Each	1500
(ii)	Dining chair cover		6.00	200.00	Rupees Two Hundred Only	Each	1200
							209100
			Quoted rate in figer +/- (%.....)				
			Quoted rate in words				


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.265680

Earnest Money:5400/

Time: One months

Name of Work : C/O Shilaroo Rachhan road km 0/0 to 2/350 (SH:- C/O 900mm dia hume pipe culvert at RD 1/390 and 2/385.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	105.04	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	22489
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 25 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	3.79	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	16594
3	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 including all leads and lifts as per direction of the Engineer-in-Charge.)	15.15	3365.50	Rupees Three Thousand Three Hundred Sixty Five and Paise Fifty Only	Per cubic meter	50987
4	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:5 including all leads and lifts as per direction of the Engineer-in-Charge.	2.16	5003.35	Rupees Five Thousand Three and Paise Thirty Five Only	Per cubic meter	10807
5	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204including all leads and lifts as per direction of the Engineer-in-Charge (1:6:12)	8.96	3503.65	Rupees Three Thousand Five Hundred Three and Paise Sixty Five Only	Per cubic meter	31393

SCHEDULE OF QUANTITY

Estimated Cost Rs.160864/

Earnest Money:3250

Time: One Months

Name of Work : C/O Runkali to Chikhar road km 0/0 to 6/500 (SH:- Re-Construction of R/wall at RD 0/450 to 0/456.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	22.74	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	per cubic meter	4869
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 40 mm	33.73	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	147683
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 40 mm	10.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	2422
4	Stone filling behind the retaining wall.B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer -in -Charge.	4.68	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	per cubic meter	5890
						160864
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.344092
Earnest Money:6900/
Time: One months

Name of Work : C/O Bhagat to Kopper road km 0/0 to 1/500 (SH:- Re-Construction of B/wall at RD 0/380 to 0/400.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	102.20	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	21881
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 25 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	71.60	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	313493
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	36.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	8717
						344092
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs. 99500/-

Earnest Money: 2000/-

Time: One Months

Name of Work : - R/R damages on Meha to Dandi road km 2/700 to 5/00 (Deha -Section) (SH:- Hiring of JCB for removal of slips)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB/ Excavator be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair ,breakage during operation will be carried out by the owner at his risk and cost shifting of machineries from one place to other required location, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum removal of earth in one hours i/c loading in tippers/trucks and disposing excavated earth i/c all leads and lifts as per direction of the Engineer-in-Charge	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			
						99750


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs:-99000
Earnest Money: 2000
Time: One month

Name of Work : R/R damages on Meha to Dandi road km 2/700 to 5/00 (Deha -Section) (SH:- Hiring of Tipper for lifting of Debris
/Stone)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of full size Tipper 5.50 cum/10 tones capacity to be deployed , for disposing /carring of material like earth ,kankar moorum , shingles and boulder etc.including cost of fuel , oil lubricants and wages of operational staff , any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of vehicle from one place to other ataccounted for the paymentand six hours per days working will be required having of front and loading capacity 1.00 Cum i/c all leads and lifts as per direction of the Engineer-in-Charge	22.00	4500.00	Rupees Four Thousand Five Hundred Only	per day	99000
					Total	99000

Executive Engineer,
Theog Division,
HP.PWD. Theog

DNIT

Estimated Cost Rs 97930
Earnest Money:1960/
Time: one month

Name of Work : - A/R and M/O Chhaila mohari Narkanda road km 0/0 to 10/500 (SH-curve cutting in earth work 1/014 to 1/250 to 1/275 to 3/030 to

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Cutting in earth work in all depths and heights in all kinds of soils including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock, with chiseling and wedging out of rock. (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required setting out true to the required lines grades side slopes, trimming of bottoms and levels as shown on the drawing and as directed by the Engineer-in charge at site, according to the HP.PWD. specification of 1990 volume-1 and sorting of useful and un useful materials and stacking the same in all lead and lifts and transportation of the un useful material for filling in road way embankments for grade improvement and leveling to required grades and then disposing of surplus excavated materials in acquired width of the road or on approved dumping site/sites through all modes of transportation including head loads, animals loads or mechanical means along with its leveling and fine dressing and carriage of all labour, machinery, materials tools, equipments and safety measures and other incidental necessary to completes the work by mechanical means and for labour (if any required complete as per directions of Engineer-in Charge) All useful materials, such as stones, shingles69.89cum useful stone during the course of execution shall be made @ 300/- cum on prorate basis. Any loss to the public and private property during the courses of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respect. including all leads and lifts as per direction of the Engineer-in-Charge.	455.85	214.83	Rupees Two Hundred Fourteen and Paise Eighty Three Only	Per cubic meter	97930
						97930
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs. 497273
Earnest Money:10000/
Time: One months

Name of Work : R/R damages on Matiana Baragaun road km 0/0 to 25/810 (SH:- C/O PCC R/wall at RD 0/415 to 0/445.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	23.10	148.75	Rupees One Hundred Forty Eight and Paise Five Only	Per cubic meter	3436
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	24.00	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	5138
3	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 25 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	102.90	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	450537
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	50.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	12108
5	Stone filling behind the retaining wall.B/wall and wing wall complete as per drawing and technical specification clauses 1204.3.8. granular material including all leads and lifts as per direction of the Engineer -in -Charge.	20.70	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per cubic meter	26054
						497273
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs:-49000/-
Earnest Money: 1000/-
Time: One month

Name of work:- A/R & M/O Ghorna Deothi Road (Deha Section) (SH:- Hiring of JCB for removal of slips i/c Dressing of Ground)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB/ Excavator to be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair ,breakage during operation will be carried out by the owner at his risk and cost shifting of machineries from one place to otherrequired location, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum removal of earth i/c all leads and lifts as per direction of the Engineer-in-Charge.Excavator cum loader	49.00	1000.00	one thousand only	Per hours	49000
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.213399
Earnest Money: 4300/
Time: One months

Name of Work : R/R damages on Matiana Baragaun Road km 0/0 to 25/810 (SH:- C/O PCC B/Wall RD 16/770 to 16/785)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopess and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	40.50	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	Per cubic meter	6024
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	16.35	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	3501
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 40 mm	45.90	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	200969
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	12.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	2906
						213399
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs. 495737
 Earnest Money: 10000/
 Time: One months

Name of Work : R/R damages on munkali to Chikhar road km 0/0 to 6/500 (SH:- C/O PCC R/wall at RD 5/888 to 5/190.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	40.73	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	8719
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 25 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	106.38	4378.40	Rupees Four Thousand Three Hundred Eight and Paise Forty Only	Per cubic meter	465774
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	35.10	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	8499
4	Stone filling behind the retaining wall.B/wall and wing wall complete as per drawing and technical specification clauses 1204,3.8, granular material including all leads and lifts as per direction of the Engineer -in -Charge.	10.13	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per cubic meter	12744
						495737
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.395434
Earnest Money:7950/
Time: One months

Name of Work : R/R damages on Rehigat Kiartoo road km 0/0 to 5/0 (SH:- C/O B/wall at RD 0/175 to 0/200)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	39.50	179.70	Rupees One Hundred Seventy Nine and Paise Seventy Only	Per cubic meter	7098
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	27.00	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	5781
3	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 20 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	83.87	4492.00	Rupees Four Thousand Four Hundred Ninety Two Only	Per cubic meter	376744
4	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	24.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	each	5812
						395434
		Quoted rate in figer +/- (%.....)				
		Quoted rate in words				

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.491445
Earnest Money: 9850/
Time: One months

Name of Work : R/R Damages on Triyali Mandari Manla Maipul road km 0/0 to 8/00 (SH:- C/O PCC R/wall at RD 4/840 to 4/965.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	56.94	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	12191
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 25 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	100.75	4378.40	Rupees Four Thousand Three Hundred Eight and Paise Forty Only	Per cubic meter	441124
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	48.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	11623
4	Stone filling behind the retaining wallB/wall and wing wall complete as per drawing and technical specification clauses 1204 3.6. granular material including all leads and lifts as per direction of the Engineer -in -Charge.	21.06	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per cubic meter	26507
						491445
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.230801
Earnest Money: 4620 /
Time: One months

Name of Work : R/R damages on Harog to Chair road km 0/0 to 5/0 (SH:- C/O PCC R/wall at RD 0/740.95 to 0/747.05.)

Sr. No.	Description of item	QTY	Rate		Unit	Amount
			Rate in	Rate in words		
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including all leads and lifts as per direction of the Engineer-in-Charge P.C.C grade M -10 Nominal mix 1:3:6	38.30	5690.73	Rupees Five Thousand Six Hundred Ninety and Paise Seventy Three Only	Per cubic meter	217955
2	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 100 mm diaPVC pipe i/c all leads and lifts.as per direction of the Engineer-in -Charge.	15.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	3632
3	Back filling behind the retaining wall all leads and lifts as per direction of the Engineer-in - Charge.	7.32	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only	Per cubic meter	9213
						230801
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			



Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs. 187781
Earnest Money: 3100/
Time: one month

Name of Work : R/R damages on Matiana Mohari via Kalzar road km 0/0 to 16/0 (SH:- C/O B/wall at Rd 0/215 to 0/232.50)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in Hilly area by Manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	25.73	179.7	Rupees Hundred Nine and Paise Seventy Only	Per cubic meter	4624
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in benches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	16.45	214.10	Rupees Hundred Fourteen and Paise Ten Only	per cubic meter	3522
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1204 including all leads and lifts as per direction of the Engineer-in-Charge (1:4:8) 25 mm	4.03	3503.65	Rupees Three Thousand Hundred Three and Paise Sixty Five Only	Per cubic meter	14120
4	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 including all leads and lifts as per direction of the Engineer-in-Charge.)	49.18	3365.50	Rupees Three Thousand Sixty Five and Paise Fifty Only	Per cubic meter	165515
						187781
			Quoted rate in figure +/-			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP PWD, Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 39115
Earnest Money: 7850.00
Time: Two Months

Name of Work :- R/R Damages on Devagarh Jarai Manolng Road Km 0/0 to 6/500 (SH:- C/O PCC B/wall at RD 4/850 to 4/875)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in hilly area by merital means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.1 with in all leads and lift as per the direction of engineer in charge.	74.26	148.75	Rupees One Hundred Forty Eight and Paise Seventy Five Only	Per Cum	11046.00
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	36.75	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum	7868.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 : 803 , 1202 and 1203 . (1:4:8) 40 mm Agg including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	82.25	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per Cum	360123.00
4	Providing and fixing weapholes in brick masonry Stone / masonry plain RCC abument , B/wall & R/wall with 100 mm dia PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	50.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	12108.00
Total						391145.00
			Quoted rate in figer+/-			
			Quoted rate in words			


Engineer (F)

SCHEDULE OF QUANTITY

Estimated Cost

Rs :- 199019

Earnest Money:

4000.00

Time: one Months

Name of Work :- R/R Damages on Jabal Sabal Deothi Bagri Dasana Kenchi Road Km 0/0 to 8/900 (SH:- C/O PVC B/wall at RD 5/378 to 5/390.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	68.40	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per Cum	14644.00
2	Providing and laying of boulder laid in wire crates with 4 mm dia GI wire conforming to IS-280 abd IS: 4826 in 100 mm X100 mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bo including all leads and lifts or as per the direction of Engineer - in Charge	62.50	2950.00	Rupees Two Thousand Nine Hundred Fifty Only	Per Cum	184375.00
Total						199019.00
			Quoted rate in figer+/-			
			Quoted rate in words			

Executive Engineer,

Theog Division,

HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs :- 199019
 Earnest Money: 4000.00
 Time: one Months

Name of Work :- R/R Damages on Jabal Sabal Deothi Bagri Dasana Kenchi Road Km 0/0 to 8/900 (SH:- C/O PVC B/wall at RD 5/378 to 5/390.)

Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
				Rate in words			
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	68.40	214.10	Rupees Two Hundred Fourteen and Paise Ten Only		Per Cum	14644.00
2	Providing and laying of boulder laid in wire crates with 4 mm dia GI wire conforming to IS-280 abd IS: 4826 in 100 mm X100 mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bo.including all leads and lifts or as per the direction of Engineer - in Charge	62.50	2950.00	Rupees Two Thousand Nine Hundred Fifty Only		Per Cum	184375.00
	Total						199019.00
				Quoted rate in figer+/-			
				Quoted rate in words			

Executive Engineer,
 Theog Division,
 HP. PWD. Theog