E- Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriates class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 06/03/2024 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 05/03/2024 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	Restoration of Rain damages on Laraghat to Soldha road Km. 0/0 to 2/500 (SH:- C/o R/wall at RD 2/145 to 2/155)	Rs 3,67,501/-	Rs. 7,400/-	Rs. 350/-	Three Month
2	Restoration of Rin damages due to laying OFC cable on Navgaon Beri road Km. 4/350 to 23/700 (SH:- Providing and laying patch work in Bituminous concrete in Km. 4/350 to 5/500) Deposit work	Rs 4,98,333/-	Rs. 10,000/-	Rs. 350/-	Three Month
3	Construction of link road from Mandaru Ki Johari to village Panga via Kathla Km. 0/0 o 4/0 (SH:- C/o 900mm dia hume pipe culverts at RD 0/045 to 0/105).	Rs 3,67,492 /-	Rs. 7,400/-	Rs. 350/-	Three Month
4	Construction of link road from NH-205 to village Kattal Bagheri Km. 00 to 2/015 (SH:- C/o R/wall at RD 0/740 to 0/755)	Rs 4,93,415 /-	Rs. 10,000/-	Rs. 350/-	Three Month
5	Construction of link road from Mandaru Ki Johari to village Panga via Kathla Km 0/0 to 4/0 (SH:- C/o 900mm dia hume pipe culverts at RD 0/250 and 0/500)	Rs 4,29,511/-	Rs. 8,600/-	Rs. 350/-	Three Month
6	Restoration of Rin damages due to laying OFC cable on Navgaon Beri road Km. 4/350 to 23/700 (SH:- Providing and laying patch work in Bituminous concrete in Km. 4/350 to 5/500) Deposit work	Rs 4,97,657/-	Rs. 10,000/-	Rs. 350/-	Three Month
7	Construction of link road from Dadwal Helipad to Dadrana Haryala Km. 0/0 to 3/500 (SH:- C/o 900mm dia hume pipe culvert culverts at RD 1/330 and 1/480)	Rs 4,30,169/-	Rs. 8,700/-	Rs. 350/-	Three Month
8	Construction of link road from NH-205 to villge Kattal Bagheri Km. 0/0 to 2/015 (SH:- C/o of R/wall at RD 1/125 to 1/136.50 and 1/390 to 1/395)	Rs 4,83,073 /-	Rs. 9,700/-	Rs. 350/-	Three Month
9	Construction of Balance work of 317.50 meter span pre stressed concrete bridge at Bagchhal over Govind Ssgar Reservoir in Distt. Bilaspur (SH:- C/o Approach road to Bagchhal Bridge Swarghat side)	Rs 4,95,547/-	Rs. 10,000/-	Rs. 350/-	Three Month
10	0Restoration og Rain damages on link road to village Seola road Km. 0/0 to 3/340 (SH:- Construction of V-shape drain at RD 2/130 to 2/435)	Rs 2,50,280/-	Rs. 5,100/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contactor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2023- 15012-21 **Dated:-** 01-03-2024

Copy forwarded to the following for information and necessary action:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur+
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,67,501/-Only.

Earnest Money :- Rs.7,400/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Larghat to Soldha road km 0/000 to 2/500 (SH:- C/o R/wall at RD 2/145 to 2/155)

Sr No.	Description of items.	Quantity		Rates in Figure.	Rates in Words.	Unit	Amount
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All Kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	36.60	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	79.60	Cubic metre			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Cubic metre.			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonary/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Nos.			Each	
	Total:-						

Executive Engineer,
Bilaspur Division No. 2,
M.P. PWD., Bilaspur (M.P.).

	SCHEDULE OF QUANTITY.		Estimated cost:- Rs.4,98,333/-Only.
			Earnest Money :- Rs.10,000/-
			Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages due to laying of OFC cable on Navgoan Beri road km 4/350 to 23/700 (SH:- Providing and laying patch work in Bituminous concrete in km 4/350 to 5/500) (Deposit work)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.20 to 0.25 Kg. (Zero point two zero to Zero point two five)Kilogram per square metre on the prepared granular surface treated with primer and cleaned with Hydrauic broom as per Technical Specification Clause-503 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royality ,Malkana toll tax ,goods and serivice ,building and other construction workers, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1230.25	Square metre.			Per Square metre.	
2	Providing and laying bituminous concrete 30 (Thirty) milimeter thick with 100-120 TPH batch type hot mix plant producing an average output of 75(Seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4(Five point four) to 5.6(Five point six) percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No 509 complete in all respectsincluding carriage of material within all leads and lifts and other incidental The rate includes octroi, royality Malkana toll tax,Goods and service Tax, building and other construction worker, welfare cess ,royality or any other tax. levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	36.91	Cubic metre.			Per Cubic metre	
	Total						

Executive Engineer,
Bilaspur Division No. 2.
HP.PWD., Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.3,67,492/-Only.					
		Earnest Money :- Rs.7,400/-					
		Time:- Three Months.					
NAME OF WORK:- Construction of link road from Mandaru ki Johari to Village Panga Via Kathla km 0/00 to 4/00(SH:- Construction of 900 mm dia Hume pipe culverts at RD							
Sr No.	Description of items.	Quantity		Rates in Figure.	Rates in Words.	Unit	Amount
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	76.76	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution work. welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.32	Cubic metre			Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) Eight graded stone aggregate 40 mm (forty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.47	Cubic Metre			Per Cubic Metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.21	Cubic metre.			Per Cubic Metre	
5	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Running Meter			Per Running Meter	

	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.220	Cubic metre.			Per Cubic Metre	
7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.26	Cubic metre.			Per Cubic Metre	
8	Providing weepholes in brick masonry/stone masonary/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Nos.			Each	
	Total:-						

Executive Engineer
Bilaspur Division No. I
HP PWD., Bilaspur(H.P.)

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.4,93,415/-Only.
		Earnest Money :- Rs.10,000/-
		Time:- Three Months.

NAME OF WORK:- Construction of link road from NH-205 to Village Kattal Bagheri km 0/00 to 2/015 (SH:- Construction of R/wall at RD 0/740 to 0/755)

Sr No.	Description of items.	Quantity		Rates in Figure.	Rates in Words.	Unit	Amount
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.75	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	98.40	Cubic metre			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.50	Cubic metre			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonary/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	36.00	Nos.			Each	
	Total:-						

Executive Engineer
Bilaspur Division No. II
HP PWD., Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.4,29,511/-Only.					
		Earnest Money :- Rs.8,600/-					
		Time:- Three Months.					
NAME OF WORK:- Construction of link road from Mandaru ki Johari to Village Panga Via Kathla km 0/00 to 4/00(SH:- Construction of 900 mm dia Hume pipe culverts at RD							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	85.41	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.06	Cubic metre			Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.58	Cubic Metre			Per Cubic Metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.42	Cubic metre.			Per Cubic Metre	
5	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement :Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Running Meter			Per Running Meter	

	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.220	Cubic metre.			Per Cubic Metre	
7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.86	Cubic metre.			Per Cubic Metre	
8	Providing weepholes in brick masonry/stone masonary/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Nos.			Each	
	Total:-						

Executive Engineer
Bilaspur Division No. I
HP PWD, Bilaspur(H.P.)

	SCHEDULE OF QUANTITY.		Estimated cost:- Rs.4,97,657/-Only.
			Earnest Money :- Rs.10,000/-
			Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages due to laying of OFC cable on Navgoan Beri road km 4/350 to 23/700 (SH:- Providing and laying patch work in Bituminous concrete in km 4/350 to 5/500) (Deposit work)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.20 to 0.25 Kg. (Zero point two zero to Zero point two five)Kilogram per square metre on the prepared granular surface treated with primer and cleaned with Hydrauic broom as per Technical Specification Clause-503 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royality ,Malkana toll tax ,goods and serivice ,building and other construction workers, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1228.50	Square metre.			Per Square metre.	
2	Providing and laying bituminous concrete 30 (Thirty) milimeter thick with 100-120 TPH batch type hot mix plant producing an average output of 75(Seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4(Five point four) to 5.6(Five point six) percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respectsincluding carriage of material within all leads and lifts and other incidental.The rate includes octroi, royality Malkana toll tax,Goods and service Tax, building and other construction worker welfare cess ,royality or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	36.86	Cubic metre.			Per Cubic metre	
	Total						

Executive Engineer,
Bilaspur Division No. 2,
HP.PW.D., Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.4,30,169/-Only.					
		Earnest Money :- Rs.8,700/-					
		Time:- Three Months.					
NAME OF WORK:- Construction of link road from Dadwal Helipad to Dadrana Haryala km 0/00 to 3/500 (SH:- Construction of 900 mm dia Hume pipe culverts at RD 1/330 and 1/480)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge, ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	85.41	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge The rate includes octori malkhana, toll tax, Goods Service Tax, building and other constrcution work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.06	Cubic metre			Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4 8 (one Cement Four coarse sand) Eight graded stone aggregate 40 mm (forty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	7.58	Cubic Metre			Per Cubic Metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement Three coarse sand six graded stone aggregate 20 mm (Twenty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.42	Cubic metre			Per Cubic Metre	
5	Providing and laying non-pressure NP2 class (light duty) R.C.C pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement Two fine sand) including testing of joints etc complete 900 mm (Nine Hundred Millimeter) dia R.C.C pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge The rates includes octroi,royality Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Running Meter			Per Running Meter	

6	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.226	Cubic metre.			Per Cubic Metre	
7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.86	Cubic metre.			Per Cubic Metre	
8	Providing weepholes in brick masonry/stone masonary/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Nos.			Each	
	Total:-						

Executive Engineer,
Bilaspur Division No. 2,
M.P.W.D., Bilaspur (M.P.)

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.4,83,073/-Only.
		Earnest Money :- Rs.9,700/-
		Time:- Three Months.

NAME OF WORK:- Construction of link road from NH-205 to Village Kattal Bagheri km 0/00 to 2/015 (SH:- Construction of R/wall at RD 1/125 to 1/136.50 and 1/390 to 1/395)

Sr No.	Description of items.	Quantity		Rates in Figure.	Rates in Words.	Unit	Amount
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.81	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	96.19	Cubic metre			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3.8 of MORD specification,1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.39	Cubic metre.			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonary/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.00	Nos.			Each	
	Total:-						

Executive Engineer
Bilaspur Division No. I,
HP PWD., Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.4,95,547/-Only.
		Earnest Money :- Rs. 10,000/- only
		Time:- Three Months.

NAME OF WORK:- Construction of Balance Work of 317.50 mtr span pre-stressed concrete bridge at Bagchhal over Govind Sagar Reservoir in Distt. Bilaspur (SH:- C/O Approach road to Bagchhal Bridge swarghat Side)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification, 2014 Clause 300 302.3.5 & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber ,embankments for grade improvements and disposal of all useful /surplus materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and execution shall be absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases as per direction of Engineer-in-Charges including carriage of materials within all leads and lifts The rate including octori royality , Malkana , toll tax, sale tax,Goods services tax or other taxes imposed by the Govt. A recovery of useful stone for 197.59 Cum (one hundred Ninety seven point fifty Nine) Cubic metre at the rate of Rs 300/- (Rs Three hundred) only shall be done on pro-rate basis in each running bill for this item including carriage of materials in all leads lifts as per the direction of the Engineer-in-Charge.	592.76	Cubic Metre			Per Cubic Metre	
	Total:-						

Executive Engineer
Bilaspur Division No. 2,
HP, PWD., Bilaspur (H.P.).

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.2,50,280/-Only.					
		Earnest Money :- Rs.5,100/-					
		Time:- Three Months.					
NAME OF WORK:- Restoration of Rain Damages on link road to village Seola road km 0/00 to3/340(SH:- Construction of V-shape drain at RD 2/130 to 2/435)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. all kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	50.32	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement Three coarse sand six graded stone aggregate 20 mm (Twenty milimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	48.04	Cubic metre			Per Cubic Metre	
	Total:-						

Executive Engineer
Bilaspur Division No. I
HP PWD, Bilaspur(H.P.)