

Himachal Pradesh  
Public Works Department

Registered

NO:- PW-RD-N.I.T/2023-24

27007

Dated:-

11/3/24

To

The Executive Engineer (IT Cell)  
Nigam Vihar Shimla.

Subject:-

Publication of Tender notice.

Jai Hind

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. Of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16<sup>th</sup>. July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender & Sechedule of Quantity.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**NOTICE INVITING TENDER**

Sealed Percentage rate tenders on form No. 6 & 8 are hereby invited by the Executive Engineer B&R Division HP.PWD, Rohru for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HP.PWD, so as to reach in this office as per time Schedule given below:-

1. Date of receipt of application for tenders forms:-

15.03.2024

2. Dated of Issue /sale of tender forms:-

15.03.2024

3. Date of receipt of tender:-

16.03.2024 up to 10:30AM

4. Date of opening of tender:-

16.03.2024 at 11.AM

Sr. No.	Name of Work	Estimated Cost	EMD (Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1.	R/R Damages to Jangla Thali Amboi road km 0/00 to 10/00 (SH:- C/O R/Wall at RD 3/463 to 3/470)	494201/-	9000/-	350/-	One months	Calss "C&D"
2.	R/R damages to Nandla Jhalwari road km 0/00 to 4/00 (SH:- C/O R/Wall at RD 2/940 to 2/960 )	498530/-	9000/-	350/-	Onemo nths	Calss "C&D"
3.	R/R damages on Badiyara jangla Todsa Devidhar banoti road km 0/0 to 11/0 (SH:- Removal of slips at various RD1/415 to 1/645)	450750/-	9000/-	350/-	One months	Calss "C&D"
4.	R/R Damage to various roads under kansakoti section Sub division Rohru ( Sh:- Hiring of JCB for removal of slips at various RD maintenance of road and dressing of road surface)	495000/-	9900/-	350/-	Two months	Calss "C&D"
5.	Dhamwari Gokswari raod km 0/0 to 5/300 ( SH:- C/O Unlines surface Drain and earther soulder km 0/00 to 2/600 )	459623/-	9192/-	350/-	Two months	Calss "C&D"
6.	R/R Damage to khabal Sindasli road km 0/00 to 6/00 under Chirgaon Sub Division in Chirgaon section) Sh:- Hiring of Pock lane i/c rock breaker boulder in various reaches)	49500/-	990/-	350/-	One months	Calss "C&D"
7.	R/R damages on Link road Masli Village to GSS Masli km 0/0 to 0/600 (SH:- C/O B/Wall in wire crate at RD 0/300 to 0/345)	386695/-	7734/-	350/-	Two months	Calss "C&D"
8.	Dhamwari Gokswari raod km 0/0 to 5/300 ( SH:- C/O Unlines surface Drain and earther soulder km 2/600 to 5/300 )	459623/-	9192/-	350/-	Two months	Calss "C&D"
9.	R/R Damage to khabal Sindasli road km 0/00 to 6/00 under Chirgaon Sub Division in Chirgaon section) Sh:- Hiring of Pock lane i/c rock breaker boulder in various reaches)	49500/-	990/-	350/-	One months	Calss "C&D"
10	R/R damages on Chirgaon Gushali Rohal road km 0/0 to 9/0 (SH:- C/O R/Wall in wire crate at RD 8/509 to 8/521)	159742/-	3195/-	350/-	Two months	Calss "C&D"
11	R/R damages on TKHR road km 69/0 to 80/600 (SH:- Removal of slips at various RDs.)	294567/-	5900/-	350/-	One months	Calss "C&D"
12	C/O link road from Desoti to HB. Kheda km 0/0 to 2/700 (SH:- C/O 5/7 mtr wide formation cutting at RD. 1/620 to 1/995)	498597/-	9972/-	350/-	Two months	Calss "C&D"
13	C/O Deorighat Tikkar via Gujandli road km 0/0 to 7/720 (SH:- Improvement of narrow reaches at RD. 3/315 to 3/354 & 3/400 to 3/445)	497340/-	9947/-	350/-	Two months	Calss "C&D"
14	C/O link road from Desoti to HB. Kheda km 0/0 to 2/700 (SH:- C/O 5/7 mtr wide formation cutting at RD. 2/430 to 2/710)	497800/-	9956/-	350/-	Two months	Calss "C&D"

15	Repair & maintenance of Govt Degree College Seema ( Staff Quarter) SH:- P/F Tiles distempering, painting etc.	499319/-	9986/-	350/-	Two months	Calss "C&D"
16	Repair & maintenance of Govt Degree College Seema ( Staff Quarter) SH:- P/F Tile work 3rd Floor and Wall care putty.)	498883/-	9978/-	350/-	Two months	Calss "C&D"
17	R/R damages on Link road to Village Jabbal Km 0/0 to 6/0 (SH:- C/o R/wall in wire crate at RD. 1/500 to 1/510, 3/045 to 3/065)	400701/-	8000/-	350/-	One months	Calss "C&D"
18	R/R Damages to Link road to village Rausi km 0/0 to 4/015 in Chirgaon sub- Divisio ( Chirgaon - Section ) (SH:- Removal of slips by JCB at various RDs and dressing of road surface Drain clearance )	495000/-	9900	350/-	Two months	Calss "C&D"
19	R/R Damages to Link road to village Rausi km 0/0 to 4/015 in Chirgaon sub- Divisio ( Chirgaon - Section ) (SH:- Removal of slips by JCB at various RDs and dressing of road surface Drain clearance )	495000/-	9900/-	350/-	Two months	Calss "C&D"
20	R/R damages on Syria Nallah Melthi kupri road km 0/0 to 6/0 (SH:- C/o R/Wall in wire crate at RD 1/050 to 1/065, & C/o 900mm dia HPC. At RD. 3/700)	462586/-	9300/-	350/-	One months	Calss "C&D"
21	C/O link road to Chanti Raha Panu km 0/00 to 2/00 (SH:- Widening of road at Rd 0/00 to 0/240)	492426/-	9800/-	350/-	One months	Calss "C&D"
22	R/R damages on Makhinallah Dashanli Kuttu Road km RD 0/00 to 4/00 (SH:- C/O B/Wall at RD 0/690 to 0/710)	305022/-	6100/-	350/-	One months	Calss "C&D"
23	C/O Link road from Rantari to Kandai road km 0/0 to 2/0 (SH:- P/L Essential Kharanja stone soling at 0/0 to 0/250)	481625/-	9700/-	350/-	One months	Calss "C&D"
24	C/o link road to village Bakora km 0/0 to 3/0 (SH:- F/C 5/7 mtr wide formation cutting at RD. 0/0 to 0/090)	461551/-	9200/-	350/-	Two months	Calss "C&D"
25	C/o Link road Jabbal Pather Nallah Shagan Teer km 0/0 to 3/0 (SH:- F/C 5/7 mtr wide road km 1/715 to 1/805)	487216/-	9744/-	350/-	Two months	Calss "C&D"
26	C/o Link road Jabbal Pather Nallah Shagan Teer km 0/0 to 3/0 (SH:- F/C 5/7 mtr wide road km 1/805 to 1/910)	479534/-	9591/-	350/-	Two months	Calss "C&D"
27	R/R damages on Chirgaon Gushali to Rohal road km 0/0 to 16/0 (SH:- C/o R/Wall in wire crate at RD. 14/272 to 14/297)	456407/-	9128/-	350/-	Two months	Calss "C&D"
28	C/O link road Nesar to Munake Dhar km 0/0 to 1 km (SH:- F/C 5/7 mtr wide road at Rd 0/00 to 0/090)	475015/-	9500/-	350/-	Two months	Calss "C&D"
29	C/O link road Nesar to Munake Dhar km 0/0 to 1 km (SH:- F/C 5/7 mtr wide road at Rd 0/165 to 0/240)	473349/-	9467/-	350/-	Two months	Calss "C&D"
30	C/O link road Nesar to Munake Dhar km 0/0 to 1 km (SH:- F/C 5/7 mtr wide road at Rd 0/315 to 0/405)	473057/-	9461/-	350/-	Two months	Calss "C&D"
31	R/R Damages on Koftu Saahnaal road km RD 0/00 to 1/00 (SH:- C/O R/Wall in 0/105 to 0/112)	441054/-	8800/-	350/-	Two months	Calss "C&D"
32	C/o Rantari Kandai road km 0/0 to 2/235 (SH:- C/o 5/7 mtr.wide formation cutting at RD. 1/030 to 1/315)	483408/-	9668/-	350/-	Two months	Calss "C&D"
33	C/o Rantari Kandai road km 0/0 to 2/235 (SH:- C/o 5/7 mtr.wide formation cutting at RD. 1/315 to 1/540)	354008/-	7100/-	350/-	Two months	Calss "C&D"
34	R/R damage on Kansakoti Kutara Dalgaon road km 0/00 to 15/00 (SH:- C/O B/Wall at RD 1/735 to 1/755)	363673/-	7273/-	350/-	Two months	Calss "C&D"
35	R/R damages on Syria Nallah Kupri Melthi Butthli kalgaon road km 0/0 to 6/0 (SH:- C/O B/Wall in wire crate at RD. 1/280 to 1/300 & C/o 900mm dia HPC. At RD. 3/200)	452131/-	9100/-	350/-	One months	Calss "C&D"
36	C/O link road from Sangrad to Hingori 0/0 to 1/500 (SH:- C/O PCC R/Wall at RD 0/150 to 0/176)	426884/-	8538/-	350/-	Two months	Calss "C&D"
37	C/O link road from Sangrad to Hingori 0/0 to 1/500 (SH:- C/O B/Wall in wire crate at RD 0/345 to 0/373)	443592/-	8872/-	350/-	Two months	Calss "C&D"
38	R/R damages on Shalawat to Wali road km 0/0 to 2/0 (SH:- C/o R/Wall at RD. 1/210 to 1/220 & B/Wall at RD 0/112 to 0/120 & U-Shape drain at Shalawat Bus Stop L=28.00 mtrs.)	421194/-	8500/-	350/-	One months	Calss "C&D"
39	R/R damages on Jagothi Nallah Andreothi road km 0/0 to 6/0 (SH:- C/o R/Wall at RD. 2/390 to 2/410)	486218/-	9700/-	350/-	One months	Calss "C&D"
40	C/o main road Lowerkoti to Vahan km 0/00 to 1/300 (SH:- F/C 5/7 mtr wide road at Rd 0/120 to 0/180)	498513/-	9970/-	350/-	Two months	Calss "C&D"
41	R/R Damages to vrious road under Rohru Section Sub-Division Rohru (SH:- Hiring of JCB for removal of slips and maintenance of road etc)	126000/-	2520/-	350/-	One months	Calss "C&D"



42	R/R damages on Link road from Tandroh Nallah to Jagtarli road km 0/0 to 2/0 (SH:- C/O B/Wall at RD 1/560 to 1/575)	342782/-	6856/-	350/-	One months	Calss "C&D"
43	R/R damages to various road under Rohru section sub-division Rohru (SH:- Hiring of of JCB for removal of slips ar various RDs , maintenance of road and dressing of road surface.)	252000/-	5040/-	350/-	One months	Calss "C&D"
44	R/R damages to various road under Rohru section sub-division Rohru (SH:- Hiring of of JCB for maintenance of road ,removal of slips )	132225/-	2600/-	350/-	One months	Calss "C&D"
45	R/R Damages on Hingwala to Mini gadam road km 0/0 to 3/0 (SH:-C/O B/Wall in wire crate at RD 1/770 to 1/882.50 )	464401/-	9288/-	350/-	Two months	Calss "C&D"
46	R/R Damages on Hingwala to Mini gadam road km 0/0 to 3/0 (SH:-C/O R/Wall in wire crate at RD 1/770 to 1/802.50 )	435989/-	8720/-	350/-	Two months	Calss "C&D"
47	R/R Damages on Hingwala to Mini gadam road km 0/0 to 3/0 (SH:-C/O R/Wall in wire crate at RD 1/820 to 1/840 & B/Wall in wire crate at RD 1/922 to 1/942 )	295717/-	5914/-	350/-	Two months	Calss "C&D"
48	R/R Damages to Bhatwari Gawas road km 0/0 to 7/00 (SH:- C/O B/Wall in wire crate at RD 1/645 to 1/690 )	406547/-	8131/-	350/-	Two months	Calss "C&D"
49	A/R & M/O Dhumadhar Jhatwari Mastot Baggi road km 0/0 to 6/500 (SH:- R/M of unlined surface drain maintenance of earthen shoulder and clearing and grubbing road land including uprooting wild vegetation grass etc. & local GSB at RD 0/0 to 3/500	488465/-	9769/-	350/-	Two months	Calss "C&D"
50	R/R damages to various roads under Samoli section sub-Division Rohru (SH:- Hiring of JCB for removal of slips and land lside maintenance of road)	495000/-	9900/-	350/-	Two months	Calss "C&D"
51	R/R damages to Baggi Khabal road under Chirgaon Sub-division ( Chirgaon Section ) (SH:- Removal of slips by JCB at various RDs and dressing of road surface Drain clearence )	495000/-	9900/-	350/-	Two months	Calss "C&D"
52	R/R damages to various roads in Chirgaon Sub Division ( Chirgaon Section ( (SH:- Hiring of Tractor for carriage of muck/stone )	150000/-	3000/-	350/-	Three months	Calss "C&D"
53	R/R damages to Shalawat wali kareetly road (SH:- R/Wall at Rd 1/120 to 1/132	482596/-	9652/-	350/-	Two months	Calss "C&D"
54	C/O link road Tandali to Dogra Khud 0/0 to 0/500 (SH:-C/o 5/7 mtr wide formation cutting at RD.0/150 to 0/330)	499083/-	9982/-	350/-	Two months	Calss "C&D"
55	R/R Damage to bhatwari Gawas road km 0/00 to 7/00(SH:- C/o B/wall in wire crate at RD 0/210 to 0/255)	409179/-	8184/-	350/-	Two months	Calss "C&D"
56	R/R damages on link road to HB. Shalawat Km 0/0 to 3/0 (SH:- C/o B/Wall at RD. 0/261.50 to 274.75, B/Wall 0/048.75 to 0/055.62)	491573/-	9800/-	350/-	One months	Calss "C&D"
57	R/R Damages on Annu Thamtari road km 0/0 to 1/250 (SH:- C/O R/wall at Rd 0/092 to 0/097 )	391986/-	7900/-	350/-	One months	Calss "C&D"
58	C/O Anu Matan to Karalash Kanchi road km 0/0 to 2/500 (SH:- Widening of road at Rd 0/0 to 0/105 )	496188/-	9924/-	350/-	Two months	Calss "C&D"
59	C/o Banoti Kandra road km 0/00 to 5/00( SH:- F/C 5/7 mtr wide road at RD 1*975 to 2/060)	406703/-	8134/-	350/-	Two months	Calss "C&D"
60	R/R Damage to jakhar to Thakuli Bartu road km 0/00 to 3/00( SH:- C/o B/wall at RD 1/320 to 1/343.10)	485288/-	9700/-	350/-	One months	Calss "C&D"
61	R/R Damage to Udo Niwas Jakhar road km 0/00 to 4/00( SH:- C/o B/wall at RD 0/270 to 0/293)	485288/-	9700/-	350/-	One months	Calss "C&D"
62	A/r & M/O SDM Residence Rohru(SH:- P/F Floor tiles repair of toilet WS & SI)	386281/-	7726/-	350/-	Two months	Calss "C&D"
63	A/R & M/O HPPWD store at Rohru( SH:- P/F M.S Sheet and prepainted sheet for roof at HPPWD store Rohru)	459708/-	9194/-	350/-	Two months	Calss "C&D"
64	A/R & M/O HPPWD Rest House at Rohru(SH:- P/L Tiles work and steel work etc)	499634/-	9993/-	350/-	Two months	Calss "C&D"
65	A/R & M/O HPPWD Rest House at Rohru(SH:- Wood work etc)	493657/-	9873/-	350/-	Two months	Calss "C&D"
66	A/R & M/O HPPWD Rest House at Rohru(SH:- P/L Wood work, wall lining etc)	493496/-	9870/-	350/-	Two months	Calss "C&D"
67	C/o Ambulance road from banoti to GSS	491539/-	9831/-	350/-	Two	Calss

	Saribasa(Devidhar)(SH:- C/o R/wall at RD 0/185 to 0/200 and 0/257 to 0/277 and P/L Kharanja stone soling at RD 0/065 to 0/277)				months	"C&D"
68	R/R Damage of lalpani Dhumara road km 0/00 to 4/330( SH:- ROFD at RD 0/390 to 0/420,0/510 to 0/525,2/105 to 2/135 & 2/165 to 2/185)	497320/-	9946/-	350/-	Two months	Calss "C&D"
69	R/M of various road under Samoli Section Sub Division Rohru(SH:- Hiring of Tipper carriage of excavated muck etc)	297000/-	6000/-	350/-	One months	Calss "C&D"
70	R/M on various road under Rohru Sub Division (Samoli Section) (SH:- Hiring of JCB for C/o Unlined surface drain and earthen shoulders and maintenance of road etc)	495000/-	9900/-	350/-	Two months	Calss "C&D"
71	R/M on various road under Rohru Sub Division (Samoli Section) (SH:- Hiring of JCB for C/o Unlined surface drain and earthen shoulders and maintenance of road etc)	495000/-	9900/-	350/-	Two months	Calss "C&D"
72	R/R of various road under Samoli Section Sub Division Rohru(SH:- Hiring of Tipper carriage of excavated muck etc)	297000/-	6000/-	350/-	One months	Calss "C&D"
73	C/o Rcd road km 0/00 to 21/195(SH:- C/o R/wall in wire crate at RD 18/900 to 18/915)	222938/-	6458/-	350/-	Two months	Calss "C&D"
74	R/R Damage on Tikkari to tangnu road km 0/00 to 15/00(SH:- C/o R/wall in wire crate at RD 0/290 to 0/300 & 10/570 to 10/585)	464910/-	9298/-	350/-	Two months	Calss "C&D"
75	R/R Damage to Dhara kapandli road km 0/00 to 0/600(SH:- C/o R/wall at Rd 0/335 to 0/345)	473672/-	9500/-	350/-	One months	Calss "C&D"
76	C/o Narkanda Baggi Khadralla Sungari road km 0/00 to 67/00(SH:- C/o R/wall in wire crate at RD 40/565 to 40/587.50)	354708/-	7100/-	350/-	One months	Calss "C&D"
77	R/R Damage to on Barara Sharog road km 0/00 to 8/00(SH:- C/o R/wall in PCC 1:4:8 at RD 6/790 to 6/801.9)	465475/-	9309/-	350/-	Two months	Calss "C&D"
78	Providing Tarring work on narkanda baggi Khadralla sidpur Sungri road (SH:- Metelling and tarring work in Portion at Rd 63/00 to 63/080)	477253/-	8500/-	350/-	Two months	Calss "C&D"
79	R/R Damage on Bhatwari Hingwala gawas road km 0/00 to 7/00(SH:- C/o 900mm dia HPC at RD 0/320 with wing wall)	416508/-	8400/-	350/-	One months	Calss "C&D"
80	C/o Link road Khorsu to Gujjar basti Bashrali road km 0/00 to 2/00(SH:- C/o R/wall in PCC at RD 9/220 to 9/236)	388489/-	7800/-	350/-	One months	Calss "C&D"
81	R/R Damage on Bhaloon Kenchi to Bhaloon road km 0/00 to 4/00(SH:- C/o B/wall in PCC 1:4:8 & wire crate at RD 2/535 to 2/560)	446797/-	9000/-	350/-	One months	Calss "C&D"
82	C/o mastot to bagi kainchi road km 0/00 to 1/235(SH:- F/C 5/7 mtyr wide road at RD 0/00 to 0/345)	485092/-	9700/-	350/-	Two months	Calss "C&D"
83	C/o Link road to village Lakhadhar Mini Gadam road km (SH:- C/o R/wall in PCC 1:4:8 at RD 0/612.5 to 0/625)	486553/-	9800/-	350/-	One months	Calss "C&D"
84	C/o Link road to village Lakhadhar Mini Gadam road km (SH:- C/o R/wall in PCC 1:4:8 at RD 0/600 to 0/612.5)	486553/-	9800/-	350/-	One months	Calss "C&D"
85	C/o H.B Khariara Seri Km 0/00 to 1/370(SH:- F/C 5/7 mtr wide road between km 0/240 to 0/480)	493202/-	9864/-	350/-	Two months	Calss "C&D"
86	GEotech Investigation for Construction of 30.00 mtr span steel truss /RCC T Beam Bridge barsheel km 0/00 to 2/200 ( Sh:- Bridge at RD 0/120)	488000/-	9760/-	350/-	One months	Calss "C&D"
87	Construction of RCD road km 0/00 to 21/235 in Distt Shimla under CRF(SH:- Axle Load Survey and Automatic Traffic Count Survey ( ATCC)	152000/-	3040/-	350/-	One months	Calss "C&D"
88	Construction of Educational Buildings :- i) Govt. High school building at Kharla in Tehsil Tikkar Distt. Shimla HP. (SH:- C/O Building portion, WS & SI works, Septic Tank, RHWT, Site development works etc.) ii) Govt. Senior Secondary school building at Pujarli No. -4 in Tehsil Tikkar Distt. Shimla HP. (SH:- C/O Building portion, WS & SI works, Septic Tank, RHWT, Site development works etc.) iii) Govt. Senior Secondary school building at Sharontha in Tehsil Tikkar Distt. Shimla HP. (SH:- C/O Building portion, WS & SI works, Septic Tank, RHWT, Site development works etc.) iv) Govt. Industrial Training Institute (ITI) building at Summerkot in Tehsil Rohru Distt. Shimla HP. (SH:- C/O Building portion, WS & SI works, Septic Tank, RHWT, Site development works etc.)(Consultancy thereof)	100000/-	2000/-	350/-	One months	Calss "C&D"




89	Restoration of rain Damage on various road under Rohru Sub Division ( Summerkot Section)(SH:- Hliring of JCB for removal of slips slush/land slide and maintenance of road etc)	495000/-	9900/-	350/-	Two months	Calss "C&D"
90	R/R Damage to various road under Rohru Section Sub Division Rohru(SH:- Hiring of JCB for removal of slips and land slide maintenance of road)	495000/-	9900/-	350/-	Two months	Calss "C&D"
91	R/R Damage various road under Pujarli section Tikkar Sub Division (SH:- Hiring of JCB for removal of slips/land slide and maintenance of road etc)	308000/-	6160/-	350/-	One months	Calss "C&D"
92	R/R Damage various road under Pujarli section Tikkar Sub Division (SH:- Hiring of JCB for removal of slips/land slide and maintenance of road etc)	308000/-	6160/-	350/-	One months	Calss "C&D"
93	R/R Damage various road under Rohru Section Rohru Sub Division (SH:- Hiring of JCB for removal of slips/ Snow and maintenance of road etc)	495000/-	9900/-	350/-	Two months	Calss "C&D"
94	R/R Damage various road under Rohru Section Rohru Sub Division (SH:- Hiring of Tipper for carriage of muck gravel material etc)	495000/-	10000/-	350/-	Three months	Calss "C&D"
95	R/R Damage to udayniwas Jakhar road km 0/00 to 12/00(SH:- C/o B/wall in PCC 1:4:8 at RD 5/193 to 5/206)	492570/-	9900/-	350/-	One months	Calss "C&D"
96	R/R Damage to udayniwas Jakhar road km 0/00 to 12/00(SH:- C/o B/wall in PCC 1:4:8 at RD 5/180 to 5/193)	492570/-	9900/-	350/-	One months	Calss "C&D"
97	C/o Dhamwari to Gokswari km 0/00 to 5/300(SH:- C/o R/wall at RD 1/910 to 1/930)	418482/-	8500/-	350/-	One months	Calss "C&D"
98	A/R & M/O HPPWD Store at Rohru(SH:- C/o Steel work at HPPWD Store at Rohru)	437005/-	8740/-	350/-	Two months	Calss "C&D"
99	R/R Damage various road under Rohru Section Rohru Sub Division (SH:- Hiring of JCB for removal of slips/ Snow and maintenance of road etc)	252000/-	5040/-	350/-	One months	Calss "C&D"
100	C/o Kui nadu road km 0/00 to 1/00(SH:- C/o R/wall at RD 0/495 to 0/507 & 14 no parapets in R/R 1:6)	437235/-	8700/-	350/-	One months	Calss "C&D"
101	R/R Damage to Badiyara Diswani road km 0/00 to 6/00(SH:- C/o R/wall at RD 1/575 to 1/589)	491799/-	9836/-	350/-	Two months	Calss "C&D"
102	R/m of Rest House at Tikkar (Sh:- C/o wood work & WS & SI)	270097/-	5402/-	350/-	One months	Calss "C&D"
103	Repair and maintenance of Rest House at Tikkar( SH:- P/F AC4 flooring and Boundary wall at Rest House Tikkar)	481647/-	9700/-	350/-	One months	Calss "C&D"
104	Repair and maintenance of rest House at Tikkar (Sh:- Construction of wood work for lining in wall)	460843/-	9300/-	350/-	One months	Calss "C&D"
105	R/M of Rest House at Tikkar(SH:- C/o Painting work and Tile work)	431629/-	8633/-	350/-	Two months	Calss "C&D"
106	C/o Link road from rai odhidhar(HB Khashdhar) km0/00 to 1/300(SH:- C/o B/wall in wire crate at RD 0/580 to 0/630)	425019/-	8500/-	350/-	One months	Calss "C&D"
107	C/o Link road from rai odhidhar(HB Khashdhar) km0/00 to 1/300(SH:- C/o 900mm dia HPC at RD 1/150)	432281/-	8700/-	350/-	One months	Calss "C&D"
108	R/R Damage to mandhali to Sharontha road km 0/00 to 10/00(SH:- C/o B/wall at RD 5/025 to 5/050 and R/wall at RD 3/585 to 3/600)	492443/-	9900/-	350/-	One months	Calss "C&D"
109	R/R Damage on Udhayniwas Jakhar rantari road km 0/00 to 4/00(SH:- C/o R/wall at RD 3/870 to 3/880)	473672/-	9500/-	350/-	One months	Calss "C&D"
110	C/o Link road Shashtwani kainchi to gartu nala km 0/00 to 2/00( SH:-F/C 5/7 mtr wide road at RD 0/135 to 0/285)	470051/-	9401/-	350/-	Two months	Calss "C&D"
111	C/o Link road Shashtwani kainchi to gartu nala km 0/00 to 2/00( SH:-F/C 5/7 mtr wide road at RD 0/285 to 0/420)	441829/-	8837/-	350/-	Two months	Calss "C&D"

**Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest**

**TERMS AND CONDITIONS:-**

- The Earnest money for the above works should be submitted with the application for the application for the purchase of the tender-documents.
- The Contractors should quoted the rates of the items in the tenders both in figures and words.
- Income tax & G.S.T. No. Latest clearance certificate.
- The contractor/firms shall accompany his enlistment/renewal & EPF submit before the award of tender.


8. The Contractors should apply for two works only at a time for tenders.
9. Work should be completed by the contractor within stipulated period.
10. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.

  
Executive Engineer  
B&R Division HP.PWD,  
Rohru

NO:- PW-<sup>RD</sup>~~DKB~~-CB-Tender/2023-24 :- 27008-17  
Copy forwarded for information and wide publicity to:-

Dated 11/3/24

11. The Chief Engineer (S) HPPWD Shimla-2
12. The S.E 14<sup>th</sup> Circle HPPWD Rohru
13. All the EE's under 14<sup>th</sup> Circle HPPWD Rohru
14. All the A.E's working under this Division (B&R)
15. The Sub Divisional Magistrate Dodra Kwar
16. The BDO Dodra Kwar.
18. The Naib tehsildhar Dodra Kwar
19. A/B and D/B in this office
20. Notice Board

  
Executive Engineer  
B&R Division HP.PWD,  
Rohru

# **BART / SCHEDULE OF QUANTITY**

Job No. \_\_\_\_\_  
 Estimated Cost:-494201/-  
 Earnest Money:-9000/-  
 Time:-One Month

**NAME OF WORK:-** R/R damages to Jangla Thali Amboi road km.0/0 to 10/0 (SII:-C/O R/wall at RD.3/463 to 3/470)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	29.67	407.00	Rupces:-Four Hundred Seven and Paisa Zero only	Cum	12076
2	Plain/reinforced cement concrete (1:3:6) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203.as directed by the Engineer-in-Charge	66.50	6972.00	Rupces:- Six Thousand Nine Hundred Seventy Two Paisa Zero only.	Cum	463638
3	Providing and laying of back filling behind abutment, wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	8.61	1474.00	Rupces:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	12691
4	Providing weephole in brick masonry /stone masonry, plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses614,709,1204.3.7.as directed by the Engineer-in-Charge	14.00	414.00	Rupces:-Four Hundred Forteen Paisa Zero only.	No.	5796
		<b>Total:-</b>				<b>494201</b>
		DNIT No. _____				
		Quoted rate in figure _____				
		Quoted rate in words _____				
		Signature of contractor with address:- _____				

Approved for Rs.494201/- only for the Year 2023-2024

Executive Engineer  
 B&R Division  
 HP.PWD Rohru



# **BNTT/ SCHEDULE OF QUANTITY**

Job No. \_\_\_\_\_  
Estimated Cost:-498530/-  
Earnest Money:-9000/-  
Time:-One Month

**NAME OF WORK:-R/R damages on Nandla Jhawari road km.0/0 to 4/0 (SH:-C/O R/wall at RD.2/940 to 2/960)**

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	29.20	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	9485
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	18.00	402.00	Rupees:-Four Hundred Two and Paisa Zero only	Cum	7236
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm ( hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 2.5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	156.25	2890.00	Rupees:-Two Thousand Eight Hundred Ninety and Paisa Zero only	Cum	451563
4	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	20.52	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	30246
		<b>Total:-</b>				498530
		<b>DNIT No. _____</b>				
		<b>Approved for Rs.498530/- only for the Year 2023-2024</b>				
		<b>Quoted rate in figure</b>				
		<b>Quoted rate in words</b>				
		<b>Signature of contractor with address:-</b>				

Executive Engineer  
B&R Division  
HP.PWD Rohru

# **BIDDER SCHEDULE OF QUANTITY**

Estimated cost Rs. 4,50,750/-  
Earnest Money Rs. 9000/-  
one Month

Name of work :- R/R Damages Badiyara Jangla Todsa Devdhar Banoti road km 0/0 to 11/0(SH- Removal of slips at various RD 1/415 to 1/645 )

Sr No	Description of items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means in cluding cutting and trimming of slips and disposal of cut materials within all lifts 1.5 metres leads upto 100m as per technical specifications 302.2.5 and 1611 within all leads and lifts as per directions of Engineer in charges	1951.30	231.00	Rs two hundred thirty one only	per cubic metre	450750
DNT NO .....Approved for Rs. 4,50,750 /-or the year 2023-24						450750

Quoted Rate in figure (+) (-)	%
Quoted Rate in Words (+) (-)	%

Signature of Contractor with full Address

Executive Engineer  
B&R Divn HP, PW  
Rohru

(3)

(4)

### SCHEDULE OF QUANTITY

NAME OF WORK--:R/R damages on various road under Rohru Sub-Division (Kansakoti Section)(SI:-Hiring of JCB for removal of slips at various RDs, maintenance of road and dressing of road surface)

Job No.:-

Estimated Cost:- 495000

Earnest Money:- 9900

Time:- Two Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of JCB (Excavator cum loader) front end loader 0.50 cum/ hour including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heights and all kinds of soils such as kankar moorum shingle boulders decomposed or soft variety of soil such a spade work pick work jumer work soft rock hard rock including their intermediate classification of soil including mechnacial transportation of necessary. The disposal of this undervicable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its. All salvaged materials such as quirted stone shall belong to the department and manikurnum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minimum 18.00 cubice metre of earth work shall be done by the machine in one hours ans 200 cum of snow shall be removed from the road surface in one hour other wise number of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge including all leads and lifts	450.00	1100.00	Rupees:-One Thousand One Hundred and Paiza Zero only	Per Hours	495000
				Total:-		495000
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

Executive Engineer  
B&R Division  
HP.PWD Rohru



5

**Schedule of Qty**

**Name of Work :- Dhamwari Gokswari road km 0/00 to 5/300(SH:- C/o Unlined Surface drain and earthen shoulder km 0/00 to 2/600)**

Sr.No	Description of Items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		Two Month
				Rate In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Construction of unlined surface drains of average cross-sectional area 0.40' sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.	2600	rmt	49.55	Rupees Fourty Nine - Paise Sixty Five Only	129090
2	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903.	1362.18	sqm	242.65	Rupees Two Hundred & Fourty Two - Paise Sixty Five Only	330533
Total						459623

**Condition:-**


1 The rates Should be quoted for all heights including all lead and lift.

2 cost. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Rohru

Job No:-

### Schedule of Qty

Schedule of Qty						
Name of Work :- R/R Damage to Khabal Sindasli road km 0/00 to 6/00 under Chirgaon Sub Division in Chirgaon Section (Sh:- Hiring of Pock lane i/c Rock breaker to break boulder in various reaches)				ESTIMATED COST		49500
				EARNEST MONEY		990
				TIME LIMIT:		One Month
Sr. No	Description of Items.	Qty	Unit	Rate	In Words	Amount
				In Fig.		
1	Hiring of Excavator-Cum-Loader (POCK LANE/L&T) with 90 H.P. Engine and lifting capacity of minimum 5000 Kgs including P.O.L. charge-shifting charges and other ancillary equipments as required at site of work for cutting in earth work in all heights in all kinds of soil such as Kanhar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, lumper work, soft rock, hard rock including their intermediate classification of soil including cheselling/wedging out of rock, etc. where blasting is prohibited including saturated soils including filling in embankments where including consolidating with sheep foot rollers and disposal of this unserviceable materials in all leads and lifts including mechanical transportation if necessary. The disposal of this unserviceable materials has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place the contractor is liable for it. All salvaged materials such as quarried stone shall belong to the department and maximum useful quantity of stones from cutting work shall have to be neatly stacked along the road side on road burns. The work involves widening from existing width to IRC single lane standard width formation width 5 meters in straight and 7 meter in curve as per their radius. Minimum 40cm of earth work shall be done by the Machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instruction of the Engineer-in-Charge including all leads and lifts, with rock breaker.	11	Per Hours	4500	Four thousand Five Hundred only	49500
Total						49500

DNT No.....Approved for Rs. 49500 /- only for the year 2023-24

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

7

**Schedule of Qty**

**Name of Work:- R/R Daamage to Masli village to Govt Sr.Sec. School masli km 0/00 to 0/600 (SI:- C/o B/wall in wire crate at RD 0/300 to 0/345**

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	TIME LIMIT	Two Month
1	2	3	4	Rate In Fig. 5	In Words 6	Amount. 7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	45	cum	324.83	Rupees Three Hundred & Twenty Four - Paise Eighty Three Only	14617
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deteriorious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	18	cum	407	Rupees Four Hundred & Seven Only	7326
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	140.63	cum	2593.7	Rupees Two Thousand Five Hundred & Ninety Three - Paise Seventy Only	364752
Total						386695

Condition:-

- 1 The Rates Should be quoted for all heights including all lead and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (Rs/-)	
Quoted rate Words (Rs/-)	

Signature of the Contractor with full address:-

**Executive Engineer**  
**B&R Division HPPWD**  
**Rohru**



(8)

## Schedule of Qty

Name of Work :- Dhamwari Gokswari road km 0/00 to 5/300(SH:- C/o Unlined Surface drain and earthen shoulder km 2/600 to 5/300)				ESTIMATED COST	
				EARNEST MONEY	459623
				TIME LIMIT:	9192
					Two Month
Sr.No	Description of Items.	Qty/ Unit	Rate	In Words	
				In Fig.	Amount.
1	2	3	4	5	7
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.	2600	rmt	49.65	Rupees Fourty Nine - Paise Sixty Five Only
2	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903.	1362.18	sqm	242.65	Rupees Two Hundred & Fourty Two - Paise Sixty Five Only
Total					459623

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

79

Job No:-

Schedule of Qty

Name of Work :- R/R Damage to Khabal Sindasli road km 0/00 to 6/00 under Chirgaon Sub Division in Chirgaon Section (Sh:- Hiring of Pock lane l/c Rock breaker to break boulder in various reaches)

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		Amount
				EARNEST MONEY	990	
				TIME LIMIT:	One Month	
1	2	3	4	Rate	In Words	
				In Fig.	6	
1	Hiring of Excavator-Cum-Loader (POCK LANE/L&T) with 90 H.P. Engine and lifting capacity of minimum 5000 Kms including P.O.L. charge, shifting charges and other ancillary equipments as required at site of work for cutting in earth work in all heights in all kinds of soil such as Kankar, moorum, shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including chiseled, wedging out of rock etc. where blasting is prohibited including saturated soils including filling in embankments where including consolidating with sheep foot rollers and disposal of this unserviceable materials in all leads and lifts including mechanical transportation if necessary. The disposal of this unserviceable materials has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place the contractor is liable for it. All salvaged materials such as quarried stone shall have to be neatly stacked along the road side on road burms. The work involves widening from existing width to IRC single lane standard width formation width 5 meters in straight and 7 meter in curve as per their radius. Minimum 40cm of earth work shall be done by the Machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instruction of the Engineer-in-Charge including all leads and lifts. with rock breaker.	11	Per Hours	4500	Four thousand Five Hundred only	49500
Total						49500

DNT No.....Approved for Rs. 49500 /- only for the year 2023-24

Quoted rate Figure ( +/-)

Quoted rate Words ( +/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

(10)

Name of Work:- R/R Damage on Chitgaon Gushali to Rohal road km 0/00 to 9/00 (SII:- C/o R/wall in wire crate at RD 8/509 to 8/521)

Schedule of Qty

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		159742
				TIME LIMIT:		Two Month
1	2	3	4	Rate	In Words	Amount.
				In Fig.	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	22.56	cum	184.59	Rupees One Hundred & Eighty Four - Paise Fifty Nine Only	4164
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	10.44	cum	407.00	Rupees Four Hundred & Seven Only	4249
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4526 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	56.25	cum	2593.7	Rupees Two Thousand Five Hundred & Ninety Three - Paise Seventy Only	145896
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material.	4.08	cum	1331.51	Rupees One Thousand Three Hundred & Thirty One - Paise Fifty One Only	5433
Total						159742

Condition:-

1. The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru



(11)

Job No.

## SCHEDULE OF QUANTITY

Estimated Cost:-294567/-  
 Earnest Money:-5900/-  
 Time:-One Month

NAME OF WORK:- R/R damages on TKHR road km.69/0 to 80/600 (SH:-Removal of slips at various RDs.)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in all leads and lifts upto 1.5m and lead upto 100 m as per technical specification 302.305 and 1611 as per directed by the Engineer in charge	1904.12	154.70	Rupees:-One Hundred Fifty Four and Paiza Seven Zero only	Per Cum	294567

	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address -					

Executive Engineer  
 B&R Division  
 H.P.PWD Rohru

(12)

## Schedule of Qty

Schedule of Qty						
Name of Work:-C/o Link road Desoit to H.B Kheda km 0/00 to 2/700(SII:- F/C/5/7 mtr wide road at RD 1/620 to 1/995)				ESTIMATED COST		
				EARNEST MONEY		498597
				TIME LIMIT:		9972
						Two Month
Sr. No	Description of Items.	Qty	Unit	Rate		Amount.
				In Fig.	In Words	
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its leveling fine dressing, and carriage of machines, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work, hard rock 1/6th (One sixth) blasting work, soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government, A recovery of useful stones 256.01 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1928.93	cum	256.484	Rupees Two Hundred & Fifty Eight - Paise Fourty Eight Only	498597
Total						498597

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 cost.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

13

Name of Work:- C/o Deorighat Tikkar Via Gujandli km 0/00 to 7/720 (SII:-Improvement of narrow reaches at Rd 3/315 to 3/354 and 3/400 to 3/445)

Schedule of Qty

Sr.No	Description of items.	Qty	Unit	ESTIMATED COST		Amount
				EARNEST MONEY	TIME LIMIT:	
				In Fig.	In Words	
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/weighing out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machines, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malakana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 293.69cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1402.35	cum	354,648	Ruppes Three Hundred & Fifty Four - Paise Sixty Five Only	497340
	Total					497340

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

2 cost

Quoted rate Figure (\*/-)

Quoted rate Words (\*/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru



(14)

## Schedule of Qty

Name of Work: C/o Link road Desoit to H.B Kheda km 0/00 to 2/700(SH: F/C 5/7 mtr wide road at RD 2/430 to 2/710)				ESTIMATED COST		497800
				EARNEST MONEY		9956
				TIME LIMIT:		Two Month
Sr. No	Description of Items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300, 1603, 1.1 603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machines, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work, hard rock 1/6th (One sixth) blasting work, soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the Engineer-in-Charge which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malakna, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stone 252.68cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1943.7	cum	256.109	Rupees Two Hundred & Fifty Six - Paise Eleven Only	497800
Total						497800

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

15

Name of Work:- Repair & Maintenance of Govt Degree College Secuna (Staff Quarter)(SH:- P/F Tiles, Distemper, painting etc.)

Schedule of Qty

Sr. No	Description of Items.	Qty	Unit	Rate		Amount
				In Fig.	In Words	
1	2	3	4	5	6	7
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	32.73	sqm	1275	Rupees One Thousand Two Hundred & Seventy Five Only	41731
2	Providing and laying in position cement concrete of specified grade excluding the cost of 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)	32.73	sqm	7594.57	Rupees Seven Thousand Five Hundred & Ninety Four - Paise Fifty	248570
3	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete 600x600mm	145.47	sqm	1436.85	Rupees One Thousand Four Hundred & Thirty Six - Paise Eighty Five Only	209019
Total						499319

Condition:-

- 1 The rates Should be quoted for all heights including all lead and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

16

Name of Work: Repair & maintenance of Govt Degree College Seema ( Staff Quarter) SII:- P/F Tiles Work 3rd floor and wall care putty)

Schedule of Qty

Schedule of Qty						
Name of Work:-Repair & maintenance of Govt Degree Collage Seena ( Staff Quarter) SII:- P/P Tiles Work 3rd floor and wall (care putty)		ESTIMATED COST				
		EARNEST MONEY		9978		
		TIME LIMIT:		Two Month		
Sr. No	Description of Items.	Qty	Unit	Rate	Amount.	
1	2	3	4	5	7	
1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete 600x600mm	70.81	sqm	1436.85	Ruppes One Thousand Four Hundred & Thirty Six - Paise Eighty Five Only	101743
2	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete	215.19	sqm	1460	Ruppes One Thousand Four Hundred & Sixty Only	314177
3	Applying white cement based wall care putty over plaster surface after thoroughly brushing the surface free from mortar droops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete. complete within all leads, lifts of materials and other incidentals	892.07	sqm	93	Ruppes Ninety Three Only	82963
Total						498883

Condition:-

1 The rates should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

(17)

## DNIT/ SCHEDULE OF QUANTITY

Job No. \_\_\_\_\_  
 Estimated Cost:-400701/-  
 Earnest Money:-8000/-  
 Time:-One Month

NAME OF WORK :- C/O link road from village Jabble km.00 to 6/0 (SIH:-C/OE/wall in wire crate at RD.1/500 to 1/510 &amp; 3/045 to 3/065)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	40.40	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	13123
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material with in all leads and lifts as per directed by the Engineer-in-Charge	23.40	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	9524
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia Gi wire conforming to 18260 and IS: 4826 in 100 mm x 100 mm ( hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 2.5 (twenty five) kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	125.00	2890.00	Rupees:-Two Thousand Eight Hundred Ninety and Paisa Zero only	Cum	361250
4	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	11.40	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	16804
		Total:-				400701
		DNIT No.		Approved for Rs.400701/- only for the Year 2023-2024		
		Quoted rate in figure		%		
		Quoted rate in words		%		
		Signature of contractor with address:-				

Executive Engineer  
 B&R Division  
 H.P.W.D Rohru



18

Schedule of QTY

Name of Work :- R/R Damage to link road to village Rausti km 0/00 to 4/015 in Chitragoon Sub Division( SII:- Hiring of JCB removal of slips at various RDs and dressing of road surface drain clearance)

Sr.No	Description of items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	Two Month
1	2	3	4	Rate	Amount.
				In Fig.	In Words
1	Hiring of J.C.B.Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as bankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450	Per Hours	1100	Rupess One Thousand One Hundred Only
					495000
Total					495000

DNIT No...1225..... approved for amounting to Rs.:495000/- for the year 2023-24

- The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.
- Quoted rate Figure (\*/-)
- Quoted rate Words (\*/-)
- Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

(19)

## Schedule of Qty

Name of Work :- R/R Damage to link road to village Rausi km 0/00 to 4/015th Chitragon Sub Division( Sil:- Hiring of JCB removal of slips at various RDs and dressing of road surface drain clearance)

Name of Work :- R/R Damage to link road to village Rausi km 0/00 to 4/015in Chitgaon Sub Division( SI:- Hiring of JCB removal of slips at various RDs and dressing of road surface drain clearance)										ESTIMATED COST		495000
										EARNEST MONEY		9900
										TIME LIMIT:-		Two Month
Sr. No	Description of items.	Qty	Unit	Rate		In Words	Amount.					
				In Fig.								
1	2	3	4	5	6	7						
1	Hiring of J.C.B(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankhar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450	Per Hours	1100	Rupees One Thousand One Hundred Only	495000						
Total						495000						

DNTT No...1724..... Approved for amounting to Rs:-495000/- for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

20


## SCHEDULE OF QUANTITY

Job No. \_\_\_\_\_  
Estimated Cost:-462586/-  
Earnest Money:-9300/-  
Time:-One Month

**NAME OF WORK:-R/R damages on Siria Nallah Kupri Melhi Badli Kalgaon road km.0/0 to 6/0 (SH:-C/O R/Wall in wire crate at RD.1/050 to 1/065 & 900mm Hume pipe culvetry at RD.3/700)**

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	23.28	324.83	Rupees:-Three Hundred Twenty Four and Paise Eighty three only	Cum	7562
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	39.52	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	16085
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	8.46	5109.04	Rupees:-Five Thousand One Hundred Nine and Paise Zero Four only	Cum	43222
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	2.10	5710.66	Rupees:-Five Thousand Seven Hundred Ten and Paise Six Six only	Cum	11992
5	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	29.40	5400.00	Rupees:-Four Thousand Four Hundred Paise Zero Only.	Cum	158760
6	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC Grade M-20 1:2:4 as per directed by the Engineer in charge	1.90	8228.35	Rupees:-Eight Thousand Two Hundred Twenty Eight and Paise Three Five only	Per Cum	15634
7	Back filling behind abutments wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	4.38	1331.51	Rupees:-One Thousand Four Hundred Seventy Four and Paise Zero only	Cum	5832
8	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection works backing filling concrete and masonry works in head walls and parapets clause 1106 as directed by the Engineer-in-Charge	7.50	5250.00	Rupees:-Five Thousand Two Hundred Fifty Paise Thirty Two only.	Cum	39375
9	Pointing with cement Mortar (1:3) on stone work as per technical specification clause 613.3 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	20.96	96.26	Rupees:-Ninety Six Paise Twenty Six only.	Cum	2018

10	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS-4826 in 100 mm x 100 mm ( hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 2.5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	62.50	2593.70	Rupees:-Two Thousand Five Hundred Ninety Three and Paise Seven Zero only	Cum	162106
				Total:-		462586
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

  
 Executive Engineer  
 B&R Division  
 HP.PWD Rohru



# **SCHEDULE OF QUANTITY**

Job No. \_\_\_\_\_  
 Estimated Cost:-492426/-  
 Earnest Money:-9800/-  
 Time:- One Month

**NAME OF WORK:-C/O link road to Chanti Raha Panu road km.0/0 to 2/0 (SI:- Widening of road at RD.0/0 to 0/240)**

Sl.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/cutting out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. Technical Specification Clause 300.1603.1.1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machines, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1:3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government/A recovery of useful stones 198.64 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lift as per the direction of Engineer in charge.	2236.43	220.184	Rupees:-Two Hundred Twenty and Pasa One Eight Four only	Cum	492426
Total:-						492426
DNIT No. 2817 Approved for Rs.492426/- only for the Year 2023-2024						
	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address:-					

Executive Engineer  
 B&R Division  
 J.P.W.D Rohru

Job No.

**SCHEDULE OF QUANTITY**

Estimated Cost:-305022/-

Earnest Money:-6100/-

Time:-One Month

**NAME OF WORK :- R/R damages on Mahbubullah Dastanli Kutub road (SIT:-C/O B/wall at RD.0/6/90 to 0/7/10)**

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	23.80	324.83	Rupees:- Three Hundred Twenty and Paisa Zero only	Cum	7731
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	19.20	407.00	Rupees:- Four Hundred Seven and Paisa Zero only	Cum	7814
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	4.53	6314.00	Rupees:- Six Thousand Three Hundred Fourteen and Paisa Zero only	Cum	28602
4	Stone masonry in cement mortar 1:6 (1 Cement :6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704, 1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	48.31	5400.00	Rupees:- Five Thousand Four Hundred Paisa Zero Only.	Cum	260874
Total:-						305022
DNIT No. Approved for Rs.305022/- only for the Year 2023-2024						
Quoted rate in figure %						
Quoted rate in words %						
Signature of contractor with address:-						

Executive Engineer  
B&R Division  
HP.PWD Rohru

23

# DNTT/SCHEDULE OF QUANTITY

Job No.  
Estimated Cost:-481635/-  
Earnest Money:-9700/-  
Time:-One Month

NAME OF WORK:-C/O link road from Kantari to Kandal road km.0/0 to 2/0 (SIL-I/II. Essential Kharanja stone soling at RD.0/0 to 0/250)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Preparation of sub - grade by dressing to camber (Earth work in cutting involved to be measured & paid for separately with in all leads and lifts as per directed by the Engineer-in-Charge	921.25	2.06	Rupees:-Two Paisa Zero Six only.	Sqm	1898
2	Consolidation of sub -grade with road roller including making good the undulations etc with earth Or quarry soil with in all leads and lifts as per directed by the Engineer-in-Charge	921.25	1.17	Rupees:-One Paisa Seventeen only.	Sqm	1078
3	Stone soling properly hand packed filling interstices with kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc complete as per HP PWD. specification 150mm spread thickness (finished work including materials and labour) with in all leads and lifts as per directed by the Engineer-in-Charge	211.89	2259.00	Rupees:-Two Thousand Two hundred Fifty Nine Paisa Zero only	Sqm	478660
Total:-						481635
DNT No. Approved for Rs.481635/-only for the Year 2023-2024						
Quoted rate in figure %						
Quoted rate in words %						
Signature of contractor with address:-						

Executive Engineer  
B&R Division  
H.P.PWD Rohru

**BILL OF SCHEDULE OF QUANTITY.**

Estimated cost Rs.461551/-  
Earnest money Rs.8200/-  
TIME : Two month

**Name of work :-C/O Link village Bakora km 0/0 to 3/0 (SH- F/C 6/7 metre wide road at RD 0/0 to 0/30)**

Sr No	Description of Items	Quantity	Rate in Figure	Rate in Words	Unit	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage. disposal of unsuitable cut material in specified manner, trimming/filling of unevenness bindage and finishing of the road to specified dimensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made from the contractor and recovery 104.52 cubic meter useful stones shall be made @300/-per cubic meter on pro rata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified dimension in all leads and lifts as per the direction of Engineer in Charge.	1371.00	336.65	Rs three hundred thirty six & paise sixty five only	per cubic metre	461551.00
Total-						461551

DNT NO. .... Approved for Rs 461551.00 for the year 2023-2024

Executive Engineer  
B&R Divn Hp PWD  
Rohru

Quoted Rate in figure (+/-)  
Quoted Rate in Words (+/-)  
Signature of Contractor with full Address

%

24



25

Name of Work:- C/o Link road Jabhal pather nalath Shagen Teer km 0/00 to 3/00(Slt. F/C 5/7 mtr wide road at RD 1/715 to 1/805)

Schedule of Qty

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		Two Month
				EARNEST MONEY	9744	
1	2	3	4	TIME LIMIT:		Amount.
				Rate	In Words	
				In Fig.	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases falling which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 262.53cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1803.3	cum	270.180	Rupees Two Hundred & Seventy - Paise Eighteen Only	487216
Total						487216

Condition:-

1 The rates should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

(26)

JOB NO.:-

## Schedule of Qty

Name of Work:- C/o Link road Jabhal pather nahal Shagen Teer km 0/00 to 3/00(SH- F/C 5/7 mtr wide road at RD 1/810 to 1/910)

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	9591	Two Month
1	2	3	4	Rate	In Words	Amount.
				In Fig.	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. Technical Specification Clause 300.1603.1.1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1:3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malakua, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 299.19cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	15213	cum	315213	Rupess Three Hundred & Fifteen - Paise Twenty One Only	479534
Total						479534

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

127

**Schedule of Qty**

Name of Work:- R/R Damage on Chirgaon Gushali to Rohal road km 0/00 to 16/00(SH:- C/o R/wall in wire crate at RD 14/272 to 14/297))

Sr.No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	9128	Two Month
				TIME LIMIT:		
				Rate		
				In Fig.		
				5		
					In Words	
					6	
						Amount.
						7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	51.25	cum	324.83	Rupees Three Hundred & Twenty Four - Paise Eighty Three Only	16648
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	27.5	cum	407	Rupees Four Hundred & Seven Only	11193
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	156.25	cum	2593.7	Rupees Two Thousand Five Hundred & Ninety Three - Paise Seventy Only	405266
4	Back filling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8	17.5	cum	1331.51	Rupees One Thousand Three Hundred & Thirty One - Paise Fifty One Only	23301
Total						456407

**Condition:-**

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

28

**Schedule of Qty**  
**Name of Work: C/o Link road Nesar to Munake dhar ( Sit:- F/C/5/7 mt wide road at Rd 0/000 to 0/090**

Name of Work: C/o Link road Nesar to Munake dhar ( SH:-F/C/5/7 int wide road at Rd/0/000 to 0/090				Schedule of Qty		
Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST		475015
				EARNEST MONEY		9500
				TIME LIMIT:		Two Month
1	2	3	4	Rate	In Words	Amount.
				In Fig.	6	
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited ) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber ,embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machines, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work, hard rock 1/6th (One sixth) blasting work, soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 214.22cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1825.81	cum	260.167	Ruppes Two Hundred & Sixty Paise Seventeen Only	475015
Total						475015

**Condition:-**  
 1 The rates Should be quoted for all heights including all lead and lifts.  
 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.  
 2 cost.  
 Quoted rate Figure ( +/-)  
 Quoted rate Words ( +/-)  
 Signature of the Contractor with full address:-

Executive Engineer  
 B&R Division HPWD  
 Rohru



29

**Schedule of Qty**


Name of Work:- C/O Link road Near to Munake dhar ( Sit:- F/C 5/7 int wide road at Rd 0/165 to 0/240						
Sr. No.	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	9467	Two Month
				TIME LIMIT:		
				Rate	In Words	Amount.
				In Fig.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/cutting out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 400.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machines, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1:3 (One third) for blasting work, hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malakana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 234.78cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lift as per the direction of Engineer in charge.	1806	cum	262.098	Rupees Two Hundred & Sixty Two - Paise Ten Only	473349
	Total					473349

Condition:-  
1 The rates Should be quoted for all heights including all lead and lifts.

2 cost.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (+/-)  
Quoted rate Words (+/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPWD  
Rohru

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure { +/- }
Quoted rate Words { +/- }

Signature of the Contractor with full address:-

**Executive Engineer**  
**B&R Division HPPWD**  
**Rohru**

**SCHEDULE OF QUANTITY**

(21)

**Name of Work: R/R Damages on Koftu Sanhaal road at RD 0/0 to 1/0(SH- C/O R/wall at RD 0/105 to 0/112)**

Estimated cost Rs 441054/-  
Earnest Money Rs 8800/-  
Time :- Two Month

Sr No	Description of Items	Quantity	Rate in Figure,	Rate in Words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	7.22	303.17	Rs three hundred three & paise seventeen only	per cubic metre	2189
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	8.96	407.00	four hundred seven only	per cubic metre	3647
3	Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	37.40	5839.05	Rs five thousand eight hundred thirty nine & paise five only	per cubic metre	218380
4	Stone Random masonry work in cement mortar 1:6 (1cement :6 sand )in foundation complete as per drawing and technical specification clause 702,704,1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charges	39.38	5400.00	Rs five thousand four hundred only	per cubic metre	212652
5	Back filling abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3,8 within all leads and lifts as per direction of Engineer in charge	2.84	1474.00	one thousand four hundred seventy four only	per cubic metre	4186
	<b>Total:-</b>					<b>441054</b>

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Signature of Contractor with full Address

Executive Engineer  
B&R Divn HP, PWD  
Rohru

(32)

Name of Work:- C/o Rantant Kandai road km 0/00 to 2/235(SH:- F/C 5/7 mtr wide road at RD1/030 to 1/315)

Schedule of Qty

Schedule of Qty						
Name of Work:- C/o Rantart Kandai road km 0/00 to 2/235(SII:- F/C 5/7 mtr wide road at RD1/030 to 1/315)				ESTIMATED COST		483408
				EARNST MONEY		9668
				TIME LIMIT:		Two Month
Sr. No	Description of Items:	Qty	Unit	Rate In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited ) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by, the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1.1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber ,embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour If required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 239.85cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1845	cum	262.010	Rupees Two Hundred & Sixty Two - Paise One Only	483408
Total						483408

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 cost  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru



(13)

(33)

**SCHEDULE OF QUANTITY**

**NAME OF WORK:-** C/O Kantari Kandal road km. 0/0 to 2/235 (Sili-E/C 5/7 Mtrs. Wide road at RD. 1/315 to 2/540)

Job No. \_\_\_\_\_  
 Estimated Cost:- 354008/-  
 Earnest Money:- 7100/-  
 Time:- One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hills area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, cherting, wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M & R 12 Technical Specification Clause 300, 1003 1, 1003 2, sorting out useful material and stacking the same in all roads and lifts in required width of the road and transportation of useful material for filling in road way, embankments for grade improvements and disposal of all surplus materials in required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means, along with its levelling, fine dressing and carriage of machines, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1 ton (One sixth) blasting work soft rock 1 1/4 ton (one 10th) jumper work in all cases falling which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all loads and lifts. The rate including octroi, royalty, Mahatma toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 252.79 cum metre @ Rs. 500/- Per cubic metre shall be done on pro-rata basis in each running mile for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked over provided dimension in all loads and lifts as per the direction of Engineer in charge.	1351.13	262.009	Rupees-Two Hundred Sixty Two and Paise /zero /zero Nine only	Cum	354008
Total:-						354008
DPT No. _____		Approved for Rs.354008/- only for the Year 2023-2024				
Quoted rate in figure		₹ 0				
Quoted rate in words		0				
Signature of contractor with address:-						

Executive Engineer  
 B&R Division  
 H-2 PWD Rohru

34

Name of Work: R/R Damage Kansoti Kutara Dalgaon road km 0/00 to 15/00(SH:- C/o B/wall at RD 1/735 to 1/755) Schedule of Qty

Sr. No	Description of Items.	Qty	Unit	EARNEST MONEY		7273
				TIME LIMIT:		Two Month
				Rate	In Words	Amount.
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	24.6	cum	193	Ruppes One Hundred & Ninety Three Only	4748
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material	25.4	cum	490	Ruppes Four Hundred & Ninety Only	12446
3	Plain/rein forced cement concrete(1:6:12)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	5.4	cum	5450	Ruppes Five Thousand Four Hundred & Fifty Only	29430
4	Plain/rein forced cement concrete(1:4:8)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	4	cum	6113.62	Ruppes Six Thousand One Hundred & Fifteen - Paise Sixty Two Only	24462
5	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702,704,1202 and1204 Random rubble masonry in cement mortar(1:6)	30.2	cum	5410	Ruppes Five Thousand Four Hundred & Ten Only	163382
6	Construction of dry masonry in Retaining walls etc. As per HPPVD specification	32.71	cum	3950	Ruppes Three Thousand Nine Hundred & Fifty Only	129205
Total						363673

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure ( ₹/-)

Quoted rate Words ( ₹/-)

Executive Engineer  
B&R Division HPPWD  
Rohru



## SCHEDULE OF QUANTITY

**NAME OF WORK:-RR damages to Syria Nallah Kupri Melthi Butli Kulgaon road km.0/0 to 6/0 (SH:-C/O B/wall in wire crate at RD.1/280 to 1/300 & C/O 900mm dia HPC at RD.3/200)**

Job No. \_\_\_\_\_  
Estimated Cost:-452131/-  
Earnest Money:-9100/-  
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in fill. Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	23.28	324.83	Rupees:-Three Hundred Twenty Four and Paise Eighty three only	Cum	7562
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	39.52	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	16085
3	Plain reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	6.19	5109.04	Rupees:-Five Thousand One Hundred Nine and Paise Zero only	Cum	31625
4	Plain reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	2.30	5710.66	Rupees:-Five Thousand Seven Hundred Ten and Paise Six Six only	Cum	13135
5	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	29.400	5400.00	Rupees:-Five Thousand Four Hundred Paise Zero Only.	Cum	158760
6	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC Grade M-20 1:2:4 as per directed by the Engineer in charge	1.90	8228.35	Rupees:-Eight Thousand Two Hundred Twenty Eight and Paise Three Five only	Per Cum	15634
7	Back filling behind abutments wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	4.38	1331.51	Rupees:-One Thousand three Hundred thirty one and Paise Five One only	Cum	5832
8	Providing and laying reinforced cement concrete pipe NP2 for culverts on forst class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection works backing filling concrete and masonry works in head walls and parapets clause 1106 as directed by the Engineer-in-Charge	7.50	5250.00	Rupees:-Five Thousand Two Hundred Fifty Paise Zero only.	Cum	39375
9	Pointing with cement Mortar (1:3) on stone work as per technical specification clause 613.3 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	20.96	96.26	Rupees:-Ninety Six Paise Twenty Six only	Cum	2018
10	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm ( hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 2.5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals	62.50	2593.70	Rupees:-Two Thousand Five Hundred Ninety Three and Paise Seven Zero only	Cum	162106
Total:-						452131

Quoted rate in figure  
Quoted rate in words  
Signature of contractor with address:-

%  
%

Executive Engineer  
B&R Division  
HP.PWD Rohru

36

Name of Work :- C/o Link road from Sangrad to Hingori km 0/00 to 1/500( Sili:- C/o PCC R/wall at RD 0/150 to 0/176)

Schedule of Qty

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		Amount.
				FARNEST MONEY	TIME LIMIT:	
				In Fig.	In Words	
1	Excavation in soil in Hills. Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1602.1	24.44	cum	324.83	Ruppes Three Hundred & Twenty Four - Paise Eighty Three Only	7939
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material and as per HPPWD specification of 1990 volume-1 or as directed by the Engineer-In-Charge	17.42	cum	407	Ruppes Four Hundred & Seven Only	7090
3	Providing concrete for plain reinforced concrete in open foundations/B-walls complete as per drawing and technical specification clause 802.803.1202 & 1203 grade (1:4:8 nominal mix), 1 cement 4sand :8graded stone aggregate, including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge	68.12	cum	5710.6	Ruppes Five Thousand Seven Hundred & Ten - Paise Sixty Only	389006
4	Back filling behind abutment wing wall and return complete as per drawing and technical specification clause 1204.3.8	17.16	cum	1331.51	Ruppes One Thousand Three Hundred & Thirty One - Paise Fifty One Only	22849
Total						426884

1 The rates should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)	(%)
Quoted rate Words (+/-)	(%)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru



37

Name of Work :- C/o Link road from Sangrard to Hingora km 0.00 to 1/500 (SIH - C/o R/wall in wire crate at RD 0/3.65 to 0/373)

Schedule of Qty

Schedule of Qty							443592
Name of Work :- C/o Link road from Sangrad to Hingrad km 0.60 to 1.500( SH - C/O R/wall in wire crate at RD 0/345 to 0/373)							8872
ESTIMATED COST							Two Month
EARNEST MONEY							
Sr. No	Description of items	Qty	Unit	TIME LIMIT		Amount	
				Rate in Pk	In Words		
1	2	3	4	5	6	7	
1	Excavation in soil in Fifth Acre by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a haul upto 20 m as per Technical Specification Clause 1605.1	90.75	cum	234.88	Rupees Three Hundred & Twenty Four - Paise Eighty Three Only	29478	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 105.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a level of 40 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material and as per HPWD specification of 1990 volume-I or as directed by the Engineer-In-Charge.	31.68	cum	407	Rupees Four Hundred & Seven Only	12894	
8	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1501	154.69	cum	2593.2	Rupees Two Thousand Five Hundred & Ninety Three - Paise Seventy Only	401219	
Total						443592	

1 The rates should be quoted for all heights including all lead and lifts.  
2 cost  
3 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and  
4 cost  
5 Quoted rate Figure ( +/+ ) (%)  
6 Quoted rate Words ( +/+ ) (%)  
7 Signature of the Contractor with full address.

Executive Engineer  
B&R Division HPWD  
Rohru

# SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on Shalwat to Wali road km. 0/0 to 3/0 (SH:-C/O R/wall at RD.1/210 to 1/210 & R/wall at RD.0/112 to 0/120 & U-Shape drain at Shalwat Bus Stop Length-28 Mtrs.)

Job No.  
Estimated Cost-421194.  
Forecast Money-800.  
Time- One Month

Sr.no	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hills Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a load upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	19.84	123.83	Rupees Three Hundred Twenty Four and Paise Eighty Three only	Per Cum	6445
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 105.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a load of 20 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material with in all leads and lifts as per directed by the Engineer-in-Charge	20.48	407.00	Rupees Four Hundred Seven and Paise Zero only	Per Cum	8335
3	Plain reinforced cement concrete (16.12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	4.96	5109.04	Rupees Five Thousand One Hundred Nine and Paise Zero Four only	Per Cum	25341
4	Same masonry in cement mortar 1:6 (Cement :6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704, 1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	57.57	5400.00	Rupees five Thousand Four Hundred Paise Zero Only	Per Cum	310878
5	Back filling between abutments, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 with in all leads and lifts as per directed by the Engineer-in-Charge	6.00	1331.51	Rupees One Thousand Three Hundred Thirty One Paise Five One only	Per Cum	7989
6	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 RCC Grade M-20 1:2:4 as per directed by the Engineer in charge	7.56	8228.35	Rupees Eight Thousand Two Hundred Twenty Eight and Paise Three Five only	Per Cum	62206
				Total:-		421194
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address					

Exe. Engineer  
R&N Division  
H.P.W.D. Rohru

(39)

# **SCHEDULE OF QUANTITY**

**NAME OF WORK:-** R/R damages on Jagothi Nallah Audhrothi road (SI:-C/O B/wall at RD. 2/390 to 2/410 )

**Sr.no.**

**Item of work**

**Quantity**

**Rate in figure**

**Rate in words**

**Unit**

**Amount**

1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	12.80	290.00	Rupess:-Two Hundred Ninety and Paise Zero only	Cum	3712
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	14.20	407.00	Rupess:-Four Hundred Seven and Paise Zero only	Cum	5779
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	8.60	5109.04	Rupess:-Five Thousand One Hundred Nine and Paise Zero Four only	Cum	43938
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leadsa and lifts as per directions of Engineer in charge	3.60	5710.66	Rupess:-Five Thousand Seven Hundred Ten Paise Six Six Only.	Cum	20558
5	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leadsa and lifts as per directions of Engineer in charge	52.00	5400.00	Rupess:-Five Thousand Four Hundred Paise Zero Only.	Cum	280800
6	Construction of dry masonry in retaining walls, breast walls etc.as per drawings and technical specification including carriage of material within all leadsa and lifts as per directions of Engineer in charge	39.76	3305.60	Rupess:-Three Thousand three Hundred five Paise Sixty Only.	Cum	131431
<b>Total:-</b>						<b>486218</b>

Quoted rate in figure	%
Quoted rate in words	%
Signature of contractor with address:-	

Executive Engineer  
B&R Division  
M.P.TWD Rohru

40

**Schedule of Qty**

Sr.No		Description of items.		EARNEST MONEY		TIME LIMIT:		9970	
								Two Month	
1	2	3	Qty Unit	4	Rate In Fig.	5	In Words	6	Amount.
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases falling which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 330.3cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1320.9	cum	377404	Rupees Three Hundred & Seventy Seven - Paise Fourty Only		498513		
Total									498513

Condition:-

1 The rates should be quoted for all heights including all lead and lifts.


The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

2

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

  
 Executive Engineer  
 B&R Division HPWD  
 Rohru



41

**Schedule of Qty**

**Name of Work :- R/R Damage to various road under Rohru Section Sub Division Rohru(SH:- Hiring of ICB for removal of slips and maintenance of road etc)**

Sr.No	Description of items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	One Month
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity 45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	3	4	Rate In Fig.	In Words
1		15	Per Day	8400	Rupees Eight Thousand Four Hundred Only
Total					126000

DNIT No. ---258. approved for amounting to Rs.:126000. for the year 2022-23

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)
Quoted rate Words (+/-)

Signature of the Contractor with full address:-

  
**Executive Engineer**  
**B&R Division HPPWD**  
**Rohru**

(42)

# SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on link road Tandroh Nallah to Jagtarli road km.0/0 to 2/0 (SH:-C/O B/wall in R.R Masonary at RD.1/560 to 1/575)

Job No. \_\_\_\_\_  
Estimated Cost:- 949827/- 342782/-  
Earnest Money:- 19000/- 28561/-  
Time:- One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	8.10	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty three only	Cum	2631
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	28.35	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	11538
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	7.80	5109.04	Rupees:-Five Thousand One Hundred Nine and Paisa Zero Four only	Cum	39851
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.90	5710.66	Rupees:-Five Thousand Seven Hundred Ten and Paisa Six Six only	Cum	22272
5	Randon Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	49.35	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	266490
Total:-						342782

Quoted rate in figure	%
Quoted rate in words	%
Signature of contractor with address:-	

Executive Engineer  
B&R Division  
HP.PWD Rohru

**SCHEDULE OF QUANTITY**

Estimate Cost Rs 252000/-  
Earnest Money 5040/-  
Time 30 days

(43)

**Name of work:- R/R damages to various road under Rohru section sub Divn Rohru (SH- Hiring of JCB for removal of slips at various RD maintenance of road and dressing of surface )**

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B (Excavator cum Loader) front end loader 1 cum bucket & 45 cum hours including P.O.L charge shifting charges and other ancillary equipment as required at site of work for cutting in earth work in all height in all kinds soil such as kankar medium shingle boulders decomposed or soft variety of soil variety of soil such as spade work, pick work, jumper work, soft rock, hard rock etc where blasting prohibited including saturated soil including chiseling wedging out rock etc where blasting disposal of this undrivable material in all leads and lifts including mechanical transportation if necessary. The disposal of this unserviceable materials has to be done in the acquired width of the road to avoid damage to the properties of people or in case any damage took place the contractor is liable for it all salvaged materials such as quarried stone shall belong to the department and maximum useful quantity of stone from cutting work shall have to be neatly stacked along the road side on road berms. The work involving widening from existing with to IRC single lane standard width formation with 5 metre in straight and 7 metre in curves as per their radius Minimum 30 cum of earth work shall be done by the machine in one hour other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instruction of the Engineer in charge	30.00	8400.00	Rs eight thousand four hundred only	per days	252000
<b>Total</b>						252000.00

UNIT No 514 4th road	%
Quoted Rate in figure (+/-)	%
Quoted Rate in Words (+/-)	%

Signature of Contractor with full Address

Executive Engineer  
B&R Divn HP, PWD  
Rohru.

(44)

## SCHEDULE OF QUANTITY

Estimate Cost Rs 132225.00  
 Earnest Money 5300/-  
 Time 30 days

Name of work:- R/R damages to various road under Rohru section sub Divn Rohru (SH- Hiring of JCB for removal of slips at various RD maintenance of road and dressing of surface)

Sr.No.	Sub-Head and item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J C B (Excavator cum Loader) front end loader 1cum bucket & 45cum/hours including POL change shifting charges and other ancillary equipment as required at site of work for cutting in earth work in all kinds of soil such as kankar morum shingle boulders decomposed or soft variety of soil variety of soil such as spade work pick work jumper work soft rock hard rock etc where blasting prohibited including saturated soil including chiseling wedging out rock etc where blasting prohibited including saturated soil including consolidating with sheep foot rollers and disposal of this unserviceable material in all leads and lifts including mechanical transportation if necessary. The disposal of this unserviceable materials has to be done in the acquired width of the road to avoid damage to the properties of people or in case any damage took place the contractor is liable for it all salvaged materials such as quarried stone shall belong to the department and maximum useful quantity of stone from cutting work shall have to be neatly stacked along the road side on road berms. The work involving widening from existing with to IRC single lane standard with formation with 5 metre in straight and 7 metre in curves as per their radius Minimum 30cum of earth work shall be done by the machine in one hour other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instruction of the Engineer in charge	15.00	8815.00	Rs Eight thousand eight hundred fifteen	per days	132225
Total						132225.00

*Dated No 111 approved for the work*

Quoted Rate in figure (+/-)	%
Quoted Rate in Words (+/-)	%

Signature of Contractor with full Address

Executive Engineer  
 B&R Divn HP PWD  
 Rohru.



45

Name of Work:- R/R Damage On Hingwala mini gadam road km 0/00 to 3/00(SH:- C/o B/wall in wire crate at RD 1/770 to 1/822.50)

Schedule of Qty

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	464401
1	2	3	4	TIME LIMIT:	Two Month
				Rate In Fig.	Amount.
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	76.75	cum	324.83	Rupees Three Hundred & Twenty Four - Paise Eighty Three Only
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	33.08	cum	402	Rupees Four Hundred & Two Only
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	164.06	cum	2593.7	Rupees Two Thousand Five Hundred & Ninety Three - Paise Seventy Only
Total					464401

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

(46)

**Schedule of QTY**

**Name of Work:- R/R Damage On Hingwala Mini Gadam road km 0/00 to 3/00(SIL:- C/o R/wall in wire crate at RD 1/770 to 1/802..50)**

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				TIME LIMIT:	EARNEST MONEY	Amount.
				Rate In Fig.	In Words	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1003.1	32.5	cum	324.83	Rupees Three Hundred & Twenty Four - Paise Eighty Three Only	10556
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	20.48	cum	402	Rupees Four Hundred & Two Only	8233
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4526 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	152.34	cum	2593.7	Rupees Two Thousand Five Hundred & Ninety Three - Paise Seventy Only	395124
4	Back filling behind abutment wing wall and return complete as per drawing and technical specification clause 1204.3.8	16.58	cum	133151	Rupees One Thousand Three Hundred & Thirty One - Paise Fifty One Only	22076
<b>Total</b>						<b>435989</b>

**Condition:-**

1. The rates should be quoted for all heights including all lead and lifts.

2. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/ )

Quoted rate Words ( +/ )

Signature of the Contractor with full address:-

**Executive Engineer**  
**B&R Division HPPWD**  
**Rohru**

47

Name of Work:- R/R Damage On Hingwala Mini Gadani road km 0/00 to 3/00(Sil:- C/o R/wall in wire crate at RD 1/820 to 1/840 and B/wall in wire crate at RD 1/922 to 1/942)

Schedule of Qty

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST		Amount.
				EARNEST MONEY	TIME LIMIT:	
1	2	3	4	Rate In Fig.	In Words	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	41.2	cum	324.83	Rupees Three Hundred & Twenty Four - Paise Eighty Three Only	13383
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	25.2	cum	402	Rupees Four Hundred & Two Only	10130
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4526 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	101.56	cum	2593.7	Rupees Two Thousand Five Hundred & Ninety Three - Paise Seventy Only	263416
4	Back filling behind abutment wing wall and return complete as per drawing and technical specification clause 1204.3.8	6.6	cum	1331.51	Rupees One Thousand Three Hundred & Thirty One - Paise Fifty One Only	8788
Total						295717

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 cost. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPWD  
Rohru

48

Name of Work :- R/R Damage to Bhatwari Gavwas road km 0/00 to 7/00( C/o B/wall in wire crate at RD 1/645 to 1/690)

Schedule of Qty

Name of Work :- K/R Damage to Bhatwari Gawas road km 0/00 to 7/00( C/o B/wall In wire crate at RD 1/645 to 1/690)						
Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST		406547
				EARNEST MONEY		8131
				TIME LIMIT:		Two Month
				Rate		
				In Fig.	In Words	Amount.
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	93.15	cum	324.83	Rupees Three Hundred & Twenty Four - Paise Eighty Three Only	30257
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	28.35	cum	407	Rupees Four Hundred & Seven Only	11538
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	140.63	cum	2593.7	Rupees Two Thousand Five Hundred & Ninety Three - Paise Seventy Only	364752
Total						406547

Condition:-

1 The rates should be quoted for all heights including all lead and lifts.

2 cost. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru



49

Schedule of Qty

Name of Work: A/ R M/O Dhumadhar Jhatwari mastot bangal road km 0/00 to 6/500(SH:- Repair and maintenance of road C/o unlined surface drain and C/o sub grade and earthen shoulders and clearing Grass & cutting of branches of trees and P/L local materials to improve the road surface km 0/00 to 3/500)				ESTIMATED COST		485624
Sr. No				EARNEST MONEY		9712
Description of items.				TIME LIMIT:		Two Month
				Rate	In Words	Amount.
				In Fig.		
1	2	Qty	Unit	5	6	7
1	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site.	2000	mnt	49.65	Ruppes Fourty Nine - Paise Sixty Five Only	99300
2	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	1500	sqm	47.2	Ruppes Fourty Seven - Paise Twenty Only	70800
3	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification cutting of trees and shrubs from the road way or with in R.O.W including disposal of wood and leaves to suitable location as per technical specification clause 1914.	0.45	hect	61161.75	Ruppes Sixty One Thousand One Hundred & Sixty One - Paise Seventy Five Only	27523
4		60	each	121.36	Ruppes One Hundred & Twenty One - Paise Thirty Six Only	7282
5	Granular sub-base surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408	298.485	cum	950	Ruppes Nine Hundred & Fifty Only	283561
Total						488465

- 1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.
- 2 cost.
- Quoted rate Figure (+/-)
- Quoted rate Words (+/-)
- Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohini

50

Name of Work :- R/R Damage to various roads under Samoli Section Sub Division Rohru (Sli:- Hiring of JCB removal of slips and land slide maintenance of road)

Schedule of Qty

Schedule of Qty									
Name of Work :- R/R Damage to various roads under Samoli Section Sub Division Rohru (SH:- Hiring of JCB removal of slips and land slide maintenance of road)									
Sr.No	Description of Items.	Qty	Unit	ESTIMATED COST		EARNEST MONEY		Amount.	
1	2	3	4	TIME LIMIT:		Two Month		7	
				Rate	In Words				
1	Hiring of J.C.B(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this on-servicable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450	Per Hours	1100	Rupess One Thousand One Hundred Only	495000			
Total								495000	

DNIT No.:1020..... approved for amounting to Rs.-487500/- for the year 2023-24

- The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.
- Quoted rate Figure (+/-)
- Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPWD  
Rohru

(51)

Name of Work :- R/R Damages to Baggi Khahal road in Chitgaon Sub Division( Chitgaon Section) (Sl:- Hlring of ICB for removal of slips/drain and dressing of surface drain clearance)

## Schedule of Qty

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	Two Month
1	2	3	4	Rate	Amount.
				In Fig. 5	In Words 6
1	Hlring of J.C.B(Excavator-Cum-Loader) with having 0.45cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of snow & slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450	Per Hours	1100	Rapes One Thousand One Hundred Only
Total					495000

1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

52

Schedule of Qty			
		Estimate Cost	150000.00
		Earnest Money	3000.00
		Time	Three Month

Name of Work:- R/R Damages to various road under Chitgaon Sub Division ( Str:- Hiring of Tractor for carriage of muck/stone )

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	
1	Hiring of Tractor for carriage of muck having capacity of 90 cu feet including P.O.L change shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-in-Charge including all leads and lifts.	30.00	5000.00	(Rs Five thousand only)	Per Day	150000.00
	Total					150000.00

Condition  
1 The rates Should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)
Quoted rate Words (+/-)

Signature of the Contractor with full address:-

  
Executive Engineer  
B&R Division HPPWD  
Rohru



53

**Schedule of Qty**

Name of Work:- R/R Damage to Shalwat wali karetey (SH:- C/o R/wall at RD 1/120 to 1/132)				ESTIMATED COST	
				EARNEST MONEY	482596
				TIME LIMIT:	Two Month
Sr. No	Description of items.	Qty	Unit	Rate	Amount.
				In Fig.	In Words
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a load upto 20 m as per drawing and Technical Specification Clause 1603.1	9.6	cum	324.83	Rupees Three Hundred & Twenty Four - Paise Eighty Three Only
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	13.92	cum	407	Rupees Four Hundred & Seven Only
3	Plain/rein forced cement concrete(1:6:12)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	8.64	cum	6314	Rupees Six Thousand Three Hundred & Fourteen Only
4	Plain/rein forced cement concrete(1:4:8)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	3.6	cum	6655.9	Rupees Six Thousand Six Hundred & Fifty Five - Paise Ninety Only
5	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702,704,1202 and1204 Random rubble masonry in cement mortar(1:6)	37.38	cum	5400	Rupees Five Thousand Four Hundred Only
6	Construction of dry masonry in Retaining walls etc . As per HPPWD specification	37.8	cum	4082	Rupees Four Thousand & Eighty Two Only
7	Backfilling behind abutment,wing wall and return wall complete as per drawings& technical specification Clause 1204.3.8	29.4	cum	1331.51	Rupees One Thousand Three Hundred & Thirty One - Paise Fifty One Only
Total					482596

Condition:-  
 1 The rates Should be quoted for all heights including all lead and lifts.  
 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.  
 2 cost.  
 Quoted rate Figure (+/-)  
 Quoted rate Words (+/-)  
 Signature of the Contractor with full address:-


Executive Engineer  
 B&R Division HPPWD  
 Rohru

54

Name of Work: Link road tandali to Dogra Khad km 0/00 to 0/500(SH: F/C 5/7 mtr wide road at RD 0/150 to 0/330) Schedule of Qty

Sr. No	Description of items.	EARNEST MONEY				
		TIME LIMIT:		Two Month		
		Rate	In Words	Amount		
1	2	3	4	5	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling, fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work, hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 260.20cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1914.45	cum	260.693	Rupess Two Hundred & Sixty Paise Sixty Nine Only	499083
Total						499083

Condition:-  
 1 The rates Should be quoted for all heights including all lead and lifts.  
 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.  
 2  
 Quoted rate Figure (+/-)  
 Quoted rate Words (+/-)  
 Signature of the Contractor with full address:-

  
 Executive Engineer  
 B&R Division HPPWD  
 Rohru

55

**Schedule of Qty**

Name of Work : R/R Damage to Bhatwari Gawas road km 0/00 to 7/00 C/n B/wall in wire crate at RD 0/210 to 0/255)				ESTIMATED COST		409180
				EARNEST MONEY		8184
				TIME LIMIT:		Two Month
Sr. No	Description of Items	Qty	Unit	Rate	In Words	Amount
				In Fig.		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	101.25	cum	324.83	Rupees Three Hundred & Twenty Four - Paise Eighty Three Only	32889
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	28.35	cum	407	Rupees Four Hundred & Seven Only	11538
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	140.63	cum	2593.7	Rupees Two Thousand Five Hundred & Ninety Three - Paise Seventy Only	364752
<b>Total</b>						<b>409180</b>

**Condition:-**

1 The rates should be quoted for all heights including all lead and lifts.

2 cost. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPWD  
Rohru

207

(56)

## DNIT/ SCHEDULE OF QUANTITY

Job No. \_\_\_\_\_  
 Estimated Cost:-491573/-  
 Earnest Money:-9800/-  
 Time:-One Month

NAME OF WORK :- C/O link road to IIB Shalawat km. 0/0 to 3/0 (SH:-C/O B/W all at RD. 0/261.50 to 0/274.75 and C/O B/W all at RD. 0/48.75 to 0/55.62)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 within all leads and lifts as per directions of Engineer in charge	16.81	324.80	Rupees:-Three Hundred Twenty Four and Paisa Eighty only	Cum	5460
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other detestious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	35.11	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	14290
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	6.77	6314.14	Rupees:-Six Thousand Three Hundred Fortem and Paisa Fortem only	Cum	42747
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	8.12	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paisa Zero Only.	Cum	54047
5	Randon Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as as per drawings and technical specification Clauses 702, 704,1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	69.45	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	375030
Total:-						491573

DNIT No. \_\_\_\_\_

Approved for Rs.491573/- only for the Year 2023-2024

Quoted rate in figure  
 Quoted rate in words  
 Signature of contractor with address:-

%

%

Executive Engineer  
 B&R Division  
 HP.PWD Rohru



Job No.

(57)

## DNIT/ SCHEDULE OF QUANTITY

Estimated Cost:-391986/-

Earnest Money:-7900/-

Time:-One Month

NAME OF WORK:- R/R damages on Anna Thamarai road km. 0/0 to 1/250 (SII:-C/O B/wall at RD.0092 to 0097)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	11.40	324.80	Ruppes:-Three Hundred Twenty Four and Paisa Eighty only	Cum	3703
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	13.20	407.00	Ruppes:-Four Hundred Seven and Paisa Zero only	Cum	5372
3	Plain/reinforced cement concrete (1:3:6) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	52.50	6965.00	Ruppes:- Six Thousand Nine Hundred Sixty Five Paisa Zero only.	Cum	365663
4	Back filling behind abutments, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 with in all leads and lifts as per directed by the Engineer-in-Charge	6.30	1422.70	Ruppes:-One Thousand Four Hundred Twenty Two Paisa Seven Zero only.	Cum	8963
5	Providing weep hole in brick masonry/stone masonry, plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses 614, 709, 1204.3.7 as directed by the Engineer-in-Charge	20.00	414.27	Ruppes:-Four Hundred Forteen Paisa Two Seven only.	No.	8285
Total:-						391986
DNIT No. Approved for Rs.391986/- only for the Year 2023-2024						
%						
Quoted rate in figure						
Quoted rate in words						
Signature of contractor with address:-						

Executive Engineer  
B&R Division  
HP.PWD Rohru

**Schedule of Qty**

**Name of Work:- C/o Anu matan to Karalash kanchi road km 0/00 to 2/50(SII):- Widening of road at RD 0/00 to 0/105)**

Name of Work:- C/o Anu matan to Karalash kanchi road km 0/00 to 2/500(Sil:- Widening of road at RD 0/00 to 0/105)							Schedule of Qty	
Sr. No	Description of Items.	2	Qty	Unit	ESTIMATED COST		Amount.	
					EARNEST MONEY	TIME LIMIT:		
1			3	4	Rate	In Words	Two Month	
					In Fig.	6		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited ) and other intermediate classification of soil setting out true to the required line, graded with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1,1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber ,embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machines, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 187.72cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.		2058.8	cum	241.008	Ruppes Two Hundred & Fourty One - Paise One Only	496188	
Total							496188	

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 cost. The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and

Quoted rate Figure ( + / - )

Quoted rate Words ( + / - )

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

(59)

JOB NO:-

## Schedule of Qty

Schedule of Qty						
Name of Work:- C/o Banoti kandara road km 0/00 to 5/00(SH:- F/C 5/7 mtr wide road at RD1/975 to 2/060)				ESTIMATED COST		406703
				EARNEST MONEY		8134
				TIME LIMIT:		Two Month
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount
				In Fig.		
1	2	3	4	5	6	7
1	Excavation in billy area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. Technical Specification Clause 300.1603.1.1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkaora, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 262.57cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1250.33	cum	325.277	Rupess Three Hundred & Twenty Five - Paise Twenty Eight Only	406703
Total						406703

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 cost  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (\*/-)

Quoted rate Words (\*/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

59 60

# SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Jakhhar to Thakuli Bantu road km.0/0 to 3/0 (SH:-C/O B/wall at RD.1/320 to 1/343.10)

Job No.  
Estimated Cost:-485288/-  
Earnest Money:-9700/-  
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	12.47	186.32	Rs. One hundred Eighty six Paise only	Cum	2323
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	43.66	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	17770
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	10.63	5109.04	Rupees:-Five Thousand One Hundred Nine and Paise Zero Four only	Cum	54309
4	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	76.09	5400.00	Rupees:-Five Thousand Four Hundred Paise Zero Only.	Cum	410886
Total:-						485288
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer  
B&R Division  
HP.PWD Rohru



(61)

# SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Udo Nivas Jakhar road km.0/0 to 4/0 (SII:-C/O B/wall at RD.0/270 to 0/293)

Job No.

Estimated Cost:-485288/-

Earnest Money:-9700/-

Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	12.47	186.32	Rupees:-One Hundred Eighty Six and Paise Three Two only	Cum	2323
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	43.66	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	17770
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	10.63	5109.04	Rupees:-Five Thousand One Hundred Nine and Paise Zero Four only	Cum	54309
4	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	76.09	5400.00	Rupees:-Five Thousand Four Hundred Paise Zero Only.	Cum	410886
Total:-						485288
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer  
B&R Division  
HP.PWD Rohru

(62)

Schedule of Qty									
Name of Work :- A/R & M/O SDM Residence Rohru (SH:- P/F Floor tiles repair of toilets WS & SI)									
				ESTIMATED COST		386281			
				EARNEST MONEY		7726			
				TIME LIMIT:		Two Month			
						Amount.			
Sr. No	Description of items.	Qty	Unit	Rate	In Words	7			
1	Demolishing cement concrete manually by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	6.94	cum	1274870354	Rupees One Thousand Two Hundred & Seventy Four - Paise Eighty Seven Only	8848			
2	Providing and laying in position cement concrete of specified grade excluding the cost of 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)	4.96	cum	7294.569078	Rupees Seven Thousand Two Hundred & Ninety Four - Paise Fifty Seven Only	36181			
3	15mm cement plaster in single coat on fair side of brick concrete stone walls for interior / exterior plastering upto all floor level including arnses, internal rounded angles, chafers and/or rounded angles not exceeding 30cm in girth and finished even and smooth in cement mortar 1:6 (1 cement : 6 sand) up to all heights in all floor levels complete with scaffolding works in all leads and lifts including carriage of material and as per the direction of the Engineer-in-Charge.	19.74	sqm	271.8	Rupees Two Hundred & Seventy One - Paise Eighty Only	5365			
4	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3:3 kg/sqm including pointing the joints with white cement and matching pigment etc complete	70.97	sqm	2280	Rupees Two Thousand Two Hundred & Eighty Only	161812			
5	Providing and fixing vitreous china dual purpose closet suitable for use as squatting pan or European type water closet (Anglo Indian W/C pan) with seat & lid fixed with C.P. brass hinges and rubber buffers, 10 litre low level flushing cistern with fitting and brackets, 40 mm flush bend, 20 mm over flow pipe, with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required.	2	each	20000	Rupees Twenty Thousand Only	40000			
6	Providing and fixing charomium plated brass soap dish with C.P. brass brackets fixed to wooden cleats with C.P. brass screws including carriage of materials within all leads and lifts.	2	each	650	Rupees Six Hundred & Fifty Only	1300			
7	Providing and fixing Shower with C.P. brass screws including all leads and lifts.	2	each	3500	Rupees Three Thousand Five Hundred Only	7000			
8	Providing and fixing white vitreous china pedestal for wash basin with mixer completely recessed at the back for the reception of pipes and fittings.	2	each	14000	Rupees Fourteen Thousand Only	28000			
9	Providing and fixing mixer tap( dievoter) including all leads and lift.	1	each	8000	Rupees Eight Thousand Only	8000			
10	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	3	each	3580	Rupees Three Thousand Five Hundred & Eighty Only	10740			

11	Providing and fixing 600mmx120mm glass shelf with C.P. brass bracket and guard rail complete.	3	each	1005	Rupees One Thousand & Five Only	3015
12	Providing and fixing bright finished brass tower bolts (Bertel type) with screws etc complete 200x10	2	each	450	Rupees Four Hundred & Fifty Only	900
13	Providing and fixing Hand towel rod with screws etc complete.	2	each	850	Rupees Eight Hundred & Fifty Only	1700
14	Providing and fixing mixer wash basin tap with screws etc complete.	2	each	250	Rupees Two Hundred & Fifty Only	500
15	Providing and fixing Angle cock with screws etc complete.	9	each	1150	Rupees One Thousand One Hundred & Fifty Only	10350
16	Providing & fixing 32 mm dia. PVC waste pipe for wash basin or sink including check nut including carriage of material within all leads and lifts.-	2	each	120	Rupees One Hundred & Twenty Only	240
17	Providing and fixing tap with screws etc complete.	3	unit	1200	Rupees One Thousand Two Hundred Only	3600
18	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge	2	unit	316	Rupees Three Hundred & Sixteen Only	632
19	Providing and fixing Paper roll stand with screws etc complete.	2	each	950	Rupees Nine Hundred & Fifty Only	1900
20	Providing and fixing Corner with screws etc complete.	4	each	1700	Rupees One Thousand Seven Hundred Only	6800
21	Providing & fixing 110mm dia C.P. grating for floor or nahani / gully / floor trap including carriage of material within all leads and lifts.	6	each	124	Rupees One Hundred & Twenty Four Only	744
22	Providing and fixing Consolder with screws etc complete.	2	each	1830	Rupees One Thousand Eight Hundred & Thirty Only	3660
23	Providing and fixing Section pipe with screws etc complete.	2	each	220	Rupees Two Hundred & Twenty Only	440
24	Providing and fixing PVC connection pipe with screws etc complete.	2	each	180	Rupees One Hundred & Eighty Only	360
25	Providing and fixing Polyethylene-Aluminium- Polyethylene PE-AL-PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes the costs of cutting chases and including	90	unit	413	Rupees Four Hundred & Thirteen Only	37170
26	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive complete including carriage of materials within all leads and lifts :- 110mm dia	4	each	180	Rupees One Hundred & Eighty Only	720

27	Providing and fixing PVC door bend with oval access door, ISI marked insertion rubber washer 3 mm thick bolts and nuts complete including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts:-110mm dia	4	each	220	Rupees Two Hundred & Twenty Only	880
28	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts :-110mm dia	12	each	452	Rupees Four Hundred & Fifty Two Only	5424
Total						386281

1 The rates should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost. ( % )

Quoted rate Figure ( + / - ) ( % )

Quoted rate Words ( + / - )

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPWD  
Rohru



**Schedule of Qty**

**Name of Work :- A/R & M/O HPPWD Store at Rohru (SIH - P/F M.S sheet and prepainted sheet for roof at HPPWD store at Rohru)**

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		Amount.
				EARNEST MONEY	TIME LIMIT	
1	2	3	4	Rate	In Words	7
				In Fig.	6	
1	Providing and fixing M.S. B.P Sheet 2.00mm (two milimetre) thick in eaves band/ fascia/ soffits/ ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer (Base members of steel work shall be measured and paid for separately) with scaffolding work including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	100.78	sqm	2376.1	Rupess Two Thousand Three hundred & Seventy Six - Paise Ten Only	239463
2	Providing and fixing 0.60mm th. Prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 microns over 5 microns primer coating to back coat polyester of 5microns over 5 microns primer coating the fixing with prepainted iron J or L hooks bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete all accessories as required as per the direction of Engineer- IN- Charge	108.04	sqm	1680	Rupess One Thousand Six hundred & Eighty Only	181507
3	Providing and fixing ridges or hips 60 cm overall with 0.60mm thick. Prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 microns over 5 microns primer coating - back coat polyester of 5microns over 5 microns primer coating the fixing with prepainted iron J or L hooks bolts and nuts 6mm dia metre with prepainted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer- IN- Charge.	14.8	sqm	1213.4	Rupess One Thousand Two hundred & Thirteen - Paise Fourty Only	17958
4	Providing fixing 20cm wide 90cm overall U-shape gutter with 45mm (milimetre) thick prepainted steel sheet of TATA DURASHINE and approved brand in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester organic coating of back coat of polyester 5microns over 5microns primer coating gutter with iron brackets 40mm X 3mm size bolt and nuts and washers etc. including making necessary connections with rain water pipe complete as per design including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	14.8	sqm	1404	Rupess One Thousand Four hundred & Four Only	20779
<b>Total</b>						<b>459708</b>

1 The rates should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)	(%)
Quoted rate Words (+/-)	(%)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

(64)

Name of Work :- A/R & M/O Hp, PWD Rest House at Rohru (Sh:- P/L Tiles work, wood and steel work etc.

**Schedule of Qty**

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	499634
				TIME LIMIT:	9993 Two Month
1	2	3	4	Rate	Amount.
				In Fig.	
1	Providing and fixing HDF decorative laminate core board flooring AC4 class 32.8mm thick of Kerio original or equivalent placed over cushion of 2mm thick expanded polystyrene foam plus 160 Microne thick polystyrene sheet under lay No. 045 Beech West including border of required shade and colour complete in all respect upto all for levels as per direction OF Engineer in charge including carriage of materials in allends and lifts	176.2	Sqm	2354	414775
2	Providing woodwork in frames of doors, windows, clerestory, windows and other frames wrought framed and fixed in position 2nd class deodar wood including all leads and lifts as per HPPWD specification of 1990 volume-I as directed by the Engineer-in-Charge	0.69	Sqm	10178.06	7023
3	Steel work welded in built up Sections and framed work, including cutting, hoisting, fixing in position and applying a coat of red lead paint in grating, framed guard bars ladder, railing, brackets and similar work including all lead and lifts as per HPPWD Specification of 1990 Volume-I as directed by the Engineer-In-Charge.	763.104	Kg	102	77837
Total					499634

**Condition:-**

- The rates should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and
- cost.
- Quoted rate Figure (+/-)
- Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

Name of Work :- A/R & M/O HP, PWD Rest House at Rohru (Sh. Wood work etc.)

Schedule of Qty

Sr. No	Description of Items	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	TIME LIMIT:	Amount.
				In Fig.	In Words	
1	Providing and fixing in wall lining medium density fibre board 15:14587:1998 marked, Pre-laminated one side decorative lamination and other side balancing lamination, with necessary fixing arrangement and screws etc. complete, 18 mm thick.	140.12	Sqm	2328.85	Rupers Two Thousand Three Hundred & Twenty Eight - Paise Eighty Five Only	326318
2	Providing wood work in frames of doors, windows, egressory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Second class teak wood	0.94	cum	124768.61	Rupers One Lakh Twenty Four Thousand Seven Hundred & Sixty Eight - Paise Sixty One Only	117282
3	Providing and fixing hinges with screws etc. as per the direction of Engineer-In-Charge including carriage of materials within all leads and lifts.	85	Each	82.8	Rupers Eighty Two - Paise Eighty Only	7038
4	Providing and fixing magnetic / ball catcher with screws etc. as per the directions of Engineer-In-Charge including carriage of materials within all leads and lifts.	20	Each	45.2	Rupers Forty Five - Paise Twenty Only	904
5	Providing and fixing lock with screws as per the actions of Engineer-In-Charge including carriage of materials within all leads and lifts.	20	Each	185	Rupers One Hundred & Eighty Five Only	3700
6	Providing and fixing aluminium handles anodized transparent or dyed to required colour or shade with necessary screws etc. complete including carriage of material within all leads and lifts as per direction of Engineer-In-Charge:-	55	Each	82.8	Rupers Eighty Two - Paise Eighty Only	4554
7	Providing and fixing aluminium tower bolts (Berril type) anodized transparent or dyed to required shade and colour with screws etc. complete including carriage of material within all leads and lifts as per direction of Engineer-In-Charge:-	10	Each	113.4	Rupers One Hundred & Thirteen - Paise Forty Only	1134
8	Providing and fixing Channel with screw as per the actions of Engineer-In-Charge including carriage of materials within all leads and lifts.	16	Each	540	Rupers Five Hundred & Forty Only	8640
9	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :	82.56	Sqm	93	Rupers Ninety Three Only	7678
10	Two or more coats on new works including a coat of wood filler/French spirit polishing	70.12	Sqm	234	Rupers Two Hundred & Thirty Four Only	16408
Total						493657

Condition:-

1 The rates should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

65

(26)

Name of Work :- A/R & M/O HP, PWD Rest House at Rohru (Sh:- P/L Wood Work, wall lining etc).

**Schedule of Qty**

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		
				TIME LIMIT:		Two Month
				Rate	In Words	Amount.
				In Fig.		
1	2 Providing and fixing 1.00 mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete.	3 280.24	4 Sqm	5 876.6	6 Rupees Eight Hundred & Seventy Six - Paise Sixty Only	7 245658
2	Providing and fixing plain lining with tongued and grooved jointing and screws ( frame work and cover fillets to be measured and paid for separately with.	69.176	Sqm	3582.71	Rupees Three Thousand Five Hundred & Eighty Two - Paise Seventy One Only	247838
Total						493496

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPWD  
Rohru

Name of Work:- C/o Ambulance road from barot to GSS Sarbasa(Bevdhar)(SH:- C/o R/wall at RD 0/185 to 0/200 and 0/257 to 0/277 and P/L Kharanla stone soling at RD 0/065 to 0/277)

Schedule of Qty

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST		Amount.
				EARNEST MONEY	9831	
1	2	3	4	TIME LIMIT:		7
				Rate	In Words	
5				In Fig.		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	17.5	cum	407	Ruppes Four Hundred & Seven Only	7123
2	Plain/rein forced cement concrete 1:6:12 in open foundation complete as per drawing and technical specification Clauses 802.803,1202&1203	5.25	cum	5109.04	Ruppes Five Thousand One Hundred & Nine - Paise Four Only	26822
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clause 702.704,1202 and 1204 Random rubble masonry in cement mortar(1:6)	73.2	cum	5523.33	Ruppes Five Thousand Five Hundred & Twenty Three - Paise Thirty Three Only	404308
4	Preparation of sub grade by dressing to combor(Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HPPWD specification	235	sqm	1.74	Ruppes One - Paise Seventy Four Only	409
5	Consolidation of sub grade with roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade completed as per HPPWD Specification.	235	sqm	1.06	Ruppes One - Paise Six Only	249
6	Stone soling properly hand-packed filling intersices with spalls and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HPPWD specification 230mm spread	35.25	cum	1493	Ruppes One Thousand Four Hundred & Ninety Three Only	52628
Total						491539

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 cost. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru



68

Name of Work:- R/R Damage of Ialpani Dhumara road km 0/00 to 4/330( SI:- ROFD at RD 0/390 to 0/420,0/510 to 0/525,2/105 to 2/135 & 2/165 to 2/185)

Schedule of Qty

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	497320	9946
1	2	3	4	TIME LIMIT:		
				Rate In Fig.	In Words	Amount.
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1.1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its leveling fine dressing, and carriage of machines, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 303.20cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1120.125	cum	443.986	Rupees Four Hundred & Fourty Three - Paise Ninety Nine Only	497320
Total						497320

Condition:-

1 The rates should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and 2 cost.

Quoted rate Figure (\*/-)

Quoted rate Words (\*/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

69

Schedule of Qty

Name of Work :- R/R damages to various road under Samoli Section Sub Division Rohru( Sh:- Lifting of Tipper for carriage of excavated earth muck etc )

Sr.No	Description of items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	297000
				TIME LIMIT:	594000
				Rate	60 Days
				In Fig.	
				In Words	
					Amount.
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L. charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	45	Per Day	6600	297000
				Rupees Six Thousand Six Hundred Only	
Total					297000

DIT No ...2132 approved for amounting to Rs:-297000 for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)	
Quoted rate Words (+/-)	

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPWD  
Rohru

(70)

## Schedule of Qty

Name of Work :- R/M on various road under Rohru Sub Division (Samoli Section) (SIH:- Hiring of JCB for C/o Unlined surface drain and earthen shoulders and maintenance of road etc)

Schedule of Qty						
Name of Work :- R/M on various road under Rohini Sub Division (Samoli Section)( SII:- Hiring of JCB for C/o Unlined surface drain and earthen shoulders and maintenance of road etc)				ESTIMATED COST		
Sr.No	Description of items.	Qty	Unit	EARNEST MONEY		995000
				TIME LIMIT:	9900	
				Rate	In Words	Two Month
1	2	3	4	In Fig.	6	Amount.
1	Hiring of J.C.B(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-servicable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burns. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450	Per Hours	1100	Ruppes One Thousand One Hundred Only	495000
Total						495000

DNIT No. 2208..... approved for amounting to Rs:-495000/- for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.

2 cost.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

71

**Schedule of Qty**

**Name of Work :- R/M on various road under Rohru Sub Division (Samoli Section) (SII:- Hiring of ICB for C/o Unlined surface drain and earthen shoulders and maintenance of road etc)**

Sr.No	Description of items	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		495000
				TIME LIMIT:		9900
				Rate	In Words	Amount.
				In Fig.		
1	Hiring of JCB (Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, mororum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450	Per Hours	1100	Rupees One Thousand One Hundred Only	495000
Total						495000

DNIT No..2208..... approved for amounting to Rs:-495000/- for the year 2023-24

- 1 The rates should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.
- 2 cost.
- Quoted rate Figure (+/-)
- Quoted rate Words (+/-)
- Signature of the Contractor with full address:-

  
**Executive Engineer**  
**B&R Division HPPWD**  
**Rohru**



72

Schedule of Qty

Name of Work :- R/R damages to various road under Samoli Section Sub Division Rohru( Sri:- Hiring of Tipper for carriage of excavated earth muck etc )

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	594000	60 Days
1	2	3	4	Rate	In Words	Amount.
				In Fig.	6	7
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in-Charge including all leads and lifts.	45	Per Day	6600	Rupees Six Thousand Six Hundred Only	297000
Total						297000

DNIIT No ... 2210.. approved for amounting to Rs.-297000 for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure ( +/- )

Quoted rate Words ( +/- )

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

Issd to Sr. \_\_\_\_\_

Executive Engineer  
B&R Divn HP, PWD

Estimated cost Rs 2,22,938/-  
EARNEST MONEY Rs6458/-  
TIME : Two month

Name of work :- C/O RCD road km 0/0 21/165 (SH- C/O R/wall in wire crate at rd 18/900 to 48/935)- 18/915

Sr No	Description of items	Quantity	Rate in Figure.	Rate in Words	unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts as per directions of Engineer in charge	11.70	184.59	Rs one hundred eighty four & paise fifty nine only	per cubic metre	2160
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification Clause 305.1 within all leads and lifts as per directions of Engineer in charge	7.80	407.00	Rs four hundred seven only	per cubic metre	3175
3	Providing and laying of boulder apron laid in wire crastes with 4mm dia G.I wire conforming to IS 280 and IS 4826 100mm into 100mm mesh (woven diagonally) including 10per cent extras for laps and join is laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 within all and lifts as per directions of Engineer in charge	70.31	2920.00	Two thousand eight hundred ninety only	per cubic metre	203196
4	Providing and laying of stone filling behind the retaining wall and return wall complete as per drawing and technical specification clause 1204.3.8 within all leads and lifts as per directions of Engineer in charge	10.50	1373.00	one thousand seven hundred seventy o	per cubic metre	14417
						222938.00

The contr. shall procure all the materials conforming to the specification of month at its on risk and cost

Quoted Rate in words (+)(-)  
Quoted rate in fig. (+)(-)  
Singof the contract with full Address

Opened by me on Dated.....  
Cutting.....  
Over writing.....  
E.E. A.E.

Executive Engineer  
B&R Divn HP, PWD  
Rohru

20  
73

Issued to En.

Executive Engineer  
B&R HPPWD Divn, Rohru

JOB NO:-

64-68-74

Job No-12

Name of Work:- R/R Damage on Tikharti to tangnu road km 0/00 to 15/00 (SH:- C/o R/wall in wire crate at RD0/290 to 0/300 & 10/570 to 10/585)

Schedule of Qty

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST		Amount
				EARNEST MONEY	TIME LIMIT:	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	3	cum	185	Rupees One Hundred & Eighty Five Only	6632
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	16.5	cum	407	Rupees Four Hundred & Seven Only	6716
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	156.25	cum	2890	Rupees Two Thousand Eight Hundred & Ninety Only	451563
Total						464910

Condition:-

- 1 The rates Should be quoted for all heights including all lead and lifts.
- 2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)	
Quoted rate Words (+/-)	

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

Opened by me on Dated.....  
Cutting.....  
Over Milling.....  
E.E. .... A.E.

Issued to Sr.

(16) (75)

**SCHEDULE OF QUANTITY**  
B & R Division HP.PWD  
Rohru  
Estimated Cost:-473672/-  
Earnest Money:-9500/-  
Time:-One Month

NAME OF WORK:-R/R damages to Dhara Kapandhi road km. 0/0 to 0/600 (SIH:-SIH:-C/O R/wall at RD.0/335 to 0/345)

Sr.No.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	33.20	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	10784
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	33.10	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	13472
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.80	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	23993
4	Plain reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	7.00	6656.00	Rupees:-Five Thousand Six Hundred Fifty Six Paisa Zero Only.	Cum	46592
5	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	38.76	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	209304
6	Construction of dry masonry in retaining walls, breast walls etc as per drawings and technical specification including carriage of material within all leads and lifts as per directions of Engineer in charge	36.15	4082.00	Rupees:-Four Thousand Eighty Two Paisa Zero Only.	Cum	147564
7	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	14.90	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	21963
		Total:-				473672
		DNIT No. Approved for Rs.473672/only for the Year 2023-2024				
		Quoted rate in figure %				
		Quoted rate in words %				
		Signature of contractor with address:-				

Opened by MTC on Date:-

Cutting

Over writing

F B A.E.

Executive Engineer  
B & R Division  
HP.PWD Rohru



Issued to Ch.

44

440

76

**SCHEDULE OF QUANTITY**

Executive Engineer  
B & R Division HRPWD  
Rohru

Job No. 44  
Estimated Cost:-354708/-  
Earnest Money:-7100/-  
Time:-One Month

NAME OF WORK:- C/O Narkanda Baggi Khadrula Surgri Rohru road km. 0/0 to 67/0 (SI:-C/O R/wall in wire crate at RD.40/565 to 40/587.50)

Sr.No.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rocks, chiseling/ wedging out of rocks ( where blasting is prohibited) as per drawings and MORD technical specification Clause 305.1 51 104 and 1606.1 a d as per direction of the Engineer-In -Charge including setting out construction of shorting and bracing, removal of stumps and otherdeleterious materials and disposal of materials upto all leads and lifts including dressing Q/sides and bottom and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm ( one hundred fifty millimetres) compacted thickness including shorting and strutting and pumping and bailing out water (surface and sub soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals,	30.94	407.00	Rupees:-Three Hundred Seven and Paise Eighty Three only	Cum	12593
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS- 4826 in 100 mm x 100 mm ( hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps end joints laid with stone boulders weighing not less than 2 5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within ail leads and lifts and other incidentals.	105.47	2890.00	Rupees:-Two Thousand Eight Hundred Ninety and Paise Zero only	Cum	304808
3	Providing and laying of back filling behind R/wall,B/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	25.31	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paise Zero only	Cum	37307
Total:-						354708
DNIT No. Approved for Rs.533224/- only for the Year 2023-2024						
Quoted rate in figure						
Quoted rate in words						
Signature of contractor with address:-						

Opened by me on Dated

Cutting

Over writing

E.E.

Executive Engineer  
B & R Division  
HRPWD Rohru

Name of Work :- R/R Damage to on Barara Sharog road km 0/00 to 8/00( Sh:- C/o R/wall in PCC  
6/801.90)

Schedule of Executive Engineer

106

Rohru

ESTIMATED COST  
EARNEST MONEY

465475  
9309  
Two Month

Sr. No	Description of Items.	Qty	Unit	TIME LIMIT:		Amount.
				Rate In Fig.	In Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material and as per HPPWD specification of 1990 volume-1 or as directed by the Engineer-In-Charge.	33.74	cum	407	Ruppes Four Hundred & Seven Only	13732
2	Providing concrete for plain reinforced concrete in open foundation/R/B-walls complete as per drawing and technical specification clause 802.803.1202 & 1203 grade (1:4:8 nominal mix), 1 cement : 4 sand : 8 graded stone aggregate, including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge	75.71	cum	5710	Ruppes Five Thousand Seven Hundred & Ten Only	432304
3	Back filling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8	7.14	cum	1331.3	Ruppes One Thousand Three Hundred & Thirty One - Paise Thirty Only	9505
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia. PVC pipe extending through the full width of the structures with slope of 1(V) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614.709.1204.3.7.	25	each	397.31	Ruppes Three Hundred & Ninety Seven - Paise Thirty One Only	9933
Total						465475

1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

2 cost.  
Quoted rate Figure (\*/-)  
Quoted rate Words (\*/-)  
Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

Opened by me on Dated .....  
Cutting .....  
Over writing .....

E.E. A.E.

(24)  
(44-77)

**SCHEDULE OF QUANTITY**

**Executive Engineer  
B & R Division  
Rohru**

Estimated cost Rs 477252-  
Earnest Money Rs 8500/-

Time :- Two Month

ne of work :- Providing Tarring work on Narkanda Baggi Khadrala sidpur Sungri Rohru road (SH Metelling and Tarring work in portion at Rd 63/0 to 63/080)

Sl. No.	Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Providing and laying spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 Kn static roller in stages to proper grade and camber applying and brooming stone screening binding materials to fill up- the interstices of coarse aggregate watering and compacting to the required density Grade 2 as per Technical specification clause 405, including cartage of materials leads and lifts as per directions of Engineer in charge	24.75	2622.82	Rs two thousand six hundred twenty two & paise eighty two only	per cubic metre	64915
2	Providing and laying spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 Kn static roller in stages to proper grade and camber applying and brooming stone screening binding materials to fill up- the interstices of coarse aggregate watering and compacting to the required density Grade 3 as per Technical specification clause 405 including cartage of materials leads and lifts as per directions of Engineer in charge	24.75	3454.71	Rs three thousand four hundred fifty four & paise seventy one only	per cubic metre	85504
3	Providing and applying printing coat with bitumen emulsion (SS1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.85 per square meter using mechanical means as per technical specification clause 502 including cartage of materials within all leads and lifts as per directions of Engineer in charge	330.00	51.63	Rs fifty one & paise sixty three only	per square metre	17038
4	Providing and applying tack coat with Bitumen emulsion (RS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.275 kilogramme per square metre using mechanical means as per technical specification clause 502 within all leads and lifts as per directions of Engineer in charge	330.00	23.25	Rs twenty three & paise twenty five only	per square metre	7673
5	Providing and laying bitumen macadam with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crust aggregate of specified grading premixed with bituminous binder @ 5.4 to 5.6 percent of mix and filler transporting the hot mix to work site laying with Hydrostatic paver finisher with consored control to the required grade level alignment rolling with smooth wheeled vibratory and tandem roller to achieve the desired compact as per MORTH specification clause mNo 501.6 and 501.7 complete in all respect within all leads and lifts as per directions of Engineer in charge	13.20	11908.08	Rs Eleven thousand nine hundred eight & paise eight only	per cubic metre	157187
6	Providing and laying bituminous concrete 30mmthick with 100-120TPH batch type Hot mix plant producing an average output of 75 tonnes per hours using crust aggregate of specified grading premixed with bituminous binder @ 5.4 to 5.6 percent of mix and filler transporting the hot mix to work site laying with JH/hydrostatic paver finisher with consored control to the required grade level and alignment rolling with smooth wheeled vibratory and tandem roller to achieve the desired compact as per MORTH spe cification clause 509 complete within all leads and lifts as per directions of Engineer in charge	9.90	14640.00	Rs fourteen thousand six thousand four only	per cubic metre	144936
						477253

Opened by                      Dated                      DNIT NO.                      Approved for Rs :477253.00 for the year 2023-24

Cutting  
Over writing

Red Rate in figure (+) (-) %  
Red Rate in Words (+) (-) %

Executive Engineer  
B&R Divn HP, PWD  
Rohru

Signature of Contractor with full Address

130  
52  
78



Issued to Sr.

79

SCHEDULE OF QUANTITY

Executive Engineer  
B & R Division H.P.W.D.  
Rohru

Job No. 22  
Estimated Cost:-416508/-  
Earnest Money:-8400/-  
Time:-One Month

NAME OF WORK:- R/R damages on Bhatwari Hingwala Gawas road km. 0/0 to 7/0 (SIL:-C/O 900mm Dia/Tlumme Pipe culvert in P.C.C 1:4:8 at RD.0/320 and wing wall)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	10.52	290.00	Rupees:-Two Hundred Ninety and Paise Zero only	Cum	3051
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	25.90	495.00	Rupees:-Four Hundred Ninety Five and Paise Zero only	Cum	12821
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	7.02	5490.00	Rupees:-Five Thousand Four Hundred Ninety and Paise Zero only	Cum	38540
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	46.74	6210.00	Rupees:-Six Thousand Two Hundred Ten Paise Six Six Only	Cum	290255
5	Providing and laying concrete 1:2:4 (1 Cement:2sand:4 graded stone aggregate 20mm nominal size) for compacting concrete and curing complete excluding cost of form work reinforcement for reinforced concrete work with in all leads and lifts as per directed by the Engineer-in-Charge	1.90	8450.00	Rupees:-Eight Thousand Four Hundred Fifty and Paise Zero only	Per Cum	16055
6	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	5.84	1400.00	Rupees:-One Thousand Four Hundred Paise zero only.	Cum	8176
7	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection works backing filling concrete and masonry works in head walls and parapets caluse 1106. as directed by the Engineer-in-Charge	7.50	5600.00	Rupees:-Five Thousand Six Hundred Paise Zero only.	Cum	42000
8	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1202 & 1204 (1:2:4) as directed by the Engineer-in-Charge	0.49	11450.00	Rupees:-Eleven Thousand Four Hundred Fifty Paise Zero only.	Cum	5611
	Total:-					416508
	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address:-					

Executive Engineer  
B & R Division  
H.P.W.D Rohru

Opened by me on Dated.....  
Cutting.....  
Over writing.....

EE  
AE

Issued to Sr.

Executive Engineer  
B & R Division H.P.W.D.

**SCHEDULE OF QUANTITY**

Job No. 24  
Estimated Cost:-388489/-  
Earnest Money:-7800/-

Time:-One Month

NAME OF WORK:- C/O link road Khorsu to Gujar Basti Bashruti road km.0/0 to 2/0 (SI:-C/O R/wall in PCC at RD.9/220 to 9/236)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	5.90	306.64	Rupess:-Three Hundred Six and Paiza Sixty Four only	Cum	1809
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	13.10	407.00	Rupess:-Four Hundred Seven and Paiza Zero only	Cum	5332
3	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	52.90	6656.00	Rupess:-Six Thousand Six Hundred Fifty Six Paiza Zero Only.	Cum	352102
4	Providing weep hole in brick masonry /stone masonry ,plain/ reinforced concrete abutment wing wall, return wall with 100mm dia A.C pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses614,709,1204,3.7 as directed by the Engineer-in-Change	24.00	414.00	Rupess:-Four Hundred Forteen Paiza Zero only.	No.	9936
5	Providing and laying of back filling behind wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Change	13.10	1474.00	Rupess:-One Thousand four Hundred Seventy four and Paiza Zero only	Cum	19309
			Total:-			388489
		DNIT No.		Approved for Rs.388489/- only for the Year 2023-2024		
		Quoted rate in figure		%		
		Quoted rate in words		%		
		Signature of contractor with address:-				

Executive Engineer  
B & R Division  
H.P.W.D. Rohru

Opened by me on Dated.....  
Cutting.....  
Over writing.....

EE



I ssued to RA.

122

(44) (81)

**SCHEDULE OF QUANTITIES & R Division HPPWD Rohru**

Job No. 422  
Estimated Cost:-446797/-  
Earnest Money:-9000/-  
Time:-One Month

NAME OF WORK:- R/R damages on Bhaloon Kanchi to Bhaloon road km. 0/0 to 4/0 (SH:-C/O B/wall in PCC 1:4:8 & wire crates at RD.2/535 to 2/560)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	30.75	324.83	Rupees:-Three Hundred Twenty Four and Paise Eighty Three only	Cum	9989
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material with in all leads and lifts as per directed by the Engineer-in-Charge	7.50	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	3053
3	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	30.00	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paise Zero Only.	Cum	199680
4	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm ( hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps end joints laid with stone boulders weighing not less than 25 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	78.13	2890.00	Rupees:-Two Thousand Eight Hundred Ninety and Paise Zero only	Cum	225796
5	Providing weep hole in brick masonry/ stone masonry, plain/ reinforced concrete abutment wing wall, return wall with 100mm dia A/C pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses 614, 709, 1204.3, 7 as directed by the Engineer-in-Charge	20.00	414.00	Rupees:-Four Hundred fourteen Paise Zero only.	No.	8280
Total:-						446797

DNIT No. Approved for Rs.446797/- only for the Year 2023-2024

Quoted rate in figure  
Quoted rate in words  
Signature of contractor with address:-

Opened by me on Dated  
Cutting  
Over writing

%  
%

Executive Engineer  
B&R Division  
HPPWD Rohru

EE AE

Issued to En.

OF SCHEDULE OF QUANTITY.

Executive Engineer  
B & R Division HPPWD  
Rohru

Estimated cost Rs 4,85,092/-  
Earnest money Rs 9700/-  
TIME : Two month

Name of work : - C/O Mastot to Bagi Kainchi road Km 0/0 to 1/235 (SH- FIC 5/7 metre wide road at Rd 0/0 to 0/345)

rNo	Description of items	Quantity	Rate in Figure.	Rate in Words	unit	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side. Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage, disposal of unsuitable cut material in specified manner, trimming/filling of unevenness blindage and finishing of the road to specified dimensions or as directed by Engineer in charge for smooth riding. The recovery 214.46 cubic meter useful stones shall be made @300/-per cubic meter on proata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified /dimension in all leads and lifts as per the direction of Engineer in Charge.	1987.51	244.07	Two hundred forty four & paise seven only	per cubic metre	485096.00
Total:-						485092.00

DNIT NO ..... Approved for Rs4,85,092/- for the year 2023-2024

Quoted Rate in figure (+)/(-) %  
Quoted Rate in Words (+)/(-) %

Signature of Contractor with full Address

Signature of Engineer  
B & R Division HPPWD  
Rohru

Executive Engineer  
B & R Division HPPWD  
Rohru

EE. A.E.

578-82

Issued to Cu.

Executive Engineer  
B & R Division HP.PWD  
Rohru

Job No. 65  
Estimated Cost:-486553/-  
Earnest Money:-9800/-  
Time:-One Month

NAME OF WORK:- C/O Link road to village Lakhadhar Mini Gadam road km. (SIH:- C/O R/wall in PCC 1:4:8 at RD.0/612.50 to 0/625)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	6.63	287.80	Rupees:-Two Hundred Eighty Seven and Paisa Eighty only	Cum	1908
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	11.50	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	4681
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.64	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	22983
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	71.71	5990.00	Rupees:- Five Thousand Nine Hundred Ninety Paisa Zero only.	Cum	429543
5	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall and retaining and breast wall with 100 (One hundred)dia millimetre PVC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 as per the direction of the Engineer-in-Charge including carriage of materials through all modes of transportation with in all leads and lifts and other incidentals, with in all leads and lifts as per directed by the Engineer-in-Charge	40.00	414.00	Rupees:- Four Hundred Forteen Paisa Zero only.	No.	16560
6	Back filling behind abutments, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 with in all leads and lifts as per directed by the Engineer-in-Charge	7.38	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paisa Zero only.	Cum	10878
		Total:-		486553		
		DNIT No.		Approved for Rs.486553/- only for the Year 2023-2024		
		Quoted rate in figure		%		
		Quoted rate in words		%		
		Signature of contractor with address:-				

Opened by me on Date:-

Cutting .....

Over writing .....

EE AE

Executive Engineer  
B & R Division  
HP.PWD Rohru



Issued to Sr..

Job No. 64

64 84

**SCHEDULE OF QUANTITY**

Executive Engineer  
B & R Division HPPWD  
P. W. D. Rohru  
Estimated Cost:-486553/-  
Tender Money:-9800/-  
Time:-One Month

NAME OF WORK:- C/O Link road to village Lakradhar Mini Gadain road km. (SH:- C/O R/wall in PCC 1:4.8 at RD 0/600 to 0/612.50)

Sl.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	6.63	287.80	Rupees:-Two Hundred Eighty Seven and Paisa Eighty only	Cum	1908
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material with in all leads and lifts as per directed by the Engineer-in-Charge	11.50	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	4681
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.64	6314.00	Rupees:-Six Thousand Three Hundred Fourteen and Paisa Zero only	Cum	22983
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	71.71	5990.00	Rupees:-Five Thousand Nine Hundred Ninety Paisa Zero only.	Cum	429543
5	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall and retaining and breast wall with 100 (One hundred)dia millimetre PVC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of the Engineer-in-Charge including carriage of materials through all modes of transportation with in all leads and lifts and other incidentals with in all leads and lifts as per directed by the Engineer-in-Charge	40.00	414.00	Rupees:- Four Hundred Forteen Paisa Zero only.	No.	16560
6	Back filling behind abutments, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 with in all leads and lifts as per directed by the Engineer-in-Charge	7.38	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paisa Zero only.	Cum	10878
		Total:-				486553
		DNIT No.		Approved for Rs.486553/- only for the Year 2023-2024		
		Quoted rate in figure		%		
		Quoted rate in words		%		
		Signature of contractor with address:-				

Opened by me on Dated

Cutting

Over writing

E.E. A.E.

Executive Engineer  
B & R Division  
H.P.W.D Rohru



Executive Engineer  
B & R Division HPPWD  
Rohru

JOB NO.:

45

150  
(44) (69)

(85)

Name of Work:- C/o H.B Khaniara Seri km 0/00 to 1/370(SH:- F/C 5/7 mtr wide between Km 0/240 to 0/480)

Schedule of Qty

Name of Work: C/o H.B Khatriara Serri km 0/00 to 1/370(SH- F/C 5/7 mtr wide between Km 0/240 to 0/480)						
				ESTIMATED COST	493202	
				EARNEST MONEY	9864	
				TIME LIMIT:	Two Month	
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
1	2	3	4	5	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1,1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way; camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its leveling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 297.65cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lift as per the direction of Engineer in charge.	1666.88	cum	295.883	Ropeses Two Hundred & Ninety Five - Paise Eighty Eight Only	493202
Total						493202

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (\*/-)

Quoted rate Words (\*/-)

Signature of the Contractor with full address:-

Executive Engineer  
B & R Division HPPWD  
Rohru

Opened by me on Dated.....

Cutting.....

Over writing.....

E.E. A.E.

112 Issued to Executive Engineer  
D.R. H.P.W.D. Div. Rohru

Good Checked.  
(42) (86)

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK:- Geotechnical Investigation For Construction of 30.00 mtrs span steel truss/RCC T beam Bridge Barsheel Km 0/00 to 2/200 Km 2/100, (SH- Bridge at RD 0/120).

488000 -

Estimated Cost	488000.00
Earnest Mon	<del>200000</del> 9760/-
Time Limit	One Month

S.No	Description of Item	Quantity		Rate		Unit	Amount
				In fig.	In word		
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia (2 no bores of 20.0 m depth each)for investigation of soil rock conditions at site of work . The scope of work includes preservation of core including relevant tests and submission of geotechnical report of comlex site of work including carriage of materials within all leads and lift as pe rthe direction of Engineer-in Charge.	40.00	Running meter	7600.00	Rupees Two Thousand Four Huundered and Fifty	Per running meter	304000.00
2	Preparation of Hydraulic data complete in all respect in manuscript form and submussion of the same in higher office for approval, if any correction/amendment has desired by the head office, the same may be corrected as desired and directed by the Engineer-in-Charge and higher office,complete in all respect . After approval of the hydraulic data from the higher office, the same will be submitted in fair shape to this office in two numbers of copies.	1.00	JOB	85000.00	Rupees EightyFive Thousand Only	Per Job	85000.00
3	Preparation of General arrangement of drawings according to the existing site conditions and submit the same in the form of two hard copies. The consultant will get the GAD approved from the competent authority. The work will be carried in accordance with latest design specification and to satisfaction of Engineer- in charge	1.00	JOB	99000.00	Rupees Ninly Nine Thousand Only	Per Job	99000.00
Total Amount in figures:-							488000

Opened by me on Certificate  
Cutting  
Over with  
E.E. AE



Executive Engineer,  
Shimla Rural Division  
H.P.P.W.D Rohru

Issued to Sr.

Executive Engineer  
B&R HPPWD Divn. Rohru

## DRAFT SCHEDULE OF QUANTITY

Name of Work : 1) Name of Work:- Construction of Rohru Chingon Boddalawar Road Km 0/00 to Km 21/235 in Dist Shimla Himachal Pradesh (Under CRF).  
(SH:-Axle Load Survey and Automatic Traffic Count Survey (ATCC)).

Estimated Cost :	
Earnest Money :	3040/-

Time Limit :

One Month

Sr. No.	Item Description	Quantity	Units	Estimated Rate	Rate in Words	Total Amount
1	Axle Load Survey for Visa more than 1.0 MSA and Third Party Automatic traffic count Survey (ATCC) for 3-days.	1,000	Each	1,52,000.00	Rupess One Lac's Forty Nine Thousand Rupess only	1,52,000.00
Total						152000.00

Opened by me

Cdr. Y. S. Singh

Overriding

EE. A.E.

Executive Engineer  
Rohru Division  
HPPWD, Rohru

44/27

88

**SCHEDULE OF QUANTITY**

**Name of Work :-** Construction of Education buildings :- i) Govt. High school building at Kharla in Tehsil Tikkar Distt. Shimla HP. (SH:-C/O Building portion, WS & SI works, Septic Tank, RHWT, Site development works etc.) ii) Govt. Senior Secondary school building at Pujari No. -4 in Tehsil Tikkar Distt. Shimla HP. (SH:- C/O Building portion, WS & SI works, Septic Tank, RHWT, Site development works etc.) iii) Govt. Senior Secondary school building at **Sharontha** in Tehsil Tikkar Distt. Shimla HP. (SH:- C/O Building portion, WS & SI works, Septic Tank, RHWT, Site development works etc.) iv) Govt. Industrial Training Institute (ITI) building at **Sumnerkot** in Tehsil Rohru Distt. Shimla HP. (SH:- C/O Building portion, WS & SI works, Septic Tank, RHWT, Site development works etc.) *(Consultancy fee off)*

**Estimated Cost Earnest Money Time**  
Rs. 1,00,000.00  
Rs. 2000.00  
One month

Sr No	Sub Head/items of work.	Qty.	Rate in figures	Rate in word	Unit.	Amount
1	Preparation of Detailed Project Report/ Detailed Estimate alongwith aynalysis of rates of building works including carriage of materials cost of materials Labour rates etc. complete. The Detailed Project Report / Estimate alongwith analysis of rates etc. have to be submitted to the Engineer -In Charge and any objections corrections in this detailed project report / Estimate alongwith analysis of roates etc. tobe attended and final three copies of the same to be supplied to the Engineer- In Charge in all respect including all taxes etc.	4.00	25000.00	Rupees two hundred twenty only	Each	1000000.00
	Total					1000000.00
	Quoted rates in figure (+/-)		%			
	Quoted rates in word (+/-)		%			

Signature of Contractor with full address:-

*[Signature]*  
Executive Engineer,  
B&R Division,  
MP&PWD., Rohru.



89

Name of Work :- Restoration of rain Damage on various road under Rohru Sub Division ( Summerkot Section)(SH:- Hiring of JCB for removal of slips slush/land slide and maintenance of road etc)

Sr.No	Description of items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	Two Month
1	2	3	4	Rate	Amount.
				In Fig.	In Words
1	Hiring of J.C.B(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankhar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450	Per Hours	1100	Rupees One Thousand One Hundred Only
					495000
Total					495000

DNTT No.-2085..... approved for amounting to Rs.-495000/- for the year 2023-24

- 1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.
- 2 cost.

Quoted rate Figure (+/-)	
Quoted rate Words (+/-)	

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

96

Name of Work :- R/R Damage to various road under Rohru Section Sub Division Rohru(SIL:- Hiring of JCB for removal of slips and land slide maintenance of road)

Schedule of Qty

Schedule of Qty									
Name of Work :- R/R Damage to various road under Rohru Section Sub Division Rohru(Sit:- Hiring of JCB for removal of slips and land slide maintenance of road)									
Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST		EARNEST MONEY		Two Month	
				TIME LIMIT:					
				Rate	In Fig.	In Words	Amount.		
1	Hiring of J.C.B(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as banhar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450	Per Hours	1100		Rupees One Thousand One Hundred Only	495000		
Total									495000

DNIT No...1573..... approved for amounting to Rs:-495000/- for the year 2023-24

- The rates should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.
- Quoted rate Figure (+/-)
- Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executing Engineer  
B&R Division HPWD  
Rohru

(91)

Name of Work :- R/R Damage various road under Pujarli section Tikkar Sub Division (Sili- lifting of JCB for removal of slips/land slide and maintenance of road etc)

## Schedule of Qty

Sr.No	Description of items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	308000
				TIME LIMIT:	6160 One Month
1	2	3	4	Rate	In Words
				In Fig.	Amount.
1	Hiring of J.C.B(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kanhar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-scrutable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	280	Per Hours	1100	Rupees One Thousand One Hundred Day
Total					308000

DNT No...1618..... approved for amounting to Rs.:308000/- for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.

2 cost. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

(92)

**Schedule of Qty**

Name of Work :- R/R Damage various road under Pujari section Tikkar Sub Division (SH:- Hiring of JCB for removal of slips/land slide and maintenance of road etc)

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	One Month
1	2	3	4	Rate	Amount.
				In Fig. 5	In Words 6
1	Hiring of J.C.B.(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All sagged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berm. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all loads and lifts.	280	Per hours	1100	Rupees One Thousand One Hundred Only
					308000
Total					308000

DNIT No...1446..... approved for amounting to Rs.:308000/- for the year 2023-24

1 The rates should be quoted for all heights including all load and lifts.

2 cost. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru



93

Name of Work :- R/R Damage various road under Rohru section Rohru Sub Division (SH:- Hitting of JCB for removal of slips/ Snow and maintenance of road etc)

Schedule of Qty

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	One Month
1	2	3	4	TIME LIMIT:	
				Rate In Fig.	In Words Amount.
1	Hitting of J.C.B (Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as bankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burns. Minimum 30 cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450	Per Hours	1100	Rupees One Thousand One Hundred Only 495000
Total					495000

DNIT No.-2113..... approved for amounting to Rs.-495000/- for the year 2023-24

- The rates Should be quoted for all heights including all lead and lifts. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.
- Quoted rate Figure (+/-)
- Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPWD  
Rohru

94

JOB NO:-

Schedule of Qty

Name of Work :- R/R damages to various road under Samoli Section Sub Division Rohru (Sh:- Hiring of Tipper for carriage of excavated earth muck etc )

Name of work :- R/R damages to various road under Samoli Section Sub Division Rohru (Sh:- Hiring of Tipper for carriage of excavated earth muck etc )						
Sr.No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		495000
				TIME LIMIT:		990000
				Rate	In Words	75 Days
				In Fig.		
1	2	3	4	5	6	7
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L. charge and other ancillary equipments as required at the site of work. The work shall to be carried out as per ministry of transport as per instructions of the Engineer-in- Charge including all leads and lifts.	75	Per Day	6600	Rupees Six Thousand Six Hundred Only	495000
Total						495000

DUNT No. ....2116.. approved for a amount upto Rs:-495000for the year 2023-24

DNT No ...2116.. approved for amounting to Rs:-495000for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)  
Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

Estimated Cost:-492570/-

**Earnest Money:-9900/-**

Time:-One Month

1:4:8 at R.D.5/193 to 5/206)

## Item of work

**Executive Engineer  
B&R Division  
HP.PWD Rohru**

### SCHEDULE OF QUANTITY

## Item of work

Estimated Cost:-492570/-
--------------------------

**Earnest Money:-9900/-**

Time:-One Month

:4:8 at RD.5/180 to 5/193)

Executive Engineer  
B&R Division  
HP.PWD Rohru



**DRAFT OF SCHEDULE OF QUANTITY.**

(97)

Estimated cost Rs 418482/-  
Earnest money Rs 8500/-  
Time one Month

**Name of work :-** C/O Dhamwal to Gokswari km 0/0 to 5/300 (SH- C/o R/wa;; at RD 1/9/10 to 1/9/30)

Sr.No	Description of Items	Quantity	Rate in Figure.	Rate in Words	unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	44.00	186.32	Rs one hundred eighty six & paise thirty two only	per cubic metre	8198
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	14.00	407.00	Rs four hundred seven only	per cubic metre	5698
3	Providing and laying of Boulder apron laid in wire crate with 4mm G.I wire conforming to IS 280mm IS 4826 100mm mesh (woven diagonally) including 10 percent extra laps and joints and wire some boulders weighing not less than 25kg as per drawing technical specification clause 1301 within all leads and lifts as per direction of Engineer in charge	125.00	2890.90	Rs two thousand eight hundred ninety only	per cubic metre	361250
4	Back filling behind abutment wing wall and return wall with granular materials complete within all leads and lifts as per direction of Engineer in charge	29.40	1474.00	Rs one thousand four hundred seventy four only	per cubic metre	43336
	<b>Total:-</b>					<b>418482</b>

DNIT NO ..... Approved for Rs 418482.00 - for the year 2023-2024

Quoted rate in Figure (+/-)	%
Quoted rate in words (+) (-)	%

Signature of contractor with full Address

Expected Engineer  
B&R DNIT HP, PWD  
Rohini

98

**Schedule of Qty**

**Name of Work:- A/R & M/O HPPWD store at Rohnu(Sh:- C/o Steel work at HPPWD store at Rohnu)**

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	437005
				TIME LIMIT:	8740
				Rate	Two Month
				In Fig.	
				In Words	
					Amount.
1	Steel work welded in built up Sections and framed work, including cutting, bolting, fixing in position and applying a coat of red lead paint in grating framed guard bars ladder, railing, brackets and similar work including all lead and lifts as per HPPWD Specification of 1990 Volume-I as directed by the Engineer-In-Charge.	3111.1	kg	127	395110
2	providing and fixing plain asbestos cement sheet ceiling of approved quality with butt jointing and wood screws 6mm thick including all lead and lifts.	68.39	sqm	612.6	41896
	<b>Total</b>				<b>437005</b>

**Condition:-**

1 The rates should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohnu

# SCHUEDE OF QUANTITY

Estimate Cost 252000/-  
Earnest Money 5040/-

Time 45days

Name :-R/R damage to Varrious road under Rohru sub Division (Rohru section)Hiring of JCB for removal of slips slush /land slide and maintenance of road etc

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of JCB (Excactor cum loader having bucket capacity 0.45cum including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heghits and all kinds of soils such as kankar moorum shingle boulders decomposed or soft variety of soil such as spade work pick work jumer work soft rock hard rock including their intermediate classification of soil including mechnacial transport if and when required. The disposal of the underecable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its . All salvaged materials such as qurried stoen shall belong to the department and manikurnum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minium 18.00 cubice metre of earth work shall be done by the machine in one hours other wise nu umber of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of he Engineer in charge	30.00	8400/-	As Eight thousand four hundred only.	per day	2,52,000.00
	<b>Total</b>					

Executive Engineer  
B&R Divn HP PWD  
Rohru

99

(100)

# **SCHEDULE OF QUANTITY**

**NAME OF WORK:-** C/O Kui Nadu road km. 0/0 to 1/0 (SH:-C/O R/wall at RD.0/495 to 0/507 & 14 Nos Parapets in R.R. 1:6)

**Job No.**  
**Estimated Cost:-** 437235/-  
**Earnest Money:-** 8700/-  
**Time:-** One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	17.40	246.65	Ruppes:-Two Hundred Forty Six and Paiza Sixty Five only	Cum	4292
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	20.28	430.51	Ruppes:-Four Hundred Thirty and Paiza Fifty One only	Cum	8731
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	5.16	4475.35	Ruppes:-Four Thousand Four Hundred Seventy Five and Paiza Thirty Five only	Cum	23093
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	2.16	5001.52	Ruppes:-Five Thousand One and Paiza Fifty Two only	Cum	10803
5	Randon Rubble Stone masonry in cement mortar for sub structure complete as per drawings and technical specification Clauses 702, 704, 1202 and 1204 rendam rubble masonry in cement mortar 1:6 as directed by the Engineer-in-Charge	23.84	4750.00	Ruppes:-Four Thousand Seven Hundred Fifty Paiza Zero Only.	Cum	113240
6	Construction of dry masonry in retaining walls, breast walls etc.as per drawings and technical specification including carriage of material within all leads and lifts as per directions of Engineer in charge	74.37	3505.03	Ruppes:-Three Thousand Five Hundred Five Paiza Zero Three Only.	Cum	260669
7	Back filling behind abutments wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	13.56	1210.00	Ruppes:-One Thousand Two Hundred Ten and Paiza Zero only	Cum	16408
	<b>Total:-</b>					<b>437235</b>
	Quoted rate in figure			%		
	Quoted rate in words			%		
	Signature of contractor with address:-					

Executive Engineer  
 B & R Division  
 H.P.V.D Rohru



101

Name of Work:- R/R Damage to Badiyara Diswani road km 0/00 to 6/00( Sh:- C/o R/wall at Rd 1/575 to 1/589) Schedule of Qty

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		Amount.
				EARNEST MONEY	Two Month	
1	2	3	4	TIME LIMIT:		7
				Rate	In Words	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	16.52	cum	In Fig.	6	5366
				5	Ruppes Three Hundred & Twenty Four - Paise Eighty Three Only	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material.	26.32	cum	407	Ruppes Four Hundred & Seven Only	10712
3	Plain/rein forced cement concrete(1:6:12)in open foundation complete as per drawing and technical specification Clauses 802.803,1202&1203	7.28	cum	5109.04	Ruppes Five Thousand One Hundred & Nine - Paise Four Only	37194
4	Plain/rein forced cement concrete(1:4:8)in open foundation complete as per drawing and technical specification Clauses 802.803,1202&1203	3.64	cum	5710.66	Ruppes Five Thousand Seven Hundred & Ten - Paise Sixty Six Only	20787
5	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702.704,1202 and1204 Random rubble masonry in cement mortar(1:6)	71.82	cum	5523.33	Ruppes Five Thousand Five Hundred & Twenty Three - Paise Thirty Three Only	396686
6	Back filling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8	11.34	cum	1331.51	Ruppes One Thousand Three Hundred & Thirty One - Paise Fifty One Only	15099
7	Providing weepholes in brick masonry/ Stone masonry, plain/reinforced concrete abutment, wing wall,return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V)20(H) towards drawing face complete as per drawing and technical specification clause 614.709,1204,3.7 including all lead and lifts.	15	No	397	Ruppes Three Hundred & Ninety Seven Only	5955
						491799

1 The rates Should be quoted for all heights including all lead and lifts.  
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.  
2 cost.  
Quoted rate Figure (+/-)  
Quoted rate Words (+/-)  
Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru

(162)

**SCHEDULE OF QUANTITY****NAME OF WORK:- R/M of Rest House at Tikkar (SH:-C/O wood work & W.S & S.I.**

Job No. \_\_\_\_\_

Estimated Cost:- 270097/-

Earnest Money:- 17100/- < 4% /

Time:- One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge.	79.84	1360.65	Rupees:- One Thousand Three Hundred Sixty and Paise Sixty Five only	Sqm	108634
2	P/P Sunmica including carriage of material with in all lead and lifts.	79.84	620.00	Rupees:- Six Hundred Twenty and Paise Zero only	Sqm	49501
3	PVC Sheet for floor	61.66	450.00	Rupees:- Four Hundred Fifty and Paise Zero only	Sqm	27747
4	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.	3.06	2575.57	Rupees:- Two Thousand Five Hundred Seventy Five and Paise Fifty Seven only	Sqm	7881
5	Providing and fixing vitreous China wash, down water closet (European Type W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1 (1 cement : 1 sand) seat and cover to be measured and paid for separately including carriage of materials within all leads and lifts :- Anglo Indian universal closet.	4.00	4818.50	Rupees:- Four Thousand Eight Hundred Eighteen and Paise Fifty only	Each	19274
6	Providing and fixing PVC Finolex floor traps ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of material within all leads and lifts as per direction of Engineer-in-charge:- (110mmx75mm)	4.00	985.70	Rupees:- Nine Hundred Eighty Five and Paise Seventy only	Each	3943

7	Providing and fixing 10.00 ltr capacity PVC low level flushing cistern Hind ware sleek ultra design No 186575 size 42 X 39 X 14 cm or equivalent with a pair of brackets with fittings such as lead valve, syphon, 15mm nominal size PVC ball valve with polythene float, with push button, couplings for connections with inlet, outlet and overflow pipe, 40mm dia C.P. flush bend including cutting holes in walls and making good the same and connecting the flush bend with cistern and closet (overflow) pipe to be measured and paid for separately including carriage of materials within all leads and lifts :-	4.00	2280.10	Rupees:-Two Thousand Two Hundred Eighty and Paise Ten only	Each	9120
8	Providing and fixing vitreous China Hind ware IS marked IS No. 2556 or equivalent wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fitting including carriage of materials within all leads and lifts :-Flat back :-550 X 400 mm size	4.00	3313.30	Rupees:-Three Thousand Three Hundred Thirteen and Paise Thirty only	Each	13253
9	Providing and fixing stainless steel kitchen sink of approved standard ISI make with drain board and C.P. waste with C.I. or M.S. Brackets painted white including cutting holes and making good the same but excluding fitting 610 x 510 mm with bowl depth 200 mm including carriage of materials within all leads and lifts	2.00	4491.90	Rupees:-Four Thousand Four Hundred Ninety One and Paise Ninety only	Each	8984
10	Providing and fixing looking mirror of superior glass with plastic frame including carriage of materials within all leads and lifts :-	4.00	800.00	Rupees:-Eight Hundred and Paise Zero only	Each	3200
11	P/F Mixer tap	2.00	6000.00	Rupees:-Six Thousand and Paise Zero only	Each	12000
12	Providing and fixing CP brass bib tap with capstan head including carriage of materials within all leads and lifts :-15mm dia :-15mm dia :-	4.00	650.00	Rupees:-Six Hundred Fifty and Paise Zero only	Each	2600
13	Providing and fixing C.P. brass towel rail complete with C.P. brass brackets fixed to wooden plugs with C.P. brass screws including carriage of materials within all leads and lifts :-600 X 20 mm	4.00	450.00	Rupees:-Four Hundred Fifty and Paise Zero only	Each	1800
14	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms.	16.00	134.99	Rupees:-One Hundred Thirty four and Paise Ninety Nine only	Each	2160
Total:-						270097
DNIT No. 2/21 Approved for Rs.270097/- only for the Year 2023-2024						

Executive Engineer  
B&R Division  
HP.PWD Rohru





~~Part~~ / SCHEDULE OF QUANTITY

Estimated Cost: 460843/-
Earnest Money: 9300/-
Time:-One Month

**Time:- (One Month)**

NAME OF WORK:-Repair and maintenance of Rest House at Tildkar (SI:-Construction of wood work for lining in wall )

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Providing wood work in trusses purlins, rafters, posts post plates, wall plates and the like wrought, framed, hoisted and fixing in position.	1.31	101001.14	Rupers - One Lac One Thousand One and Paise sixteen only	Sqm	132311
2	Providing and fixing plain lining with tongued and grooved jointing and screws ( frame work and cover fillets to be measured and paid for separately with.	142.84	2300.00	Rupers - Two Thousand Three Hundred and Paise Zero only	Sqm	328532
				Total:-		460843
	DNIT No. 2123 Approved for Rs.460843/- only for the Year 2023-2024					

Executive Engineer  
B&R Division  
HP.PWD Rohru

Executive Engineer  
B&R Division  
HP.PWD Rohru

105

Name of Work:- R/M of Rest House at Tikkar(SH:- C/o Painting work and Tile work)

Schedule of Qty

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	TIME LIMIT:	Amount.
1	2	3	4	Rate In Fig.	In Words	7
1	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer, complete including carriage of material within all leads and lifts and as per H.P.P.W.D., specifications of 1990 volume-1 and as per direction of Engineer-in-Charge.	466.02	sqm	120	Rupees One Hundred & Twenty Only	56018
2	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : including carriage of material within all leads and lifts and as per H.P.P.W.D., specifications of 1990 volume-1 and as per direction of Engineer-in-Charge.	466.82	sqm	105	Rupees One Hundred & Five Only	49016
3	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete.	62.29	sqm	1438.31	Rupees One Thousand Four Hundred & Thirty Eight - Paise Thirtly One Only	89592
4	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).	154.16	sqm	1567.89	Rupees One Thousand Five Hundred & Sixty Seven - Paise Eighty Nine Only	237002
Total						431629

Condition:-

1. The rates Should be quoted for all heights including all lead and lifts.

2. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure ( +/ )

Quoted rate Words ( +/ )

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Bofnu

(106)

**SCHEDULE OF QUANTITY****NAME OF WORK:-C/O link road from Rai Odhidhar (H.B. Khasdhar) km.0/0 to 1/300 (SH:-C/O B/wall in wire crate at RD.0/580 to 0/630)**Job No.  
Estimated Cost:-425019/-  
Earnest Money:-8500/-  
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	34.50	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty three only	Cum	11207
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	21.00	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	8547
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm ( hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 2.5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	156.25	2593.70	Rupees:-Two Thousand Five Hundred Ninety Three and Paisa Seven Zero only	Cum	405266
		Total:-				425019
		DNIT No. Approved for Rs.425019/- only for the Year 2023-2024				
		Quoted rate in figure				
		Quoted rate in words				
		Signature of contractor with address:-				

Executive Engineer  
B&R Division  
HP.PWD Rohru

107

**SCHEDULE OF QUANTITY**

**NAME OF WORK:-C/O link road from Rai Odhidhar (IIB Khasdhar) km.0/0 to 1/300 (SH:-C/O 900mm dia HPC at RD.1/150)**

Job No. \_\_\_\_\_  
Estimated Cost:-432281/-  
Earnest Money:-8700/-  
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	13.86	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty three only	Cum	4502
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	45.80	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	18641
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	6.22	5109.04	Rupees:-Five Thousand One Hundred Nine and Paisa Zero Four only	Cum	31778
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	4.65	5710.66	Rupees:-Five Thousand Seven Hundred Ten and Paisa Six Six only	Cum	26555
5	Randon Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	35.40	5400.00	Rupees:-Four Thousand Four Hundred Paisa Zero Only.	Cum	191160
6	Construction of dry rubble masonry for retaining wall, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawings and technical specification Clauses 704.6, 1302.5 as directed by the Engineer-in-Charge	28.14	3677.35	Rupees:-Three Thousand Six Hundred Seventy Seven Paisa Three Five only	Cum	103481
7	Back filling behind abutments wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	7.91	1331.51	Rupees:-One Thousand three Hundred thirty one and Paisa Five One only	Cum	10532



8	Providing and laying reinforced cement concrete pipe N/2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection works backing filling concrete and masonry works in head walls and parapets clause 1106 as directed by the Engineer-in-Charge	7.50	5250.00	Rupees:-Five Thousand Two Hundred Fifty Paisa /zero only.	Cum	39375
9	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303 as directed by the Engineer-in-Charge	0.49	12770.56	Rupees:-Twelve Thousand Seven Hundred Seventy Paisa Five Six only.	Cum	6258
				Total:-		432281
		DNIT No.		Approved for Rs.432281/- only for the Year 2023-2024		
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

Executing Engineer  
 B&R Division  
 HP.PWD Rohru

108

**SCHEDULE OF QUANTITY**

**NAME OF WORK :- R/R damages to Mandharli to Sharontha road km. 0/0 to 10/0 (SH:-C/O B/wall at RD.5/025 to 5/050 & R/wall at Rd.3/585 to 3/600)**

Job No.  
Estimated Cost:-492443/-  
Earnest Money:-9900/-  
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	79.75	324.80	Rupees:-Three Hundred Twenty Four and Paiza Eighty only	Cum	25903
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	31.125	407.00	Rupees:-Four Hundred Seven and Paiza Zero only	Cum	12668
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	148.44	2890.00	Rupees:-Two Thousand Eight Hundred Ninety Paiza Zero only.	Cum	428992
4	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	16.88	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paiza Zero only.	Cum	24881
		Total:-				492443
		DNIT No.		Approved for Rs.492443/- only for the Year 2023-2024		
		Quoted rate in figure		%		
		Quoted rate in words		%		
		Signature of contractor with address:-				

Executive Engineer  
B&R Division  
Rohru

(109)

Job No.

**SCHEDULE OF QUANTITY**

Estimated Cost:-473672/-

Earnest Money:-9500/-

Time:-One Month

**NAME OF WORK:- R/R damages on Udayniwas Jakhar Rantari road km. 0/0 to 4/0 (SH:-C/O R/wall at RD 3/870 to 3/880)**

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	33.20	324.83	Rupees:-Three Hundred Twenty Four and Paise Eighty Three only	Cum	10784
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	33.10	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	13472
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.80	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paise Zero only	Cum	23993
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	7.00	6656.00	Rupees:- Five Thousand Five Hundred Forty Paise Zero only.	Cum	46592
5	Stone masonry in cement mortar 1:6 (1:Cement :6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704,1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	38.76	5400.00	Rupees:-Five Thousand Four Hundred Paise Zero Only.	Cum	209304
6	Construction dry rubble Stone masonry for retaining walls breast wall reventment walls and parapets etc for sub structure and superstructure complete as per drawings and technical specification Clauses 704.6 and 1302.5 within all leads and lifts as per directions of Engineer in charge	36.15	4082.00	Rupees:-Four Thousand Eighty Two Paise Zero only.	Cum	147564
7	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3, 8 as directed by the Engineer-in-Charge	14.90	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paise Zero only.	Cum	21963
			Total:-			473672
		DNIT No.				Approved for Rs.473672/- only for the Year 2023-2024
		Quoted rate in figure				%
		Quoted rate in words				%
		Signature of contractor with address:-				

Executive Engineer  
B&R Division  
HP.PWD Rohru

Schedule of Qty			
Name of Work:- C/o Link road Shashitwani kainchi to gartu mala km 0/00 to 2/000 Sil:-F/C 5/7 nitr wide road at RD 0/135 to 0/285)			
		ESTIMATED COST	470051
		EARNEST MONEY	9401
		TIME LIMIT:	Two Month

Sr. No	Description of Items.	Qty	Unit	Rate		In Words	Amount.
				In Fig.			
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work, hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Mallana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 199.13cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	2060.625	cum	226.111		Ruppes Two Hundred & Twenty Eight - Paise Eleven Only	470051
	Total						470051

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru



(111)

Name of Work:- C/o Link road Shasthwan kainchi to gattu nala km 0/00 to 2/00(SH-F/C 5/7 mtr wide road at RD 0/285 to 0/420)

Schedule of Qty

Sr.No	Description of Items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY	TIME LIMIT:	Two Month
1	2	3	4	Rate	In Words	Amount.
				In Fig.	6	7
1	Excavation in billy area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603,1,1603,2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way; camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including bead load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machines, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 187.27cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1935	cum	226.335	Rupess Two Hundred & Twenty Eight - Paile Thury Four Only	441829
	Total					441829

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 cost. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer  
B&R Division HPPWD  
Rohru