




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

**CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
19561-19610 DATED 01-03-2024 ARE URGENT NATURE
AND PUBLIC INTEREST.**


**Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.**



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate on tender form No 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **13.03.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **12.03.2024 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **11.03.2024 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr No	Name of Works	Amount put to tender/Estimated cost	Earnest Money	Cost of tender form	Time limit
1	C/O Govt. Degree College at Multhan (SH: Preparation and Supplying Structural Design Drawings from Foundation to Roof Level (Phase-I))	Rs.5,00,000/-	Rs.10,000/-	Rs.350/-	Three months
2	C/O Bir Palampur Road to Mandher via Gharnallah Km 0/00 to 3/500 (SH: P/L C.C. Pavement at Km 1/285 to 1/320)	Rs.1,96,088/-	Rs.3,900/-	Rs.350/-	Two Months
3	Restoration of Rain Damages on Mahakal Narghore Road km 0/00 to 4/200 (SH: C/O B/wall at RD 2/795 to 2/805)	Rs.1,66,989/-	Rs.3,400/-	Rs.350/-	One Month
4	Construction of Link Road Simbal to Drug via Rakh Moon km 0/00 to 2/00 (SH: F/C in Km 0/00 to 0/180)	Rs.4,98,523/-	Rs.10,000/-	Rs.350/-	Two Months
5	Balance work for C/O way side Facility on Barot to Nalhota Road km 0/00 to 16/00 (SH: C/O Rain Shelter for Bus stop at RD 12/705)	Rs.1,46,291/-	Rs.3,000/-	Rs.350/-	Two Months
6	R/R Damages on Barot Polling Road km 0/00 to 8/050 (SH: Balance work for repair of 2.00 mtr span culvert i.e. wing wall at RD 2/230 to 2/232 & R/wall at RD 2/391 to 2/399)	Rs.3,86,145/-	Rs.7,700/-	Rs.350/-	Two Months
7	S/R to Pandit Sant Ram Govt. Degree College at Baijnath (SH: Renewing Glass Panes 5 mm thick)	Rs.1,13,911/-	Rs.2,300/-	Rs.350/-	One Month
8	C/O Mahalpatt Mahakal via Talashan Road km 0/00 to 2/00 (SH: C/O 1.00 mtr span RCC slab culvert at RD 1/705)	Rs.1,99,114/-	Rs.4,000/-	Rs.350/-	Two Months

Terms and conditions -

- The contractor should be registered as dealer under H.P. GST Tax Act, 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD. Baijnath

For & On behalf of the governor of H.P.

Dated:- 01.03.2024

NO:-PWD/BD/TA/NIT/2023-24/- 19561-19610

- Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- Drawing Branch in this office
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.
-

Executive Engineer,
Baijnath Division.,
H.P.PWD. Baijnath

①

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work : C/O Govt Degree College at Multhan (SH:Preparation and Supplying Structural Design Drawings from Foundation to Roof Level (Phase- I))				Estimate Cost: 500000.00/- Earnest Money: 10,000.00/- Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Preparation and supplying of Structural design including analysis, drawings etc complete for C/O Govt Degree collage at Multhan . The Job shall include submission of input data anyalsis and design data check print structural drawings 4 (Four) blue prints of each drawings along with soft copy in shape of CD as per approved structural design and drawings including proof checked from any Govt approved institute to the rank of IIT/NIT/Deemed University etc as per entire satisfaction and direction of Engineer - in - Charge. The rate including of GST or other Taxes imposed by government	1.00	Per Job			
Total						

Executive Engineer
Math Division
MID, Belgaon

DNIT/DRAFT SCHEDULE OF QUANTITY

2

Name of Work :- C/O Bir Palampur Road to Mandhed via Gharnallah Km 0/00 to 3/500.
(SH:- P/L C. C Pavement at km 1/285 to 1/320).

Estimate Cost: 196088.00/-
Earnest Money: 3900.00/-
Time Limit : Two Months


SCHEDULE OF WORKS

Sr	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
					Words	
1	Construction of un-reinforced, plain cement concrete pavement thickness as per design, over a prepared sub base with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weight batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing spreading the concrete with shovels rakes compact using needle, screed and plate vibrator and finishing in continuous operation including construction joints, admixtures as approved, curing the concrete slab for 14 days using curing compound (where specified) and water finishing to lines and grade as per drawing and technical specification clause 1501 The rate shall be made from the quantity of stone aggregates supplies. The rate shall include all lead, lift and proper stacking complete in all respect as per the direction of the Engineer-in-charge.	26.25	Per Cubic Metre			
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (Eighty to One Hundred Kilo Newton) static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-II as per Technical Specification Clause 405.(63mm to 45mm) (sixty three millimeter to forty five millimeter). The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	5.25	Per Cubic metre			
Total						


Executive Engineer
Bajinath Division
HPPWD, Bajinath


DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain Damages on Mahnkal Narghore Road km 0/00 to 4/200 . (SH:- C/O B/wall at RD 2/795 to 2/805)				Estimate Cost:1,66,989.00/- Earnest Money: 3,400.00/- Time Limit : One Month		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	10.60	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	34.00	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V) 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	9.00	Each			
Total						


 Engineer
 Division
 H.P.W.D.,
 2

4

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction of Link Road Simbal to Drug via Rakh Moon km 0/00 to 2/00 . (SH: F/C in Km 0/00 to 0/180)				Estimate Cost: 4,98,523.00/- Earnest Money: 10,000.00/- Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 174.02 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost.	2157.08	Per Cubic metre			
	Total					

Executive Engineer
Road Division
BWD, Ballari
[Signature]


DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : - Balance work for C/O way side Facility on Barot to Nalhota Road km 0/00 to 16/00 . (Sub Head : C/O Rain Shelter for Bus stop at RD 12/705).	Estimate Cost: 1,46,291.00 Earnest Money: 3000.00 Time Limit : Two Months
--	--

SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Rates		AMOUNT Rs. P	
				Figures	Words		
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.60	Per cubic metre				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (one Cement : three coarse sand): six graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.80	Per cubic metre				
3	Stone filling under floor complete as per PWD specification. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.80	Per Cubic metre				
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one Cement : two coarse sand) : four graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	3.60	Per cubic metre				
5	Providing and Fixing 100 mm (hundred millimeter) diameter mild steel hollow pipe (heavy grade) embedded Square /Round bar complete as per PWD specification, including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	15.00	Per running metre				
6	Providing and fixing pre-painted sheet roofing of kotar metal single skin trapezoidal sheeting 0.60mm (sixty milimetre) thickness having 1060mm (one thousand sixty millimetre) cover width cover all width 1126mm (one thousand one hundred twenty six milimetre) . 28mm (twenty eight milimetre) crest depth at 353mm (three hundred fifty three milimetre) 2.50mm (two point fifty millimetre) the main crest with at top 25mm (twenty five) and at lower 81mm (eighty one milimetre) base metal of coil rolled steel coil with zinc waiting top coat with regular modified polysters coating of approved shade and balancing reverse coat with self topping screws 5.5mm (five decimal five millimetre) dia and 55mm (fifty five milimetre) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	19.11	Per square metre				

7	Providing and fixing plain M.S. B.P. sheet 1.66mm (one decimal sixty six millimetre) thick to 2.00mm in evels board/ Facia / Soffit / Ceilling including cutting fixing jointing with gass/electric welding to steel roofs members and applying a coat of red lead primer complete as per PWD specification (frame work is to be measured paid for separately). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.64	Per square metre			
8	Providing tor steel reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all respects as per drawing and design in all floor levels including the cost of binding wire as per PWD specification and approved design. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	658.32	Per kilo gram			


 Executive Engineer
 District Engineer
 P.W.D., Jaipur

DNIT/DRAFT SCHEDULE OF QUANTITY

6

Name of work : R/R Damages on Barot Polling Road km 0/00 to 8/050 (Sh:- Balance work for repair of 2.00 mtr span culvert i.e wing wall at RD 2/230 to 2/232 & R/wall at RD 2/391 to 2/399)				Estimate Cost: 3,86,145.00/- Earnest Money: 7700.00/- Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	23.16	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	58.48	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	11.82	Per Cum			
4	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	5.14	Per Cum			
5	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	15.00	Each			
Total						

The Engineer
Division
Bhopal

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- S/R to Pandit Sant Ram Govt Degree college at Baijnath
(SH: Renewing Glass Panes 5 mm thick .)

Estimate Cost: 1,13,911.00 ✓

Earnest Money: 2,300.00

Time Limit : One Month

SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Rate to be entered by the Bidder in		AMOUNT Rs. P
				Figures	Words	
1	Supplying and Fixing glass panes with putty and nails including removal of broken glass panes wherever necessary glass 5 mm (five) thick disposal of surplus material upto 20 (twenty) mtrs lead with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	134.40	Per Sqm			

Executive
Baijnath
KARNATAKA


(8) (a)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O MahalPatt Mahnkhal via Talashan Road km 0/00 to km 2/00 (SH:- C/O 1.00 mtr Span RCC slab culvert at RD 1/705)				Estimate Cost: 1,99,114.00/- Earnest Money: 4,000.00/- Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing . removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge Including carriage of materials within all leads and lifts and other incidental The rate is including octroi, royalty, GST, toll tax. Sale Tax or other taxes imposed by the government.	32.66	Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect The rate including of octroi, royalty, Malkana, or other taxes imposed by the government.	3.24	Cum			
3	Providing and laying mechanically mixed and vibrated plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water . dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800,900 & 1200 and curing complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	18.49	Cum			

(8) (6)

4	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.84	Per Cubic metre			
5	Reinforced cement concrete work in flat surfaces including columns pillars piers abutments posts and sturts etc above plinth level upto floor five level excluding cost of centering, shuttering finished and reinforcement 1:1.5:3 (one cement one point five graded sand three graded stone) and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	2.69	Cum			
6	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position in beams joists channels, angles, tee, flats with connecting plates or angle cleats as in straps, wall ties, inserts, knee pieces and similar works including cutting hoisting fixing in position & applying a priming coat of red lead paint complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	320.50	Per Kilogram			


 Executive Engineer
 Bajjnath Division
 HPPWD, Bajjnath


 -28-