




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
1654-64 DATED 15-06-2024 ARE URGENT NATURE
AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **04.07.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **03.07.2024** between **2.00 PM** up to **4.30 P.M** and the application for issue of tender forms shall be received on **02.07.2024** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	A/R & M/O various roads under Baijnath Sub-Division HPPWD Baijnath (Paprola Section) (SH: Supplying and stacking of G-III, Grit & Sand)	Rs.1,95,547/-	Rs.3,900/-	Rs.350/-	Two Months
2	C/O Link road from Bir Billing to Bangroo water fall (SH: P/L C.C. Pavement)	Rs.1,47,557/-	Rs.3,000/-	Rs.350/-	One Month
3	C/O road link road from Gunehar to Lahar via Phat (SH: P/L Kharnja stone soling at RD 0/380 to 0/580)	Rs.1,46,691/-	Rs.3,000/-	Rs.350/-	Two Months
4	C/O Mahalpatt via Talshan Nohra Road (SH: P/L C.C Pavement & WBM G-II at km 1/920 to 1/965)	Rs.1,73,571/-	Rs.3,500/-	Rs.350/-	One Month
5	C/O Link road from Bani Di Hatti to Dadin (SH: Improvement of Road (C/O R/wall) & Providing and laying C.C Pavement & Kharnja stone soling at km 1/900 to 1/945)	Rs.3,85,842/-	Rs.7,800/-	Rs.350/-	Two Months
6	C/O Pucca Path Towards Rajal Village (SH: Providing and laying C.C Pavement)	Rs.78,804/-	Rs.1,600/-	Rs.350/-	One Month
7	Development of Ground at Gram Panchayat Kudail (SH: C/O Steps in G.S.S. School Krishna Nagar)	Rs.2,97,271/-	Rs.6,000/-	Rs.350/-	One Month
8	C/O R/wall to Protect the Land & House of Sh. Balbir Singh S/o Shri Tokha Ram V.P.O. Chobin (SH: C/O R/wall at km 0/00 to 0/007.20)	Rs.99,316/-	Rs.2,000/-	Rs.350/-	One Month
9	C/O link road from Baijnath LadhBharol Kandapattan to Village Kuni (SH: Improvement of Formation Deficiency of C/O R/wall at km 0/165 to 0/177)	Rs.2,75,597/-	Rs.5,600/-	Rs.350/-	One Month
10	C/O link road from Majherna to Chakol Behru km 0/00 to 1/930 (SH: Providing and laying C.C Pavement at km 0/543 to 0/628)	Rs.2,94,347/-	Rs.5,900/-	Rs.350/-	One Month
11	C/O link road from Marh to Sanehar (SH: Providing laying C.C Pavement & WBM G-II at km 0/110 to 0/190)	Rs.2,29,763/-	Rs.4,600/-	Rs.350/-	One Month
12	A/R & M/O Various residential building of PWD under Baijnath Division Baijnath (SH: Providing and supplying of form No.8 and File cover with printed for various works)	Rs.1,15,000/-	Rs.2,300/-	Rs.350/-	One Month
13	R/D on Paprola Andretta road & Majherna Jandpur Nauri Road (SH: Scarifying, P/L WMM, Tack Coat, Primer Coat and B.M at Various reaches)	Rs.4,64,683/-	Rs.9,300/-	Rs.350/-	Two Months
14	Balance work for CHC at Chadhiar in Tehsil Baijnath (SH: Steel work for roofing and ceiling etc.)	Rs.2,10,665/-	Rs.4,300/-	Rs.350/-	One Month

Terms and conditions:-

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the TIN number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.

E.E.

2. The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Bajnath Division.,
H.P.PWD..Bajnath.

For & On behalf of the Governor of H.P.

Dated:- 15.06.2024

NO:-PWD/BD/TA/NIT/2023-24/-

16 SL-64

- 1 Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief.Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Bajnath Division.,
H.P.PWD..Bajnath.

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- A/R & M/O various roads Under Baijnath Sub Division HPPWD Baijnath (Paprola Section) (SH: Supplying and stacking of G-III , Grit & Sand)				Estimate Cost: 1,94,547.00/- Earnest Money: 3,900.00/- Time Limit : Two Months		
SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing stone aggregate size 53mm to 22.40 mm (fifty three millimeter into twenty four point four millimeter) Grading-III [75mm (seventy five millimeters) consolidated thick to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 by manual mean and to the entire satisfaction and direction of Engineer - in- Charge including carriage of material with in all leads and lifts and other incidental. The rate includes octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	40.00	Per Cubic metre			
2	Supply and stacking of fine aggregate sand of size greater than 0.06mm (zero decimal zero six millimeters) and shall consist of clean, hard, durable uncoated dry particles and shall be free from dust, soft or flaky material organic matter or other deleterious substances. The material shall stacked at road side clear of carriage way and shoulders or on even ground as per instruction of Engineer-in-Charge. The aggregate shall pass 1.7mm sieve and retained on 180 micron sieve The rate includes octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	25.00	Per Cubic metre			
3	Supply and stacking of crushed stone aggregate 12mm (twelve millimeter) and 10mm (ten millimeter) size consisting of angular, fragments of clean, hard, tough and durable rock. The aggregates shall be free of elongated and flaky pieces, soft and disintegrated stones and vegetable and other deleterious matter. The aggregates shall be stacked in proper stacks of road side clear of carriage way and shoulders or on even ground as per the instruction of Engineer-in-Charge. The proportion of the quantities of the material shall be as under:-a) Stone chippings 12mm (twelve millimeter) size passing 20mm (twenty millimeter) sieve and retained on 10mm (ten millimeter) sieve 0.18 cubic metre. Stone chippings 10mm (ten millimeter) size passing 12.5mm (twelve decimal five millimeters) sieve and retained on 6.30mm (six decimal three millimeters) sieve 0.09 (zero point zero nine cubic metre).	60.00	Per Cubic metre			

Executive Engineer
Baijnath Division
H.P.P.W.D., Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Link road from Bir Billing to Bangron water fall.
(NH-1/1 C.C. Pavement.)

Estimate Cost: 1,47,557.00/-
Earnest Money: 3,000.00/-
Time Limit: One Month

SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	21.14	Per Cubic metre			
Total						


Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajjnath (H.P.)

DNIT DRAFT SCHEDULE OF QUANTITY

③

Name of work :- C/O road link road from Gunchar to Lahar via Phat.
(NH - P/T Kharnja stone soling at RD 0/380 to 0/580).

Estimate Cost : 1,46,691.00/-
Earnest Money : 3,000.00/-
Time Limit : Two Months

SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P.
				Figures	Words	
1	Providing and laying hard stone Soling properly hand packed intersects with kharanja stone and consolidating with power hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per H.P.W.D specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana tolltax, Sale Tax or other taxes imposed by the government.	81.00	Per Cubic metre			

Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajjnath (H.P.)

DNIT/DRAFT SCHEDULE OF QUANTITY

4

Name of Work : C/O Mahalpatia via Talshan Nohra Road
(SH:-P/L C. C Pavement & W B M G-II at km 1/920 to 1/965)

Estimate Cost: 1,73,571.00/-

Earnest Money: 3,500.00/-

Time Limit :One Month

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
					Words	Rs.	P
1	Providing laying spreading and compacting stone aggregate of size 65mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K N static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the interspaces of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer-in-Charge including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.68	Per Cubic Metre				
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and M.O.R.D. technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	23.39	Per Cubic metre				
Total							


Executive Engineer
Road Division
Talshan Nohra, Baljati

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Link Road from Bani Di Hatti to Dadin (Sh)- Improvement of Road (C/O R/wall) & Providing and Laying C.C Pavement & Kharanja stone Soling at km 1.900 TO 1.945).				Estimate Cost: 3,85,842.00/- Earnest Money: ₹ 800,000/- Time Limit: Two Months		
Sr. No.	Description of work	No. or QTY.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	7.88	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	27.45	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	22.05	Per Cum			
4	Construction of embankment with approved material deposited at site from road way cutting and excavation from drain and foundation or other structures graded and compacted to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5 with in all leads, lifts and other incidental The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	80.50	Per Cum			
5	Providing and laying hard stone Soling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	24.81	Per Cubic metre			

(56)

6	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	24.81	Per Cubic metre				
Total							


 Executive Engineer
 Ballari Division
 Ballari, South


DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Pucca Path ~~1-200m~~ Towards Rajal Village
(SHE:-Providing and laying C. C. Pavement)

Estimate Cost: 78,804.00/-
Earnest Money: 1,600,000/-
Time Limit: One Month

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P.
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (three hundred fifty kilograms) per cubic meter with 20 mm (twenty Millimeters) nominal size graded crushed broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.29	Per Cubic metre			
	Total					


Executive Engineer
Road Division
H.P.W.D., Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

4


Name of work : Development of Ground at Gram Panchayat Kudail (Sh:- C/O Steps in G.S.S School Krishna Nagar)				Estimate Cost: 2,37,271.00 Earnest Money: 6,000.00 Time Limit : One Month		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	44.55	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm (forty millimetre) nominal size) in or under water and curing complete including pumping or hauling out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer-in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	50.50	Per cubic metre			
Total						

Executive Engineer
Division
H.R.M.D., Baljnath

DNIT/DRAFT SCHEDULE OF QUANTITY

8

Name of work: C/O R/wall to Protect the Land & House of Sh. Balbir Singh S/O Shri Tokha Ram V.P.O Chobin (Sh:- C/O R/wall at km 0.00 to 0.007.20).						Estimate Cost: 99,316.00 + Earnest Money: 2,000.00 Time Limit :One Month
Sr. No.	Description of work	No. or QTY.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks) (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	9.79	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth as per drawing and M.O.R.D. technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.86	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.03	Per Cum			
4	Providing weep holes in brick masonry, stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia P.V.C. pipe extending through the full width of the structures with slope of 1(V) 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	5.00	Each			
Total						


 Executive Engineer
 S.D.O. Division
 H.N.P.W.D., Baljath

DRAFT SCHEDULE OF QUANTITY

9

Name of work: C/O link Road from Baijnath LadhBharol Kandapattan to Village Kuni
(Sh:- Improvement of ~~Formation~~ Deficiency of C/O R/wall at Km 0.165 to 0.177).

Estimate Cost: 2,75,597.00/-

Earnest Money: 5,000.00/-

Time Limit: One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks) Where blasting is prohibited for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 505] and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps, and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.24	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800-900 & 1200 for nominal mix 1:4:10 (one cement, five sand, ten graded stone up to 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	49.56	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.24	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment wing wall, return wall with 100mm dia P.V.C. pipe extending through the full width of the structures with slope of 1(V) 20(H) towards drawing face complete as per drawing and technical specification clause 614-709-1204.3.7 including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	24.00	Each			
Total						

Executive Engineer
Project Division
H.P.W.D., Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Link Road from Majhera to Chakol Behru km 0/00 to 1/930
(SH:-Providing and laying C.C Pavement at km 0/543 to 0/628)

Estimate Cost: 2,94,347.00/-
Earnest Money: 5,900.00/-
Time Limit :One Month

SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	42.17	Per Cubic metre			
Total						

Executive Engineer
Division
H.R.P.W.D., Baljnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O Link Road from Marh to Sunchar

(SH:-Providing laying C. C. Pavement & W B M G-II at km 0/110 to 0/190)

Estimate Cost: 2,29,763.00/-

Earnest Money: 4,600.00/-

Time Limit :One Month

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
					Words	Rs.	P
1	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K N static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the interspaces of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	18.90	Per Cubic Metre				
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed broken stone aggregate and curing complete including the cost of form work complete as per drawings and M.O.R.D. technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malsana, tolltax, Sale Tax or other taxes imposed by the government.	25.20	Per Cubic metre				
Total							

Executive Engineer
 Railway Division
 (Mechanical)

SCHEDULE OF QUANTITY

Name of Work: A/R & M/O various residential building of PWD under Baijnath Division Baijnath
(SH: Providing and supplying of form No. 8 and File cover ^{in printed} for various works).

Estimated Cost: Rs. 111500/-

Earnest Money: Rs. 2300/-

Time Limit : One Month

SCHEDULE OF WORKS

S No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P	
				Figure	Words		
1	Providing and supplying of form No. 8 (Eight) comprising 112 (one hundred twelve) pages printed with black ink as per the norms of CPWD manual complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government including GST.	500.00	Each				
2	Supplying for standard size file cover 250 x 350 mm inside plastic coted of supplier best quality. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government including GST.	500.00	Each				

Executive Engineer
Baijnath Division,
H.P.P.W.D. Baijnath (H.P.)

13

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- R/D on Paprola Andretta Road & Majherna Jandpur Nauri Road.
(SH:Scarifying , P.L WMM , Tack Coat , Primer Coat and B.M at Various Reaches)

Estimate Cost: 4,64,683.00
Earnest Money: 9,300.00
Time Limit : Two Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material within all lifts and lead upto 1km (by mechanical means) as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the government.	726.75	Per Square metre			
2	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC (in for all leads & lifts, laying in uniform layers with mechanical paver/finisher in sub-base & base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the government.	70.52	Per Cubic Meter			
3	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface with hydraulic broom and spraying primer at the rate of 0.50 to 1.00 Kg. per Square metres using mechanical means as per MORID technical specification clause 502, and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the government.	910.25	Per Square metre			
4	Providing, laying Bituminous macadam with hot mix plant using crushed aggregates of grading as per table 500.4 premixed with bituminous binder transported to site upto lead of 1000 m laid over a previously prepared surface with paver finisher to required grade level and alignment and rolled to achieve the desired compaction as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the government.	25.74	Per Cubic Meter			
Total						

Executive Engineer
Division
[Signature]

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work : Balance work for CHC at Chadhiar in Tehsil Baijnath
(SHE: Steel work for roofing and ceiling etc)

Estimate Cost: 2,10,665.00

Earnest Money: 4,300.00

Time Limit : One Month

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Rates		AMOUNT Rs. P
				Figures	Words	
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing, brackets and similar works including Carriage of Material within all lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1740.48	Per Kilogram			
2	Providing and fixing on wall face PVC (D-plast) rain water pipes of working pressure not less than 4.5 kg (four decimal five kilogram) per square meter including filling the joints with approved adhesive complete 110 mm (one hundred ten milimeter) dia. including curring and carriage of material within all leads and lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	40.00	Per running metre			
3	Providing and fixing PVC Shoe 110 mm (one hundred ten milimeter) dia and carriage of material within all leads and lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.00	Per running metre			
4	Providing and fixing PVC Clamp 110 (one hundred ten milimeter) dia and carriage of material within all leads and lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	24.00	Per running metre			
5	Providing and fixing PVC Bend 110 (one hundred ten milimeter) dia and carriage of material within all leads and lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.00	Per running metre			

Executive Engineer
Baijnath Division,
H.P.W.D. Baijnath (H.P.)