




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

**CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
1343-1392 DATED 10-06-2024 ARE URGENT NATURE
AND PUBLIC INTEREST.**


**Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.**



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **27.06.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **26.06.2024** between **2.00 PM** up to **4.30 P.M** and the application for issue of tender forms shall be received on **25.06.2024** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	R/O Jeepable road bridge Near the house of Dhilip Singh work No.2 (SH: C/O Gablin wall at RD 0/050 to 0/054, 0/051.6 to 0/054 & 0/055 to 0/059.6)	Rs.1,10,346/-	Rs.2,300/-	Rs.350/-	Two Months
2	C/O Approach Road Govt. Ayurvedic Hospital Paprola (Deposit work) (SH: C/O Grating above U-shape and V-Shape Drain at RD 0/05.35 to 0/070)	Rs.97,327/-	Rs.2,000/-	Rs.350/-	One Month
3	A/R & M/O various roads under Baijnath sub-division HPPWD Baijnath (Chobin Section) (SH: Supplying and stacking of Grit & Sand	Rs.1,53,022/-	Rs.3,100/-	Rs.350/-	One Month
4	C/O link road from Chadhiar to Saklani Basti (SH: C/O C.C. Pavement at RD 0/445 to 0/584)	Rs.4,96,402/-	Rs.10,000/-	Rs.350/-	One Month
5	A/R & M/O Various road under Baijnath Sub-Division HPPWD Baijnath (SH: Supply and Stacking of hard fuel wood for patch work)	Rs.1,37,700/-	Rs.3,000/-	Rs.350/-	One Month
6	R/D on Link Road from Holta to Chadhiar 56/00 to 75/00 (SH: C/O B/wall at km 60/070 to 60/080)	Rs.2,02,350/-	Rs.4,100/-	Rs.350/-	Two Months
7	Completion of Under construction road Village Nanward GP Chadhiar 0/00 to 0/400 (SH: Cutting in Earth Work at RD 0/050 to 0/082 & Providing and laying C.C Pavement & Kharanja Soling at km 0/050 to 0/114)	Rs.1,94,730/-	Rs.3,900/-	Rs.350/-	Two Months

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.

11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Bajnath Division.,
H.P.PWD..Bajnath.

For & On behalf of the governor of H.P.

Dated:- 10.06.2024

NO:-PWD/BD/TA/NIT/2023-24/- 1343-1392

- 1 Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Bajnath Division.,
H.P.PWD..Bajnath.

D.N.I.T/ SCHEDULE OF QUANTITY

Name of work :- R/O Jeepable road bridge Near the house of Dhillip Singh Word No 2.

(Sh:- C/O Gablin Wall at RD 0/050 to 0/054, 0/051.6 to 0/054 & 0/055 to 0/059.6). (D-~~prant~~ Wale)

Estimated Cost 110346.00

Earnest Money 2300.00

Time limit Two Months

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m. (fifty meter) dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the entire satisfaction and direction of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	39.42	Per Cum			
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milli meter) dia GI wire confirming to IS 280 and IS 4826 in 100mm x 100 mm (Hundred milli meter into Hundred milli meter) mesh (woven diagonally) including 10 per (ten) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilo gram) each as per drawing and technical specifications clause 1301 Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	35.00	Per Cum			

Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajjnath (H.P.)

(2)

DNII/DRAFT SCHEDULE OF QUANTITY

Name of work : C/O Approach Road Govt . Ayurvedic Hospital Paprola (Deposit work)
 (SI:- C/O Grating above U shape and V shape Drain at RD 0/05.35 to 0/070.)

Estimate Cost: 97,327.00
 Earnest Money: 2,000.00
 Time Limit : One Month


SCHEDULE OF WORKS						
Sl. No.	Description of work	No.or Qty.	Unit	Rates		AMOUNT Rs. P
				Figures	Words	
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in gratings framed guard bars, ladders, railing, brackets and similar works including Carriage of Material with in all lifts and other incidental and as per entire Satisfaction of Engineer in Charge	3.70	Qtl.			
2	Supplying and Fixing expended metal to wood or steel members in partitions etc weight exceeding 3 (Three) kg and not exceeding 5 (Five) kg per Sqm including Carriage of Material with in all lifts and other incidental and as per entire Satisfaction of Engineer in Charge	60.00	Sqm			
3	Painting two coats (excluding priming cost on new steel and other metal surfaces with enamel paint brushin to give an even shade including cleaning the surface of all dirt, dust and other foreign matters Enamel paint other than white including Carriage of Material with in all lifts and other incidental and as per entire Satisfaction of Engineer in Charge	42.67	Sqm			


 Executive Engineer
 Bajinath Division
 H.P.P.W.D. Bajinath

2

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- A/R & M/O various roads Under Baijnath Sub Division HPPWD Baijnath (Chobin Section) (SH: Supplying and stacking of Grit & Sand)				Estimate Cost: 1,53,022.00/- Earnest Money: 3100.00/- Time Limit : One Month		
SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Supply and stacking of fine aggregate sand of size greater than 0.06mm (zero decimal zero six millimeters) and shall consist of clean, hard, durable uncoated dry particles and shall be free from dust, soft or flaky material organic matter or other deleterious substances. The material shall stacked at road side clear of carriage way and shoulders or on even ground as per instruction of Engineer-in-Charge. The aggregate shall pass 1.7mm sieve and retained on 180 micron sieve. The rate includes octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.00	Per Cubic metre			
2	Supply and stacking of crushed stone aggregate 12mm (twelve millimeter) and 10mm (ten millimeter) size consisting of angular, fragements of clean, hard, tough and durable rock. The aggregates shall be free of elongated and flaky pieces, soft and disintegrated stones and vegetable and other deleterious matter. The aggregates shall be stacked in proper stacks of road side clear of carriage way and shoulders or on even ground as per the instruction of Engineer-in-Charge. The proportion of the quantities of the material shall be as under:-a) Stone chippings 12mm (twelve millimeter) size passing 20mm (twenty millimeter) sieve and retained on 10mm (ten millimeter) sieve 0.18 cubic metre, Stone chippings 10mm (ten millimeter) size passing 12.5mm (twelve decimal five millimeters) sieve and retained on 6.30mm (six decimal three millimeters) sieve 0.09 (zero point zero nine cubic metre).	60.00	Per Cubic metre			
3	Supplying and stacking at site broken/crushed stone aggregate from hard stone of approved quarry 40mm (forty millimeter) of disintegrated pieced deleterious and organic matter from the approved quarry in specified stacks as per instruction of Engineer-in-Charge. The aggregates shall be free of elongated and flaky pieces, soft and disintegrated stones and vegetable and other deleterious matter. The aggregates shall be stacked in proper stacks of road side clear of carriage way and shoulders or on even ground as per the instruction of Engineer-in-Charge.	12.00	Per Cubic metre			


 Engineer
 Baijnath Division
 H.P.W.D. Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O kink road From Chadhiar to Saklani Basti.
(SH:- C/O C.C Pavement at RD 0/445 to 0/584).

Estimate Cost: 4,96,402.00/-
Earnest Money: ~~2,000.00/-~~ 10,000/-
Time Limit :One Month

SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	68.94	Per Cubic metre			
Total						

Executive Engineer
Road Division
W.D., Bijnor


5

DNIT /Schedule of Quantity

Name of Work: A/R & M/O various road under Baijnath Sub-Division HPPWD Baijnath.
Sub Head: - Supply and Stacking of hard fuel wood for patch work

Estimated Cost: Rs.137700/-
Earnest Money: Rs.3000/-
Time Limit: One Month

Sr. No.	Description of items.	Qty	Rate	Rate (In figures)	Unit	Amount
1	Supplying and stacking of dry hard fuel wood at site of work as per PWD Specification and direction of Engineer-In-Charge including carriage of material within all lead lifts complete in all respect.	300.00			Per Qtl	
	Total:-					



Executive Engineer
Baijnath Division
H.P.P.W.D. Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: R/D on Link Road from Holta to Chadhiar 56/00 to 75/00.
(Sh:- C/O B/wall at km 60/070 to 60/080).

Estimate Cost: 2,02,350.00 -
Earnest Money: 4,100.00 -
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M O R D technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	3.20	Per Cum				
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	18.16	Per Cum				
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana tolltax, or other taxes imposed by the government	16.00	Each				
	Total						


Executive Engineer
Baijnath Division
H.P.P.W.D. Baijnath

DNIT DRAFT SCHEDULE OF QUANTITY

Name of work : Completion of Underconstruction road Village Nanward G.P. Chhadhar 0+00 to 0+400

(NH-4 cutting in Earth Work at RD 0+050 to 0+082 & Providing and laying C.C. Pavement & Kharnja Soling at km 0+050 to 0+114)


Estimate Cost : 1,84,750.00/-

Earnest Money : 3,900.00/-

Time Limit : Two Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P.
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling, carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	22.40	Per cubic metre			
2	Providing and laying hard stone Soling properly hand packed intersects with kharnja stone and consolidating with power hand roller to requested gradient and camber including spreading watering and rolling of binding motrum or earth etc. complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	29.28	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	19.82	Per cubic metre			
Total						


 Executive Engineer
 Bajjnath Division
 H.P.P.W.D. Bhatnagar