

Himachal Pradesh
Public works Department

Notice inviting Tender

Sealed item rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD. Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **20-06-2024 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on **19-06-2024**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 18-06-2024**

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	A/R & M/O Jachh Lot road km 0/00 to 6/390 (Providing G-III and patch work at RD 5/00 to 6/00)	4,83,355	10000	Two Months
2	Construction of Kalouti mod to Kalouti village km 0/00 to 1/500 (SH; P/L G-I, G-II, Primer coat, Tack coat seal coat and premix carpet at RD 0/00 to 0/120)	329438	7000	Two Months
3	A/R & M/O Shimla Mandi via Tattapani road km 145/00 to 172/400 (SH: Repair of pot holes between km 152/00 to 155/00)	491175	10000	Two Months
4	A/R & M/O Shimla Mandi via Tattapani road km 145/00 to 172/400 (SH: Repair of pot holes between km 155/00 to 158/00)	486117	10000	Two Months
5	Construction of Gani Bhumi road km 0/00 to 7/500 (SH: C/o Dry stone masonry retaining wall at RD 2/625 to 2/640)	155266	3500	Two Months
6	Restoration of rain damages on Gohar to Neori road km 0/00 to 5/00 (SH: C/O PCC B/wall at RD 4/355 to 4/373 and 4/410 to 4/425)	499296	10000	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the rates of all the items in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. The contractor can apply only for one work at a time.
8. Conditional and incomplete tenders shall be rejected
9. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.


No. PW-GHR-Tender/NIT/2023

1060-76

Dated 10-06-2024

Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1stCircle, HP.PWD Mandi.
4. **The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.**
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
8. Various contractors.
9. Notice Board/DB/AB.


Executive Engineer,
Gohar Division (B&R),
HPPWD, Gohar.

SCHEDULE OF QUANTITY

①

Estimate Cost: Rs.4,83,355/- only

Earnest Money: Rs 10,000/- only

Time : Two month

Name of Work :- A/R & M/O Jachh lot road KM 0/000 to 6/390 (SH:-Providing G-III and patch work at Rd 5/00 to 6/00)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (By manual . means) including all leads , lifts of material and other incidentals as per direction of Engineer -in -Charge complete in all respect.	11.43			per Cubic metre	-
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by Lying tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads , lifts of material and other incidentals.as per direction of Engineer -in -Charge complete in all respect.	1171.11			Per square metre	-
					Total	-


 Executive Engineer
 B & R Division
 H.P.P.W.D Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs.3,29,438/- only


Earnest Money: Rs 7,000/- only

Time : Two month

Name of Work :- Constructtion of Kalouti mod to Kalouti Village KM 0/000 to 1/500 (SH:-Providing and Laying G-I,G-II, Primer coat, Tack coat Seal coat and permix carpet at Rd 0/00 to 0/120)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 405. (By manual . means) including all leads , lifts of material and other incidentals as per direction of Engineer -in -Charge complete in all respect.	41.58			per Cubic metre	-
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405. including all leads , lifts of material and other incidentals as per direction of Engineer -in -Charge complete in all respect.	30.24			per Cubic metre	-
3	Applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using manual mean as per Technical Specification Clause 502 as per direction and entire satisfaction of Engineer -in- Charge with in all leads .lifts and carriage of materials and other incidentals	384.30			Per square metre	-
4	Providing and applying tack coat with bitumen (VG-10) using bitumen distributor at the of 0.30 kg to 0.40 kg per square meter on the prepared dry and hungry bituminous surface cleaned with hydraulic broom as per technical specification clause 503 as per direction and entire satisfaction of Engineer -in- Charge with in all leads .lifts and carriage of materials and other incidentals .	384.30			Per square metre	-

	Providing , laying and rolling of open graded premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm to 5.6mm aggregates either using penetration grade bitumen or emulsion to required line , grade and level to serve as wearing course on a previously prepared base , including mixing in a suitable plant, laying and rolling with three wheel 80-100 KN static roller capacity finished to required level and grades to be followed by seal coat of either Type B as per Technical Specification Clause 508 (Manual Mean)Bitumen (S-90/ VG-10) as per direction and entire satisfaction of Engineer -in- Charge with in all leads .lifts and carriage of materials and other incidentals .	384.30			Per square metre	-
6	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type B as per Technical Specification Clause 510 in all respect as per direction and entire satisfaction of Engineer -in Charge with in all leads .lifts and carriage of materials and other incidentals .	384.30			Per square metre	-
					Total	-


 Executive Engineer
 B & R Division
 H.P.P.W.D Gohar

SCHEDULE OF QUANTITY

Name of Work :-A/R & M/O Shimla Mandi via Tattapani road Km 145/00 to 172/400 (SH:- Repair of Pot Holes between Km 152/000 to 155/000)

Estimate Cost: Rs 4,91,175/- only

Earnest Money: Rs 10,000- only

Time :- Two Months

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Laying bituminous macadam with hot mix plant using crushed aggregates of grading as per Table 500.4 premixed with bituminous binder, transported to site upto a lead of 1000 m laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification Clause 504.as per direction and entire satisfaction of Engineer -in- Charge with in all leads .lifts and carriage of materials and other incidentals .	48.55			per Cubic metre	-
					Total	-

Executive Engineer
B & R Division
H.P.P.W.D Gohar

(4)

SCHEDULE OF QUANTITY

Estimate Cost: Rs 4,86,117/- only

Earnest Money: Rs 10,000- only

Time :- Two Months

Name of Work :-A/R & M/O Shimla Mandi via Tattapani road Km 145/00 to 172/400 (SH:- Repair of Pot Holes between Km 155/000 to 158/000)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Laying bituminous macadam with hot mix plant using crushed aggregates of grading as per Table 500.4 premixed with bituminous binder, transported to site upto a lead of 1000 m laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification Clause 504.as per direction and entire satisfaction of Engineer -in- Charge with in all leads .lifts and carriage of materials and other incidentals .	48.05			per Cubic metre	-
					Total	-


 Executive Engineer
 B & R Division
 H.P.P.W.D Gohar

(5) (7)

SCHEDULE OF QUANTITY


Estimate Cost: Rs 1,55,266/- only

Earnest Money: Rs 3500- only

Time :- Two Months

Name of Work :- Construction of Gani Bhurani road km 0/00 to 7/500 (SH:- Construction of Dry stone Masonary Retaining Wall at RD 2/625 to 2/640) *Under OT MHP*

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths as per direction of Engineer -in -Charge complete in all respect.	8.29			per Cubic metre	-
2	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	42.75			per Cubic metre	-
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge complete in all respect.	4.76			per Cubic metre	-
					Total	-



 Executive Engineer
 B & R Division
 H.P.P.W.D Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs 4,99,296/- only
 Earnest Money: Rs 10,000- only
 Time :- Two Months

Name of Work :- Restoration of rain damages on Gohar to Neori road KM 0/00 to 5/000 (SH:- Construction of PCC B/Wall at RD 4/355 to 4/373 and 4/410 to 4/425)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths per direction of Engineer -in -Charge complete in all respect.	37.46			per Cubic metre	-
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	100.65			per Cubic metre	-
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	12.00			Each	-
					Total	-


 Executive Engineer
 B & R Division
 H.P.P.W.D Gohar