

**Himachal Pradesh
Public works Department**

Notice inviting Tender

Sealed item rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD: Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **26-06-2024 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on **25-06-2024**. The applications for issue of tender forms will be received up to **2.00 P.M. on 24-06-2024**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	Construction of link road from Naitla, Brikhmani to Khohar Harizan basti Tathyar village sarkwahan kaflon and Dhanwas KM. 0/00 to 3/00 (SH:- Construction of PCC R/Wall at RD 1/110 to 1/116) Under SCSP	177732	4000	Two Months
2	Construction of link road from Naitla, Brikhmani to Khohar Harizan basti Tathyar village sarkwahan kaflon and Dhanwas KM. 0/00 to 3/00 (SH:- Construction of PCC R/Wall at RD 1/870 to 1/878) Under SCSP	236949	4800	Two Months
3	Construction of open GYM at Mahadev Tehsil Sundernagar Distt. Mandi H.P (SH:- Construction of Steel railing and gate etc.) Balance work	78051	1600	Two Months
4	Construction of open GYM at Chail Chowk (SH:- Construction of Steel railing boundary wall for GYM at Chailchowk	68147	1500	Two Months
5	RRD on Shimla Mandi via tattapani road km. 115/00 to 135/00 (SH:- C/o B/Wall at RD. 119/525 to 119/542).	147873	3000	Two Months
6	Construction of Jail Pul Saryach road KM 0/00 to 5/700 SH:- Providing and laying CC Pavement at KM 0/355 to 0/500) Under OTMNP	380078	8000	Two Months
7	Construction of Jail Pul Saryach road KM 0/00 to 5/700 SH:- Providing and laying CC Pavement at KM 0/200 to 0/355) Under OTMNP	406233	8200	Two Months
8	Construction of Chugan to Satkhan road km 0/00 to 1/500 (SH:- Construction of V-Shape drain at RD 0/00 to 1/00) Under OTMNP	481920	10000	Two Months
9	Construction of Chugan to Satkhan road km 0/00 to 1/500 (SH:- Providing and Laying G-III, Primer coat, Tack coat, Seal coat and premix carpet at RD 1/00 to 1/200) Under OTMNP	367043	7500	Two Months
10	Construction of Sianj Saroya via Jhaploh Katwandhi batoli road KM 0/0 to 3/00 (SH:- Providing and Laying CC Pavement 1:2:4 at KM 0/500 to 0/630) Under SCDP	329766	6600	Two Months
11	Construction of Sianj Ropa Nandi road KM 0/00 to 1/390 (SH:- Balance work of 10 mtr span RCC Slab Culvert at RD 1/840)	99704	2000	Three Months
12	A/R & M/O Badhu Shilanu Nachet road KM 0/00 to 5/100 (SH:- Repair of Pot Holes between KM 2/500 to 5/100)	497449	10000	Two Months
13	A/R & M/O Badhu Shilanu Nachet road KM 0/00 to 5/100 (SH:- Repair of Pot Holes between KM 0/00 to 2/500	498124	10000	Two Months
14	Balance work of 10 mtr span RCC Culvert on Sianj Ropa Nandi road KM 0/00 to 1/390 (SH:- Balance work of 10 mtr span RCC Slab Culvert at RD 1/840)	99929	2000	Three Months

15	A/R & M/O Shimla mandi via Tattapani road KM 146/00 to 171/400 (SH:- Repair of Pot Holes between KM 164/00 to 171/00)	498584	10000	Two Months
16	A/R & M/O Bhagwanpur Katlog road KM 0/00 to 3/300 (SH:- Repair of Pot Holes between KM 0/00 to 3/300)	493916	10000	Two Months
17	C/o Bassa Delag Tikkri road KM0/0 to 3/520 from Delag side (SH:- Improvement of Turning Point at RD 3/470 to 3/510 and protection wall to protect the Shiv Mandir at RD 3/480 to 3/505) Under SCDP	475896	9600	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form
2. The Contractors should quote the rates of all the items in the tenders both in figures and words
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10 -2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13 03 2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10 05 2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. The contractor can apply only for one work at a time.
8. Conditional and incomplete tenders shall be rejected.
9. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.

No. PW-GHR-Tender/NIT/2024 1191-1220
Copy along with Tender inviting Notice forwarded for information:-

Dated 14-06-2024

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1stCircle, HP.PWD Mandi.
4. The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
8. Various contractors.
9. Notice Board/DB/AB.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.

SCHEDULE OF QUANTITY

Estimate Cost: Rs 1,77,732/- only

Earnest Money: Rs 4000/- only

Time :- Two Months

Name of Work :- Construction of link road from Naitla, Brikhmani to Khohar harizan basti Tathyar village Sarkwahan Kafion and Dhanwas Km. 0/00 to 3/00 (SH:- Construction of PCC R/Wall at RD 1/110 to 1/116) Under SCSP

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths as per direction of Engineer -in -Charge complete in all respect.	6.30 cum			per Cubic metre	-
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge complete in all respect.	35.10 cum			per Cubic metre	-
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	2.66 cum			per Cubic metre	-
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	10.00 Nos			Each	-
					Total	-


Executive Engineer
Gohar Division (B&R)
HP.PWD. Gohar

23

SCHEDULE OF QUANTITY


Estimate Cost: Rs 2,36,949/- only

Earnest Money: Rs 4800/- only

Time :- Two Months

Name of Work :- Construction of link road from Naitla, Brihmani to Khohar harizan basti Tathyar village Sarkwahan Kafion and Dhanwas Km. 0/00 to 3/00 (SH:- Construction of PCC R/Wall at RD 1/870 to 1/878) Under SCSP

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths per direction of Engineer -in -Charge complete in all respect.	9.00 cum			per Cubic metre	-
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	46.80 cum			per Cubic metre	-
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	3.48 cum			per Cubic metre	-
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	13.00 Nos			Each	-


Executive Engineer
Gohar Division (B&R)
HP.PWD. Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs 78,051/- only

Earnest Money: Rs 1600 only

Time :- Two Months

Name of Work :- Construction of open GYM at Mahadev Tehsil Sundernagar Distt. Mandi H.P (SH:- Construction of Steel railing and gate etc.) Balance work

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths per direction of Engineer -in -Charge complete in all respect.	1.91			per Cubic metre	-
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803,1202 & 1203 P.C.C. grade M 20 (twenty millimre) Nominal mix 1:2:4 (one cement : two sand : four graded crashed stone aggregate) within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer - in - charge .	1.91			Per Cubic Metre	-
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including making necessary connections with rain water pipes complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	622.07			per Kilogram	-
					Total	-


Executive Engineer
 Gohar Division (B&R)
 HP.PWD. Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs 68,147/- only

Earnest Money: Rs 1500 only

Time :- Two Months

Name of Work :- Construction of open GYM at Chail Chowk (SH:- Construction of Steel railing Boundary wall for GYM at Chailchowk)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths as per direction of Engineer -in -Charge complete in all respect.	1.28			per Cubic metre	-
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade M 20 (twenty millimetre) Nominal mix 1:2:4 (one cement : two sand : four graded crashed stone aggregate) within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer - in - charge .	1.28			Per Cubic Metre	-
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including making necessary connections with rain water pipes complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	564.31			per Kilogram	-
					Total	-


Executive Engineer
Gohar Division (B&R)
HP.PWD. Gohar

DRAFT SCHEDULE OF QUANTITY

Estimate Cost: Rs 1,47,873.00 Only

Earnest Money: 3,000.00 Only

Time :- Two Months

Name of Work :- RRD on Shimla Mandi via Tattapani road km. 115/00 to 135/00 (SH:- C/o B/wall at RD. 119/525 to 119/542) .

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	In Word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead, lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads, lifts and carriage of materials and other incidentals.	14.96 cum			per Cubic metre	
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregate and curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads, lifts and carriage of materials and other incidentals.	28.90 cum			per Cubic metre	
3	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	15.00 Each			Each	
					Total	

Executive Engineer
Gohar Division (B&R)
HPPWD Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs.3,80,078/- only

Earnest Money: Rs 8000/- only

Time :- Two month

Name of Work :- Construction of Jail Pul Saryach road KM 0/00 to 5/700 (SH:- Providing and laying CC Pavement at KM 0/355 to 0/500) Under OTMNP

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing and laying concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203 PCC 1:2:4 (1 Cement : 2 coarse sand) : 8 graded stone aggregate 20 mm nominal size) with in all leads .lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	59.00			Per Cubic Metre	-
					Total	-


Executive Engineer
 Gohar Division (B&R)
 HP.PWD. Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs.4,06,233/- only

Earnest Money: Rs 8200/- only

Time :- Two month

Name of Work :- Construction of Jail Pul Saryach road KM 0/00 to 5/700 (SH:- Providing and laying CC Pavement at KM 0/200 to 0/355) Under OTMNP

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing and laying concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203 PCC 1:2:4 (1 Cement : 2 coarse sand) : 8 graded stone aggregate 20 mm nominal size) with in all leads .lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	63.06			Per Cubic Metre	-
					Total	-


Executive Engineer
Gohar Division (B&R)
HP.PWD, Gohar

22

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 4,81,920/- only

Earnest Money: Rs 10,000/- only

Time : Two month

Name of Work :- Construction of Chugan to Satkhan road km 0/000 to 1/500 (SH:- Construction of V-Shape drain at RD 0/00 to 1/00) Under OTMNP

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per direction of Engineer -in -Charge complete in all respect.	80.00			per Cubic metre	-
2	Providing concrete for plain/reinforced concrete in open foundations 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) mechanically mixed and vibrated and curing complete including cost of formwork complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of material within all leads, lifts and other incidental charges.	77.00			per Cubic metre	-
					Total	-


 Executive Engineer
 Gohar Division (B&R)
 HP.PWD. Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs.3,67,043/- only

Earnest Money: Rs 7500/- only

Time : Two month

Name of Work :- Construction of Chugan to Satkhan road KM 0/000 to 1/500 (SH:-Providing and Laying G-III, Primer coat, Tack coat, Seal coat and permix carpet at Rd 1/00 to 1/200) Under OTMNP

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (By manual . means) including all leads , lifts of material and other incidentals as per direction of Engineer –in –Charge complete in all respect.	48.83			per Cubic metre	0.00
2	Applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using manual mean as per Technical Specification Clause 502 as per direction and entire satisfaction of Engineer –in- Charge with in all leads .lifts and carriage of materials and other	640.50			Per square metre	0.00
3	Providing and applying tack coat with bitumen (VG-10) using bitumen distributor at the of 0.30 kg to 0.40 kg per square meter on the prepared dry and hungry bituminous surface cleaned with hydraulic broom as per technical specification clause 503 as per direction and entire satisfaction of Engineer –in- Charge with in all leads .lifts and carriage of materials and other incidentals .	640.50			Per square metre	0.00
4	Providing , laying and rolling of open graded premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm to 5.6mm aggregates either using penetration grade bitumen or emulsion to required line , grade and level to serve as wearing course on a previously prepared base , including mixing in a suitable plant, laying and rolling with three wheel 80-100 KN static roller capacity finished to required level and grades to be followed by seal coat of either Type B as per Technical Specification Clause 508 (Manual Mean)Bitumen (S-90/ VG-10) as per direction and entire satisfaction of Engineer –in- Charge with in all leads .lifts and carriage of materials and other incidentals .	640.50			Per square metre	0.00

Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type B as per Technical Specification Clause 510 in all respect as per direction and entire satisfaction of Engineer -in Charge with in all leads .lifts and carriage of materials and other incidentals .	640.50					Per square metre	0.00
						Total	-


Executive Engineer
 Gohar Division (B&R)
 HP.PWD. Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs.3,29,766/- only

Earnest Money: Rs 6600/- only

Time :- Two month

Name of Work :- Construction of Sianj Saroya via Jhaploh Katwandhi Batoli road KM 0/00 to 3/00 (SH:- Providing and laying CC Pavement 1:2:4 at KM 0/500 to 0/630) Under SCDP

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing and laying concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203 PCC 1:2:4 (1 Cement : 2 coarse sand) : 8 graded stone aggregate 20 mm nominal size) with in all leads .lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	51.19			Per Cubic Metre	-
					Total	-



Executive Engineer
Gohar Division (B&R)
HP,PWD, Gohar

SCHEDULE OF QUANTITY


Estimate Cost: Rs. 99,704/- only

Earnest Money: Rs 2,000 /- only

Time : Three month

Name of Work :- Construction of Sianj Ropa Nandi road KM 0/000 to 1/390 (SH:- Balance work of 10 mtr span RCC Slab Culvert at Rd 1/840)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths per direction of Engineer -in -Charge complete in all respect.	3.85			per Cubic metre	-
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	19.95			per Cubic metre	-
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	2.17			per Cubic metre	-
					Total	-


Executive Engineer
 Gohar Division (B&R)
 HP.PWD, Gohar

SCHEDULE OF QUANTITY


Estimate Cost: Rs 4,97,449/- only

Earnest Money: Rs 10,000- only

Time :- Two Months

Name of Work :-A/R & M/O Badhu Shilanu Nachet road km 0/00 to 5/100 (SH:- Repair of Pot Holes between Km 2/500 to 5/100)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (By manual . means) including all leads , lifts of material and other incidentals as per direction of Engineer –in –Charge complete in all respect.	9.17			per Cubic metre	-
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by Lying tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads , lifts of material and other incidentals.as per direction of Engineer –in –Charge complete in all respect.	1,223.29			per Square metre	-
					Total	-


Executive Engineer
Gohar Division (B&R)
HP.PWD. Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs 4,98,124/- only
Earnest Money: Rs 10,000/- only
Time :- Two Months

Name of Work :-A/R & M/O Badhu Shilanu Nachet road km 0/00 to 5/100 (SH:- Repair of Pot Holes between Km 0/00 to 2/500)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (By manual . means) including all leads , lifts of material and other incidentals as per direction of Engineer –in –Charge complete in all respect.	10.92			per Cubic metre	-
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by Lying tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads , lifts of material and other incidentals.as per direction of Engineer –in –Charge complete in all respect.	1,212.87			per Square metre	-
					Total	-



Executive Engineer
Gohar Division (B&R)
HP.PWD. Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 99,929/- only
Earnest Money: Rs 2,000 /- only
Time : Three month

Name of Work :- Balance work of 10 mtr span RCC Slab Culvert on Sianj Ropa Nandi road KM 0/000 to 1/390 (SH:- Balance work of 10 mtr span RCC Slab Culvert at Rd 1/840)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	13.04			per Cubic metre	-
2	Filling in foundation trenches as per drawing and technical specification Clause 305.3.9 Earth filling (For marshy soil) including all leads , lifts of material and other incidentals as per direction of Engineer -in -Charge complete in all respect.	340.20			per Cubic metre	-
					Total	-


Executive Engineer
Gohar Division (B&R)
HP.PWD, Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs 4,98,584- only

Earnest Money: Rs 10,000- only

Time :- Two Months

Name of Work :-A/R & M/O Shimla Mandi via Tattapani road km 146/00 to 171/400 (SH:- Repair of Pot Holes between Km 164/00 to 171/00)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (By manual . means) including all leads , lifts of material and other incidentals as per direction of Engineer -in -Charge complete in all respect.	9.19			per Cubic metre	-
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by Lying tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads , lifts of material and other incidentals.as per direction of Engineer -in -Charge complete in all respect.	1,226.09			per Square metre	-
					Total	-


Executive Engineer
 Gohar Division (B&R)
 HP.PWD. Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs 4,93,916- only

Earnest Money: Rs 10,000- only

Time :- Two Months

Name of Work :-A/R & M/O Bhagwanpur Katlog road km 0/00 to 3/300 (SH:- Repair of Pot Holes between Km 0/00 to 3/300)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (By manual . means) including all leads , lifts of material and other incidentals as per direction of Engineer -in -Charge complete in all respect.	13.33			per Cubic metre	-
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by Lying tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads , lifts of material and other incidentals.as per direction of Engineer -in -Charge complete in all respect.	1,185.22			per Square metre	-
					Total	-


Executive Engineer
 Gohar Division (B&R)
 HP.PWD. Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs 4,75,896/- only

Earnest Money: Rs 9600- only

Time :- Two Months

Name of Work :-Construction of Bassa Delag Tikkari road KM 0/00 to 3/520 from Delag side (SH:- Improvement of Turning point at RD 3/470 to 3/510 and protection wall to protect the shiv Mandir at RD 3/480 to 3/505)Under SCDP

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer -in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries , materials , tools equipment's and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 26.75cubic metre @ Rs. 300.00 per cubic metre amount Rs.8,025/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leads and lifts and materials and as per direction of Engineer in charge .	668.79			per cubic metre	-
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (i) Upto 3 m depths as per direction of Engineer -in -Charge complete in all respect.	12.69			per Cubic metre	-

Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40 mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	73.13				per Cubic metre	-
					Total	0.00


 Executive Engineer
 B & R Division
 H.P.P.W.D Gohar