



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 04-07-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 03-07-2024 up to 10:00 A.M. to 12:30 P.M. and tender form can be had from this office on 03-07-2024 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R. of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	A/R & M/O various road under Joginder Nagar Sub Division, HP PWD, Joginder Nagar (Ladruhin Section) (SH:- Hiring of tractor with trolley for carriage/ shifting of various type of patch work materials etc).	Rs. 98,800/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months
2	Construction of link road from Panjalatar Nallahto Magharoo link road km. 0/00 to 0/370 (Makreri section) (SH:- Hiring of Tipper for shifting and carriage of land slide materials and other various type of materials etc).	Rs. 99,000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months
3	A/R & M/O various road under Joginder Nagar Sub Division, HP PWD, Joginder Nagar (SH:- Supplying and stacking wearing G-II 63mm to 45mm size in various roads (under Ladruhin section).	Rs. 98000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month
4	A/R & M/O various roads under Joginder Nagar Division, Sub Division Joginder Nagar (SH:- Supplying and stacking of crushed/ broken stone aggregate 53mm to 22.4mm size at various reaches in Local Section).	Rs. 99000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
5	Restoration of Baijnath Lad Bharoi Kandapattan road km. 0/0 to 46/0 (SH:- Improvement of sharp curve in km. 35/120 to 36/160).	Rs. 99,999/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months
6	Restoration of Baijnath Lad Bharoi Kandapattan road km. 0/00 to 46/00 (SH:- Improvement of sharp curve in km. 35/150 to 35/240).	Rs. 99,999/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/Firm shall have his registration and GST No. the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar,
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-UNIT/Press/2023-24- 3855-3904

Dated:- 21/06/2024

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar

Schedule of Quantity

Name of work:- A/R&M/O various road under Joginder Nagar Sub Division, HPPWD, Joginder Nagar (Ladruhin Section) (SH Hiring of tractor with trolley for carriage/shifting of various type of patch work materials etc.)(Job No.2)

Estimated Cost:- 98800.00

Earnest Money:- 2000.00

Time:- Two months

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Tractor with trolley in working condition per day basis (eight working hour per day) with including Sunday/ Holiday for carriage of patch work materials etc. The operational , maintenance and P.O.L charges and other miscellaneous supply / replacement required for smooth running of vehicle will be borne by the owner of the tractor within all leads and lifts to the entire satisfaction of Engineer-in-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	38.00			Per day	
				Total:-		


 Executive Engineer
 B&R Division ,HP PWD,
 Joginder Nagar

(2)

(17)

Schedule of Quantity

Estimated Cost:- 99000.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- Construction of link road from Panjalatar Nallah to Magharoo link road Km. 0/0 to 0/370 (makreri section)

Sub Head:- Hiring of Tipper for shifting and carriage of land slide materials and other various type of materials etc.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hire charges of tipper for carriage/shifting of soling stone earth, moorum, premix material, seal coat etc. having capacity of 5.50 (five point five zero) cubic metre per trip and covering 70 (seventy) kilometers per day (9AM to 5PM), the contractor/ owner of tipper shall bear the expensive of P.O.L charges, repair of machineries including driver and helper wages. Any accident and other damages to private and Govt property occur during the working hours in the work shall be the responsibility of the contractor and disposal of excavated material/ slips debris with in all leads and lifts as per the direction of Engineer-in-Charge. The rates are inclusive of all taxes including GST levy by the Govt. time to time	22.00			Per day	
				Total:-		


 Executive Engineer,
 B&R Sub Division,
 W&PWD, Jodhpur Nagar

Schedule of Quantity

Estimated Cost:- 98000.00
 Earnest Money:- 2000.00
 Time:- One month

Name of work:-A/R&M/O various roads under Joginder Nagar Division, Sub Division, Joginder Nagar
 (SH:- Supplying and stacking wearing G-II 63mm to 45mm size in various roads under ladruhin section.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of crushed/broken stone aggregate 63mm to 45mm (Sixty three millimeter to forty five millimeter) nominal size at site for wearing free from dirt,dust, disintegrated pieces deleterious and organic matter in proper stacks along road side as per HP PWD specification and as directed by the Engineer-in-Charge within all leads and lifts complete in all respect. The rate is inclusive all taxes including GST levy by the Govt. time to time.	49.00			Per cubic metre	0.00
				Total:-		0.00


 Executive Engineer,
 B&R Division, HPPWD,
 Joginder Nagar

Schedule of Quantity

Estimated Cost:- 99000.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- A/R&M/O various roads under Joginder Nagar Division, Sub Division, Joginder Nagar (Sub Head:- Supplying and stacking of crushed/broken stone aggregate 53mm to 22.4mm size at various reaches in Local Section)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate Grading -III 53mm to 22.4mm/fifty three millimeter to twenty two point four millimeter nominal size at site for wearing free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	49.50			Per cubic meter	
			Total:-			


 Executive Engineer,
 B&R Division HP.PWD,
 Jogginder Nagar

5

SCHEDULE OF QUANTITY

Name of Work: Restoration of Baijnath Lad Bharol Kandapattan Road km 0.00 to 46.00 (SH: Improvement of sharp curve in Km. 36/120 to 36/160)				Estimate Cost: Earnest Money: Time Limit :		99,989.00 2,000.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all loads and lifts in acquired width of the road and transportation of useful material for filling in road ways, culverts, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 50.30 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	370.85	Per cubic metre				
Total							

Executive Engineer

B & R Division HP.PWD.

Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work: Restoration of Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00
(SI: Improvement of sharp curve in Km. 36/160 to 36/240)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :	99,999.00 2,000.00 Two Months
				Figures	Words		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means (including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 50,30 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	370.89	Per cubic metre				
	Total						


Executive Engineer
B & R Division HP.PWD.
Jodhpur Nagar