



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 28-06-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 26-06-2024 up to 10:00 A.M. to 12:30 P.M. and tender form can be had from this office on 27-06-2024 from 2:00 P.M. to 5:00 P.M. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Restoration of Joginder Nagar Sarkaghat Ghumanwin road km. 0/00 to 34/300 (SH:- Construction of Retaining wall in wire Grate at km. 27/555 to 27/570).	Rs.2,59,879/-	Rs.5,200/-	Rs.350/-	Class "D"	Three months
2	Restoration of Rain Damages on Drubbal Banwar road km. 0/00 to 8/600 (SH:- Construction of breast/ protection wall at km. 6/525 to 6/540)	Rs.2,00,830/-	Rs.4,000/-	Rs.350/-	Class "D"	Three months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2023-24-2919-2968

Dated:- 12/06/2024

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (M2), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar

7 SCHEDULE OF QUANTITY

Name of Work : Restoration of Joginder Nagar Sarkaghat Ghumarwin Road km 0/00 to 34/300
(SH: Construction of Retaining wall in wire Crate at km 27/555 to 27/570)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :	2,59,879.00 5,200.00 Three Months
				Figures	Words		
1	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	46.88	Per Cubic metre				
2	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	121.80	Per cubic metre				
Total							


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P.
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plants and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.25	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.00	Each			
	Total					


 B & R Division HP, PWD,
 Jodhpur, Rajasthan