

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(Padhar)E-Tender-NIT/2024-25- 2680-82 Dated:- 15/6/24

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 25.06.2024 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 24.06.2024 upto 1.00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.


Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of Rain damages on Silh Kenchi Nihon road Km 0/0 to 0/900. (SH:- Construction of Retaining wall at R.D. 0/510 to 0/525)	3,01,935.00	6,000/-	350/-	Three months
2	Restoration of rain damages on Urla Kotropi Chukku Khajri Road Km 0/0 to 16/225. (SH:- Construction of Wire Crate Retaining wall at R.D. 13/645 to 13/665)	2,84,171.56	5,700/-	350/-	One month
3	Restoration of rain damages on Shingari Babli Chhahri road Km 0/0 to 5/0 (SH:- Construction of Breast Wall at R.D. 2/885 to 2/900)	3,87,064.79	7,700/-	350/-	One month
4	Restoration of rain damages on Nashadhara Batdhar road Km 0/0 to 10/050. ((SH:- Construction of Retaining wall P.C.C. 1:5:10 at R.D. 9/770 to 9/780)	2,43,210.34	4,900/-	350/-	Three months
5	Restoration of Rain damages on Nagrota Segaldugh road Km 0/00 to 9/090) (SH:- Construction of Retaining wall in wire crate at R.D. 0/035 to 0/045)	2,91,820.54	5,800/-	350/-	One month
6	Restoration of Rain damages on Nagrota Segaldugh road Km 0/00 to 9/090) (SH:- Construction of Retaining wall in wire crate at R.D. 0/045 to 0/055)	3,57,573.76	7,200/-	350/-	One month
7	Restoration of Rain damages on Nagrota Segaldugh road Km 0/00 to 9/090) (SH:- Construction of Retaining wall in wire crate at R.D. 0/055 to 0/065)	3,57,573.76	7,200/-	350/-	One month
8	Restoration of rain damages on Pakhari Galu Bada Gaun road Km 0/0 to 5/800. (SH:- Construction of Breast wall at R.D. 0/795 to 0/808.50)	2,15,893.09	4,300/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh


PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 301935.00
Earnest Money Rs:- 6000.00
Time Three month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP PWD. at Padhar.						
Name of work :- Restoration of Rain damages on Silh Kenchi to Nihon road km. 0/0 to 0/900 (S.H.-C/O Retaining wall at R.D. 0/510 to 0/525).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.60	Per cubic metre	461.00	11341.00	Rupees Eleven Thousand Hundred Forty One Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	54.00	Per cubic metre	5019.80	271069.00	Rupees Two Lakh Seventy One Thousand Sixty Nine Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	283.40	3401.00	Rupees Three Thousand Hundred One Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	11.25	Per cubic metre	1433.20	16124.00	Rupees Sixteen Thousand Hundred Twenty Four Only
Total in figure :					301935.00	Rupees Three Lakh One Thousand Nine Hundred Thirty Five Only
Total in Words :						


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 284171.56
 Earnest Money Rs:- 5700.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain Damages on Urta Kotropi Chukku Khajri Road Km. 0/00 to 16/225. (Sub Head: - Construction of Wire Crate Retaining wall at R.D. 13/645 to 13/665).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	37.80	Per cubic metre	461.00	17426.00	Rupees Seventeen Thousand Four Hundred Twenty Six Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	108.00	Per cubic metre	2326.55	251267.00	Rupees Two Lakh Fifty One Thousand Two Hundred Sixty Seven Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.80	Per cubic metre	1433.20	15478.56	Rupees Fifteen Thousand Four Hundred Seventy Eight and Paise Fifty Six Only
Total in figure :					284171.56	Rupees Two Lakh Eighty Four Thousand One Hundred and Paise Fifty Six Only
Total in Words :					Rupees Two Lakh Eighty Four Thousand One Hundred and Paise Fifty Six Only	

Executive Engineer,
 Mandi Division No. I,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 387064.79
Earnest Money Rs:- 7700.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.						
Name of work :- Restoration of rain damages on Shingari Babli Chhahri road Km. 0/0 to 5/00. (Sub Head:- Construction of Breast wall at R D. 2/885 to 2/900).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
	Excavation in hilly Area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes and disposing of cut materials with a lift upto 1.5mtr. and lead upto 20 m as per technical specification clauses 1603.2 (8.3 (iv) including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	39.15	Per cubic metre	257.50	10081.13	Rupees Ten Thousand Eighty One and Paise Thirteen Only
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.50	Per cubic metre	461.00	4840.50	Rupees Four Thousand Eight Hundred Forty and Paise Fifty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	74.11	Per cubic metre	4912.40	364057.96	Rupees Three Lakh Sixty Four Thousand Fifty Seven and Paise Ninety Six Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	29.00	Each	278.80	8085.20	Rupees Eight Thousand Eighty Five and Paise Twenty Only
Total in figure :					387064.79	Rupees Three Lakh Eighty Seven Thousand Sixty Four and Paise Seventy Nine Only
Total in Words :		Rupees Three Lakh Eighty Seven Thousand Sixty Four and Paise Seventy Nine Only				

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 243210.34
Earnest Money Rs:- 4900 00

Time Three month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.


Name of work :- Restoration of rain damages on Nashadhar Batdhar road km. 0/0 to 10/050(S.H)-Construction of Retaining wall P.C.C. 1:5:10 at R.D. 9770 to 9780).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	19.00	Per cubic metre	491.80	9344.20	Rupees Nine Thousand Three Hundred Forty Four and Paise Twenty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (one cement : six sand : twelve graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	2.92	Per cubic metre	5067.70	14797.68	Rupees Fourteen Thousand Seven Hundred Ninety Seven and Paise Sixty Eight Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	26.73	Per cubic metre	5228.20	139749.79	Rupees One Lakh Thirty Thousand Seven Hundred Forty Nine and Paise Seventy Nine Only
4	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 & 1204 .in cement mortar 1:6 (One : Six)complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.46	Per cubic metre	6110.60	63916.88	Rupees Sixty Three Thousand Nine Hundred Sixteen and Paise Eighty Eight Only
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	19.00	Each	291.30	5534.70	Rupees Five Thousand Five Hundred Thirty Four and Paise Seventy Only
6	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.70	Per cubic metre	1472.70	9867.09	Rupees Nine Thousand Eight Hundred Sixty Seven and Paise Nine Only
Total in figure :					243210.34	Rupees Two Lakh Forty Three Thousand Two Hundred Ten and Paise Thirty Four Only
Total in Words :		Rupees Two Lakh Forty Three Thousand Two Hundred Ten and Paise Thirty Four Only				


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 291820.54
 Earnest Money Rs:- 5800.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.P.W.D. at Padhar.						
Name of work :- Restoration of Rain Damages on Nagrota Segaldugh road km. 0/00 to 9/090. (Sub Head:- Consturction of Retaining wall in wire crate at R.D. 0/035 to 0/045).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	34.40	Per cubic metre	491.80	16917.92	Rupees Sixteen Thousand Nine Hundred Seventeen and Paise Ninety Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	40.20	Per cubic metre	4831.50	194226.30	Rupees One Lakh Ninety Four Thousand Two Hundred Twenty Six and Paise Thirty Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.00	Each	270.80	2708.00	Rupees Two Thousand Seven Hundred Eight Only
4	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	19.58	Per cubic metre	2357.40	46158.00	Rupees Forty Six Thousand One Hundred Fifty Eight Only
5	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	21.60	Per cubic metre	1472.70	31810.32	Rupees Thirty One Thousand Eight Hundred Ten and Paise Thirty Two Only
Total in figure :					291820.54	Rupees Two Lakh Ninety One Thousand Eight Hundred Twenty and Paise Fifty Four Only
Total in Words :		Rupees Two Lakh Ninety One Thousand Eight Hundred Four Only			Twenty and Paise Fifty	


 Executive Engineer
 Mandi Division No 1
 H.P.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 357573.76
 Earnest Money Rs:- 7200.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 H.P.W.D. at Padhar.						
Name of work :- Restoration of Rain Damages on Nagrota Segaldugh road km. 0/00 to 9/090. (Sub Head:- Consturction of Retaining wall in wire crate at R.D. 0/045 to 0/055).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	35.00	Per cubic metre	491.80	17213.00	Rupees Seventeen Thousand Two Hundred Thirteen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	42.00	Per cubic metre	4831.50	202923.00	Rupees Two Lakh Thousand Nine Hundred Twenty Three Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.00	Each	270.80	2708.00	Rupees Two Thousand Seven Hundred Eight Only
4	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	39.16	Per cubic metre	2357.40	92316.00	Rupees Ninety Two Thousand Three Hundred Sixteen Only
5	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	28.80	Per cubic metre	1472.70	42413.76	Rupees Forty Two Thousand Four Hundred Thirteen and Paise Seventy Six Only
Total in figure :					357573.76	Rupees Three Lakh Fifty Seven Thousand Five Hundred Seventy Three and Paise
Total in Words :		Rupees Three Lakh Fifty Seven Thousand Five Hundred Seventy Three and Paise Seventy Six Only				

Executive Engineer
 Mandi Division No 1
 H.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 357573.76
 Earnest Money Rs:- 7200.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP PWD. at Padhar.						
Name of work :- Restoration of Rain Damages on Nagrota Segaldugh road km. 0/00 to 9/090. (Sub Head:- Consturction of Retaining wall in wire crate at R.D. 0/055 to 0/065).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	35.00	Per cubic metre	491.80	17213.00	Rupees Seventeen Thousand Two Hundred Thirteen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	42.00	Per cubic metre	4831.50	202923.00	Rupees Two Lakh Nine Hundred Twenty Three Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.00	Each	270.80	2708.00	Rupees Two Thousand Seven Hundred Eight Only
4	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	39.16	Per cubic metre	2357.40	92316.00	Rupees Ninety Two Thousand Three Hundred Sixteen Only
5	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	28.80	Per cubic metre	1472.70	42413.76	Rupees Forty Two Thousand Four Hundred Thirteen and Paise Seventy Six Only
Total in figure :					357573.76	Rupees Three Lakh Fifty Seven Thousand Five Hundred Seventy Three and Paise Seventy Six Only
Total in Words :		Rupees Three Lakh Fifty Seven Thousand Five Hundred Seventy Six Only				

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 215893.09

Earnest Money Rs:- 4300.00

Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Pakhari Galu Bada Gaun road Km. 0/0 to 5/800. (Sub Head:- Construction of Breast wall at R.D. 0/795 to 0/808.50).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in hilly Area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes and disposing of cut materials with a lift upto 1.5mtr. and lead upto 20 m as per technical specification clauses 1603.2 (8.3.(iv) including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	21.26	Per cubic metre	159.90	3399.47	Rupees Three Thousand Three Hundred Ninety Nine and Paise Forty Seven Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.37	Per cubic metre	491.80	6575.37	Rupees Six Thousand Five Hundred Seventy Five and Paise Thirty Seven Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	43.23	Per cubic metre	4661.50	201516.65	Rupees Two Lakh One Thousand Five Hundred Sixteen and Paise Sixty Five Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	16.00	Each	275.10	4401.60	Rupees Four Thousand One and Paise Sixty Only
Total in figure :					215893.09	Rupees Two Lakh Fifteen Thousand Eight Hundred Ninety Three and Paise Nine Only
Total in Words :		Rupees Two Lakh Fifteen Thousand Eight Hundred Ninety Three and Paise Nine				

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.