

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No:-PW-NCD-E-Tender-NIT/2024-25:- 1327-34

Dated:- 15-06-2024

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject: -

Publishing of tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of H.P. letter No.PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA: - Notice Inviting Tender.
(67 No. Works)


**Executive Engineer
Nerchowk Division
HPPWD Nerchowk**

Copy forwarded to for information:-

Copy forwarded to the Superintending Engineer, 1st Circle, HP.PWD.,
Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.
Copy to Account Branch in this office.
Copy to Drawing Branch in this office.
Notice Board.


**Executive Engineer
Nerchowk Division
HPPWD Nerchowk**

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDER"

Engineer, Nerchowk, H.P.PWD. Nerchowk for the following works from the approved and eligible contractors enlisted in H.P.PWD. so as to reach in this office on or before **27.06.2024 upto 02.30 P.M.** and will be opened on the same day at **3.30 P.M.** in the presence of interested contractors or their authorized representatives who may like to be present. If it happen to be holiday on the tender will be open on next working day. The application for obtaining the tender form will be received up to **11:30 AM on 26.06.2024** and tender form will be issued on dated **27.06.2024 upto 12:30 PM.** The EMD should be attached during the submission of application for obtaining the tender form. The application will not be accepted without Earnest Money & Cost of tender form.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany with each tender. The conditional tender's and the tender's received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for **90 days**. The Executive Engineer reserves the right to reject the tender's without assigning any reason:-

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender From (Rs.)	Time limit	Eligible Class of Contractor
1	Construction of Doppler weather Radar building near Murari Mata Temple. (SH:- Providing and fixing G.I. Chain link fabric fencing).	149581	3000	350	One Month	"D"
2	Construction of Kalkhar Galoo to Naundhar Upper Dibhri, Lower Dibhri Bhout Sidhyani road km 0/0 to 4/600. (SH:- Construction of 900 mm dia RCC hume pipe culvert at RD 3/210 alongwith both side wing walls).	321273	6500	350	Two Months	"D"
3	A/R M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Ratti Section) (SH:- Hiring of JCB clearing of debris drains and dressing of berms etc).	269850	5400	350	Two Months	"D"
4	Restoration of road damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Removal of formation deficiency/ widening of curves in km 13/465 to 13/900).	379673	7600	350	One Month	"D"
5	A/R M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Ratti Section) (SH:- Hiring of JCB clearing of debris drains and dressing of berms etc).	269850	5400	350	Two Months	"D"
6	Restoration of road damages on Pairi Pasta Hawanu Luhardi road km 0/0 to 4/100. (SH:- Construction of Breast wall at RD. 1/165 to 1/185).	236249	4800	350	Two Months	"D"
7	Construction of Primary Health Centre building (with Residence) at Lohara, Tehsil Balh Distt Mandi (H.P.). (SH:- Prepration of working estimate for C/O building portion with W.S. & S.I., Septic Tank, Rain water harvesting system and development of site etc).	49500	1000	350	One Month	"D"
8	A/R M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Hiring of Tipper for carriage of muck & patch work material). (Ratti Section)	122000	2500	350	Two Months	"D"
9	A/R M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Gagal Section) (SH:- Hiring of JCB clearing of debris drains and dressing of berms etc).	269850	5400	350	Two Months	"D"
10	A/R M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Hiring of Tipper for carriage of muck & patch work material). (Ratti Section)	183000	3700	350	Two Months	"D"

11	A/R M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Providing and fixing road stud with lens reflector). (Nerchowk Section).	249780	5000	350	One Month	"D"
12	A/R M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Gagal Section) (SH:- Hiring of JCB clearing of debris drains and dressing of berms etc).	269850	5400	350	Two Months	"D"
13	Restoration of rain damages on Chandigarh Mandi Manali road km 184/600 to 190/00 and 191/190 to 198/050. (SH:- Repair of slab culvert in PCC 1:3:6 at RD 188/333).	312050	6300	350	Two Months	"D"
14	Restoration of road damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Construction of PCC Retaining wall at RD 1/675 to 1/685 & 1/090 to 1/100).	322050	6500	350	Two Months	"D"
15	Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar. (Leda Section) (SH:- Hiring of Tipper for carriage of muck and patch work material). Job No-I.	137250	2800	350	Two Months	"D"
16	Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar. (Leda Section) (SH:- Hiring of Earth cutting/ Excavating machine for removal of slips, clearing of debris and dressing of berms etcetra). Job No-I.	220500	4500	350	One Month	"D"
17	Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar. (Rewalsar Section) (SH:- Hiring of Tipper for carriage of muck and patch work material). Job No-II.	183000	3700	350	Two Months	"D"
18	Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar. (Leda Section) (SH:- Hiring of Earth cutting/ Excavating machine for removal of slips, clearing of debris and dressing of berms etcetra). Job No-II.	220500	4500	350	One Month	"D"
19	Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar. (Rewalsar Section) (SH:- Hiring of Tipper for carriage of muck and patch work material). Job No-II.	183000	3700	350	Two Months	"D"
20	Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar. (Rewalsar Section) (SH:- Hiring of Earth cutting/ Excavating machine for removal of slips, clearing of debris and dressing of berms etcetra). Job No-I.	220500	4500	350	One Month	"D"
21	Restoration of rain damages on various roads under Rewalsar Sub- Division HPPWD Rewalsar. (Leda Section) (SH:- Hiring of Earth cutting/ Excavating machine for removal of slips, clearing of debris, drains and dressing of berms etcetra. (Job No. III)	220500	4500	350	One Month	"D"
22	Restoration of rain damages on various roads under Rewalsar Sub- Division HPPWD Rewalsar. (Sardhwar Section) (SH:- Hiring of Earth cutting/ Excavating machine for removal of slips, clearing of debris, drains and dressing of berms etcetra. (Job No. I)	220500	4500	350	One Month	"D"
23	Restoration of rain damages on various roads under Rewalsar Sub- Division HPPWD Rewalsar. (SH:- Hiring of Hydraulic excavator/ breaker machine for breaking of stone/ boulder). (Leda Section).	74000	1500	350	One Month	"D"

24	Restoration of rain damages on various roads under Rewalsar Sub- Division HPPWD Rewalsar. (Sardhwar Section) (SH:- Hiring of Earth cutting/ Exacavating machine for removal of slips, clearing of debris, drains and dressing of berms etecetra. (Job No. II)	220500	4500	350	One Month	"D"
25	RRD on various roads under Rewalsar Sub Division HPPWD Rewalsar (Leda Section). (SH:- Hiring of Tractor with trolley for carriage of muck/ debris and shifting of material etc).	148500	3000	350	Three Months	"D"
26	Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar. (Sardhwar Section). (SH:- Hiring of Tipper for carriage of muck and patch work matrial). (Job No. I)	137250	2800	350	Two Months	"D"
27	Restoration of rain damages on Manjhyali Samloun via Safru road km 0/000 to 9/945. (SH:- Construction of Retaining wall with Toe wall at RD 6/450 to 6/462).	479667	9600	350	Two Months	"D"
28	R.R. damages various roads under Rewalsar Sub Division. (SH:- Hiring of JCB for removal of slips/ muck/ debris, dressing of berms, clearing unlined drain. Section Rewalsar.	220500	4500	350	One Month	"D"
29	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Providing and Fixing road stud with lens reflector). Nerchowk Section.	249780	5000	350	One Month	"D"
30	Construction of link road from Gas Godawn to Chhukhran GP lower Rewlasar km 0/000 to 2/000. (SH:- Construction of 900 mm dia RCC Hume pipe culvert at RD 0/450 alongwith both side wing walls). Under OTMNP	236266	4700	350	Two Months	"D"
31	RRD on Gutkar Behna Tikkar Malwana Badhyal road km 0/00 to 5/00. (SH:- C/O PCC Retaining wall at RD 1/980 to 1/995).	238952	4800	350	Two Months	"D"
32	A/R & M/O on various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Hiring of Tipper for carriage of muck & Patch work material). (Gagal Section)	274500	5500	350	Three Months	"D"
33	Construction of Kalkhar Galoo to Naundhar Upper Dibhri, Lower Dibhri Bhout Sidhyani road km 0/0 to 5/0. (SH:- Construction of 900 mm dia RCC hume pipe culvert at RD 3/550 alongwith both side wing walls). Under OTMNP	252056	5100	350	Two Months	"D"
34	M/T on village Kummi to Harizan Basti Khandla Rajgarh Gadraur Kummi road km 0/0 to 5/500. (SH:- Providing and laying WBM G-III and Tarring at RD 0/200 to 0/320, 0/600 to 0/730 and 1/650 to 1/760). Under SCDP.	430984	8700	350	Two Months	"D"
35	A/R & M/O on various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Hiring of Tipper for carriage of muck & Patch work material). (Nerchowk Section)	137250	2800	350	Two Months	"D"
36	Construction of Damka Samloun to Pargi Pul road km 0/00 to 2/660. (SH:- Providing and laying stone soling at RD 1/420 to 2/00).	432634	8700	350	Two Months	"D"
37	Providing and Fixing stainless steel gate for existing boundary near Labana Basti village Troh on Ratti Randhara road. (SH:- Providing and Fixing steel Railing & Gate at RD. 3/050). Deposti Work.	47580	1000	350	Two Months	"D"
38	Restoration of road damages caused due to laying of optical cable on Ratti Kalkhar road km 0/00 to 10/00. (SH:- Construction of U-shape drain in km 4/700 to 4/980). (LHS) Deposit Work.	475722	9600	350	One Month	"D"

39	Construction of Stadium Near GPS Arthi GP Mandal, development Block Balh at Nerchowk. (SH:- Construction of Retaining wall and stage).	489134	9800	350	Two Months	"D"
40	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Ratti Section) (SH:- Hiring of JCB clearing of debris drains and dressing of berms etc).	252000	5100	350	One Month	"D"
41	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Gagal Section) (SH:- Hiring of JCB clearing of debris drains and dressing of berms etc).	269850	5400	350	One Month	"D"
42	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Hiring of Tipper for carriage of muck & patch work material). (Nerchowk Section).	183000	3700	350	Two Months	"D"
43	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Nerchowk Section) (SH:- Hiring of JCB clearing of debris drains and dressing of berms etc).	250950	5100	350	Two Months	"D"
44	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Nerchowk Section) (SH:- Hiring of JCB clearing of debris drains and dressing of berms etc).	220500	4500	350	One Month	"D"
45	Improvement of black spot on Ratti Kalkhar road km 0/0 to 10/0. (SH:- Improvement of black spot by widening of curve at RD 4/555 to 4/600 & 5/855 to 5/1050).	292570	5900	350	One Month	"D"
46	A/R & M/O Non-Residential Building at Nerchowk, Tehsil Balh Distt. Mandi HP. (SH:- Preparation of working estimate for C/O building portion 2nd & 3rd floor with WS & SI in Phase-II)	65000	1400	350	One Month	"D"
47	RRD on various roads under Chakkar Sub-Division HPPWD Nerchowk. (SH:- Hiring of JCB for clearing of debris drains and dressing of berms etc). (Gagal Section)	262500	5300	350	Two Months	"D"
48	Restoration of rain damages on Galma Manjhyali road km 0/000 to 9/000. (SH:- Construction of Retaining wall at RD 1/558.50 to 1/568.50 with toe wall).	351909	7100	350	Two Months	"D"
49	Construction of link road from Koop Galoo Thina to DPF Baglu road km 0/000 to 5/000. (SH:- Construction of PCC Retaining wall at RD 2/630 to 2/645). Under OTMNP	326372	6600	350	Two Months	"D"
50	Construction of Kalkhar Galoo to Noundhar upper Dibhri Lower Dibhri Bhaut Sidhyani road km 0/000 to 4/500. (SH:- Providing and laying WBM Grading II in km 0/830 to 1/715). Under OTMNP	498086	10000	350	Two Months	"D"
51	Construction of Kalkhar Galoo to Naundhar upper Dibhri Lower Dibhri Bhaut Sidhyani road km 0/000 to 4/500. (SH:- Providing and laying WBM Grading II in km 1/715 to 2/600). Under OTMNP.	498086	10000	350	Two Months	"D"
52	A/R & M/O Non-Residential Building under Nerchowk Division HPPWD Nerchowk. (SH:- Refilling of fire extinguishers).	99900	2000	350	One Month	"D"
53	A/R & M/O Ratti Kalkhar road km 0/0 to 10/0. (SH:- Cutting of branches, dressing of berms and clearing of drain etc). Ratti Section.	101980	2100	350	One Month	"D"
54	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Gagal Section) (SH:- Hiring of Tractor with trolley for carriage of muck/ debris and shifting of materials etc).	74250	1500	350	Three Months	"D"
55	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Hiring of JCB for clearing of debris, drain and dressing of	262500	5300	350	Two Months	"D"

	berms etc). Nerchowk Section.					
56	Construction of 10.00 mtr span RCC slab culvert over Chandyal to Chhatru via Sihal Trambi road at RD 0/085. (SH:- Construction of wing wall at RD 0/0 to 0/10 U/S Chandyla Side).	489908	9800	350	Two Months	"D"
57	RRD on various roads under Chakkar Sub-Division HPPWD Nerchowk. (SH:- Hiring of JCB for clearing of debris drains and dressing of berms etc). (Ratti Section)	262500	5300	350	Two Months	"D"
58	Construction of 10.00 mtr span RCC slab culvert over Chandyal to Chhatru via Sihal Trambi road at RD 0/085. (SH:- Construction of wing wall at RD 0/0 to 0/14 D/S Chandyla Side).	483918	9700	350	Two Months	"D"
59	RRD on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Construction of wire crate R/wall at RD 0/600 to 0/615).	473860	9500	350	Two Months	"D"
60	Restoration of rain damages on various road under Chakkar Sub Division. (in Nerchowk Section) (SH:- Hiring of Tractor with trolley for carriage of muck/ debris/ stone, boulders ectetra).	74250	1500	350	45 Days	"D"
61	RRD on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Construction of wire crate R/wall at RD 0/615 to 0/630).	474377	9500	350	Two Months	"D"
62	Construction of Devri Ambe ka Ghar to Gajrehra Rathol road km 0/0 to 0/500. (SH:- Construction of PCC pavement at RD 0/060 to 0/140).	317304	6400	350	Two Months	"D"
63	Restoration of rain damages on Leda Ghangnoo road km 0/000 to 12/000. (SH:- Construction of Retaining wall at RD 4/080 to 4/095).	253184	5100	350	Two Months	"D"
64	A/R & M/O Chandigarh Mandi Manali (Old NH-21) road km 184/650 to 198/050. (SH:- Repair of pot holes in km 184/650 to 190/00)	491624	9900	350	One Month	"D"
65	A/R & M/O Mandi Gagal Chailchowk Janjehli Chhatari Nagan road km 0/0 to 16/190. (SH:- Repair of pot holes in km 1/0 to 2/00).	497078	10000	350	One Month	"D"
66	A/R & M/O Chandigarh Mandi Manali (Old NH-21) road km 184/650 to 198/050. (SH:- Repair of pot holes in km 190/00 to 198/050)	490826	9900	350	One Month	"D"
67	A/R & M/O Ratti to Kalkhar road km 0/0 to 10/00. (SH:- Repair of pot holes in km 0/0 to 4/00).	458020	9200	350	One Month	"D"

It is certified that the above tenders are very "urgent nature", so may be uploaded on department website in public interest.

Note:- The Constructors/Firms should possess the following documents (Photo copy to be attached).

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. The list of similar type of work executed and work done performance certificate issued by the concerned Executive Engineer required to be produced by the contractor along with application.
4. **Only two tenders shall be issued to each contractor.**
5. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
6. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
7. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and vide Govt notification No.PBW (B)A(3)1/2020-I dated 10.05.2023 tendered amount below 30% of the estimated cost will be accepted.

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

①

DNIT S.NO. (14) For the year 2024-25

Draft Schedule of Quantity

Estimated Cost:-Rs. 149581.00

Earnest Money:-Rs 3000.00

Time:- One month

Name of work:- Construction of Doppler Weather Radar building near Murari Mata Temple.

Sub Head:- Providing and fixing G.I. Chain link fabric fencing.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 25x25 mm (twenty five into twenty five millimetre) made of G.I. wire of dia 3 mm (three millimetre) including strengthening with 2 mm (two millimetre) dia wire or nuts, bolts and washers as required within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	187.00 Sqm.	799.90	Rupees seven hundred ninety nine and paise ninety only	Per Square metre	149581.00
				Total:-		149581.00

Draft schedule of quantity checked and approved for Rs. 149581/- (Rupees one lac forty nine thousand five hundred eighty one) only.

Executive Engineer,
Nerchowk Division,
HP. PWD, Nerchowk

②

DNIT S.NO. ④ for the year 2024-25

Draft Schedule of Quantity

Estimated Cost:- Rs. 321273.00

Earnest Money:- Rs. 6500.00

Time:- Two Months

Name of work:- Construction of Kalkhar Galoo to Naundhar Upper Dibhri, Lower Dibhri Bhout Sidhyani road Km. 0/0 to 4/600.

Sub Head:- Construction of 900mm dia. R.C.C. Hume pipe culvert at RD. 3/210 alongwith both side wing walls.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	7.20 Cubic metre	172.00	Rupees one hundred seventy two and paise nil only	Per cubic metre	1238.00
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	63.76 Cubic metre	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	18299.00
3	Providing and laying concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	10.52 Cubic metre	4770.00	Rupees four thousand seven hundred seventy and paise nil only.	Per cubic metre	50180.00
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	48.28 Cubic metre	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	204707.00
5	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (one cement : six sand : twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	3.54 Cubic metre	3090.00	Rupees three thousand ninety and paise nil only.	Per cubic metre	10939.00

(2)

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
6	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00 metre	3550.00	Rupees three thousand five hundred fifty and paise nil only	Per Running metre	24850.00
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	10.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	2870.00
8	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	7.80 Cubic metre	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	8190.00
					Total:-	321273.00

Draft schedule of quantity checked and approved for Rs 321273/- (Rupees three lac twenty one thousand two hundred seventy three) only.

[Signature]
Executive Engineer,
HP.PWD.Division,
Nagarkot, D.D.

(3)

DNIP 3. NO. 27 for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Ratti section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 269850/-
Earnest Money Rs. 5400/-
Time: -Two Month.

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	257 hours	1050.00	Rupees one Thousand fifty only	Per hours	269850.00
					Total:-	269850.00

Draft schedule of quantity approved for Rs. 2,69,850/-

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

(4)

DNI P.S. NO 14.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road km. 0/0 to 14/580. (SH:- Removal of formation deficiency/ widening of curves in km. 13/465 to 13/900)

Estimated Cost:- 379673.00

Earnest Money :- 7600.00

Time :- One Month

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Excavation in soil in hilly area all heights and depths, in all kind of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-Charge at site according to technical specifications clause 1603.1 & 1603.2 sorting out useful unuseful materials and stacking the same in all leads and lift and transportation of useful materials for filling in road ways. embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means) along with its levelling fine dressing and all labour, machineries. materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if required). Recovery of useful stone of 100.95 cum. @ 300/- per cubic metre amounting to Rs.30,285/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including all leads and lift of materials or as per direction of Engineer in-Charge.	2019.00	188.050	Rupees One hundred eighty eight and paise zero five only.	Per cubic Metre	379673.00
					Total	379673.00

Draft schedule of quantity approved for Rs. 3,79,673/-

Executive Engineer,
HPPWD Division
Nerchowk

(5)

DNP NO 21

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Ratti section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 269850/-
Earnest Money Rs. 5400/-
Time: -Two Month.

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	257 hours	1050.00	Rupees one Thousand fifty only	Per hours	269850.00
Total:-						269850.00

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

(6)

DNI P S NO 24 for the F/y 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Pairi Pasta Hawanu Luharadi road km. 0/0 to 4/100.
(SH:- Construction of Breast wall at RD. 1/165 to 1/185)

Estimated Cost:- 236249.00

Earnest Money :- 4800.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	21.60	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	3715.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	18.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	5166.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	52.00	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	220480.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	24.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	6888.00
					Total	236249.00

Draft schedule of quantity approved for 2,36,249/-

Executive Engineer,
HPRWD Division,
HPRWD Nerchova

⑦

Draft S.No (26) for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Primary Health Centre building (With Residence) at Lohara, Tehsil Balh Distt.Mandi (H.P.). (SH:- Preparation of working estimate for C/O building portion with W.S.& S.I., Septic Tank, Rain water harvesting system and Development of Site etc.)					Estimated Cost:- 49500.00	
					Earnest Money :- 1000.00	
					Time :- One Month	
S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Prparation of working estimate of whole project as per Architectural Drawing for the C/O Primary Health Centre buuilding at Lohara with WS & S.I, Septic Tank, Rain water harvesting system and Development of Site etc. The Job shall also include supplying detailed estimate as per analysis of rates based on HPSR 2020 /market rates for all the items appearing in the estimate The work shall also exclude supplying the estimate in triplicate and approval of the same in divisional office/Circle office/CE office (MZ) Mandi complete as per directions of Engineer- in- charge.	1	49500.00	Rupees Forty Nine Thousand Five Hundred and Paise Zero Only	Per Job	49500.00
					Total	49500.00

Draft Schedule of quantity approved for 2 49,500/- only.

Executive Engineer,
HPPWD Division
Nerchowk

(8)

DMP S.NO 23 for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work: - A/R & M/O various roads under Chakkar Sub Division H.P.PWD Nerchowk
(SH:- Hiring of Tipper for carriage of muck & Patch work material) (Ratti Section)

Estimated Cost Rs. 1,22,000/-
Earnest Money Rs. 137250/-
Time: - Two Month

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different sites of work with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8 hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	40 Days	3050.00	Rupees Three thousand Fifty only	Per Days	122000.00
Total:-						122000.00

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

(9)

Draft S.No 18

for the year 2024-25.

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 269850/-
Earnest Money Rs. 5400/-
Time: -Two Month.

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	257 hours	1050.00	Rupees one Thousand fifty only	Per hours	269850.00
Total:-						269850.00

draft schedule of quantity approved for 2 2,69,850/-

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

10

DNI P S NO 15

for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work: - A/R & M/O various roads under Chakkar Sub Division H.P.PWD Nerchowk
(SH:- Hiring of Tipper for carriage of muck & Patch work material) (Ratti Section)

Estimated Cost Rs. 183000/-
Earnest Money Rs. 3700/-
Time: - Two Month

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different sites of work with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8 hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	60 Days	3050.00	Rupees Three thousand Fifty only	Per Days	183000.00
Total -						183000.00

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

(11)

DNI P S NO 13 for the year 2024-25

Draft Schedule of Quantity

Estimated Cost : Rs.249780/-

Earnest Money : Rs. 5000 /-

Time : One Month.
(SH:- Providing and Fixing road studName of work : A/R and M/O various roads under Chakkar Sub Division HPPWD Nerchowk
with lens reflector) (Nerchowk Section).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	2	3	4	5	6	7
1	Providing and Fixing road stud 100 x 100 mm (one hundred into one hundred millimetre) dia cast in aluminium, resistant to corrosive effect of salt and grit, fitted with lense reflectors, installed in concrete or asphaltic surface by deniling holes 30mm (Thirty millimetre) upto a depth of 600 mm (Six hundred millimetre) bedded in a suitable bituminous grout of epoxy mortar, all as per BS : 873 (Part 4) 1973 including carriage of material within all leads and lift and any other incidental charges.	724.00	345.00	Rupees three hundred forty five only.	Each.	249780.00
					Total :-	249780.00

draft schedule of quantity approved for Rs. 2,49,780/-

Assistant Engineer,
Chakkar Sub Division,
HP,PWD,Nerchowk.Executive Engineer,
HPPWD Division,
HP,PWD,Nerchowk.

(12)

DNI P.S. NO 12 for the year 2024-25.

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 269850/-
Earnest Money Rs. 5400/-
Time: -Two Month.

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	257 hours	1050.00	Rupees one Thousand fifty only	Per hours	269850.00
					Total:-	269850.00

Draft schedule of quantity approved for Rs. 2,69,850/-

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

(13)

DMPS.No (20) for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Chandigarh Mandi Manali road Km. 184/600 to 190/00 and 191/190 to 198/050. (SH:- Repair of slab culvert in PCC 1:3:6 at RD. 188/333)

Estimated Cost:- Rs. 312050.00

Earnest Money :- Rs. 6300.00

Time :- Two Months

S. No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	22.50	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	6458.00
2	Providing and laying concrete mechanically mixed and vibrated mix 1:3:6 (one cement: three sand: six graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in abutments, open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	60.58	4770.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per Cubic Metre	288967.00
3	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm (Six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 including carriage of material within all leads, lifts/depths or as per the entire satisfaction and direction of Engineer-in-Charge.	13.30	1250.00	Rupees One thousand two hundred fifty and paise zero only.	Per Cubic Metre	16625.00
					Total	312050.00

Draft schedule of quantity approved for Rs. 3,12,050/-

Executive Engineer,
HPPWD Division,
Nerchowk

(14)

DMFS No 11 for the year 2024-25.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical fiber cable on Ratti Meramasit Leda road
km. 0 to 14/580. (SH:- Construction of PCC Retaining wall at RD. 1/675 to 1/685 & 1/090 to 1/100)

Estimated Cost:- 322050.00

Earnest Money :- 6500.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	30.20	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	8667.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	68.60	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	290864.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	12.70	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	13335.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	32.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	9184.00
					Total	322050.00

Draft schedule of quantity approved for Rs 3,22,050/-

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

(15)

DNIT S.No. (08) for the year 2024-25

Draft Schedule of Quantity

Estimated Cost:- Rs. 137250.00 ✓

Earnest Money:-Rs. 2800.00 ✓

Time:- Two months ✓

Name of work:-Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. (Leda Section)

Sub Head:- Hiring of Tipper for carriage of muck and patch work material.(Job No.I)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Tipper 5.5 cum / 10 tonne capacity (five point five cubic metre/ten tonne capacity) capacity having lift system for carriage of earth/ debries, boulder and other construction materials from various location etc. complete with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 6 (six) hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	45.00 days	3050.00	Rupees three thousand fifty and paise nil only ✓	Per day	137250.00 ✓
				Total:-		137250.00 ✓

Draft schedule of quantity checked and approved for Rs. 137250/- (Rupees one lac thirty seven thousand two hundred fifty) only.

Assistant Engineer
Rewalsar Sub-Divn.
HPPWD Rewalsar

Executive Engineer
H.P.R.W.D. Division
Nerchowk-175008

(16)

DNIT S.No. (07) for the year 2024-25

Draft Schedule of Quantity

Estimated Cost:- 220500.00

Earnest Money:-Rs 4500.00

Time:- One month

Name of work:-Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. (Leda Section)


Sub Head:- Hiring of Earth cutting / Excavating machine for removal of slips,clearing of debris drains and dressing of berms etcetra. (Job No.I)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of earth cutting/excavating machineries to be deployed for removal of slips/earth cutting/filling/cleaning of unlined drains and catchpits including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk shifting of machinery from one place to other place will be absolute responsibility of the contractor, Only actual working hour will be accounted for the payment. Earth cutting in all kind of soils including loading in to tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	210.00 Hours	1050.00	Rupees one thousand fifty and paise nil only	Per hour	220500.00
				Total:-		220500.00

Conditions:-

Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Draft schedule of quantity checked and approved for Rs. 220500/- (Rupees two lac twenty thousand five hundred) only.


Assistant Engineer,
Rewalsar Sub-Division,
HP.PWD. Rewalsar.


Executive Engineer,
Nerchowk Division,
HP.PWD. Nerchowk.

(17)

DNIT S.NO. (22) for the year 2024-25

Draft Schedule of Quantity

Estimated Cost:- Rs. 183000.00

Earnest Money:-Rs. 3700.00

Time:- Two months

Name of work:-Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. (Rewalsar Section)

Sub Head:- Hiring of Tipper for carriage of muck and patch work material.(Job No.II)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Tipper 5.5 cum / 10 tonne capacity (five point five cubic metre/ten tonne capacity) capacity having lift system for carriage of earth/ debries, boulder and other construction materials from various location etc. complete with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 6 (six) hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	60.00 days	3050.00	Rupees three thousand fifty and paise nil only	Per day	183000.00
				Total:-		183000.00

Draft Schedule of quantity checked and approved for Rs. 183000/- (Rupees one lac eighty three thousand) only.

Assistant Engineer,
Rewalsar Sub-Division,
HP.PWD. Rewalsar

Executive Engineer,
Nerchowk Division,
HP.PWD. Nerchowk

(18)

DNIT NO. (21) FOR THE FY 2024-25

Draft Schedule of Quantity

Estimated Cost:-Rs. 220500.00 ✓

Earnest Money:-Rs 4500.00 ✓

Time:- One month

Name of work:- Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. (Rewalsar Section)

Sub Head:- Hiring of Earth cutting / Excavating machine for removal of slips, clearing of debris drains and dressing of berms etcetra. (Job No.II)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of earth cutting/excavating machineries to be deployed for removal of slips/earth cutting/filling/cleaning of unlined drains and catchpits including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk shifting of machinery from one place to other place will be absolute responsibility of the contractor, Only actual working hour will be accounted for the payment. Earth cutting in all kind of soils including loading in to tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	210.00 Hours	1050.00	Rupees one thousand fifty and paise nil only	Per hour	220500.00
				Total:-		220500.00

Conditions:-

Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Draft schedule of quantity checked and approved for Rs. 220500/- (Rupees Two Lac Twenty Thousand Five Hundred) Only

Assistant Engineer,
Rewalsar Sub-Division,
HP.PWD. Rewalsar.

Executive Engineer,
Nerchowk Division,
HP.PWD. Nerchowk

(19)

DNIT NO. (20) FOR THE YEAR 2024

Draft Schedule of Quantity**Estimated Cost:- Rs.** 183000.00**Earnest Money:-Rs.** 3700.00**Time:-**

Two months

Name of work:-Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. **(Rewalsar Section)****Sub Head:-** Hiring of Tipper for carriage of muck and patch work material. **(Job No.I)**

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Tipper 5.5 cum / 10 tonne capacity (five point five cubic metre/ten tonne capacity) capacity having lift system for carriage of earth/ debries, boulder and other construction materials from various location etc. complete with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 6 (six) hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	60.00 days	3050.00	Rupees three thousand fifty and paise nil only	Per day	183000.00
				Total:-		183000.00

Draft schedule of quantity checked & approved for Rs. 183000/- (Rupees One Lac Eighty Three Thousand) only.

Assistant Engineer,
Rewalsar Sub-Division,
HP.PWD. Rewalsar

Executive Engineer,
Nerchowk Division,
HP.PWD. Nerchowk

(20)

DNIT NO. (19) FOR THE FINANCIAL YEAR 2024-25

Draft Schedule of Quantity

Estimated Cost:-Rs. 220500.00 ✓

Earnest Money:-Rs 4500.00 ✓

Time:- One month

Name of work:- Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. (Rewalsar Section)

Sub Head:- Hiring of Earth cutting / Excavating machine for removal of slips, clearing of debris drains and dressing of berms etcetra. (Job No.I)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of earth cutting/excavating machineries to be deployed for removal of slips/earth cutting/filling/cleaning of unlined drains and catchpits including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk shifting of machinery from one place to other place will be absolute responsibility of the contractor, Only actual working hour will be accounted for the payment. Earth cutting in all kind of soils including loading in to tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	210.00 Hours	1050.00 ✓	Rupees one thousand fifty and paise nil only ✓	Per hour ✓	220500.00 ✓
				Total:-		220500.00

Conditions:-

Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Draft schedule of quantity checked & approved for Rs. 220500/- (Rupees Two Lac Twenty Thousand Five Hundred) only

Assistant Engineer,
Rewalsar Sub-Division,
HP.PWD. Rewalsar.

Executive Engineer,
Nerchowk Division,
HP.PWD. Nerchowk

(21)

DNIT S.NO. (09)

for the year 2024-25

Draft Schedule of Quantity

Estimated Cost:- Rs 220500.00 ✓

Earnest Money:-Rs 4500.00 ✓

Time:- One month ✓

Name of work:- Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. (Leda Section)**Sub Head:-** Hiring of Earth cutting / Excavating machine for removal of slips, clearing of debris drains and dressing of berms etcetra. (Job No.II)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of earth cutting/excavating machineries to be deployed for removal of slips/earth cutting/filling/cleaning of unlined drains and catchpits including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk shifting of machinery from one place to other place will be absolute responsibility of the contractor, Only actual working hour will be accounted for the payment. Earth cutting in all kind of soils including loading in to tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	210.00 Hours	1050.00	Rupees one thousand fifty and paise nil only	Per hour	220500.00
				Total:-		220500.00

Conditions:-

Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Draft schedule of quantity checked and approved for Rs 220500/- (Rupees two lac twenty thousand five hundred) only.

Assistant Engineer,
Rewalsar Sub-Division,
HP.PWD. Rewalsar.

Executive Engineer,
Nerchowk Division,
HP.PWD. Nerchowk

(22)

DNIT S.NO. (16) FOR THE YEAR 2024-25

Draft Schedule of Quantity

Estimated Cost:-Rs. 220500.00 ✓

Earnest Money:-Rs 4500.00 ✓

Time:- One month ✓

Name of work:- Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. (Sardhwar Section)
Sub Head:- Hiring of Earth cutting / Excavating machine for removal of slips, clearing of debris drains and dressing of berms etcetra. (Job No.I)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of earth cutting/excavating machineries to be deployed for removal of slips/earth cutting/filling/cleaning of unlined drains and catchpits including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk shifting of machinery from one place to other place will be absolute responsibility of the contractor, Only actual working hour will be accounted for the payment. Earth cutting in all kind of soils including loading in to tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	210.00 Hours	1050.00	Rupees one thousand fifty and paise nil only	Per hour	220500.00
				Total:-		220500.00

Conditions:-

Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Draft schedule of quantity checked
 & approved for Rs. 220500/- (Rupees Two
 Lac Twenty Thousand Five Hundred) only

Assistant Engineer,
 Rewalsar Sub-Division,
 HP.PWD. Rewalsar.

Executive Engineer,
 Nerchowk Division,
 HP.PWD. Nerchowk.

(23)

DNIT S.NO. (11) for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD
 Rewalsar. (SH:- Hiring of Hydraulic excavator/ breaker machine for breaking of stone / boulder) Leda
 Section

Estimated Cost:- 74000.00 ✓
 Earnest Money:- 1500.00 ✓
 Time:- One month ✓

Sr. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator/ Breaking machineries to be deployed for cutting of rocky strata and breaking of stone/boulder and dismantling of existing structure like bridges and other structures comprising of masonry cement concrete / reinforced cement concrete including cost of fuel oil lubricants and wages of operating staff. Any repair /breakage during operation will be carried out by the contractor/owner at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the contractor. Only actual working hour will be accounted for the payment. Disposal of unserviceable material including loading into tipper/ Truck in all leads and lifts to the entire satisfaction of Engineer-in-Charge	50.00	1480.00	Rupees One thousand four hundred eighty and paise zero only.	Per hour	74000.00 ✓
			Total:-			74000.00 ✓

Draft schedule of quantity checked and approved
 for Rs. 74000/- (Rupees seventy four thousand) only.

Assistant Engineer
 Rewalsar Sub-Division
 HPPWD Rewalsar

Executive Engineer,
 Nerchowk Division,
 HPPWD Nerchowk.

(24)

DNIT NO. (18) FOR THE YEAR 2024-25

Draft Schedule of Quantity

Estimated Cost:-Rs. 220500.00

Earnest Money:-Rs 4500.00

Time:- One month

Name of work:- Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. (Sardhwar Section)
Sub Head:- Hiring of Earth cutting / Excavating machine for removal of slips, clearing of debris drains and dressing of berms etcetra. (Job No.II)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of earth cutting/excavating machineries to be deployed for removal of slips/earth cutting/filling/cleaning of unlined drains and catchpits including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk shifting of machinery from one place to other place will be absolute responsibility of the contractor, Only actual working hour will be accounted for the payment. Earth cutting in all kind of soils including loading in to tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	210.00 Hours	1050.00 ✓	Rupees one thousand fifty and paise nil only ✓	Per hour ✓	220500.00 ✓
				Total:-		220500.00

Conditions:-

Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Draft schedule of quantity checked and approved for Rs. 220500/- (Rupees Two lac Twenty Thousand Five Hundred) only.

Assistant Engineer,
Rewalsar Sub-Division,
HP.PWD. Rewalsar.

Executive Engineer,
Nerchowk Division,
HP.PWD. Nerchowk.

(25)


DNIT S.NO. (10) for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work: - R.R. D. various roads under Rewalsar Sub Division, H.P.PWD, Rewalsar (Leda Section)
 (SH:- Hiring of Tractor with trolley for carriage of muck/debris and shifting of material etc.

Estimated Cost Rs.148500/-
 Earnest Money Rs.3000/-
 Time: -Three Month

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of tractor with trolley with hydraulic lift system for carriage of material to different sites of work with in all leads & lifts and to the entire satisfaction of the Engineer-in-Charge. The tractor should work minimum 8 hours from 9 AM to 5 PM daily, any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the tractor owner which shall have to be fully compensated by him in all cases. The expenditure for fuel, lubricants, driver and repair work shall have to be borne by the tractor owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in Charge.	90 days	1650.00	Rupees one thousand Six Hundred Fifty only	Per Days	148500.00
Total -						148500.00


 Assistant Engineer,
 Rewalsar Sub Division,
 HPPWD Rewalsar.

Draft schedule of quantity checked and approved
 for Rs 148500/- (Rupees one lac forty eight
 thousand five hundred) only.


 Executive Engineer
 H.P.P.W.D. Division
 Nerchowk-175008

(26)

DNIT S.NO. (17) FOR THE YEAR 2024-25

Draft Schedule of Quantity

Estimated Cost:- Rs. 137250.00

Earnest Money:-Rs. 2800.00

Time:- Two months

Name of work:-Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. (Sardhwar Section)
 Sub Head:- Hiring of Tipper for carriage of muck and patch work material.(Job No.I)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Tipper 5.5 cum / 10 tonne capacity (five point five cubic metre/ten tonne capacity) capacity having lift system for carriage of earth/ debries, boulder and other construction materials from various location etc. complete with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 6 (six) hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	45.00 days	3050.00	Rupees three thousand fifty and paise nil only	Per day	137250.00
				Total:-		137250.00

Draft schedule of quantity checked and approved for Rs. 137250/- (Rupees One lac twenty seven thousand Two Hundred Fifty) only.

Executive Engineer,
 Nerchowk Division,
 HP.PWD. Nerchowk

(27)

DNIT S.NO. ③ for the year 2024-25

Draft Schedule of Quantity

Estimated Cost:- Rs. 479667.00

Earnest Money:- Rs. 9600.00

Time:- Two Months

Name of work:- Restoration of rain damages on Manjhyali Samloun Via Safru road Km. 0/000 to 9/945.
Sub Head:- Construction of Retaining wall with Toe wall at R.D. 6/450 to 6/462.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	37.32 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	10711.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	61.92 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	262541.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702,704,1202 & 1204 Random rubble masonry in cement mortar 1:6 (one cement : six sand) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	22.24 Cum	3650.00	Rupees three thousand six hundred fifty and paise nil only	Per cubic metre	81176.00
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 25mm (twenty five millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	2.40 Cum	4408.00	Rupees four thousand four hundred eight and paise nil only	Per cubic metre	10579.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub structure and super structure complete as per Drawing and technical specifications clauses 704.6 & 1302.5 complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge	47.52 Cum	2100.00	Rupees two thousand one hundred and paise nil only	Per cubic metre	99792.00
6	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	14.16 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	14868.00
					Total	479667.00

Draft schedule of quantity checked and approved for Rs 479667/- (Rupees four lac seventy nine thousand six hundred sixty seven) only.

Executive Engineer,
H.P.R.W.D. Division,
Nerchowk

(28)

DNIT S.No. (5) for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work :- R.R. damages Various Roads under Rewalsar Sub-Division.
Hiring of JCB for Removal of slips/ muck/debris, dressing of berms, clearing unlined drain). Section

Rewalsar.

(SH:- Estimated Cost Rs.220500/-
Earnest Money Rs. 4410/- ~~4500/-~~
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of J.C.B. for earth cutting / excavating. machineries to be deployed for earth cutting / excavating / filling / removal of slips / muck/debris, dressing of berms, clearing unlined drain i/c cost of fuel oil lubricants and wages of operating staff. Any repair/ breakage during operation will be carried out by the contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor. Only actual working hours will be accounted for the payment. Cutting in earth work removal of slips in all kinds of soil in/c loading in tipper/ trucks and disposal of all excavated earth in all leads and lifts to the entire satisfaction of the Engineer in Charge.	210.00	1050.00	Rupees One thousand fifty only	Per Hour	2,20,500.00
					Total	2,20,500.00

Draft schedule of quantity checked and approved for Rs. 220500/- (Rupees two lac twenty thousand five hundred) only.

Assistant Engineer,
B&R Sub Division HP.PWD.
Rewalsar.

Executive Engineer
H.P.F.W.D. Division
NAT Chowk-175008

(29)

DNIT S.No 55 for the year 2024-25

Draft Schedule of Quantity

Estimated Cost:- Rs. 249780/-
 Earnest Money:- Rs. 5000/-
 Time:- One Month

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Providing and Fixing road stud with lens reflector). Nerchowk Section.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Providing and Fixing road stud 100 x100 mm (one hundred into one hundred millimetre) dia cast in aluminium, resistant to corrosive effect of salt and grit, fitted with lense reflectors, installed in concrete or asphaltic surface by deniling holes 30 mm (Thirty millimetre) upto a depth of 600 mm (Six hundred millimetre) bedded in a suitable bituminous grout of epoxy mortar, all as per BS : 873 (Part 4) 1973 including carriage of material within all leads and lift and any other incidental charges.	724.00	345.00	Rupees Three Hundred Forty Five only.	Each.	249780.00
					Total:-	249780.00

Draft Schedule of quantity approved for Rs. 249780/-

Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

(30)

DNIT S. NO. (249) for the year 2023-24

Draft Schedule of Quantity

Name of work:- Construction of link road from Gas Godawn to Chhukrahan GP lower Rewalsar Km. 0/000 to 2/000.

Sub Head:- Construction of 900mm dia RCC Hume Pipe Culvert at RD. 0/450 alongwith both side wing walls. Under OTMNP

Estimated Cost:- Rs. 236266 00
 Earnest Money:- Rs. 4700 00
 Time:- Two Months

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge	46 79 Cubic metre	287 00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	13429.00
2	Providing and laying concrete mechanically mixed and vibrated P.C.C. M-10 (ten) grade for plain concrete in open foundations and plinths or similar works complete as per drawings and technical specification clauses 1202, 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge	11 58 Cubic metre	4770.00	Rupees four thousand seven hundred seventy and paise nil only	Per cubic metre	55237.00
3	Providing and laying concrete Mechanically mixed and vibrated mix 1:5:10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge	29 68 Cubic metre	4240 00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	125843.00
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 & 1203 Plain cement concrete nominal mix 1:6:12 (one cement six sand twelve graded crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge	2 83 Cubic metre	3090.00	Rupees three thousand ninety and paise nil only.	Per cubic metre	8745.00
5	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7 00 metre	3550.00	Rupees three thousand five hundred fifty and paise nil only	Per Running metre	24850.00
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204 3 7 including carriage of material and other incidentals as per direction of Engineer-in-Charge	10 00 Nos	287 00	Rupees two hundred eighty seven and paise nil only	Each	2870.00

30

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204 3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	5.04 Cubic metre	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	5292.00
					Total:-	236266.00

Draft schedule of quantity checked and approved for
Rs. 236266/- (Rupees two lac thirty six thousand
two hundred sixty six) only.

Executive Engineer,
HP PWD Division,
Netchawki

(31)

DNI F 8 NO 1 - 506

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on Gutkar Behna Tikkar Malwana Badhyal road km. 0/00 to 5/00. (SH:- C/O PCC Retaining wall at RD. 1/980 to 1/995)

Estimated Cost:- 238952.00

Earnest Money :- 4800.00

Time :- Two Months

S.N o		Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
				Rs.	P.		
				In figure	In word		
1		Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	26.60	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	7634.00
2		Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	52.48	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	222515.00
3		Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	5.65	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	5933.00
4		Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	10.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	2870.00
						Total	238952.00

Draft schedule of quantity approved 2,38,952/-

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk,

(32)

DNIP S.No! - 537 for FY 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O on various roads under Chakkar Sub Division HPPWD Nerchowk.
(SH:- Hiring of Tipper for carriage of muck & patch work material) (Gagal Section)

Estimated Cost:- 274500.00

Earnest Money:- 5500.00

Time:- Three months

S. No	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different sites of work with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8 hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	90.00	3050.00	Rupees Three thousand fifty and paise zero only.	Per day	274500.00
					Total	274500.00

Draft schedule of quantity approved for 2,74,500/-

Assistant Engineer
Chakkar Sub-Division
H.P.W.D. Ner Chowk

Executive Engineer
HPPWD Division
Nerchowk.

(33)

DNIT S.No. (208) for the yr. 2023-24

As Per W.P.

Draft Schedule of Quantity

Name of work:- Construction of Kalkhar Galoo to Naundhar Upper Dibhri, Lower Dibhri Bhout Sidhyani road Km. 0/0 to 5/0.
 Sub Head:- Construction of 900mm dia. R.C.C. Hume pipe culvert at RD 3/550 alongwith both side wing walls. Under OTMNP

Estimated Cost:- Rs. 252056.00
 Earnest Money:- Rs. 5100.00
 Time:- Two Months

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs P		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	60.01 Cubic metre	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	17223.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (one cement : six sand : twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	7.90 Cubic metre	3040.00	Rupees three thousand forty and paise nil only.	Per cubic metre	24016.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	4.74 Cubic metre	4408.00	Rupees four thousand four hundred eight and paise nil only.	Per cubic metre	20894.00
4	Stone masonry in cement mortar in sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 Random rubble masonry in cement mortar 1:6 (one cement : six sand) and curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	32.38 Cubic metre	3650.00	Rupees three thousand six hundred fifty and paise nil only	Per cubic metre	118187.00
5	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00 metre	3550.00	Rupees three thousand five hundred fifty and paise nil only	Per Running metre	24850.00
6	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	1.12 Cubic metre	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	4749.00

33

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs P		Unit	Amount
			In Figure	In words		
7	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub structure and super structure complete as per Drawing and technical specifications clauses 704.6 & 1302.5 complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	15.16 Cubic metre	2100.00	Rupees two thousand one hundred and paise nil only	Per cubic metre	31836.00
8	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 complete Granular material within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.81 Cubic metre	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	10301.00
					Total:-	252056.00

Draft schedule of quantity checked and approved for Rs. 252056/-
(Rupees two lac fifty two thousand fifty six) only.

Executive Engineer,
HP.PWD.Division,
Nerchowk.

(34)

DNITS.NO.1(299) for the year 2023-24.

DRAFT SCHEDULE OF QUANTITY

Name of work:- M/T on village Kummi to Harizan Basti Khandla Rajgarh Gadraor Kummi road km. 0/0 to 5/500. (SH:- Providing and laying WBM G-III and Tarring at RD. 0/200 to 0/320, 0/600 to 0/730 and 1/650 to 1/760) (under SCDP) Against Working Programme

Estimated Cost:- 430984.00

Earnest Money :- 8700.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Providing, laying, spreading and compacting stone aggregate of sizes 53-22.4mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-III by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	59.53	2290.00	Ruppes Two thousand two hundred ninety and paise zero only.	Per Cubic Metre	136324.00
2	Providing and applying a primer coat with bitumen emulsion (SS-I) on prepared surface of granular base cleaned of dust and extraneous material with hydraulic broom or any other approved equipment and spraying primer at the rate of 0.70-1.00 Kg./Sqm. (zero point seven zero to one point zero zero kilogram per square metre) using mechanical means as per technical specification clause 502 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	793.80	62.00	Ruppes Sixty two and paise zero only.	Per Square Metre	49216.00
3	Providing and applying tack coat with bitumen emulsion (RS-1) on prepared dry and hungry bitumen surface cleaned of dust and extraneous material with Hydraulic brooms or any other approved equipment and spraying priming at the rate of 0.25 to 0.30 kg. (zero point two five to zero point three zero kilogram) per square metre with emulsion pressure distributor equipped for spraying uniformly complete as per technical specification clause 503 with in all leads lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	793.80	17.00	Ruppes Seventeen and paise zero only.	Per Square Metre	13495.00
4	Providing, laying and rolling by mechanical means with bitumen (VG-10/S-90) of open graded premix carpet of 20mm (twenty millimetre) thickness composed of 13.2mm to 5.6mm (thirteen point two millimetre to five point six millimetre) aggregates either using penetration grade bitumen to required line, grade and level to surve as wearing course on a previously prepared base, including mixing in suitable plant, laying and rolling with a three wheel 80-100 kN (eighty-hundred kilo newton) static roller capacity, finished to required level and grades to be followed by seal coat of Type-B as per Technical Sepcification Clause 508 including carriage of material within all leads, lifts and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	793.80	216.00	Ruppes Two hundred sixteen and paise zero only.	Per Square Metre	171461.00
5	Providing and laying seal coat Type-B by mechanical means sealing the voids in a bituminous surface laid to the sepcified levels, grade and crossfall using Bitumen (VG-10/S-90) as per Technical Specifacaiton Clause 510 including carriage of material within all leads, lifts and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	793.80	76.20	Ruppes Seventy six and paise twenty only.	Per Square Metre	60488.00
					Total	430984.00

Draft schedule of quantity approved for 2,43,0984/-

Executive Engineer,
HPPWD-Division
Nerchowk

(35)

DN/P8.NO 389

DRAFT SCHEDULE OF QUANTITY

Name of work: - A/R & M/O on various roads under Chakkar Sub Division H.P.PWD Nerchowk
(SH:- Hiring of Tipper for carriage of muck & Patch work material) (Nerchowk Section)

Estimated Cost Rs. 137250/-
Earnest Money Rs. 2800/-
Time: - Two Month

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different sites of work with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 6 hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	45 Days	3050.00	Rupees Three thousand Fifty only	Per Days	137250.00
Total -						137250.00

Draft schedule of quantity approved for Rs. 1,37,250/- only

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk

36

DNI PS. No (994) for the year 2023-24.

Name of work:- Construction of DamKa Samloun to Pargi Pul road km. 0/00 to 2/660. (SH:- Providing and laying stone soling at RD. 1/420 to 2/00)

DRAFT SCHEDULE OF QUANTITY

Estimated Cost:- 432634.00

Earnest Money :- 8700.00

Time :-Two Months

S.N o		Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
				In figure	In word		
1		Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the required gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (One hundred millimetre) spread thickness (finished work including materials and labour) including carriage of material with in all leads, lifts and other incidentals and as per the direction of the Engineer-in Charge.	292.32	1480.00	Rupees One thousand four hundred eighty and paise zero only.	Per Cubic Metre	432634.00
						Total	432634.00

Draft schedule of quantity approved for 24,32,634/-

Executive Engineer,
HPPWD Division
Nerchowk

(37)

LNI PS NO (433) for the year 2023-24.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Providing and fixing stainless steel gate for existing boundary near Labana basti village Troh on Ratti Randhara road. (SH:- Providing and fixing steel Railing & Gate at RD. 3/050) Deposit work

Estimated Cost:- 47580.00

Earnest Money :- 1000.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	89.90	529.25	Rupees Five hundred twenty nine and paise twenty five only.	Per Kilogram	47580.00
					Total	47580.00

Draft schedule of quantity approved for ₹ 47,580/- only

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

(38)

DNIPS.No! - 461

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical cable on Ratti Kalkhar road Km. 0/00 to 10/00. (SH:- Construction of U-Shape drain in km. 4/700 to 4/980) (LHS) Deposit work

Estimated Cost:- 475722.00

Earnest Money :- 9600.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation of foundation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	142.80	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	40984.00
2	Providing and laying plain/reinforced cement concrete in substructure as per drawing and technical specification clause 802,803,1202 and 1203 P.C.C nominal mix 1:3:6 (One cement: three sand:six graded stone aggregate) including carriage of material with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	91.14	4770.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per Cubic Metre	434738.00
					Total	475722.00

Draft schedule of quantity approved for ₹ 4,75,722/-

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

(39)

DNI P.S. NO. 497

①

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Stadium Near GPS Arthi GP Mandal, Development Block Balh at Nerchowk . (SH:- Construction of Retaining wall and Stage)

Estimated Cost:- 489134.00

Earnest Money :- 9800.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.			
			In figure	In word		
			Estimated Cost:- 489134.00 Earnest Money :- 9800.00 Time :-Two Months			
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	38.70	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	11107.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	74.33	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	315159.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	46.80	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	49140.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	40.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	11480.00
5	Providing and laying in position reinforced cement concrete 1:2:4 (one cement : two coarse sand : four graded stone aggregate 40 mm (forty millimetre) nominal size), excluding the cost of centering, shuttering, finishing and reinforcement all work up to plinth level including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	9.36	5810.00	Rupees Five thousand eight hundred ten and paise zero only.	Per cubic metre	54382.00
	Providing and laying 40mm (forty millimetre) thick fine dressed stone flooring over 20mm (twenty millimetre) (average) thick base of cement mortar 1:5 (one cement : five coarse sand) with joints finished flush red sand stone including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	48.00	930.00	Rupees Nine hundred fifty eight and paise zero only.	Per square metre	45600.00
	15 mm (Fifteen millimetre) thick cement plaster to ceiling with cement mortar 1:4 (one cement :four sand) and curing complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	24.78	91.45	Rupees Ninety one and paise forty five only.	Per square metre	2266.00
					Total	489134.00

Draft schedule of quantity

Draft schedule of quantity approved for Rs 2,48,9134/-

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

(40)

DNI No 501 for F.Y. 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Ratti section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 252000/-

Earnest Money Rs. 5100/-

Time: -One Month.

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	240 hours	1050.00	Rupees one Thousand fifty only	Per hours	252000.00
					Total:-	252000.00

Draft schedule of quantity approved for ₹ 2,52,000/-

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

(41)

DNIT S. No 56 for the year 2024-25

Draft Schedule of Quantity

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Gagal Section)

Estimated Cost:-

Rs. 269850/-

Earnest Money:-

Rs. 5400/-

Time:-

Two Months

(SH:- Hiring of JCB clearing of debris drains and dressing of berms etc).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Hiring of JCB one cum bucket capacity for debris/ cleaning of drain from various sited of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Any loss to the public/ private property or any accident etc. happened during the course of hiring period shall be absolute responsibility by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also born by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	257 hours	1050.00	Rupees One Thousand Fifty only	Per hours	269850.00
					Total:-	269850.00

Draft Schedule of Quantity approved for Rs. 269850/-

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

(42)

DNI P.S. NO (29) for the year 2024-25.

DRAFT SCHEDULE OF QUANTITY

Name of work: - A/R & M/O various roads under Chakkar Sub Division H.P.PWD Nerchowk
(SH:- Hiring of Tipper for carriage of muck & Patch work material) (Nerchowk Section)

Estimated Cost Rs. 183000/-
Earnest Money Rs. 3700/-
Time: - Two Month

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different sites of work with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 6 hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	60 Days	3050.00	Rupees Three thousand Fifty only	Per Days	183000.00
					Total -	183000.00

Draft schedule of quantity approved for Rs. 1,83,000/- up.

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

43

DNIP S.NO 31 for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Nerchowk Section)

Estimated Cost Rs. 250950/-
Earnest Money Rs. 5100/-
Time: -Two Month.

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	239 hours	1050.00	Rupees one Thousand fifty only	Per hours	250950.00
					Total:-	250950.00

Draft schedule of quantity approved for 2,50,950/-

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

(44)

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Nerchowk section)

Estimated Cost Rs. 220500/-

Earnest Money Rs. 4500/-

Time: -One Month.

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	210 hours	1050.00	Rupees one Thousand fifty only	Per hours	220500.00
					Total:-	220500.00

Draft schedule of quantity approved for Rs. 2,20,500/-

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

(45)

DNIT S.No. (25) for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work:- Improvement of black spot on Ratti Kalkhar road km. 0/0 to 10/00. (SH:- Improvement of black spot by widening of curve at RD. 4/555 to 4/600 & 5/855 to 5/1050)

Estimated Cost:- 292570.00

Earnest Money :- 5900.00

Time :- One Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area all heights and depths, in all kind of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-Charge at site according to technical specifications clause 1603.1 & 1603.2 sorting out useful unuseful materials and stacking the same in all leads and lift and transportation of useful materials for filling in road ways. embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means) along with its levelling fine dressing and all labour, machineries. materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if required). Recovery of useful stone of 130.03 cum. @ 300/- per cubic metre amounting to Rs.39,009/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including all leads and lift of materials or as per direction of Engineer in-Charge.	1354.00	216.08	Rupees Two hundred sixteen and paise zero eight only.	Per cubic Metre	292570.00
					Total	292570.00

Draft Schedule of quantity approved for ₹ 2,92,570/- only.

Executive Engineer,
HPPWD Division
Nerchowk

(46)

DNI P.S. NO (16) for the year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Non- Residential Building at Nerchowk, Tehsil Balh, Distt. Mandi (H.P.). (SH:- Preparation of working estimate for C/O building portion 2nd & 3rd floor with W.S. & S.I., in Phase-II)

Estimated Cost:- 65000.00

Earnest Money :- 1400.00

Time :- One Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Preparation of working estimate of whole project as per Architectural Drawing for the C/O Divisional Office building at Nerchowk with building portion 2nd & 3rd floor with W.S. & S.I., in Phase-II etc. The Job shall also include supplying detailed estimate as per analysis of rates based on HPSR 2020 /market rates for all the items appearing in the estimate. The work shall also exclude supplying the estimate in triplicate and approval of the same in divisional office/Circle office/CE office (MZ) Mandi complete as per directions of Engineer-in- charge.	1	65000.00	Rupees Sixty Five Thousand and Paise Zero Only.	Per Job	65000.00
					Total	65000.00

Draft schedule of quantity approved for Rs 65000/-

Executive Engineer,
HPPWD Division
Nerchowk

(47)

DRAFT S.NO 35 for the year 2024-25.

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Chakkar Sub Division HPPWD Nerchowk . (SH:- Hiring of JCB for clearing of debris drains and dressing of berms etc.) (Gagal Section)

Estimated Cost:- 262500.00

Earnest Money:- 5300.00

Time:- Two months

S. No	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount
			Figure	Words		
1	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	250.00	1050.00	Rupees One thousand fifty only.	Per hour	262500.00
					Total	262500.00

Draft schedule of quantity approved for 2,62,500/-

Assistant Engineer
Sub Division Chakkar
HPPWD Nerchowk.

Executive Engineer
HPPWD Division
Nerchowk.

(48)

DNI (S.No) - (34)

Draft Schedule of Quantity

Estimated Cost:- Rs. 351909.00

Earnest Money:- Rs. 7100.00

Time:- Two Months

Name of work:- Restoration of rain damages on Galma Manjhyali road Km. 0/000 to 9/000.

Sub Head:- Construction of Retaining wall at R.D. 1/558.50 to 1/568.50 with toe wall.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	27.30 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	7835.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	76.90 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	326056.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	10.60 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	11130.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	24.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	6888.00
					Total	351909.00

Draft schedule of quantity approved for 2 351,909/-

Executive Engineer,
H.P.P.W.D. Division,
Nellore

(49)

Draft Schedule of Quantity

Estimated Cost:- Rs. 326372.00
 Earnest Money:- Rs. 6600.00
 Time:- Two Months

Name of work:- Construction of link road from Koop Galoo Thina to DPF Baglu road Km. 0/000 to 5/000.

Sub Head:- Construction of PCC. Retaining wall at R.D. 2/630 to 2/645. Under OTMNP

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	48.15 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	13819.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	69.72 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	295613.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	9.30 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	9765.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	25.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	7175.00
					Total	326372.00

Draft schedule of quantity checked and approved for Rs. 326372/-
 (Rupees three lac twenty six thousand three hundred seventy two) only.

Executive Engineer,
 Nerchowk Division,
 H.P.W.D. Nerchowk

(50)

DNIT S.NO. (23) for the year 2024-25

Draft Schedule of Quantity

Estimated Cost:- 498086.00

Earnest Money:- 10000.00

Time:- Two Months

Name of work:- Construction of Kalkhar Galoo to Naundhar upper Dabhri lower Dabhri Bhaut Sidhyani road km. 0/000 to 4/500.
Sub Head:- Providing and laying WBM Grading II in Km. 0/830 to 1/715) Under OTMNP

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting by mechanical means stone aggregates 63mm to 45mm (sixty three millimetre to forty five millimetre) of sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading-2 (two) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges as per direction of Engineer-in-Charge.	222.36 Cum.	2240.00	Rupees two thousand two hundred forty and paise nil only.	Per cubic metre	498086.00
				Total:-		498086.00

Draft schedule of quantity checked and approved for Rs 498086/- (Rupees four lac ninety eight thousand eighty six) only.

Executive Engineer,
H.P.P.W.D. Division,
Nag Chowk

(51)

DNIT S.NO. (25) For the Year 2024-25

Draft Schedule of Quantity

Estimated Cost:- 498086.00

Earnest Money:- 10000.00

Time:- Two Months

Name of work:- Construction of Kalkhar Galoo to Naundhar upper Dibhri lower Dibhri Bhaut Sidhyani road km. 0/000 to 4/500.
Sub Head:- Providing and laying WBM Grading II in Km. 1/715 to 2/600) Under OTMNP

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting by mechanical means stone aggregates 63mm to 45mm (sixty three millimetre to forty five millimetre) of sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading-2 (two) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges as per direction of Engineer-in-Charge.	222.36 Cum.	2240.00	Rupees two thousand four hundred forty and paise nil only.	Per cubic metre	498086.00
				Total:-		498086.00

Draft schedule of quantity checked and approved for Rs 498086/- (Rupees four lac ninety eight thousand eighty six) only.

Executive Engineer,
H.P.P.W.D. Division,
Marchowk.

(52)

DNIP S.NO (36) for the year 2024-25.

DRAFT SHHEDULE OF QUANTITY

Name of work:- A/R & M/O Non-Residential building under Nerchowk Division HPPWD
Nerchowk. (SH:- Refilling of fire extinguishers).

Estimated Cost Rs. 99900.00

Earnest Money Rs. 2000.00

Time : One Month.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	2	3	4	5	6	7
1	Refilling charges for DCP type Powder Fire Extiguishers ISI Marked with 10.00 (ten) kilogramme capacity complete in all respect as per direction of Engineer in Charge including all lead and lift and carriage of material through all modes of transport including all incidental charges.	27.00	3700.00	Rupees Three thousand three hundred and paise zero only.	Each.	99900.00
					Total :-	99900.00

Draft schedule of quantity approved for ₹ 99,900/-

Assistant Engineer
Chakkar Sub-Division
H.P.P.W.D. Ner Chowk

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk

(53)

DNIF S.No. 41

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Ratti Kalkhar road km. 0/0 to 10/0. (SH:- Cutting of branches, dressing of berms and cleaning of drain etc.) Ratti Section

Estimated Cost:- 101980.00

Earnest Money :- 2100.00

Time :- One Month

S.No	Description of item	Quantity	Rate with all taxes including GST in Rs. P		Unit	Amount
			In figure	In word		
1	Cutting of branches of trees shrubs and trimming of grass and weeds Trimming of grass and weeds from the shoulders/ berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	6300.00	3.50	Rupees Three and paise fifty only.	Per square Metre	22050.00
2	Maintenance of Earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	4800.00	14.00	Rupees Fourteen and paise zero only.	Per square Metre	67200.00
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 as per the entire satisfaction and direction of Engineer-in-Charge.	3800.00	3.35	Rupees Three and paise thirty five only.	Per Running Metre	12730.00
					Total	101980.00

Draft schedule of quantity approved for 21,01,980/-

Executive Engineer,
HPPWD Division
HPPWD-Nerchowk

(54)

DNFS.No 43

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division, HPPWD Nerchowk. (Gagal Section) (SH:- Hiring of Tractor with trolly for carriage of muck/ debris and shifting of materials etc.)	Estimated Cost:-	74250.00
	Earnest Money:-	1500.00
	Time:- Three Month	

S. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount
			Figure	Words		
1	Hiring of tractor with trolley with hydraulic lift system for carriage of material to different sites of work with in all leads & lifts and to the entire satisfaction of the Engineer-in-Charge. The tractor should work minimum 8 hours from 9 AM to 5 PM daily. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the tractor owner which shall have to be fully compensated by him in all cases. The expenditure for fuel, lubricants, driver and repair work shall have to be borne by the tractor owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in Charge.	45.00	1650.00	Rupees One thousand six hundred fifty only.	Per day	74250.00
					Total:-	74250.00

Draft schedule of quantity approved for 74,250/-

Assistant Engineer
Chakkar Sub Division
HPPWD Nerchowk

Executive Engineer
HPPWD Division
Nerchowk.

(55)

DNI P.S. NO } (50)

DRAFT SCHEDULE OF QUANTITY

Name of work :- A/R & M/O various road under Chakkar Sub Division HPPWD Nerchowk.
(SH:- Hiring of JCB for cleaning of debris, drain and dressing of berma etc)(Nerchowk section)

Estimated Cost Rs. 2,62,500/-
Earnest Money Rs. 5340/-
Time :- Two month.

Sr. No.	Description of items.	Quant ity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	250	1050.00	Rupees One Thousand Fifty only	Per Hour	2,62,500.00
					Total	2,62,500.00

Assistant Engineer
Chakkar Sub-Division
H.P.P.W.D. Ner Chowk

Draft schedule of quantity approved for ₹ 2,62,500/-

Executive Engineer
HP.PWD Division
Nerchowk-175003

(56)

DNIP S.NO 48

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of 10.00 mtr span RCC slab culvert over Chandyal to Chhatru via Sishal Trambi road at RD. 0/085. (Sub Head:- Construction of wing wall at RD. 0/0 to 0/10 U/S Chandyal side).

Estimated Cost:- Rs. 489908.00

Earnest Money :- Rs. 9800.00

Time :- Two Months

S. No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	38.10	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	10935.00
2	Providing and laying concrete Mechanically mixed and vibrated 1:5:10 (one cement: five sand: ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material with in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	103.90	4240.00	Rupees Four thousand two hundred forty and paise zero only	Per Cubic Metre	440536.00
3	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specifications 1204.3.8 complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	29.50	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	30975.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge .	26.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	7462.00
					Total	489908.00

Draft schedule of quantity approved 24.89.908/-

Executive Engineer,
HPPWD Division,
Nerchowk

(57)

DNI F S. NO. (49)

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Chakkar Sub Division HPPWD Nerchowk . (SH:-
Hiring of JCB for clearing of debris drains and dressing of berms etc.) (Ratti Section)

Estimated Cost:- 262500.00

Earnest Money:- 5300.00

Time:- Two months

S. No.	Description of item	Qty.	Rate with all taxes including GST in Rs P		Unit	Amount
			Figure	Words		
1	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	250.00	1050.00	Rupees One thousand fifty only.	Per hour	262500.00
Total						262500.00

Draft schedule of quantity approved for 2,62,500/-

Assistant Engineer
Sub Division Chakkar
HPPWD Nerchowk.

Executive Engineer
HPPWD Division
Nerchowk.

(58)

DNI P.S. NO. 46

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of 10.00 mtr span RCC slab culvert over Chandyal to Chhatru via Sishal Trambi road at RD. 0/085. (Sub Head:- Construction of wing wall at RD. 0/0 to 0/14 D/S Chandyal side).

Estimated Cost:- Rs. 483918.00

Earnest Money :- Rs. 9700.00

Time :- Two Months

S. No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
			3	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	21.10	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	6056.00
2	Providing and laying concrete Mechanically mixed and vibrated 1:5:10 (one cement: five sand: ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material with in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	102.20	4240.00	Rupees Four thousand two hundred forty and paise zero only	Per Cubic Metre	433328.00
3	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specifications 1204.3.8 complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	36.40	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	38220.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge .	22.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	6314.00
					Total	483918.00

Draft schedule of quantity approved for Rs. 4,83,918/-

Executive Engineer,
HPPWD Division,
Nerchowk

(59)

DMF S.No. 32

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on Ratti Meramasit Leda road km. 0/0 to 14/580. (SH:- Construction of wire crate R/wall at RD. 0/600 to 0/615)

Estimated Cost:- 473860.00

Earnest Money :- 9500.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	43.20	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	12398.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	144.56	2880.00	Rupees Two thousand eight hundred eighty and paise zero only.	Per Cubic Metre	416333.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	42.98	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	45129.00
					Total	473860.00

Draft schedule of quantity approved for Rs 4,73,860/-

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

(60)

D.N.P. 8.10. (39) for the year 2024-25.

Draft Schedule of Quantity

Estimated Cost:- 74250.00
 Earnest Money:- 1500.00
 Time:- 45 Days


Name of work:- Restoration of rain damages on various road under Chakkar Sub-Division . (In Nerchowk section).

Sub Head:- Hiring of Tractor with trolley for carriage of muck/ debris/stone,boulders etcetra.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of tractor with trolley with hydraulic lift system for carriage of aggregates/earth/debries/boulders and other construction/ tarring materials from various locations etc. complete with in all leads and lifts and to the entire satisfaction of the Engineer-in-Charge. The tractor should work minimum 8 (eight) hours from 9 AM to 5 PM daily. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the tractor owner which shall have to be fully compensated by him in all cases. The expenditure for fuel, lubricants, driver and repair work shall have to be borne by the tractor owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	45.00	1650.00	Rupees one thousand six hundred fifty and paise nil only	Per day	74250.00
				Total:-		74250.00

Draft schedule of quantity approved for ₹ 74,250/-


 H.P.W.D. Nerchowk


 Executive Engineer,
 Nerchowk Division,
 HP.PWD. Nerchowk.

(61)

DMF S.No (38)

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on Ratti Meramasit Leda road km. 0/0 to 14/580. (SH:- Construction of wire crate R/wall at RD. 0/615 to 0/630)

Estimated Cost:- 474377.00

Earnest Money :- 9500.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	45.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	12915.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	144.56	2880.00	Rupees Two thousand eight hundred eighty and paise zero only.	Per Cubic Metre	416333.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	42.98	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	45129.00
					Total	474377.00

Draft schedule of quantity approved for 4,74,377/-

Executive Engineer,
HPPWD Division,
HPPWD Nerchowki

(62)

DNI F.S.No 9

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Devri Ambe ka Ghar to Gajrehra Rathol road km. 0/0 to 0/500. (SH:- Construction of PCC Pavement at RD.
0/060 to 0/140)

Estimated Cost:- 317304.00

Earnest Money :- 6400.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Providing, laying, spreading and compacting stone aggregate of sizes 53-22.4mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-III by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	10.69	2290.00	Rupees Two thousand two hundred ninety and paise zero only.	Per Cubic Metre	24480.00
2	Providing and laying plain/reinforced cement concrete in foundation/substructure as per drawing and technical specification clause 802.803.1202 and 1203 P.C.C nominal mix 1:2:4 (One cement: two sand: four graded stone aggregate) 40 mm (forty millimetre) nominal size of aggregates including carriage of material with in all leads, lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	50.40	5810.00	Rupees Five thousand eight hundred ten and paise zero only.	Per Cubic Metre	292824.00
					Total	317304.00

Draft schedule of quantity approved for ₹ 3,17,304/-

Executive Engineer,
HPPWD Division
Nerchowk

(63)

DNIT S.No. (26) for the year 2024-25

Draft Schedule of Quantity

Estimated Cost:- Rs. 253184.00

Earnest Money:- Rs. 5100.00

Time:- Two Months

Name of work:- Restoration of rain damages on Leda Ghangnoo road Km. 0/000 to 12/000.

Sub Head:- Construction of Retaining wall at R.D. 4/080 to 4/095.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	34.50 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	9902.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	53.19 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	225526.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	10.35 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	10868.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	24.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	6888.00
					Total	253184.00

Draft schedule of quantity checked and approved for Rs. 253184/- (Rupees Two lac fifty three thousand one hundred eighty four) only.

Executive Engineer,
H.P.P.W.D. Division,
Netchowk

(64)

DRI F.S. No. 1. (552) 78. 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Chandigarh Mandi Manali (Old NH-21) road km. 184/650 to 198/050.
(SH:- Repair of Pot Holes in km. 184/650 to 190/00)

Estimated Cost:- 491624.00

Earnest Money :- 9900.00

Time :- One Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
1	Repairing of pot holes up to any depth and removal of loose material, trimming of sides, cleaning of surface by providing tack coat bitumen VG-10 at the rate of 0.300kg. /sqm. (Zero point three zero zero kilogrammes per squiremetre) 20mm (Twenty millimetre) thick premix carpet at the rate of 1.46kg./sqm.(One point four six kilogramme per square metre) and seal coat at the rate of 0.68kg./sqm. (Zero point six eight kilogramme per square metre) type B specification clause 1904.2, including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in- Charge	1355.27	362.75	Rupees Three hundred sixty two and paise seventy five only.	Per Square Metre	491624.00
					Total	491624.00

Draft schedule of quantity approved for Rs 24,91,624/-

Executive Engineer,
HPPWD Division
Nerchowk

(65)

DMFB.NO! - (549) 78. 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Mandi Gagal Chailchowk Janjehli Chhatari Nagan road km. 0/0 to 16/190. (SH:- Repair of Pot Holes in km. 1/0 to 2/00)

Estimated Cost:- 497078.00

Earnest Money :- 10000.00

Time :- One Month

S.N o	Description of item	Quantity	Time :- One Month		Unit	Amount
			Rate with all taxes including GST in			
			Rs.	P.		
			In figure	In word		
1	Providing, laying, spreading and compacting stone aggregate of sizes 53mm to 22.40mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-III by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	18.78	2290.00	Rupees Two thousand two hundred ninety and paise zero only	Per Cubic Metre	43006.00
2	Repairing of pot holes up to any depth and removal of loose material, trimming of sides, cleaning of surface by providing tack coat bitumen VG-10 at the rate of 0.300kg. /sqm. (Zero point three zero zero kilogrammes per squaremetre) 20mm (Twenty millimetre) thick premix carpet at the rate of 1.46kg./sqm.(One point four six kilogramme per square metre) and seal coat at the rate of 0.68kg./sqm. (Zero point six eight kilogramme per square metre) type B specification clause 1904.2, including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in- Charge	1251.75	362.75	Rupees Three hundred sixty two and paise seventy five only.	Per Square Metre	454072.00
					Total	497078.00

Draft schedule of quantity approved for 4,97,078/-

Executive Engineer,
HRPWD Division
Nerchowk

(66)

DMF S.NO. - 550 Yr. 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Chandigarh Mandi Manali (Old NH-21) road km. 184/650 to 198/050.
(SH:- Repair of Pot Holes in km. 190/0 to 198/050)

Estimated Cost:- 490826.00

Earnest Money :- 9900.00

Time :- One Month

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Repairing of pot holes up to any depth and removal of loose material, trimming of sides, cleaning of surface by providing tack coat bitumen VG-10 at the rate of 0.300kg./sqm. (Zero point three zero zero kilogrammes per squaremetre) 20mm (Twenty millimetre) thick premix carpet at the rate of 1.46kg./sqm. (One point four six kilogramme per square metre) and seal coat at the rate of 0.68kg./sqm. (Zero point six eight kilogramme per square metre) type B specification clause 1904.2, including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in- Charge	1353.07	362.75	Rupees Three hundred sixty two and paise seventy five only.	Per Square Metre	490826.00
					Total	490826.00

Draft schedule of quantity approved for 24,90,826/-

Executive Engineer,
HPPWD Division
Nerchowk

(67)

DNIT S.NO (553) Yr. 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Ratti to Kalkhar road km. 0/0 to 10/00. (SH:- Repair of Pot Holes in km. 0/0 to 4/00)


Estimated Cost:- 458020.00

Earnest Money :- 9200.00

Time :- One Month

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Providing, laying, spreading and compacting stone aggregate of sizes 53mm to 22.40mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-III by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	27.84	2290.00	Rupees Two thousand two hundred ninety and paise zero only	Per Cubic Metre	63754.00
2	Repairing of pot holes up to any depth and removal of loose material, trimming of sides, cleaning of surface by providing tack coat bitumen VG-10 at the rate of 0.300kg. /sqm. (Zero point three zero zero kilogrammes per square metre) 20mm (Twenty millimetre) thick premix carpet at the rate of 1.46kg./sqm. (One point four six kilogramme per square metre) and seal coat at the rate of 0.68kg./sqm. (Zero point six eight kilogramme per square metre) type B specification clause 1904.2, including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge	1086.88	362.75	Rupees Three hundred sixty two and paise seventy five only.	Per Square Metre	394266.00
					Total	458020.00

Draft schedule of quantity approved for 24.53.0281 P


 Executive Engineer,
 HPPWD Division
 Nerchowk