



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125 *
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

**CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
3717-25 DATED 20-07-2024 ARE URGENT NATURE
AND PUBLIC INTEREST.**

**Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.**



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Scaled item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before 05.08.2024 up to 11.30 A.M and will be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on 03.08.2024 between 2.00 PM up to 4.30 P.M and the application for issue of tender forms shall be received on 02.08.2024 up to 12.00 Noon.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Construction of Link road from Gawal Tikkar to Utrala 9/500 to 10/700 (SH: P/L C.C. Pavement at Km 9/400 to 9/450)	Rs.1,70,394/-	Rs.3,500/-	Rs.350/-	One Month
2	R.R. Damages on Sangrehar Dharman Road Km 0/00 to 8/050 (SH: C/O R/Wall along with C.C. Pusta at RD 0/341 to 0/350.50)	Rs.4,82,375/-	Rs.9,700/-	Rs.350/-	Two Months
3	Restoration of Rain Damages on Baijnath to Bhadoo road Km 0/00 to 6/00 (SH: C/O R/Wall at RD 1/150 to 1/162 alongwith C.C. Pusta)	Rs.3,53,403/-	Rs.7,100/-	Rs.350/-	One Month
4	R/R Damages for Laying of OFC on Paprola Utrala Binwa Nagar Road (SH: Supply and fixing Computer system in HPPWD Division Baijnath)	Rs.2,40,000/-	Rs.4,800/-	Rs.350/-	15 Days
5	R/R Damage on Binwa Nagar Road (SH: Supplying and Stacking of Cat Eyes)	Rs.2,55,094/-	Rs.5,200/-	Rs.350/-	One Month
6	R/R Damage on Binwa Nagar Road (SH: Supplying and Stacking of Delineators Km 10/0 to 18/0)	Rs.2,60,400/-	Rs.5,200/-	Rs.350/-	One Month
7	Main Bazar Bir to Bir Bus Stand (SH: C/O R/Wall at RD 0/225 to 0/245.30)	Rs.4,95,989/-	Rs.10,000/-	Rs.350/-	Two Months
8	Restoration of Rain Damages on Baijnath Phathar Binwa Nagar Road (SH: Unlined Drain)	Rs.4,95,600/-	Rs.10,000/-	Rs.350/-	One Month

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD., Baijnath.

For & On behalf of the governor of H.P.
Dated:- 20.07.2024

NO:-PWD/BD/TA/NIT/2024-25/-

- Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Baijnath Division.,
H.P.PWD., Baijnath.

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: Construction of Link Road From Gawal Tikhar to Utrala 9/500 to 10/700.
 (S.R. 1/1) (i. Pavement at km 9/400 to 9/450.)

Estimate Cost: 1,70,394.00/-
 Earnest Money: 3,200,000/-
 Tender Limit of one Month

SCHEDULE OF WORKS

Sl. No.	Description of work.	No. or QTY.	Unit	Rate		AMOUNT RS. P
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of petrol, royalty, Maakana, tolltax, Sale Tax or other taxes imposed by the government.	74.41	Per Cubic metre			
Total						

[Signature]
 Engineer
 P. Division
 D.D., P. Quater

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work : R/R Damages on Sangrehar Dhamman Road km 0.00 to 8.050.
(Shr. C/O R/W all along with C/C Pusta at RD 0.341 to 0.350.50)

Sr. No.	Description of work	No. or Qty	Unit	Rate		Amount Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other detentions materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantity of water including clearing of slush which may arise out during dewatering as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	8.17	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (1:1:4) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm forty millimeter) nominal size) in or under water and curing complete including pumping or hauling out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work, and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer-in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	51.30	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	44.01	Per Cum			
4	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	7.03	Per Cum			
5	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V) 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	18.00	Each			
	Total					

Executive Engineer
Bajnath Division
H.P.P.W.D. Bajinath (H.P.)

(3)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: Restoration of Rain Drainages on Baijnath to Bhattoo road km 0/00 to 6/00.
(Sb:- C/O R/W all at RD 1/150 to 1/162 along with C C Pasta).

Estimate Cost: 3,53,403.00/-
Earned Money: 1,00,000/-
Time Limit :One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. p
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks) Where blasting is prohibited for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	33.12	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth as per drawing and M.O.R.D. technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and bailing carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidentals complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	66.24	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	8.52	Per Cum			
4	Providing weep holes in brick masonry stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1% (20g/11) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	18.00	Each			
Total						

Engineer

Baijnath Division

P.O. P.W.D., Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - R/R Damages for laying of OFC on Paprola Utrala Binwa Nagar Road
(SH: Supply and fixing Computer system in HPPWD Division Baijnath)

Estimate Cost: 2,40,000.00
Earnest Money: 4,800.00
Time Limit : 15 Days

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Rate to be entered by the Bidder in		AMOUNT IN RS.
				Figures	Words	
1	Providing and installation HP AIO 3 27IAP7 Desktop with Intel Core i5-12450/1-12th Gen. Processor 16 GB DDR4 RAM expandable upto 32 GB, 1TB Hd Drive (7200RPM) 27" FHD LED colour display with FHD (1920x1080) integrated HD Graphics & webcam 2xUSB 3.0, 2xUSB 2.0, Audio jack/VGA/HDMI/DP port, 10/100/1000M compliant LAN USB keyboard & USB Mouse with High Definition Audio Chip connectivity 802.11b/g/n/ac, PL-Window 10Pro 64bit.O.S with three year onsite warranty.	2.00	Each			
2	Providing and installation HP Laser Jet Printer 3 IN 1 (Print + scanner + copy) with One Year Warranty The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of tolltax, GST & other taxes imposed by the government.	1.00	Each			
3	Providing and installation of Canon Printer A4 size printer upto 600 dpi resolution legal size printing. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	1.00	Each			


Baijnath Division,
H.P.P.W.D. Baijnath (H.P.)


SCHEDULE OF QUANTITY

Name of Work: R/R Damage ~~on Binwa Nagar Road~~
(SH: Supplying and Stacking of Delinators Km 10/0 to 18/0).

Estimated Cost: Rs. 260400/-
Earnest Money: Rs. 5200/-
Time Limit: One Month

SCHEDULE OF WORKS

S. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT RS. P
				Figure	Words	
1	Providing and installation of delinator of 60cm (sixty centimeters) height made out of M.S. pipe 40mm (forty millimeters) dia meter and 2mm (two millimeters) thickness painted yellow and white alternative strips with reflective tape on the top covered in M.S. wire 15cm (fifteen centimeters) height laminated with plastic coated paint complete as per direction of Engineer in Charge including carriage of material with in all leads and lifts and any other incidental charges.	465.00	Each			


Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajjnath (D.P.)

DNIT/DRAFT SCHEDULE OF QUANTITIES

Name of work: Mario Bazar Bir To Bir Bus Stand
(Sho- C/O R/W all at RD 0/225 to 0/245.30).

Estimate Cost: 4,95,989.00 -
Earnest Money: 10,000/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Amount Rs. p
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling, wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters), compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise on during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	22.14	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and North technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	94.80	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	10.96	Per Cum			
4	Providing weep holes in brick masonry stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(X:20(H)) towards drawing face complete as per drawing and technical specification clause 614, 700, 1204.3.7 including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	38.00	Each			
	Total					

Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajjnath (H.P.)

8

SCHEDULE OF QUANTITY

Name of Work: Restoration of Rain Damages on Baijnath Phathar Binwa Nagar Road
(SH: Unlined Drain)

Estimated Cost: Rs. 495600/-
Earnest Money: Rs. 10000/-
Time Limit: One Month

SCHEDULE OF WORKS

S. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Construction of unlined surface drains of average cross-sectional area 0.40 (zero point forty) square meter in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift up to 3m (three millimeter) and lead of 50m (fifty) millimeter average lead 25m (twenty five) millimeter specification clause 307, as directed by the Engineer-in-charge, within all leads, lifts of materials and other incidentals. Gradients- The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	16800.00	Per Run			


Executive Engineer
Baijnath Division,
H.P.P.W.D. Bajina (H.P.)