



Office of  
Executive Engineer Baijnath Division HP.PWD, Baijnath  
Himachal Pradesh Public works Department Baijnath-176125  
Phone No. 01894-263035 Fax 262704 e-mail:- [ee-baij-hp@nic.in](mailto:ee-baij-hp@nic.in)

## **CERTIFICATE**

**CERTIFIED THAT THE TENDERS OF WORKS, AS  
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-  
3824-33 DATED 15-07-2024 ARE URGENT NATURE  
AND PUBLIC INTEREST.**

**Executive Engineer,  
Baijnath Division,  
HP PWD, Baijnath.**



**Office of**  
**Executive Engineer Baijnath Division HP.PWD, Baijnath**  
**Himachal Pradesh Public works Department Baijnath-176125**  
**Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in**

**"NOTICE INVITING TENDER"**

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before 31.07.2024 up to 11.30 A.M and will be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on 30.07.2024 between 2.00 PM up to 4.30 P.M and the application for issue of tender forms shall be received on 29.07.2024 up to 12.00 Noon.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	R/R Damages on Barot Nalhota Road Km 0/00 to 15/225 (SH: C/O C.C. Pusta wall at RD 8/030 to 8/046)	Rs.2,19,836/-	Rs.4,400/-	Rs.350/-	Two Months
2	Restoration of rain damages on various Roads under Bir Sub Division (Multhan Section) (SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & cleaning of Slush from Catch Pit of Culverts)	Rs.2,53,000/-	Rs.5,100/-	Rs.350/-	Two Months
3	Restoration of Rain damages on Bir to Barot road Km 0/00 to 48/00 (SH: Hiring of JCB for removal of slips, dressing of road berms, filling depressions, clearance of Drain and Culvert in portion 14/00 to 32/00)	Rs.3,87,200/-	Rs.7,800/-	Rs.350/-	Two Months
4	Restoration of rain damages on Bir to Barot Raod Km 0/00 to 48/00 (SH: Hiring of Tipper for Carriage and disposal of Muck/slips)	Rs.94,500/-	Rs.2,000/-	Rs.350/-	Two Months
5	Restoration of rain damages on various Road under Baijnath Sub Division (Chadhiar Section) (SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & cleaning of slush from catch pit of culverts)	Rs.2,53,000/-	Rs.5,100/-	Rs.350/-	Two Months
6	C/O link road from Rainabari to Balh (SH: C/O Approaches Both Side Bridge at RD 1/209 to 1/210.95)	Rs.4,90,432/-	Rs.10,000/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,  
Baijnath Division.,  
H.P.PWD..Baijnath.

For & On behalf of the governor of H.P.  
Dated:- 15.07.2024

NO:-PWD/BD/TA/NIT/2024-25/-

3524-33

- Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,  
Baijnath Division.,  
H.P.PWD..Baijnath.



# DNIT/DRAFT SCHEDULE OF QUANTITY

①

Name of work : R/R Damages on Barot Nalhotu Road km 0.00 to 15.225.

(Sh:- C/O C C Pusta wall at RD 8.030 to 8.046.)

Estimate Cost: 2,19,836.00

Earnest Money: 4400.00

Time Limit : Two Months

Sr. No.	Description of work	No. or QTY	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling, wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	6.24	Per Cum				
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement, five sand, ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	11.92	Per Cum				
3	Providing weep holes in brick masonry, stone masonry, plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V) 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204 3.7 including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	14.00	Each				
Total							

Executive Engineer  
Bajnath Division,  
H.P.P.W.D. Bajjnath (H.P.)

②

## DNIT/SCHEDULE OF QUANTITY

Estimated Cost:- 2,53,000.00

Earnest Money:- 5,100.00

Time Limit:- Two Months

Name of work:- : Restoration of rain damages on various Roads under Bir Sub Division (Multhan Section )  
 (SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & cleaning of slush from catchpit of culverts)

Sr. No.	Description of items	Quantity	Rates (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In words		
1	2	3	4	5	6	7
1.	Hiring of Hydraulic Excavator having capacity of 0.9 Cum (zero point nine) in working condition per day basis with 8 (eight) hours per day excluding Sunday Holiday, for rainy seasons as and when required. The operational and maintenance charges POL charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator.	230.00 Hours			Per Hour	
Total						

Executive Engineer  
 Baijnath Division,  
 H.P.P.W.D. Baijnath (H.P.)

### Schedule of Quantity

③


Name of work:-Restoration of rain damages on Bir to Barot road km 0/00 to 48/00 (SH:-Hiring of JCB for removal of slips, dressing of road berms, filling depressions, clearance of Drain and Culvert in portion 14/00 to 32/00)

Estimate Cost 387200.00

Earnest Money 7800.00

Time Limit 2 months

Sr.No.	Description of item	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of JCB (Excavator cum Loader) having bucket capacity .50 cum including P.O.L. charges, shifting charges and other ancillary equipment as required at site of work for removal of slips in all heights in all kinds of soils such as kankar, moorum, shingle, boulders, decomposed or soft variety of soil with spade work, pick work, jumper work, soft rock, hard rock, if and when required. The disposal of this unserviceable material has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place, the contractor shall be liable for it. All salvaged material such as quarried stone shall have to be neatly stacked along road side on road berms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly The work shall have to be carried out as per the instructions of the Engineer-in-Charge including all leads and lifts.	352 00			Per hour	
	Total					

  
Executive Engineer  
Bajinath Division,  
H.P.P.W.D. Bajinath (H.P.)

④

Schedule of Quantity


Name of work-Restoration of rain damages on Bir to Barot Road km 0/00 to 48/00 ( SH :- Hiring of Tipper for Carriage and disposal of Muck/slips )

Estimated Cost 94500.00

Earnest Money 2000.00

Time 2 months

Sr.No.	Description of items	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of tipper for carriage of material having capacity of 200 cubic feet including POL charges and other ancillary equipment as required at the site of work .The work shall be carried out as per the Engineer in charge within all leads and lifts.	21.00			Per Day	
Total						

  
Engineer  
Division,  
J. B. Bijnath (H.P.)



(5)

## DNIT/SCHEDULE OF QUANTITY

Estimated Cost:- 2,53,000.00

Earnest Money:- 5,100.00

Time Limit:- Two Months

Name of work:- : Restoration of rain damages on various Roads under Baijnath Sub Division (Chadhiar Section)  
(SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & cleaning of slush from catchpit of culverts)

Sr. No.	Description of items	Quantity	Rates (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In words		
1	2		4	5	6	7
1.	Hiring of Hydraulic Excavator having capacity of 0.9 Cum (zero point nine) in working condition per day basis with 8 (eight) hours per day excluding Sunday Holiday, for rainy seasons as and when required. The operational and maintenance charges POL charges and other miscellaneous supply replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator.	230.00 Hours			Per Hour	
Total						

Executive Engineer  
Baijnath Division,  
H.P.P.W.D. Baijnath (H.P.)

## DNIT/DRAFT SCHEDULE OF QUANTITY

⑥ ②

Name of work: C/O Link Road From Rainabari to Balh.

(Sh:- C/O Approaches Both Side Bridge at RD 1/209 to 1/210.95).

Estimate Cost: 4,90,432.00/-

Earnest Money: ~~50,000~~ 10,000/- only.


Time Limit: Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P.
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D technical specification clause 305.1 and as per direction of the Engineer- In Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	14.61	Per Cum				
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:4:8 stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	39.53	Per Cum				
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm( forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.	54.21	Per cubic metre				
4	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	25.02	Per Cum				



(5/16)

5	Provide and sweep holes in brick masonry stone masonry plain reinforced concrete abutment, wing wall return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V to 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204 & 7 including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	12.00	Each			
	Total					

  
 Executive Engineer  
 Baijnath Division,  
 H.P.R.W.D. Baijnath (H.P.)