



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

SHORT TERM NOTICE INVITING TENDERS

Scaled item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **02/08/2024** up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **01/08/2024** up to 4.00 P.M and the application for issue of tender form shall be received on **31/07/2024** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	C/o link road from Boda to Rara Mandap via Harizan Basti Km. 0/0 to 2/0 (SW:- Providing and laying Soling in Km. 0/450 to 0/506 & Wearing in Km. 0/450 to 1/490) (under SCDP)	4,96,648/-	9900/-	Two Months	350/-
2	Restoration of rain damages on Parour Dheera Naura road Km. 0/0 to 17/0 (SW:- C/o R/Wall at Rd 14/110 to 14/115 & 14/135 to 14/151)	4,79,405/-	9600/-	One Month	350/-
3	C/o link road from Bhagolu da Ghatta Umri via Mohrian Km. 0/0 to 4/00 (SW:- P/L Soling in Km.0/00 to 4/00 (SW:- P/L Soling in Km. 1/500 to 2/250)	4,85,410/-	9700/-	Three Months	350/-
4	C/o Building at Dheera Tehsil Dheera Distt. Kangra (SW:- Balance work of Door & windows accessories, WS & SI and painting work)	4,32,882/-	8700/-	Three Months	350/-
5	Restoration of rain damages on Rud Panyali to Kohlru Ghamoon Galuhi Km. 0/0 to 9/330 (SW:- C/o PCC R/Wall at Rd 4/710 to 4/726)	4,94,400/-	9900/-	Two Months	350/-
6	C/o Santoshi Mata Malander Garthoon Road Km. 0/0 7/0 (SW:- Improvement of curve at Rd 1/870 to 1/960 & 2/130 to 2/265)	4,77,971/-	9500/-	Three Months	350/-
7	C/o link road from Boda to Rara Mandap via Harizan Basti Km. 0/0 to 2/0 (SW:- C/o 0.60mtr span Culvert at Rd 0/0 & Providing and laying CC Work in Km. 0/450 to 0/620) (under SCDP)	4,60,517/-	9200/-	Two Months	350/-
8	Restoration of rain damages on Bhadroon Kona Lahru Road Km. 5/0 to 12/800 (SW:- C/o R/Wall at Rd 9/893 to 9/910)	4,93,123/-	9800/-	Three Months	350/-
9	C/o link road from Bhagolu da Ghatta Umri Via Mohrian Km. 0/00 to 4/00 (SW:- P/L Soling and Wearing in Km. 2/250 to 2/500)	2,81,510/-	5600/-	Two Months	350/-
10	C/o Galu Ghanetta Baba Kripa Road Km. 0/0 to 5/00 (SW:- C/o RWall at Rd 1/390 to 1/401, Pusta 1/370 to 1/390 & U-Shape Drain at Rd 1/355 to 1/415)	4,46,523/-	8900/-	Two Months	350/-
11	C/o 19.75 metre span RCC T-Beam over Rian Khad on Sullah Majhakra Harbaral road at Rd 0/360 (SW:- C/o approaches Harbaral Side drom Rd 0/327 to.50 to 0/351.50)	4,99,888/-	10,000/-	Two Months	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK

Executive Engineer
Bhawarna Division
HPPWD Bhawarna
(On behalf of Governor of Himachal Pradesh)

No. PWD/BWD/Tender/NIT/2024-25/-

Copy to following for information and necessary action:-

1. The Principal Secy.(PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ),HPPWD, Dharamshala.
4. The Director, Information & Publications Department, HP Shimla.
5. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. The Sub-Divisional Officer(Civil) Palampur.
9. All the S.E.s/E.E.s under Kangra Zone.
10. All the Assistant Engineers under this Division.
11. The Drawing /Accounts Branch in this office.
12. Notice Board.

1
Executive Engineer
Bhawarna Division
HPPWD Bhawarna

Schedule of Quantity

Name of Work :- C/o link road from Boda to Rara Mandap via Harizan Basti Km 0/0 to 2/0. (SH:- Providing and Laying Soling in Km 0/450 to 0/506 & Wearing in Km 0/450 to 1/490) (Under SCDP).

Estimate Cost :-Rs. 4,96,648/-
Earnest Money :-Rs. 9900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	187.60			Per Square metre	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and reolling the sub- grade completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	187.60			Per Square metre	
3	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.76			Per Cubic metre	
4	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading in and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	249.80			Per Cubic metre	
Total :-						



Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of work:- Restoration of rain damages on Parour Dheera Naura road Km 0/0 to 17/0 (SH:- C/o R/wall at RD 14/110 to 14/115 & 14/135 to 14/151).

Estimated Cost :- Rs. 4,79,405/-
Earnest Money :- Rs. 9600/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing . removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	35.62			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	115.50			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	34			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of link road from Bhagolu Da Ghatta Umri Via Mohrian Km 0/00 to 4/00. (SH:-P/L Soling in Km. 1/500 to 2/250). Estimate Cost :-Rs. 4,85,410/-
Earnest Money :-9700/-

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2638.13			Per Square metre	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub- grade completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2638.13			Per Square metre	
3	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	263.81			Per Cubic metre	
Total :-						


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of work:- Construction of CHC Building at Dheera Tehsil Dheera Distt. Kangra (SH:- Balance work of Door & windows accessories, WS.& S.I and painting work).

Estimate Cost :- Rs. 4,32,882/-

Earnest Money :- Rs. 8700/-

Time Limit :- Three Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1.00	Providing and fixing coloured / anodized aluminum sliding door bolt, anodized transparent or dyed to required colour and shade with bolts and nuts, screws etcetra complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	20			Each	
1.01	300x16mm (Three hundred into sixteen millimeter) size	61			Each	
1.02	250x16mm (two hundred fifty into sixteen millimeter) size					
2.00	Providing and fixing coloured anodized aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	40			Each	
2.01	250x10mm (Two hundred fifty into ten millimetre) size	72			Each	
2.02	200x10mm (Two hundred into ten millimetre) size	82			Each	
2.03	150x10mm (One hundred fifty into ten millimetre) size	12			Each	
3.00	Providing and fixing aluminum round shape handle of outer dis 100mm (one hundred) powder coated minimum thickness 50 (fifty) with SS screws etcetra complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.					
4.00	Providing and fixing coloured / anodized aluminum handle anodized transparent or dyed to required shade or colour with necessary screws etcetra complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	110			Each	
4.01	125mm (one hundred twenty five millimetre) size					
4.02	100mm (one hundred millimetre) size	82			Each	

5.00	Providing and fixing 150mm (One hundred fifty millimetre) bright finished brass floor door stopper with rubber cushion screws etcetra to suit shutter thickness complete including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	41	Each	
6.00	Providing and fixing 150mm (One hundred fifty millimetre) M.S. acting spring hinges with necessary screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	66	Each	
7.00	Providing and fixing 20mm (Twenty millimetre) diameter chromium plated brass curtain rod and brackets plugs etc. complete including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	195.00	Per Running metre	
8.00	Providing and fixing 15mm (Fifteen millimetre) dia G.I. pipes ISI marked including fixing with approved adhesive etcetra complete upto all heights including entire carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	240	Per Running metre	
9.00	Providing and fixing heavy quality stainless steel kitchen sink of approved standard ISI marked with drain board and C.P. waste pipe C.I. or M.S. brackets painted white i/c cutting holes and making good the same including fitting 600x450x250 mm (six hundred into four hundred fifty into two hundred fifty millimetre) with bowl depth 20 mm (twenty millimetre) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	8	Each	
10.00	Providing and fixing 15mm (Fifteen millimetre) diameters C.P. brass bib cock of continental series of Jaguar/ Classic series of Hindware/ Floral series of Cera/ Hindson/ series of Jal as per specifications including carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	8	Each	
11.00	Providing and fixing 15mm (fifteen millimetre) bore, 105mm (one hundred five millimetre) long, weighing not less than 138 gms (one hundred thirty eight gram) PTMT Ball cock of approved brand and manufacture, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	4	Each	
12.00	Providing and fixing 15mm (Fifteen millimetre) dia uplasticised PVC connection pipe with brass unions of approved brand and manufacture, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.			
12.01	45cm length (Forty five centimetre) size	35	Each	

12.02	60cm length (Six centimetre) size	25		Each	
13.00	Applying Birla white cement based putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1013		Per Square Metre	
14.00	Applying priming coat on new concrete/ masonry/ asbestos cement plastered surfaces after and including preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand appearing as required with ready mixed primer complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3114		Per Square Metre	
		Total:-			


 Executive Engineer
 Bhawarna Divya
 HP-PWD Bhawarna

Schedule of Quantity

Name of work:- Restoration of rain damages on Rud Panyali to Kohlr Ghamoon Galuhi Km 0/0 to 9/330 (SH:- Construction of PCC R/wall at RD 4/710 to 4/726).

Estimated Cost :- Rs. 4,94,400/-
Earnest Money :- Rs. 9900/-
Time Limit :- Two Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	29.28			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	119.52			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	36			Each	
Total :-						


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of Work: -Construction of Santoshi Mata Malandher Garthoon Road Km 0/0 to 7/0 (SH:-Improvement of curve at Rd 1/873 to 1/960 & 2/130 to 2/265).

Estimate Cost :-Rs. 4,77,971/-
Earnest Money :- Rs. 9500/-
Time Limit :- Three Months

Sl. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chieselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling fine dressing and carriage of machineries, materials, tools, equipment and safety measured and other incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stones to the tune of 816 98 cubic metre quantity at the rate of Rs. 300/- per cum shall be effected from the contractor's running bill on Pro-rata basis as per actual quantity executed. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	3438 64			Per Cubic metre	
			Total :-			


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of work:- C/o link road from Boda to Rara Mandap via Harizan Basti Km 0/0 to 2/0. (SW:- C/o 0.60 mtr span culvert at RD 0/0 & Providing and laying CC work in Km 0/450 to 0/620) (Under SCDP).

Estimate Cost :- Rs. 4,60,517/-
Earnest Money :- Rs. 9200/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	3.42			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge. Including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	3.42			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete nominal mix 1: 2 ½ : 5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments, parapet etcetra and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	6.73			Per Cubic metre	
4	Providing and laying mechanically mixed and vibrated reinforced cement concrete in super structure as per drawing and M.O.R.D. technical specification section 800, 900 & 1400 RCC Grade M-25 (M- twenty five) designed mix with minimum cement contents not less than 400 (Four hundred) Kilogram per cubic meter with 20mm (Twenty millimeter) nominal size grade crushed stone aggregate and curing complete including cost of form work, but excluding the cost of reinforcement for reinforced cement concrete work in slab & wheel guard etcetra as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.28			Per Cubic metre	

5	Supplying, fitting and placing HYSD bar reinforcement in super structure complete with straightening, bending, binding of bars including the cost of binding wire in all heights / depths as per drawing and MORD technical specification section 1000 and 1400 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the government.	113 850			Per Kilogram
6	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	63 75			Per Cubic metre
		Total:-			


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- Restoration of Rain Damages on Bhadroon Kona Lahro Road Km 5/0 to 12/800. (SH:-C/o R/Wall at Rd 9/893 to 9/910).

Estimate Cost :- Rs. 4,93,123/-
Earnest Money :-9800/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	38.93			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	118.66			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	35			Each	
		Total :-				


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of link road from Bhagolu Da Ghatta Umri Via Mohrian Km 0/00 to 4/00. (SH:-P/L Soling and Wearing in Km.
2/250/- to 2/500). Estimate Cost :-Rs. 2,81,510/-
Earnest Money :-5600/-

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	879.38			Per Square metre	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub- grade completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	879.38			Per Square metre	
3	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	87.94			Per Cubic metre	
4	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	63.00			Per Cubic metre	
Total :-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of work:- Construction of Galu Ghanetta Baba Kripa Road Km. 0/00 to 5/000 (SH:-C/O R/Wall at Rd.1/390 to 1/401, Pustta 1/370 to 1/390 & U-Shape Drain at Rd 1/355 to 1/415).

Estimate Cost :- Rs. 4,46,523/-
Earnest Money :- Rs. 8900/-

Time Limit :- Two Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling and wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	53.11			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge. Including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	8.93			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	96.89			Per Cubic metre	
4	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22			Each	
Total:-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- Construction of 19.75 metre span RCC T-Beam Bridge over Rain Khad on Sullah Majhakra Harbaral road at RD 0/360. (SH:- C/o approaches Harbaral Side from RD 0/327.50 to 0/351.50).

Estimate Cost :- Rs. 4,99,888/-
Earnest Money :- Rs. 10000/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers, including shoring and strutting and pumping and bailing, out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	65.52			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana.toll tax, GST or other taxes imposed by the Government.	112.46			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	50			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.24			Per Cubic metre	
Total :-						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna


Executive Engineer
Bhawarna Division
HP PWD Bhawarna