



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
INVITATION FOR BIDS (IFB)

Office 01783-260033

Email : ee-cho-hp@nic.in

No. PW.CHD.CB.E-9/2024-

2714-2813

Dated : 25/07/2024

NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited by the Executive Engineer HPPWD Chopal District Shimla H.P. in form No. 6 & 8 on behalf of Governor of H.P for the following works from the contractors of appropriate class enlisted with HPPWD. The tenders shall be opened in the presence of the contractors/firms or their representative who wish to be present.

TIME SCHEDULE OF TENDER

1. Date and time of receipt of application for tender form : 06.08.2024 up to 04:00 PM
2. Date and time of issue of tender form : 06.08.2024 04:00 PM to 05:00 PM
3. Date and time of receipt of tenders : 07.08.2024 11:00 AM
4. Date and time of opening of tender : 07.08.2024 11:30 AM

The tender forms will be issued to only those contractors who qualify the criteria after the scrutiny of application forms.

Sl. No	Name of Work	Estimated Cost	EMD	Cost of tender	Time Limit	Eligible class of contractor
1.	A/R & M/O Naura to Kulag road km. 0/0 to 5/345 (SH: C/o balance work of wire crated R/wall at R.D. 0/615 to 0/637).	183019.00	3700.00	350.00	One month	Class D or above
2.	A/R & M/O Arr to Lilidhar road km. 0/0 to 1/200 (SH: Improvement of black spot in km. 0/360 to 0/420 & 0/915 to 0/960).	223295.00	4500.00	350.00	One month	Class D or above
3.	Restoration of rain damages on Belog to Ranvi road km. 0/0 to 12/0 (SH: C/o B/wall at R.D. 10/753 to 10/764.25).	484709.00	10000.00	350.00	One month	Class D or above
4.	A/R & M/O Batera to Kandal road km. 0/0 to 10/405 (SH: C/o wire crate B/wall at R.D. 9/915 to 9/940).	278142.00	6000.00	350.00	One month	Class D or above
5.	A/R & M/O Dhanat to Maneoty road km. 0/0 to 13/0 (SH: C/o Edging and P/L stone soling in between km. 2/800 to 2/900).	213561.00	4500.00	350.00	One month	Class D or above
6.	C/o link road to Kanwarani Bassa road km. 0/0 to 1/0 (SH: C/o PCC 1:4:8 B/wall at R.D. 0/700 to 0/730).	263334.00	6000.00	350.00	One month	Class D or above
7.	Repair & maintenance of HPPWD Rest House Chopal (SH: Repair of tiles work and sanitary items for set No.1 & 3).	498996.00	10000.00	350.00	One month	Class D or above


TERMS AND CONDITIONS:-

1. The earnest money in the shape of National Saving Certificate, Time Deposit Account in any of the post office in HP/FDR of any Bank duly pledged in favour of Executive Engineer, Chopal Division HPPWD Chopal must be accompanied with the application for receipt of tender form along with cost of tender form in cash (Non refundable).
2. The conditional tender(s) and the application received without earnest money will summarily be rejected without assigning any reason(s).
3. The contractors/firms should possess the following documents (photo copy to be self attested with application for obtaining the tenders documents :-
 - a. Latest enlistment/renewal orders with application.
 - b. GST Number issued by the Sale Tax Department.

- c. PAN (Permanent Account Number) issued by the Income Tax Department shall contain scanned copies of EPF issued from competent authority.
4. The Executive Engineer, Chopal Division HPPWD Chopal reserves the right to reject any tender without assigning any reason(s).
 5. Only two number tender forms will be issued to the eligible contractor. If he bids for more than two works, only the first two works in sequence will be opened.
 6. The work shall have to be started within fifteen days from the date of award. If the contractor fails to start the work within fifteen days, the work shall be cancelled and earnest money deposited will be forfeited.
 7. The Cess Charges @ 1% will be deducted from the gross amount of work done of the contractor.
 8. The work will be completed by the contractor within the stipulated period.
 9. The contractor/firms are required to insert the rate of percentage in words as well as in figures, failing which Executive Engineer reserves the right to accept/reject any/overall tender.
 10. The tender shall be issued to only those contractor/firms who are eligible suitable and competent.
 11. The tender forms shall be issued to eligible contractors depending upon their past performance and work experience.
 12. The contractor/firm having necessary documents and past adequate experience shall be preferred.
 13. The contractor who has failed to start/complete the work already allotted in his favour within stipulated period shall not be issued tender forms.
 14. A contractor enlisted in a particular class is eligible to tender for his own class and one step below.
 15. In case the tender opening/sale date falls on a holiday, the fixed eventualities shall take place on the next working day at the same time and venue.
 16. GST will be deducted as per rates fixed by the Government.


CERTIFICATE


It is certified that tender for the above works are urgently required please.


Executive Engineer,
Chopal Division HPPWD Chopal
On behalf of Governor of H.P.

Copy forwarded for information to :-


1. The Chief Engineer (Shimla Zone) HPPWD Shimla.
2. The Superintending Engineer, 04th Circle, HPPWD Shimla.
3. The Deputy Commissioner, Shimla.
4. The SDO(C) Chopal Tehsil Chopal District Shimla H.P.
5. The BDO Chopal Tehsil Chopal District Shimla H.P.
6. All the Assistant Engineers working under this Division.
7. All the intending contractors in HPPWD.
8. Notice Board.


Executive Engineer,
Chopal Division HPPWD Chopal



CERTIFICATE

Certified that the tender(s) of work(s) as called vide this
office NIT No. PW.CHD.CB.C-9/2023-24- 2714-2813 dated
25/7/2024 are of urgent nature work(s).


Executive Engineer
Chopal Div. HPPWD Chopal
On behalf of Governor of H.P.

SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 183019
Earnest Money	Rs. 3700
Time Allowed	One Month

Name of work : A/R & M/O Naura to Kulag road km 0/00 to 5/345 (SH : C/O balance work of wire crated R/wall at RD 0/615 to 0/637 .)						
Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming IS: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	54.56	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre	158224
2	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.10	950.00	Rupees nine hundred fifty and paisa zero only	Per cubic metre	24795
					Total	183019
	Quoted rate in figure.					
	Quoted rate in words.					

31
Executive Engineer
S&R Division H.P.P.
Gopald

SCHEDULED OF QUANTITY.

(3)

Estimated Cost	Rs. 223295
Earnest Money	Rs. 4500
Time Allowed	One Month

Name of work : A/R & M/O Arr to Liliidhar road km 0/00 to 1/200 (SH : Improvement of black spot at RD 0/360 to 0/420 & 0/915 to 0/960 .)						
Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Excavation in earth work in hilly area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformity with the requirement of technical specification for Rural Roads clause 1600 and 300, 8.3 (ii)(iv)(v) to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material in specified manner, trimming, filling of uneven ness, blind age and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. At least 54.54 Cubic metre useful stone shall be recovered from the contractor in each running bill as per pro-rata basis if fails recovery @ Rs. 300/- (Rupees three hundred) per cum will be made. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	909.00	245.65	Rupees two hundred fourty five and paisa sixty five only	Per cubic metre	223295
					Total	223295
	Quoted rate in figure.					
	Quoted rate in words.					

(Signature)
Executive Engineer
B&R Division HRPV
Oregeal

SCHEDULED OF QUANTITY.

(20/6)

Estimated Cost	Rs. 484709
Earnest Money	Rs. 10000
Time Allowed	One Month

Name of work : R/R damage on Belog to Ranvi road km 0/00 to 12/00 (SH : C/O wire crate R/wall at RD 10/753 to 10/764.25.)						
Sl. No.	Description of item	Qty.	Rate	In words	Unit	Amount
			In figure			
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 m and a lead upto 20 m as per drawing and technical specification clause 1603.1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	77.34	195.00	Rupees one hundred ninety five and paisa zero only	Per cubic metre	15081
2	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	21.26	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	4465
3	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming IS: 280 and IS:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	158.19	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre	458751
4	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.75	950.00	Rupees nine hundred fifty and paisa zero only	Per cubic metre	6413
					Total	484709
	Quoted rate in figure.					
	Quoted rate in words.					

EXCLUSIVE ENGINEER
S&R Division H.P.V.M.
[Signature]

SCHEDULED OF QUANTITY.

Name of work : A/R & M/O Batera to Kandal road km 0/00 to 10/405

(SH : C/O wire crate B/wall at RD 9/915 to 9/940 .)

Estimated Cost	Rs. 278142
Earnest Money	Rs. 6000
Time Allowed	One Month

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.50	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	6615
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming IS: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	93.63	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre.	271527
	Quoted rate in figure.				Total	278142
	Quoted rate in words.					

278
Executive Engineer
S&R Division HPPV
Chopped

SCHEDULED OF QUANTITY.

(6)

Estimated Cost	Rs. 213561
Earnest Money	Rs. 4500
Time Allowed	One Month

Name of work : A/R & M/O Dhanat to Maneoty road km 0/00 to 13/00		(SH : C/O Edging and P/L stone soling at RD 2/800 to 2/900 .)				
Sl. No.	Description of item	Qty.	Rate	In words	Unit	Amount
1	Preparing the surface by brushing with wire brushes for removing of all cocked mud etc. sweeping with brooms and finally fanning the cleaned surface with gunny bags in remove all loose dirt etc size including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	167.50	2.00	Rupees two and paisa zero only	Per cubic metre.	335
2	Consolidation of subgrade with road roller to the required gradient and camber including making good the undulations etc and rolling the subgrade including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	167.50	3.00	Rupees three and paisa zero only	Per cubic metre.	502
3	Stone soling properly hand packed filling interies with kharanja stone and consolidation with power road roller to the required gradient and camber including spreading watering and rolling of widding materials moorum or earth etc including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.12	2200.00	Rupees two thousands two hundred and paisa zero only	Per cubic metre.	55264
4	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36.00	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	7560
5	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00	950.00	Rupees nine hundred fifty and paisa zero only	Per cubic metre.	9500

Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by machanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.

27.00	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre	140400
			Total	213561
Quoted rate in figure.				
Quoted rate in words.				

CH
EXECUTIVE ENGINEER,
B&R Division HPT,
Chennai

SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 263334
Earnest Money	Rs. 5500
Time Allowed	One Month

Name of work : C/O link road to Kanwari Bassa road km 0/00 to 1/00

(SH : C/O PCC 1:4:8 B/wall at RD 0/700 to 0/730 .) Under MND

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	42.00	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	8820
2	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	48.00	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre.	249600
3	Providing weep holes in brick masonry plain/reinforced concrete abutment wing wall retaining wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (v) 20 (h) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204, 3.7. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.20	195.00	Rupees one hundred ninety five and paisa zero only	Per running metre.	4914
					Total	263334
	Quoted rate in figure.					
	Quoted rate in words.					

Executive Engineer
B&R Division HPP
Chennai

SCHEDULED OF QUANTITY.

(8)

Estimated Cost	Rs. 498996
Earnest Money	Rs. 10000
Time Allowed	One Month

Name of work : Repair & maintenance of HPPWD Rest House Chopal (SH: Repair of Tile work and Sanitary work for set no 1 & 3.)						
Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead, including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	62.40	172.20	Rupees one thousand seventy two and twenty paise only	Per square metre.	10745
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	62.40	1571.05	Rupees one thousand five hundred seventy one and five paise only	Per square metre.	98034
3	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete, including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	62.40	490.00	Rupees four hundred ninety and paise zero only	Per square metre.	30576
4	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). (Item No. 11.47.2) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	62.40	2065.10	Rupees two thousand sixty five and ten paise only	Per square metre.	128862

5	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.(Item No .11.37A) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	58.80	1278.60	Rupees one thousand two hundred seventy eight and sixty paisa only	Per square metre .	75182
6	Providing and Fixing Electric Giger for the bathrooms of rest house, including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	10,000.00	Rupees ten thousand and paisa zero only	Each .	20000
7	Providing and fixing floor mounted, white vitreous china single piece, double traps syphonic water closet of approved brand/make, shape, size and pattern including integrated white vitreous china cistern of capacity 10 litres with dual flushing system, including all fittings and fixtures with seat cover, cistern fittings, nuts, bolts and gasket etc. including making connection with the existing P/S trap, complete in all respect as per directions of Engineer-in-Charge. (Item No. 17.81) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	17,726.30	Rupees Seventeen thousand seven hundred twenty six and thirty paisa only	Each .	35453
8	White Vitreous China Surgeon type wash basin of size 660x460 mm with single 15 mm C.P. brass pillar taps with elbow operated levers ISI Marked. (Item No. 17.7.9) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	5,448.25	Rupees five thousand four hundred forty eight and twenty five paisa only	Each .	10897
9	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. (Item No. 17.31) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	1,350.00	Rupees one thousand three hundred fifty and paisa zero only	Each .	2700
10	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms. (Item No. 17.71) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	185.20	Rupees one hundred eighty five and twenty paisa only	Each .	370

11	Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms. (Item No. 17.72) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	228.20	Rupees two hundred twenty eight and twenty paise only	Each	456
12	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., complete. (Item No. 17.33) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	660.60	Rupees six hundred sixty and sixty paise only	Each	1321
13	Providing and fixing to wall ceiling floor galvanised mild steel tubes (Medium grade), tube fittings and clamps (Medium grade) tube fitting and clamps including making good the wall ceiling and floor all modes of transportation in all leads lifts and all incidental charges. a) 20mm nominal bore including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	134.00	250.00	Rupees two hundred fifty and paise zero only	Per running metre	33500
14	Providing and fixing PVC soil, waste and ventilating pipes and jointing complete all modes of transportation in all leads lifts and all incidental charges. (i) 100 mm (one hundred millimeter) nominal bore including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	57.00	450.00	Rupees four hundred fifty and paise zero only	Per running metre	25650
15	Providing PVC fittings and accessories required all modes of transportation in all leads lifts and all incidental charges. Plain Bend/ single equal branch/ other fittings etc (i) 100 mm (one hundred millimeter) nominal bore (A.R.) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00	250.00	Rupees two hundred fifty and paise zero only	Each	2500
16	Providing & fixing 100mm (hundred mm) dia PVC floor trap of self cleaning design i/c cutting and making good the walls and floors all modes of transportation in all leads lifts and all incidental charges. :- (i) 75 mm (one hundred millimeter) nominal bore (A.R.) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00	300.00	Rupees three hundred and paise zero only	Each	3000

17	Providing and fixing 100 mm size P or S trap for water closet squatting pan including jointing the trap with soil pipe with approved quality adhesive all modes of transportation in all leads lifts and all incidental charges. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00 ✓	600.00 ✓	Rupees six hundred and paisa zero only	Each	2400 ✓
18	Providing & fixing dia CI union for wash basin or sink all modes of transportation in all leads lifts and all incidental charges. (a) 32mm dia including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00 ✓	400.00 ✓	Rupees four hundred and paisa zero only	Each	1600 ✓
19	Providing and fixing 100 mm (Hundred milimetre) sand cast iron grating for gully, floor or Nahni Trap including carriage of materials within all leads, lifts and other incidentals and as directed by the Engineer-in-Charge including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00 ✓	150.00 ✓	Rupees one hundred fifty and paisa zero only	Each	1500 ✓
20	Providing & fixing CP brass bib tap with capstan head all modes of transportation in all leads lifts and all incidental charges. (a) 20 mm dia including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.00 ✓	700.00 ✓	Rupees seven hundred and paisa zero only	Each	8400 ✓
21	P/F CP brass angle valve 15 mm without nut and pipe all modes of transportation in all leads lifts and all incidental charges. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.00 ✓	450.00 ✓	Rupees four hundred fifty and paisa zero only	Each	4050 ✓
22	P/F CP brass waste for wash basin/ sink including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.00 ✓	300.00 ✓	Rupees three hundred and paisa zero only	Each	1800 ✓
					Total	498996
	Quoted rate in figure.					
	Quoted rate in words.					

✓
Executive Engineer,
B&R Division HPT
Gangolli