



Office of
Executive Engineer B&R Division HP.PWD, Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P.) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 05-08-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 01-08-2024 up to 10:00 A.M. to 12:30 P.M. and tender form can be had from this office on 02-08-2024 from 2.00 P.M. to 5.00 P.M. The earnest money as shown against each in the shape of F.D.R. of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Restoration of rain damages on Link road from Triveni Mahadev to Sainthal Link km. 0/00 to 1/00 (SH:- Construction of Breast wall at km. 0/00 to 0/020).	Rs. 2,68,595/-	Rs. 5,400/-	Rs. 350/-	Class "D"	Three Months
2	Restoration of rain damages on Bhararu Banaru Dom road km. 0/00 to 4/500 (SH:- Providing and laying Kharanja Stone Soling & Cement Concrete pavement at km. 1/745 to 1/760 & 1/770 to 1/780).	Rs. 1,18,166/-	Rs. 2,400/-	Rs. 350/-	Class "D"	Three Months
3	Restoration of rain damages on Dhelu Yora Tikru road km. 0/00 to 5/525 (SH:- Construction of Retaining wall at km. 2/960 to 3/005).	Rs. 4,98,192/-	Rs. 10,000/-	Rs. 350/-	Class "D"	Three Months
4	Restoration of rain damages on Ladruhin to Dohag road km. 0/00 to 2/300 (SH:- Providing and laying of wearing G-II & Cement concrete pavement in Shoulder at km. 1/085 to 1/305).	Rs. 2,44,870/-	Rs. 4,900/-	Rs. 350/-	Class "D"	Three Months
5	A/R & M/O to various Non Residential Buildings under Joginder Nagar Division HP PWD, Joginder Nagar (SH:- Providing and Fixing PVC Paneling at Inspection Hut Makrin).	Rs. 4,93,999/-	Rs. 9,900/-	Rs. 350/-	Class "D"	Three Months
6	A/R & M/O to various Non Residential Buildings under Joginder Nagar Division HP PWD, Joginder Nagar (SH:- Providing and Fixing PVC Paneling and Aluminum Door Window at Inspection Hut Neri).	Rs. 1,82,246/-	Rs. 7,500/-	Rs. 350/-	Class "D"	Three Months
7	Construction of road C.C. from Pargi-Khodpadhar Sarlu to Dhan Village in G.P. Ner Gharwasra under MPLAD Deposit (SH:- Providing and laying Kharanja Stone Soling & C.C. pavement at km. 0/038 to 0/080 & 0/180 to 0/218).	Rs. 2,56,017/-	Rs. 5,100/-	Rs. 350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/firm shall have his registration and GST No. the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar,
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2023-24- 4800-49

Dated:- 02/07/2024

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar

(1) **SCHEDULE OF QUANTITY**

Name of Work: Restoration of Rain Damages on Link road from Triveni Mahadev to Sainthal Link km 0/00 to 1/00				Estimate Cost: 2,68,596.00	
SH: Construction of Breast wall at km 0/00 to 0/020)				Earnest Money: 5,400.00	
Description of work				Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT
				Figures	Words
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.80	Per cubic metre		
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	47.00	Per cubic metre		

①

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	36.00	Each			
Total						


 Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

(2)

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Bharau Banaru Dom Road km 0/00 to 4/500 (SH: Providing and Laying Kharanja Stone Soling & Cement Concrete Pavement at km 1/745 to 1/760 & 1/770 to 1/780)					Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.00	Per Cubic metre				
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.50	Per Cubic metre				
Total							


 Executive Engineer
 B & R Division HP.PWD.
 Jodhpur Nagar

(2)
SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Dhelu Yora Tikru road km 0/00 to 5/525 (SH: Construction of Retaining wall at km 2/960 to 3/005)				Estimate Cost: Earnest Money: Time Limit :			4,98,192.00 10,000.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Figures	Rate	AMOUNT	
					Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	28.80	Per cubic metre				
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	93.60	Per cubic metre				

(4)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.40	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	29.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

DNIT/DRAET SCHEDULE OF QUANTITY

Name of Work: Restoration of Rain Damages on Lad Rubin to Dobag road km 0.00 to 2.300 (S.H. : Providing and laying of Wearing C-II & Cement Concrete pavement in Shoulder at km 1.085 to 1.305)					Estimate Cost: 2,44,970.00 Earnest Money: 4,998.00 Time Limit: Three Months		
Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D as per specification without 100 & 1000 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, timber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials used for construction at suitable sites and safe disposal of unsuitable cut materials as specified in contract. Filling of unevenness and finishing the road to specified dimension as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water to meet with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	48.51	Per cubic metre	452 95	Rupees Four Hundred Fifty Two And Paise Ninety Five Only	21,973.00	
2	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three-wheel 80-100 KN (eighty hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening, binding materials to fillup the interstices of coarse aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.79	Per cubic metre	2,300.90	Rupees Two Thousand Three Hundred And Paise Ninety Only	47,836.00	

(4)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications: M-20 (twenty) grade coarse and fine aggregate conforming to IS-383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	26.40	Per Cubic metre			
	Total					


 Engineer
 B & R Division HP PWD,
 Jodhpur Nagar

SCHEDULE OF QUANTITY

name of work : A/R & M/O to various Non Residential Buildings under Joginder Nagar Division HPPWD Joginder Nagar (SH: Providing and Fixing PVC Paneling at Inspection Hut Makriri)

Sl. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit : Three Months
				Figures	Words	
						AMOUNT Rs. P
1.	Providing and fixing of pvc wall panels complete in all respect including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	122.57	Per Square Meter			
2.	Providing and fixing 19mm (nineteen millimeter) thick water proof termite resistant commercial board box including shelves. Back side of the box shall be of 6mm thick ply and all cut portion of the shelves shall be finished with 6mm hard wood edging. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.21	Per Square Meter			
3.	Providing and fixing 1.00mm (one millimeter) thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.21	Per Square Meter			
4.	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) in 2nd class deodar wood. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer -In- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.0098	Per Cubic Meter			
Total						


 B & R Division HP PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of work: V/R & M/O to various Non Residential Buildings under Joginder Nagar Division HPPWD Joginder Nagar (SH: Providing and Fixing PVC Paneling and Aluminum Door Window at Inspection Hut Neri)					Estimate Cost: 3,82,246.00 Earnest Money: 7,600.00 Time Limit: Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate			AMOUNT Rs. P
				Figures	Words		
1	Providing and fixing of pvc wall panels complete in all respect including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	40.42	Per Square Meter				
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS- 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including cleat angle, Aluminium snap heading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For shutters of doors, windows & ventilators including providing and fixing hinges, pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket require (Fittings shall be paid for separately) for fixed portion Powder coated aluminium (minimum thickness of powder coating 50 (fifty micron) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.90	Per Kilogramme				
3	Providing and fixing 12mm (twelve millimeter) curtain rods of 25 mm (one point two five millimeter) thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	31.05	Per Square Meter				

(6)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing, stitching and fixing curtain cloth of cotton of fine quality of size 2.10 (two point one zero) metre, long and 1.20 (one point two zero) metre wide including fixing rings of approved quality at suitable spacing complete in all respect including carriage of materials within all leads and lifts and other incidentals. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	41.00	Each			
5	Providing and fixing in wall lining flat pressed three layer (medium density) particle board or graded wood Pre-laminated one side decorative lamination and other side balancing lamination Grade 1, Type II, IS : 12823 marked, including priming coat on unexposed surface, with necessary fixing arrangement and screws etc. complete. 12mm (twelve millimeter) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.73	Per Square Meter			
6	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.76	Per cubic metre			
7	Providing and laying cement concrete work 1:2:4 (one Cement isto two Sand isto four graded stone aggregate twenty millimeter nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in foundations, footings bases of columns and the like and mass concrete as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.76	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
8	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	637.56	Per Kilogramme			
9	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows With 12 mm (twelve millimeter) mild steel U beading using wire gauge with average width of aperture 1.4 mm (one point four millimeter) in both directions with wire of dia 0.63 mm (zero point six three millimeter) all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	106.70	Per Square Meter			
	Total					

Executive Engineer
B & R Division HP.PWD,
Jalandhar

SCHEDULE OF QUANTITY

Name of Work : Construction of road C.C. from Pargi-Khodpadhar- sarfu to Dhan Village in G.P. Ner Gharwasra under MPLAD Deposit (SH: Providing and Laying Kharanja Stone Soling & CC Pavement at km 0/038 to 0/080 & 180 to 0/218)				Estimate Cost:		
				Earnest Money:		
				Time Limit :		
Description of work				Rate	AMOUNT	
				Figures	Words	Rs. P
No. or Qty.	Unit					
33.00	Per Cubic metre	1. Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.				
27.50	Per Cubic metre	2. Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.				
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar