



Office of
Executive Engineer B&R Division HP.PWD, Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Scaled item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 13-08-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 09-08-2024 up to 10:00 A.M. to 12:30 P.M. and tender form can be had from this office on 12-08-2024 from 2:00 P.M. to 5:00 P.M. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Restoration of Baijnath Jatehar Golwan Draman Ahju Chowki Sainthal Dahag Joginder Nagar Garoru Majharnoo Basi Kundani Manoh Kaa Bhararu Bahun Naultali Damela Padhar road km. 0/00 to 85/00 (Portion Dhelu Bhatehar) (SH:- Construction of Retaining wall at km. 33/970 to 33/974 & 33/940 to 33/943.50).	Rs.2,59,679/-	Rs.5,200/-	Rs.350/-	Class "D"	Three Months
2	Restoration of rain damages various roads under Joginder Nagar Division Sub Division HP PWD, Joginder Nagar (Bhararu Section) Monsoon 2023-24 (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.).	Rs. 99,060/-	Rs.2,000/-	Rs.350/-	Class "D"	One month
3	Restoration of Joginder Nagar Sarkaghat Ghumanwin road km. 0/00 to 34/300 (SH:- C/O R/Wall at km. 12/195 to 12/205).	Rs. 4,57,384/-	Rs.9,100/-	Rs.350/-	Class "D"	Three Months
4	Restoration of Sandapattan Bharol Bagora Bagla Haru Ropari Kolang Triambli Bashaal Drubbal Charonj Banwar Kun Ka Tar Mandokhar Bhargoan Kotli road (MDR-57) km. 0/00 to 810/00 (SH:- C/O Retaining wall at km. 43/160 to 43/170).	Rs.2,42,498/-	Rs.4,800/-	Rs.350/-	Class "D"	Three Months
5	Restoration of rain damages various roads under Joginder Nagar Division Sub Division HP PWD, Joginder Nagar (Bhararu Section) Monsoon 2023-24 (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.).	Rs. 99,060/-	Rs.2,000/-	Rs.350/-	Class "D"	One month
6	Construction of link road from Ladruhin to Join Dhelu Chowki Chauntra road km. 0/0 to 2/300 (SH:- Providing and laying of Wearing G-II and Cement Concrete pavement in berms at km. 0/435 to 0/657).	Rs.4,96,214/-	Rs.9,900	Rs.350/-	Class "D"	Three months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar,
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW/JND-B&R-EA-INIT/Press/2023-24- 5317-66

Dated:- 08/07/2024

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

SCHEDULE OF QUANTITIES

Name of Work: Restoration of Baijnath Jathar Golwan Draman Ahju Chowki Sainthal Dohag Joginder Nagar Garoru Majharnoo Bassi Kundani Manoh Kas Bhararu Bihun Nauhali Damela Padhar Road km 0/00 to 85/00 (Portion Dhelu Bhatehar) (SH: Construction of Retaining wall at km 33/970 to 33/974 & 33/940 to 33/943.50)				Estimate Cost: Earnest Money: Time Limit :		
Description of work				Rate		AMOUNT Rs. P
Sr. No.	No. or Qty.		Unit	Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and A.L.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials, useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.		13.50	Per cubic metre		
2	Providing and laying cement concrete 1:5:10 (one cement, five sand, ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plants and curing complete including the cost of form work in Retaining walls Breast walls, in of under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MOR technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.		48.60	Per cubic metre		

(7)

Description of work

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.50	Per cubic metre			
Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
Total					

Executive Engineer
B & R Division HP, PWD,
Jodhpur Nagar

9.00
0.00
nths

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time:- One Month

Name of work:- Restoration of rain damages on various roads under Joginder Nagar Division sub Division Joginder Nagar (Bhararu Section) (Mon-Soon 2023-24).
 Sub Head:-Hiring of excavator cum loader for removal of slips,dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips,dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk,shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all loads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
			Total:-			


 Executive Engineer,
 B&R Division, HPPWD,
 Joginder Nagar.

3 **SCHEDULE OF QUANTITY**

Name of Work : Restoration on Joginder Ngar Sarkaghat Chumarwin Road km 0/00 to 34/300 (SIH: Construction of Retaining wall at km 12/195 to 12/205)					Estimate Cost: Earnest Money: Time Limit :		4,57,384.00 9,100.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	Words		AMOUNT	
					Figures		Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	32.60	Per cubic metre					
2	Providing and laying cement concrete 1:5:10 one cement: five sand: ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size & plums and curing complete including the cost of form work in Retaining walls Breast walls cut or under water complete including pumping or bailing out water, dewatering, removal of slush acquired at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R.D technical specifications section 800, 600, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other essentials. The rate is inclusive all taxes levy by the government time to time excluding GST.	79.80	Per cubic metre					

No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	21.90	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	46.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Jodhpur Nagarpur

(4)

SCHEDULE OF QUANTITY

Name of Work : Restoration of Sandapattan Bharel Bagora Bagla Hard Ropari Kolang Triambli Bashai Drubbal Charonj Banwar Kun Ka Tar Mandokhar Bhargoan Kotli Road (MDR-57) km 0/00 to 80/00 (SH: Construction of Retaining wall at km 43/160 to 43/170)			Estimate Cost: 2,42,498.00 Earnest Money: 4,800.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc, and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, hailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.00	Per cubic metre		
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	41.70	Per cubic metre		
					AMOUNT Rs. P

(4)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.25	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

(5)

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- Restoration of rain damages on various roads under Joginder Nagar Division sub Division Joginder Nagar (Bharat Section)
 Sub Head:-Hiring of excavator cum loader for removal of slips dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i.e. loading in to tipper/truck within 25 loads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-In-Charge. The rate is inclusive of all taxes including GST levied by the Govt. time to time.	78.00			Per working hours	
						total:-

[Signature]
 B&R Division E&P.W.D.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of link road from Ladruhin to join Dhelu Chowki Chauntra road Km. 0/0 to 2/300 (S.H. : Providing and laying of Wearing G-II & Cement Concrete pavement in berms at km 0/435 to 0/857)				Estimate Cost: 4,96,214.00 Earnest Money: 9,900.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	107.10	Per cubic metre			
2	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of coarse aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	40.16	Per cubic metre			

7

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	53.55	Per Cubic metre			
Total						


 Accutivity Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar