



Office of
Executive Engineer B&R Division HP.PWD, Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail: ee-jog-hip@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD, Joginder Nagar District Mandi (H.P.) from the eligible contractors of the appropriate class registered in HP.PWD, as per revised enlistment rules so as to reach in the office of under signed on 29-08-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 27-08-2024 up to 10:00 A.M. to 12:30 P.M. and tender form can be had from this office on 28-08-2024 from 2:00 P.M. to 5:00 P.M. The earnest money as shown against each in the shape of F.D.R. of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST, Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction & M/T of Link road Village Patku to Changrehar upto Galu School km. 0/00 to 3/500 (SH- Formation Cutting in km. 2/530 to 3/430).	Rs.4,86,071/-	Rs.9,700/-	Rs.350/-	Class "D"	Three Months
2	Construction & M/T on link road Kimani Basti Dhelu Har km. 0/00 to 1/530 (SH- Providing and laying Granular Sub Base at km. 0/705 to 0/855).	Rs.1,20,989/-	Rs.2,400/-	Rs.350/-	Class "D"	Three Months
3	Construction of Junior Engineer & Work Inspector Residence at Harabag in Joginder Nagar Dist. Mandi (H.P.) (SH- Site Development by providing Retaining wall at RD. 0/00 to 0/014).	Rs.4,86,071/-	Rs.9,700/-	Rs.350/-	Class "D"	Three Months
4	Construction and Metalling of Chakroad to Roparu road km. 0/00 to 1/200 under Deposit (SH- Providing and laying Kharanja Soling & Cement Concrete pavement at km. 0/00 to 0/075).	Rs. 2,75,436/-	Rs.5,500/-	Rs.350/-	Class "D"	Three months
5	Restoration of rain damages on Padhar Bhararu via Nauhal road (SH- Construction o Retaining wall at km. 12/300 to 12/315).	Rs.4,44,532/-	Rs.8,900/-	Rs.350/-	Class "D"	Three Months
6	Restoration of Rain damages on Sandapatan Bharol Bagora Bagla Hard Ropari Kolang Triambli Bashaal Chubbal Charonj Banwar Kun Ka Tar Mandokhar Bhargoan Kothi road (MR-57) km. 0/00 to 80/00 (SH- Construction of Retaining wall at km. 43/240 to 43/252.50).	Rs. 4,51,254/-	Rs.9,000/-	Rs.350/-	Class "D"	Three Months
7	Restoration of rain damages on link road from Lidwan to Mata Chatarbhaja Temple km. 0/00 to 2/00 (SH- Formation cutting / Removal of formation deficiency between km. 0/405 to 0/855).	Rs.4,92,343/-	Rs.9,800/-	Rs.350/-	Class "D"	Three Months
8	Restoration of rain damages on link road to Village Chawal road km. 0/00 to 0/200 (SH- Construction of U-Shape Drain from km. 0/142 to 0/182, Providing and laying 600mm dia RCC Hume Pipe culvert, Cement Concrete pavement from Km. 0/158 to 0/185 and construction of 4 Nos. Parapets etc.)	Rs. 1,51,322/-	Rs.3,000/-	Rs.350/-	Class "D"	Three Months
9	Construction & M/T on link road Kimani Basti Dhelu Har km. 0/00 to 1/530 (SH- Providing and laying Granular Sub Base at km. 0/805 to 1/042).	Rs.4,86,357/-	Rs.9,900/-	Rs.350/-	Class "D"	Three Months
10	Restoration of rain damages on Gachul to Chardunai road km. 0/00 to 3/00 (SH- Construction of Edge wall at km. 0/210 to 0/225).	Rs.59,213/-	Rs.1,200/-	Rs.350/-	Class "D"	Two Months
11	Construction and M/T on Sandha Makan Kalan to Fagra road km. 0/00 to 4/500 (SH- Formation cutting in km. 1/330 to 1/590).	Rs.4,90,428/-	Rs.9,800/-	Rs.350/-	Class "D"	Three Months
12	A/R & M/O various Non Residential building under HP PWD, Division Joginder Nagar (SH- Providing and fixing Ceiling, Railing, plastering, Sanetry fitting and steel work etc.)	Rs.3,13,854/-	Rs.6,300/-	Rs.350/-	Class "D"	Three Months
13	A/R & M/O various Residential/ Non-Residential building under HP PWD Division Joginder Nagar (SH- Providing and fixing Solar light)	Rs.1,02,354/-	Rs.2,100/-	Rs.350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest
Terms and conditions:-

- The contractor should produce a copy of enlistment/ renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/firm shall have his registration and GST No. the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar,
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA/UNIT/Press/2023-24- 6476-6525

Dated:- 29/07/2024

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (M2), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work: Construction & M/T of link road village Patku to Changrehar upto Galu School km 0/00 to 3/500 (SH: Formation Cutting in km 2/930 to 3/430)				Estimate Cost: Earnest Money: Time Limit : 4,95,315.00 9,900.00 Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT	
				Figures	Words	Rs. P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 146.96 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2345.76	Per cubic metre			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

(2)

SCHEDULE OF QUANTITY

Name of Work : Construction & M/T on Link road Kirmani Basti Dhelu Har km 0/00 to 1/530 (Sub Head:- Providing and laying Granular Sub Base at km 0/705 to 0/855)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification clause as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	69.53	Per Cubic metre			
		Total				


 Engineer
 B & R Division HP, PWD.
 Joginder Nagar

(3)

SCHEDULE OF QUANTITY

Name of Work: Construction of Junior Engineer & Work Inspector Residence at Harabag in Jogindernagar Distt. Mandi (H.P.) (SI: Site Development by providing Retaining wall at RD 0/00 to 0/014)				Estimate Cost: Earnest Money: Time Limit:		4,86,071.00 9,700.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner. Filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	27.43	Per cubic metre				
2	Providing and laying cement concrete 1:2:10 (one cement five sand/finer graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size 1 parts and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of silt as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and M.O.R.D. technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	85.67	Per cubic metre				

SCHEDULE OF QUANTITY

Name of Work : Construction and Metalling of Chakroad to Roparu road km 0/00 to 1/200 under Deposit (SH: Providing and Laying Kharanja Soling & Cement Concretet Pavement at km 0/00 to 0/075)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification, 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.44	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 45 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	29.54	Per Cubic metre			
	Total					


 Engineer
 B & R Division HP.PWD.
 Jalandhar

5

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Padhar Bhararu via Naubali road (SI: Construction of Retaining wall at km 12/300 to 12/315)				Estimate Cost: Earnest Money: Time Limit :		4,44,532.00 8,900.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, culber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	36.68	Per cubic metre				
2	Providing and laying cement concrete 1:5:10 (one cement, five sand, ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	79.35	Per cubic metre				

(5)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	22.05	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 in 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	28.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Sandapattan Bharol Bagora Bagla Hard Ropari Kolang Triambli Baskai Drubbal Charanj Banwar Kun Ka Tar Mandokhar Bhargoan Kotli Road (MDR-57) km 0/00 to 80/00 (SH: Construction of Retaining wall at km 43/240 to 43/252.50)				Estimate Cost: Earnest Money: Time Limit :		4,91,254.00 9,800.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge. Loading and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cat materials in specified manner, filling or coverings and finishing the road to specified dimensions or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	34.69	Per cubic metre				
2	Providing and laying cement concrete 1:5:10 (one cement, five smaller graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plumbs and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	82.38	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.63	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.C.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge (including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge). The rate is inclusive all taxes levy by the government time to time excluding GST.	48.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work: Restoration of rain damages on link road from Ladwan to Mata Chatarbhuja Temple km 0/00 to 2/00 (SH: Formation cutting / Removal of formation deficiency between km 0/405 to 0/855)				Estimate Cost: 4,92,343.00 Earnest Money: 9,800.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 119.88 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2397.58	Per cubic metre			
Total						

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on link road to Village Dhawal road km 0/00 to 0/200 (Sub Head:- Construction of U-Spade Drain from km 0/142 to 0/182, Providing and laying 600mm dia RCC hume pipe culvert, Cement Concrete pavement from km 0/158 to 0/185 and Construction of 4 Nos. Parapets etc.)				Estimate Cost: Earnest Money: Time Limit :		1,81,322.00 3,600.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.60	Per cubic metre			
2	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203, Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.76	Per cubic metre			
3	Stone soling properly handpacked filling interstices with Kharapa stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials in-situ or earth etc. complete as per HP.PWD specification, 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer in- Charge including hauling, carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.15	Per Cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS-383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.10	Per Cubic metre			
5	Providing and laying 600mm (Six hundred millimetre) diametre reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.00	Per running metre			
6	Providing and laying concrete for plain reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 & 1203. (Plain cement concrete nominal mix 1:4:8 (one cement : four sand) eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.00	Per cubic metre			
	Total					


 Technical Engineer
 B & R Division HP.PWD.
 Joginder Nagar

9

SCHEDULE OF QUANTITY

Name of Work : Construction & M/T on Link road Kirmani Basti Dhelu Har km 0/00 to 1/530 (SH: Providing and Laying Cement Concrete Pavement at km 0/855 to 1/042)				Estimate Cost: Earnest Money: Time Limit :		4,96,357.00 9,900.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and planks and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	72.23	Per Cubic metre				
Total							

Executive Engineer
B & R Division HP, PWD,
Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain Damages on Gadhui to Chardunal road km 0/00 to 3/00
(SH: Construction of Edge wall at km 0/210 to 0/255)

				Estimate Cost:		
				Earnest Money:		
				Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.22	Per cubic metre			
2	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1(v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	9.00	Each			
Total						


 Executive Engineer
 B & R Division HP, PWD,
 Jalandhar Nagar

last 11 **SCHEDULE OF QUANTITY**

Name of Work: Construction & M/T on Sandha Makan Kalan to Fagla road km 0/00 to 4/500
(Sft: Formation Cutting in km 1/330 to 1/590)

Sr. No.	Description of work	No. or Qty.	Unit	Estimate Cost: Earnest Money: Time Limit :		
				Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 151.22 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2326.40	Per cubic metre			4,90,428.00 9,800.00
Total						

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar