



Office of
EXECUTIVE ENGINEER (KULLU DIVISION)
H.P. PUBLIC WORKS DEPARTMENT, KULLU-175101
FAX: 01902-222571, E.mail. ee-kul2-hp@nic.in

No.PW/KD/TA/Tender/2024-2025- **3744-51**
To


Dated:- **23-7-24**

The Executive Engineer, I.T. Cell,
Nigam Bihar Shimla-2.

Subject:- Publishing of Notice inviting tender.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website 03.08.2024 as per notification issued by Secretary (PW) to the Govt. of HP Shimla vide letter No.PBW(S)A(3)1/2020 dated 16.07.2021. As per works mentioned in the Tender Notice is urgent nature of work in the public interest.

DA/As above.


Executive Engineer,
Kullu Division,
HP. PWD, Kullu.

Copy alongwith notice inviting tender is forwarded to the following for information and necessary action.

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. Supdt./DAO/HDM of this office.
5. Notice Board.

DA/Nil.


Executive Engineer,
Kullu Division,
HP. PWD, Kullu.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

The Executive Engineer, Kullu Division HP.PWD, Kullu on behalf of the Government of Himachal Pradesh invites the **offline tender i.e. on percentage rates** for the following works from the eligible contractors/Firms registered with HP.PWD, department, so as to reach in the office as per time schedule given below:-

1	Date of receipt of application for tender form.	02.08.2024 upto 4:00 PM			
2	Date of issue/sale of tender form.	02.08.2024 upto 4:00 PM			
3	Date of receipt of tender.	03.08.2024 upto 10:30 AM			
4	Date of opening tender.	03.08.2024 upto 11:00 AM			
Sr. No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	2	3	4	5	6
1	Restoration of rain damages on Mohal Soh Jamot Khokhan road Km. 0/00 to 4/415 (SH:- Repair of Pot holes in Km. 2/090 to 2/225) DC Deposit.	4,99,035/-	10,000/-	Two months	350/-
2	Restoration of rain damages on Mohal Soh Jamot Khokhan road Km. 0/00 to 4/415 (SH:- Repair of Pot holes in Km. 2/235 to 2/370) DC Deposit.	4,99,791/-	10,000/-	Two months	350/-
3	Restoration of rain damages on Mohal Soh Jamot Khokhan road Km. 0/00 to 4/415 (SH:- Repair of Pot holes in Km. 2/380 to 2/515) DC Deposit.	4,98,098/-	10,000/-	Two months	350/-
4	Restoration of rain damages on Mohal Soh Jamot Khokhan road Km. 0/00 to 4/415 (SH:- Repair of Pot holes in various roads) DC Deposit.	4,99,380/-	10,000/-	Two months	350/-
5	Restoration of rain damages on Mohal Soh PWD work shop road Km. 0/00 to 3/665 (SH:- Repair of Pot holes in various reaches) DC Deposit.	4,68,929/-	9,500/-	Two months	350/-
6	A/R and M/O Ruzak Shallang road Km. 0/00 to 7/00 (SH:- Repair of Pot holes in Km. 0/00 to 3/00) Against OFC cable Deposit.	4,82,500/-	9,800/-	Two months	350/-
7	A/R and M/O Kullu Karon road Km. 0/00 to 15/00 (SH:- Repair of Pot holes in Km. 0/0 to 2/00 and 12/00 to 14/00) Against OFC cable Deposit.	4,99,180/-	10,000/-	Two months	350/-
8	Restoration of rain damages on Kullu Karon road Km. 0/00 to 15/00 (SH:- Construction of Breast wall at RD 12/440 to 12/460).	4,26,628/-	8,600/-	Two months	350/-
9	Restoration of rain damages on various road under Bhunter Sub Division (Bhunter Section-I) (SH:- Hiring of Excavator Cum Loader (JCB) for the removal of slips/debris/muck etc. at various RDs) Job No.1.	3,44,116/-	7,000/-	One month	350/-
10	Restoration of rain damages on various road under Bhunter Sub Division (Bhunter Section-I) (SH:- Hiring of Excavator Cum Loader (JCB) for the removal of slips/debris/muck etc. at various RDs) Job No.2.	3,44,116/-	7,000/-	One month	350/-





11	Restoration of rain damages on various road under Bhunter Sub Division (Bhunter Section-II) (SH:- Hiring of Excavator Cum Loader (JCB) for the removal of slips/debris/muck etc. at various RDs) Job No.1.	3,50,609/-	7,000/-	One month	350/-
12	Restoration of rain damages on various road under Bhunter Sub Division (Bhunter Section-I) (SH:- Hiring of Excavator Cum Loader (JCB) for the removal of slips/debris/muck etc. at various RDs) Job No.2.	3,50,609/-	7,000/-	One month	350/-
13	Restoration of rain damages on various road under Bhunter Sub Division (Pah Nallah Section) (SH:- Hiring of Excavator Cum Loader (JCB) for the removal of slips/debris/muck etc. at various RDs) Job No.1.	3,57,101/-	7,200/-	One month	350/-
14	Restoration of rain damages on various road under Bhunter Sub Division (Pah Nallah Section) (SH:- Hiring of Excavator Cum Loader (JCB) for the removal of slips/debris/muck etc. at various RDs) Job No.2.	3,57,101/-	7,200/-	One month	350/-
15	RRD on Badah Pahnallah road Km. 0/00 to 19/700 (SH:- C/O Retaining wall at RD 9/435 to 9/450).	4,78,228/-	9,600/-	Two months	350/-
16	Restoration of rain damages on Bhuins Bai Bhulang road Km. 0/00 to 11/020 (SH:- Construction of Breast wall in Km. 5/935 to 5/955).	4,19,900/-	8,500/-	Two months	350/-
17	Restoration of rain damaged on Bhuins Bai Bhulang road Km. 0/00 to 11/020 (SH:- Construction of Breast wall in Km. 5/915 to 5/935).	4,19,443/-	8,500/-	Two months	350/-
18	Restoration of rain damaged on Bhuins Bai Bhulang road Km. 0/00 to 11/020 (SH:- Construction of retaining wall in Km. 5/957.50 to 5/972).	4,95,283/-	10,000/-	Two months	350/-
19	Repair of Pot holes in Bhuin Shillihar road km. 0/00 to 6/00 (SH:- Repair of Pot holes in Km. 0/00 to 2/00)	4,94,937/-	10,000/-	Two months	350/-
20	Repair of Pot holes in Chharour Nallah to Barogi road Km. 0/00 to 7/850 (SH:- Repair of Pot holes in Km. 0/00 to 2/00).	4,94,350/-	10,000/-	Two months	350/-
21	RRD on Badah Pahnallah to Rajgiri road Km. 0/00 to 19/700 (SH:- Repair of Pot holes in various RD's) Deposit SDF/2023/925-630).	4,80,060/-	9,800/-	Two months	350/-
22	Metalling/Tarring and up gradation on Sharni Pinni road Km. 0/0 to 13/700 under MLA priority (SH:- Preparation of DPR).	4,04,150/-	8,000/-	Two months	350/-
23	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- C/O Stone masonry R/wall at RD 30/020 to 30/028.50).	4,85,307/-	9,800/-	Two months	350/-
24	A/R and M/O residential building under Kullu Division (SH:- Balance work of Type-III residence (AC Kullu P/F Panelling PVC flooring, verandah partitioned and tiles etc.).	4,51,704/-	9,200/-	Two months	350/-

[Handwritten signature]

[Handwritten signature]

25	RRD on Dughilag to Dubkan road (SH:- Construction of stair etc.).	1,63,384/-	3,400/-	Two months	350/-
26	RRD on Dughilag to Dubkan road (SH:- C/O Retaining wall at RD 3/810 to 3/814.50) Job No.1.	4,94,541/-	10,000/-	Two months	350/-
27	RRD on Dughilag to Dubkan road (SH:- Construction of retaining wall at RD 3/814.50 to 3/819) Job No.2.	4,96,031/-	10,000/-	Two months	350/-
28	RRD on Dughilag to Dubkan road (SH:- Construction of retaining wall at RD 3/819 to 3/823.50) Job No.3.	4,97,499/-	10,000/-	Two months	350/-
29	RRD on Dughilag to Dubkan road (SH:- Construction of retaining wall at RD 3/823.50 to 3/28) Job No.4.	4,95,056/-	10,000/-	Two months	350/-
30	A/R and M/O Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Repair of Pot holes in Km. 5/00 to 6/00).	2,77,857/-	5,600/-	Two months	350/-
31	RRD on Sarsari Chong road Km. 0/0 to 5/300 (SH:- C/O Breast wall at Km. 3/675 to 3/690).	2,46,794/-	5,000/-	Two months	350/-
32	C/O Shetajol to Lashani road Km. 0/00 to 4/500 (SH:- P/L Kharanja stone soling at various RD's) as per working programme.	4,96,295/-	10,000/-	Two months	350/-
33	Repair of pot holes in Bhuin Shilihar road Km. 0/00 to 6/00 (SH:- Repair of Pot holes in Km. 2/00 to 4/00).	4,94,350/-	10,000/-	Two months	350/-
34	RRD on Chharour Nallah to Badogi road Km. 0/00 to 7/850 (SH:- C/O wire crated protection wall and PCC protection wall for 6.0 mtr. Span slab culvert at RD 5/780).	2,55,119/-	5,200/-	Two months	350/-
35	Repair of pot holes in Chharour Nallah to Badogi road Km. 0/00 to 7/850 (SH:- Repair of Pot holes in Km. 2/00 to 4/00)	4,93,998/-	10,000/-	Two months	350/-
36	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 0/810 to 0/945).	4,11,314/-	8,400/-	Two months	350/-
37	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 0/945 to 1/165).	4,69,450/-	9,500/-	Two months	350/-
38	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 1/165 to 1/555).	4,64,882/-	9,400/-	Two months	350/-
39	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 1/555 to 1/795).	4,39,715/-	8,800/-	Two months	350/-
40	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 1/795 to 2/135).	4,67,221/-	9,500/-	Two months	350/-
41	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 2/135 to 2/255).	4,25,555/-	8,600/-	Two months	350/-
42	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 0/745 to 0/810).	4,01,256/-	8,200/-	Two months	350/-
43	Construction of Strong room in Govt. Degree College Kullu (SH:- Closing the ventilation through half brick masonry and painting distempering in GF Tennis hall, FF room No.102, 2nd floor room No. 204A & 203A & back room No.1 &2 etc.).	3,44,583/-	7,000/-	Two months	350/-

44	Restoration of rain damages on link road to village Kharkha Km. 0/00 to 1/450 (SH:- Removal of slips at various RD's) Job No.1.	4,91,343/-	10,000/-	Two months	350/-
45	Restoration of rain damages on link road to village Kharkha Km. 0/00 to 1/450 (SH:- Removal of slips at various RD's) Job No.2.	4,83,837/-	9,800/-	Two months	350/-
46	C/O Lashani Sangtehar road Km. Km. 0/00 to 3/660 (SH:- C/O wire crated B/wall at RD 2/915 to 2/940).	3,89,034/-	8,000/-	Two months	350/-
47	C/O Lashani Sangtehar road Km. Km. 0/00 to 3/660 (SH:- C/O Retaining wall at RD 3/035 to 3/050)	2,84,369/-	5,800/-	Two months	350/-
48	C/O Lashani Sangtehar road Km. 0/0 to 3/660 (SH:- C/O wire crated R/wall with PCC Toe wall at RD 2/952 to.50 to 2/971.25).	4,89,044/-	9,800/-	Two months	350/-
49	C/O Lashani Sangtehar road Km. 0/00 to 3/660 (SH:- C/O wire crated R/wall with PCC Toe wall at RD 2/933.75 to 2/952.50)	4,89,497/-	9,800/-	Two months	350/-
50	C/L Lashani Sangtehar road Km. 0/00 to 3/660 (SH:- C/O wire crated R/wall with PCC Toe wall at RD 2/915 to 2/933.75).	4,89,949/-	9,800/-	Two months	350/-
51	Restoration of rain damages on Bhunter Bus Stop to Parganoo Chowk road Km. 0/00 to 1/200 (SH:- C/O CC edge wall in Km. 0/078 to 0/098 with 900mm dia Hume pipe at Km. 0/098).	1,60,115/-	3,400/-	Two months	350/-
52	Construction of Mohal (Buins Bai) Bhulang road Km. 0/00 to 11/020 (SH:- ROFD in Km. 10/817.50 to 10/863.50).	4,85,312/-	9,800/-	Two months	350/-
53	Restoration of rain damages on Dohranallah to Kharihar road Km. 0/00 to 10/120 (SH:- C/O Retaining wall at RD 2/369.70 to 2/379).	4,97,853/-	10,000/-	Two months	350/-
54	Restoration of rain damages due to laying underground 250 mm dia pipe line (LIS) on Workshop Gadouri road Km. 0/00 to 1/200 (SH:- P/L GSB, G-III in Km. 0/400 to 0/800).	4,62,923/-	9,400/-	Two months	350/-
55	Restoration of rain damages on Dohranallah to Barahar road Km. 0/00 to 10/00 (SH:- C/o Retaining wall at RD 1/450 to 1/460).	1,83,708/-	3,800/-	Two months	350/-
56	Restoration of rain damages on Dohranallah to Barahar road Km. 0/00 to 10/00 (SH:- C/O Retaining wall at RD 0/630 to 0/642.50).	3,73,000/-	7,500/-	Two months	350/-
57	Restoration of rain damages on Dohranallah to Barahar road Km. 0/00 to 10/00 (SH:- C/O Retaining wall at RD 1/225 to 1/242.50).	3,73,000/-	7,500/-	Two months	350/-
58	Restoration of rain damages on Linger Bansu road Km. 0/0 to 11/500 (SH:- Removal of slips/debries in various RD's).	4,93,945/-	10,000/-	Two months	350/-
59	A/R and M/O non-residential/residential building under Bhunter Sub Division HP.PWD, Bhunter (SH:- Re-filling of fire extinguishers and painting and distempering work at Bhunter S/D office).	1,36,664/-	3,000/-	One month	350/-

60	Up-gradation, Metalling and tarring on Dohranallah Shillihar Chestha Rolgi road under MLA priority (SH:- Preparation of DPR).	4,72,000/-	10,000/-	Two months	350/-
61	Consultancy services for Construction of Type IV Residence to the Secretary District Legal Service Authority Kullu at Badah District Kullu (HP) (SH:- Preparation of estimate of whole Project as per Architectural Drawings).	80,000/-	2,000/-	Two months	350/-
62	C/O Pechha to Deoghara road Km. 0/00 to 6/850 (SH:- C/O Retaining wall at RD 2/411 to 2/417).	4,99,424/-	10,000/-	Two months	350/-
63	C/O Pechha to Deoghara road Km. 0/00 to 6/850 (SH:- C/O Retaining wall at RD 2/405 to 2/411).	4,99,599/-	10,000/-	Two months	350/-
64	C/O Shishamati Bypass road Km. 0/00 to 1/00 (SH:- C/O wire crated R/wall with PCC toe wall and laying of NP3 pipes at RD 0/724.05 to 0/731.55).	3,72,241/-	7,500/-	Two months	350/-
65	RRD due to laying of optical fiber cable on Kullu Karon road Km. 0/00 to 15/00 (SH:- Construction of PCC retaining wall at RD 2/00 to 2/017) OFC Deposit.	4,17,822/-	8,500/-	Two months	350/-
66	Repair of treasury Office building Kullu District Kullu (SH:- C/O additional male & female WC and bath toilet for security/gaurds etc.).	4,95,263/-	10,000/-	Two months	350/-
67	A/R and M/O residential building under Kullu Division (SH:- P/L outer sewer line, renovation of old damaged WC and p/f CB in room No.2 etc. type-3 quarter near 6 th Circle Kullu).	3,96,768/-	8,000/-	Two months	350/-
68	RRD on Manikaran Barshaini road Km. 0/00 to 15/00 (SH:- C/O Toe wall of R/wall from RD 0/710 to 0/750) Job No.1 (NHPC Deposit).	4,92,660/-	10,000/-	Two months	350/-
69	RRD on Manikaran Barshaini road Km. 0/00 to 15/00 (SH:- C/O Toe wall of R/wall from RD 0/710 to 0/750) Job No.2 (NHPC Deposit).	4,97,890/-	10,000/-	Two months	350/-
70	RRD on Manikaran Barshaini road Km. 0/00 to 15/00 (SH:- C/O Toe wall of R/wall from RD 0/710 to 0/750) Job No.3 (NHPC Deposit).	4,85,785/-	9,800/-	Two months	350/-
71	RRD on Manikaran Barshaini road Km. 0/00 to 15/00 (SH:- C/O Toe wall of R/wall from RD 0/710 to 0/750) Job No.4 (NHPC Deposit).	4,97,890/-	10,000/-	Two months	350/-
72	RRD on Manikaran Barshaini road Km. 0/00 to 15/00 (SH:- C/O Toe wall of R/wall from RD 0/710 to 0/750) Job No.5 (NHPC Deposit).	4,96,977/-	10,000/-	Two months	350/-
73	RRD on Manikaran Barshaini road Km. 0/00 to 15/00 (SH:- C/O Toe wall of R/wall from RD 0/710 to 0/750) Job No.6 (NHPC Deposit).	4,99,603/-	10,000/-	Two months	350/-
74	Restoration of rain damages due to laying underground 250 mm dia pipe line (LIS) on Workshop Gadouri road Km. 0/00 to 1/200 (SH:- P/L GSB, G-III in Km. 0/800 to 1/200).	4,62,923/-	9,400/-	Two months	350/-

The tender documents shall be issued only to those contractor/firm who fulfill the following documents with the application.

1	The valid enlistment/Registration of contractor in Appropriate Class.
2	Permanent account No. (PAN No.).
3	G.S.T. No.
4	Earnest Money in the shape of National Saving certificate/time deposit account in the any of the post office in HP F.D.R. from any Nationalized Bank duly pleaded in favour of the Executive Engineer, Kullu Division HP.PWD, Kullu.
5	The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6	The offer of the tender shall remain valid upto 90 days after the opening of tender.
7	Ambiguous/telephonic conditional tenders of tender by fax/E-mail not be considered and will be summarily be rejected.
8	Executive Engineer, reserve the right to reject or cancel any or all tenders without assigning any reasons.
9	If the date given above happens to be holiday the same shall be processed on next working day.
10	The contractor/firm must quote their rates in words as well as in figures failing which XEN reserve the right to accept/reject any or all tenders.
11	The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12	One contractor shall not have more than two major works in hand at a time.
13	Work should be completed by the contractor within stipulated period.
14	The rates beyond over +5% will be rejected, besides this the Additional Performance security will have to borne @ 20% & 30% for unbalanced bid in case rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively. The tender beyond the limit of -30% will also be excepted.


Executive Engineer,
Kullu Division,
HP.PWD, Kullu.

Dated:- 23-7-24

No.PW/KD/TA/2024-2025-

3752-3825

Copy is forwarded to the following for information and necessary action:-

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. All the Executive Engineers, in HP.PWD,
5. All the Assistant Engineers, working under this Division.
6. All the registered contractors, in HP.PWD.
7. Supdt./DA/HDM of this office.
8. Notice Board.


Executive Engineer,
Kullu Division,
HP.PWD, Kullu.

CERTIFICATE

It is certified that the above works are required to be carried out immediately being emergent nature of work in the public interest.


**Executive Engineer,
Kullu Division, 
HP.PWD, Kullu.**


318126

SCHEDULE OF QUANTITY**Name of work:-** Restrator of rain damages on Mohal Soh Jamot Khokhan road Km 0/00 to

Estimated cost:- Rs. 4,99,035.00

4/415 (SH:- Repair of Pot holes in Km 2/090 to 2/225) DC Deposit .

Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	#	Rate in		Unit	Amount
				Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 by Manual Means Grading-III including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	32.23	1	13470.05	Rupees Three thousand four hundred seventy and paise zero five only.	Per Square metre	111840.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg. (Zero point seven zero to one point zero kilogramme) / squaremetre using mechanical means as per Technical specification clause 502. including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	429.74	2	55.05	Rupees Fifty five and paise zero five only.	Per Square metre	23657.00
3	Providing and laying 50 mm (Fifty millimetre) bituminous macadam with hot mix plant using crushed aggregates of grading as per Table 500.4 premixed with bituminous binder @3.50% (Three point five zero percent), transported to site upto any lead, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification Clause 504 including carriage of material with in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	21.48	2	10538.35	Rupees Ten thousand five hundred thirty eight and paise thirty five only.	Per Cubic metre	226364.00

4	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	350.74	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	137174.00
---	---	--------	--------	---	-----------------	-----------


 Executive Engineer
 Kulu Division
 H.P.P.W.D. Kulu

SCHEDULE OF QUANTITY

Name of work:- Restroration of rain damages on Mohal Soh Jamot Khokhan road Km 0/00 to 4/415 . **(SH:-** Repair of Pot holes in Km 2/235 to 2/370) DC Deposit.

Estimated cost:- Rs. 4,99,791.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 by Manual Means Grading-III including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	31.89	3470.05	Rupees Three thousand four hundred seventy and paise zero five only.	Per Square metre	110660.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg. (Zero point seven zero to one point zero kilogramme) / squaremetre using mechanical means as per Technical specification clause 502. including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	425.25	55.05	Rupees Fifty five and paise zero five only.	Per Square metre	23410.00
3	Providing and laying 50 mm (Fifty millimetre) bituminous macadam with hot mix plant using crushed aggregates of grading as per Table 500.4 premixed with bituminous binder @3.50% (Three point five zero percent), transported to site upto any lead, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification Clause 504 including carriage of material with in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	21.26	10538.35	Rupees Ten thousand five hundred thirty eight and paise thirty five only.	Per Cubic metre	224045.00

4	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	362.25	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	141676.00
					Total	499791.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

3

SCHEDULE OF QUANTITY

Name of work:- Restroration of rain damages on Mohal Soh Jamot Khokhan road Km 0/00 to 4/415 . (SH:- Repair of Pot holes in Km 2/380 to 2/515) DC Deposit .

Estimated cost:- Rs. 4,98,098.00

Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 by Manual Means Grading-III including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	31.39	3470.05	Rupees Three thousand four hundred seventy and paise zero five only.	Per Square metre	108925.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg. (Zero point seven zero to one point zero kilogramme) / squaremetre using mechanical means as per Technical specification clause 502. including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	418.50	55.05	Rupees Fifty five and paise zero five only.	Per Square metre	23038.00
3	Providing and laying 50 mm (Fifty millimetre) bituminous macadam with hot mix plant using crushed aggregates of grading as per Table 500.4 premixed with bituminous binder @3.50% (Three point five zero percent), transported to site upto any lead, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification Clause 504 including carriage of material with in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	20.92	10538.35	Rupees Ten thousand five hundred thirty eight and paise thirty five only.	Per Cubic metre	220462.00

4-	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	372.47	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	145673.00
					Total	498098.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restroration of rain damages on Mohal Soh Jamot Khokhan road Km 0/00 to 4/415. **(SH:-** Repair of Pot holes in in various reaches) **DC Deposit:-**

Estimated cost:- Rs. 4,99,380.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	1276.86	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	499380.00
					Total	499380.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restroration of rain damages on Mohal Soh PWD Work shop road Km 0/00 to 3/665. (**SH:-** Repair of Pot holes in various reaches) DC Deposit .

Estimated cost:- Rs. 4,68,929.00

Earnest money :- Rs. 9,500.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Reapir to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	1199.00	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	468929.00
					Total	468929.00


Executive Engineer,
Kullu Division
HP PWD Kullu

6

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Rujag Shallang road Km 0/00 to 7/00
(SH:- (Repair of Pot holes in Km 0/00 to 3/00) Against OFC cable Deposit)

Estimated cost:- Rs. 4,82,500.00

Earnest money :- Rs. 9,800.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing off surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In- charge.	1233.70	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	482500.00
					Total	482500.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Kullu Karon road Km 0/00 to 15/00 .
(SH:- Repair of Pot holes in Km 0/00 to 2/00 and 12/00 to 14/00) Against OFC cable Deposit .

Estimated cost:- Rs. 4,99,180.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	1276.35	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	499180.00
					Total	499180.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Kullu Karon Km 0/00 to 15/00.
(SH:- Construction of Breast wall at RD 12/440 to 12/460).

Estimated cost:- Rs. 4,26,628.00
Earnest money :- Rs. 8,600.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	49.20	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	11235.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	24.20	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	8841.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702.704, 1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	48.96	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only.	Per cubic metre	257160.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	50.31	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	137664.00
5	Providing/ laying weep holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	30	390.95	Rupees Three hundred ninety and paise ninety five only.	Each	11728.00
					Total	426628.00

Executive Engineer,
Kullu Division ,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on various road under Bhunter Sub Division (Bhnuter Section-I)
(SH:- Hiring of Excavator cum loader(JCB) for the removal of slips/debris/ Muck etc. at various RDs.) **Job -I**

Estimated cost:-3,44,116.00
Earnest money :-7,000.00
Time :- One month.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of J.C.B. / Excavator- cum- loader for removal of slips/ debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable materials from the road surface when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour . The useful material shall be stacked along the road side as per direction of Engineer-in-charge.	265	1298.55	Rupees one thousand two hundred ninety eight and paise fifty five only.	Per Hour	344116.00
					Total	344116.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

Estimated cost:-3,44,116.00
Earnest money :-7,000.00
Time :- One month.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on various road under Bhunter Sub Division (Bhnuter Section-I)
(SH):- Hiring of Excavator cum loader(JCB) for the removal of slips/debris/ Muck etc. at various RDs.) Job-II

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of J.C.B. / Excavator- cum- loader for removal of slips/ debries / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and disposing of all excavated earth or unserviceable materials from the road surface when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour. The useful material shall be stacked along the road side as per direction of Engineer-in-charge.	265	1298.55	Rupees one thousand two hundred ninety eight and paise fifty five only.	Per Hour	344116.00
					Total	344116.00


Executive Engineer,
Kullu Division
HP.PWD Kullu.

Estimated cost :-3,50,609.00

Earnest money :-7,000.00

Time :- One month.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various road under Bhunter Sub Division (Bhnuter Section-II)
(SH:- Hiring of Excavator cum loader(JCB) for the removal of slips/debris/ Muck etc. at various RDs.) **Job -I**

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of J.C.B. / Excavator- cum- loader for removal of slips/ debries / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and disposing of all excavated earth or unserviceable materials from the road surface when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour. The useful material shall be stacked along the road side as per direction of Engineer-in-charge.	270	1298.55	Rupees one thousand two hundred ninety eight and paise fifty five only.	Per Hour	350609.00
					Total	350609.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu.

SCHEDULE OF QUANTITY

Estimated cost:-3,50,609.00
Earnest money :-7,000.00
Time :- One month.

Name of work:- Restoration of rain damages on various road under Bhunter Sub Division (Bhnuter Section-II)
(SH:- Hiring of Excavator cum loader(JCB) for the removal of slips/debris/ Muck etc. at various RDs.) **Job -II**

Sr. No.	Description	Qty	Figure	Rate In Words	Unit	Amount
1	Hiring of J.C.B. / Excavator- cum- loader for removal of slips/ debries / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable materials from the road surface when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour . The useful material shall be stacked along the road side as per direction of Engineer-in-charge.	270	1298.55	Rupees one thousand two hundred ninety eight and paise fifty five only.	Per Hour	350609.00
					Total	350609.00


Executive Engineer,
Kultu Division
HP.PWD Kultu.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on various road under Bhunter Sub Division (Pah Nallah Section)
(SH:- Hiring of Excavator cum loader(JCB) for the removal of slips/debris/ Muck etc. at various RDs.) **Job -I**

Estimated cost:-3,57,101.00
 Earnest money :-7,200.00
 Time :- One month.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of J.C.B. / Excavator- cum- loader for removal of slips/ debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and disposing of all excavated earth or unserviceable materials from the road surface when required or as per direction of Engineer-in-charge. The machine/ JCB should work 8 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour . The useful material shall be stacked along the road side as per direction of Engineer-in-charge.	275	1298.55	Rupees one thousand two hundred ninety eight and paise fifty five only.	Per Hour	357101.00
					Total	357101.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Estimated cost-3,57,101.00
Earnest money :-7,200.00
Time :- One month.

Name of work:- Restoration of rain damages on various road under Bhunter Sub Division (Pah Nallah Section)
(SH:- Hiring of Excavator cum loader(JCB) for the removal of slips/debris/ Muck etc. at various RDs.) Job -II

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of J.C.B. / Excavator- cum- loader for removal of slips/ debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and disposing of all excavated earth or unserviceable materials from the road surface when required or as per direction of Engineer-in-charge. The machine/ JCB should work 6 hours daily and remove at least 25.00 cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 cubic metre per hour. The useful material shall be stacked along the road side as per direction of Engineer-in-charge	275	1298.55	Rupees one thousand two hundred ninety eight and paise fifty five only.	Per Hour	357101.00
					Total	357101.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- RRD on Badah Pahnallah road Km. 0/00 to 19/700.
(SH:- C/o Retaining wall at RD 9/435 to 9/450)

Estimated cost:- Rs. 4,78,228.00
Earnest money :- Rs. 9,600.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in	Unit	Amount
			Figure	Words	
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	57.30	228.35	Rupees Two hundred twenty eight and paise thirty five only	13084.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	19.80	365.35	Rupees Three hundred Sixty five and paise thirty five only.	7234.00
3	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	48699.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	43.98	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	231003.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	52.78	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	144422.00
6	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment. wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	31.00	390.95	Rupees Three hundred ninety and paise ninety five only	12119.00

7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material, within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	13.50	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	21667.00
		Total				478228.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

16

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bhuians Bai Bhulang road Km. 0/00 to 11/020 .
(SB):- Construction of Breast wall in Km. 5/935 to 5/955)

Estimated cost:- Rs. 4,19,900.00
 Earnest money :- Rs. 8,500.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1c	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	66.00	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	15071.00
2e	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	27.40	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10011.00
3c	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	48.96	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	257160.00
4s	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc, for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportatin within all leads and lift of materials and as per direction of Engineer-in-charge.	50.31	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	137658.00
					Total	419900.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bhuins Bai Bhulang road Km. 0/00 to 11/020 .
(SH:- Construction of Breast wall in Km. 5/915 to 5/935) .

Estimated cost:- Rs. 4,19,443.00
 Earnest money :- Rs. 8,500.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	64.00	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	14614.00
2	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	27.40	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10011.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702.704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	48.96	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	257160.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportatin within all leads and lift of materials and as per direction of Engineer-in-charge.	50.31	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	137658.00
					Total	419443.00


 Executive Engineer,
 Kullu Division,
 HP PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bhains Bai Bhulang road Km. 0/00 to 11/020.
(SH:- C/o Retaining wall in Km. 5/957.50 to 5/972).

Estimated cost:- Rs. 4,95,283.00
 Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	33.93	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	12396.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.44	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	47076.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone aggregate nominal size in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	6.24	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only.	Per cubic metre	30934.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:5 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	42.06	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	220918.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	48.18	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	131830.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	32.48	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	52129.00
					Total	495283.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

19

SCHEDULE OF QUANTITY

Name of work:- Repair of Pot holes in Bhuin Shillihar road Km. 0/00 to 6/00 .
(SH:- Repair of Pot holes in Km 0/00 to 2/00).

Estimated cost:- Rs. 4,94,937.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	1265.50	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	494937.00
					Total	494937.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Repair of Pot holes in Chharour Nallah to Barogi road Km. 0/00 to 7/850
(SH:- Repair of Pot holes in Km 0/00 to 2/00).

Estimated cost:- Rs. 4,94,350.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	1284.00	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	494350.00
					Total	494350.00


 Executive Engineer,
 Kulu Division,
 HP.PWD Kulu

21

SCHEDULE OF QUANTITY

Name of work:- RRD on Badah Pahnallah to Rajgiri road Km. 0/00 to 19/700
(SH):- Repair of Pot holes lat various RD's) Deposit SDF/2023/625-630 .

Estimated cost:- Rs. 4,80,060.00
 Earnest money :- Rs. 9,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 by Manual Means Grading-III including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	9.58	3470.05	Rupees Three thousand four hundred seventy and paise zero five only.	Per Square metre	33243.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg. (Zero point seven zero to one point zero kilogramme) / squaremetre using mechanical means as per Technical specification clause 502. including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	127.76	55.05	Rupees Fifty five and paise zero five only.	Per Square metre	7033.00
3	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In- charge.	1124.48	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	439784.00
					Total	480060.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITIES

Estimated Cost Rs. : 4,04,150/-only
Earnest Money Rs. : 8,000/- only
Time: Two months

Name of work:- Metalling / Tarring and up gradation on Sharni Pinni Road Km. 0/0 to 13/700 under MLA priority (SH:- Preparation of DPR.)

Sr.No.	Description	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Preparation of Detailed Project Report i/c Surveying and Investigation for preparation of manuscript copy of detailed Estimate i.c Cross-sections, Plan, Preparation of Detailed Estimate in the Shape of manuscript copy duly approved from the Circle Office & Chief office. Preparation of approved copies of Detailed Estimate along with relevant working drawings. (Five sets of DPR's and five additional sets of working drawing complete) and soft copies in the form of Compact Disc (C.D.) of below mentioned works including Estimate and Drawings.					
a.	Metalling / Tarring and up gradation on Sharni Pinni Road Km. 0/0 to 13/700 under MLA priority (SH:- ROFD, M/T, CD works , R/walls , B/walls, road singages etc.)	13.700	29500.00	Twenty nine thousand and five hundred only	Per Km	404150.00
					Total	404150.00


 Executive Engineer
 Kullu Division
 HP.PWD, Kullu

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhunter Manikaran road Km. 1/610 to 35/110.
(SH:- C/o Stone masonry R/wall at RD 30/020 to 30/028.50)

Estimated cost:- Rs. 4,85,307.00
Earnest money :- Rs. 9,800.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	72.08	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	26334.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	28.9	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only	Per cubic metre	150173.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	4.00	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	19830.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	34.93	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	183468.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	33.22	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	90897.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material, within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.10	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	14605.00
	Total					485307.00


Executive Engineer,
Kullu Division
HP, PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Residential building under Kullu Division
(SH:- Balance work of Type -III residence (AE Kullu) P/F Panelling, PVC flooring, varandah partitiond and tiles etc.

Estimated cost:- Rs. 4,51,704.00
 Earnest money :- Rs. 9,200.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. Sal wood/ hard wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	0.44	122082.60	Rupees One lac twenty two thousand eighty two and paise sixty only.	Per Cubic metre	53716
2	Providing and fixing Australian pine wood panelling manufacture tounge and grooved join in plain lining fixed on wood work complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	42.03	2462.15	Rupees Two thousand four hundred sixty two and paise fifteen only.	Per Square metre	103484
3	French sprit polishing two or more coats on new works including a coat of wood filler with in all leads and lift of materials and as per direction of Engineer-in-charge.	46.23	290.75	Rupees Two hundred ninety and paise seventy five only.	Per Square metre	13442
4	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete :2nd class teak wood 50x12 mm (Fifty x Twelve millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	36.23	175.60	Rupees One hundred seventy five and paise sixty only.	Per Running metre	6362
5	Providing and fixing 2mm thick PVC antistatic vinyl Flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately with in all leads and lift of materials and as per direction of Engineer-in-charge.	38.81	1588.90	Rupees One thousand five hundred eighty eight and paise ninety only.	Per Square metre	61665

6.	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm (Twelve millimetre) thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm (Three point three kilogram per square metre), including pointing in white cement mixed with pigment of matching shade complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	33.75	1833.60	Rupees One thousand eight hundred thirty three and paise sixty only.	Per Square metre	61884
7	Providing and fixing polycarbonated transparent sheet 1.20 mm (One point twenty millimetre) thick in roofing galvanised or L hooks bolts and nuts with G.I. Limpet and bitumen rubber washer complete with all accessories as required with in all leads and lift of materials and as per direction of Engineer-in-charge.	13.49	4000.00	Rupees Four thousand only.	Per Square metre	53960
8	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works with in all leads and lift of materials and as per direction of Engineer-in-charge.	313.20	135.00	Rupees One hundred thirty five only.	Per Kilogram	42282
9	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:4 (1 cement : 4 coarse sand) with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.96	10718.00	Rupees Ten thousand seven hundred eighteen only.	Per Cubic metre	53161
10	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (Zero point eighty litre/ Ten square metre of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge	15.66	111.60	Rupees One hundred eleven and paise sixty only.	Per square metre	1748
	Total					451704


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Estimated cost:- Rs. 1,63,384.00
Earnest money :- Rs. 3,400.00
Time :- Two months.

Name of work:- RRD on Dughilag to Dubkan road.
(SH):- Construction of Stair etc.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	17.96	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	6562.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	2.00	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	9018.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	28.14	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	147804.00
		Total				153384.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- RRD on Dughilag to Dubkan road.
(SH:- C/o Retaining wall at RD 3/810 to 3/814.50) Job No. 1.

Estimated cost:- Rs. 4,94,541.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	305.141.58	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	15191.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.99	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	27010.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	67.50	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	334625.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	8.89	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	46694.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	13.72	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	37541.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	14.04	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	22533.00
7	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	28.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	10947.00
	Total					494541.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- RRD on Dughilag to Dubkan road.
(SH:- C/o Retaining wall at RD 3/8/14.50 to 3/8/19) Job No. 2.

Estimated cost:- Rs. 4,96,031.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	50.40	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	18414.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.99	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	27010.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	67.50	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	334625.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	8.89	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	46694.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	13.72	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	37541.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	12.96	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	20800.00
7	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	28.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	10947.00
	Total					496031.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu.

28

SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,97,499.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Name of work:- RRD on Dughilag to Dubkan road.
 (SH:- C/o Retaining wall at RD 3/819 to 3/823.50) Job No. 3.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	23.58	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	8615.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.99	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	27010.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	67.50	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	334625.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	8.89	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	46694.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	13.72	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	37541.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	19.98	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	32067.00
7	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	28.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	10947.00
	Total					497499.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- RRD on Dughilag to Dubkan road.
(SH:- C/o Retaining wall at RD 3/823.50 to 3/828) Job No. 4.

Estimated cost:- Rs. 4,95,056.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	451.36	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	16572.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.99	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	27010.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	671.50	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	334625.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	8.89	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	46694.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportatin within all leads and lift of materials and as per direction of Engineer-in-charge.	1372	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	37541.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	131.50	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	21667.00
7	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full with of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	28.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	10947.00
	Total					495056.00


 Executive Engineer,
 Kullu Division,
 HP PWD Kullu

30


SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Bhunter Manikaran road Km. 1/610 to 35/110.
(SH:- Repair of Pot holes in Km. 5/00 to 6/00).

Estimated cost:- Rs. 2,77,857.00
Earnest money :- Rs. 5,600.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	710.45	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	277857.00
					Total	277857.00


Executive Engineer,
Kullu Division,
HP PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- RRD on Sarsari Chong road Km. 0/00 to 5/300
(SH:- C/O Breast wall at Km. 3/675 to 3/690).

Estimated cost:- Rs. 2,46,794.00
Earnest money :- Rs. 5,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1803.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	24.23	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	5533.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	20.10	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	7344.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	32.10	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	168604.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	23.87	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	65313.00
					Total	246794.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

SCHEDULE OF QUANTITY

Estimated cost:- 4,96,295.00
Earnest money :- 10,000.00
Time :- Two months.

Name of work:- C/o Shetajol to Lashani road Km 0/00 to 4/500 (SH:- P/L Kharanja stone soling at various RD's) as per working programme.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (One hundred millimetre) spread thickness complete within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	387.05	1282.25	Rupees One thousand two hundred eighty two and paise twenty five only.	Per Cubic metre	496295.00
					Total:-	496295.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Repair of pot holes in Bhuin Shilihar road Km. 0/00 to 6/00 .
(SH):- Repair of Pot holes in Km. 2/00 to 4/00) .

Estimated cost:- Rs. 4,94,350.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	1264.00	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	494350.00
					Total	494350.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

34

SCHEDULE OF QUANTITY

Name of work:- RRD on Chharour Nallah to Badogi road Km 0/00 to 7/850

Estimated cost:- Rs. 2,55,119.00

(SH):- C/o wire crated protection wall and PCC protection wall for 6.0 mtr. span slab culvert at RD 5/780).

Earnest money :- Rs. 5,200.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in- charge.	305.1	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	5623.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in- charge.	9.36	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only	Per cubic metre	48637.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	62.50	3213.75	Rupees Three thousand two hundred thirteen and paise seventy five only	Per cubic metre	200859.00
					Total	255119.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

35

SCHEDULE OF QUANTITY

Name of work:- Repair of pot holes in Chharour Nallah to Badogi road Km. 0/00 to 7/850 .
(SH:- Repair of Pot holes in Km. 2/00 to 4/00).

Estimated cost:- Rs. 4,93,998.00

Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	1263.10	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	493998.00
					Total	493998.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

36

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohgi GP Shillrajgiri Km. 0/00 to 3/500.
(SH:- Formation cutting in Km. 0/810 to 0/945)

Estimated cost:- Rs. 4,11,314.00
Earnest money :- Rs. 8,400.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 89.68 Cum @ 300/- per cubic metre amounting to Rs. 26,904/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1494.60	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	411314.00
					Total:-	411314.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

37 **SCHEDULE OF QUANTITY**

Name of work:- Construction of link road to village Rohgi GP Shillrajgiri Km. 0/00 to 3/500 .
(SH:- Formation cutting in Km. 0/945 to 1/165).

Estimated cost:- Rs. 4,69,450.00
Earnest money :- Rs. 9,500.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1 & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 102.35 Cum @ 300/- per cubic metre amounting to Rs. 30,705/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1705.85	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	469450.00
					Total:-	469450.00


Executive Engineer,
Kullu Division
HP PWD Kullu.

SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,64,882.00
 Earnest money :- Rs. 9,400.00
 Time :- Two months.

Name of work:- Construction of link road to village Rohgi GP Shilliraigiri Km. 0/00 to 3/500.
(SH:- Formation cutting in Km. 1/165 to 1/555).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required). Recovery for useful material of 101.36 Cum @ 300/- per cubic metre amounting to Rs. 30,408/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1689.25	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	464882.00
					Total:-	464882.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu.

39

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohgi GP Shillirajiri Km. 0/00 to 3/500.
(SH:- Formation cutting in Km. 1/555 to 1/795).

Estimated cost:- Rs. 4,39,715.00
 Earnest money :- Rs. 8,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 95.87 Cum @ 300/- per cubic metre amounting to Rs. 28,761/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1597.80	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	439715.00
					Total:-	439715.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

40

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohgi GP Shilliraigiri Km. 0/00 to 3/500 .
(SH:- Formation cutting in Km. 1/795 to 2/135).

Estimated cost:- Rs. 4,67,221.00
 Earnest money :- Rs. 9,500.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 101.87 Cum @ 300/- per cubic metre amounting to Rs. 30,560/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1697.75	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	467221.00
					Total:-	467221.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/500
(SH:- Formation cutting in Km. 2/135 to 2/255)
Estimated cost:- Rs. 4,25,555.00
Earnest money :- Rs. 8,600.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1.&1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 92.78 Cum @ 300/- per cubic metre amounting to Rs. 27,834/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1546.35	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	425555.00
					Total:-	425555.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohgi GP Shilliraigiri Km. 0/00 to 3/500 .
(SH:- Formation cutting in Km. 0/745 to 0/810) .

Estimated cost:- Rs. 4,01,256.00
Earnest money :- Rs. 8,200.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1.&1603.2 and sorting out useful/urn useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 87.48 Cum @ 300/-per cubic metre amounting to Rs. 26,244/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1458.05	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	401256.00
					Total:-	401256.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Construction of Strong room in Govt. Degree College Kullu.
(SH):- Closing the ventilation through half brick masonry and painting distempering in GF Tennis hall, FF room no. 102, 2nd floor room no. 204A & 203A & back room no. 1 & 2 etc.)

Estimated cost:- Rs. 3,44,583.00
 Earnest money :- Rs. 7,000.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Half brick masonry in common burnt clay building bricks in super structure Cement Mortar 1:4 (1 cement:4 sand) First Class Bricks upto 2nd floor within all leads and lift of materials and as per direction of Engineer-in-charge.	84.01	1188.40	Rupees One thousand one hundred eighty eight and paise forty only.	Per Square metre	99837
2	Demolition brick work above G.L. upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials with in 20 m (Twenty metre) with cement mortar 1:3 (1 cement : 3 sand) complete with all accessories as required as per direction of Engineer-in-Chief within all leads and lift of materials and as per direction of Engineer-in-charge.	8.40	1226.94	Rupees One thousand two hundred twenty six and paise ninety four only.	Per Cubic metre	10306
3	Repairs to plaster of thickness 10 mm (Ten millimetre) to 15 mm (Fifteen millimetre) in patches of area 2.5 sq.meters (Two point five square metre) and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within lead of 20 m (Two metre) all complete With cement mortar 1:3 (1 cement : 3 sand) with in all leads and lift of materials and as per direction of Engineer-in-charge.	33.89	384.46	Rupees Three hundred eighty four and paise forty six only	Per Square metre	13029
4	Providing and applying white cement based putty of average thickness 1 mm (One millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	256.18	103.40	Rupees One hundred three and paise forty only.	Per Square metre	26489
5	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre (Fifty grams/ litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. 13.42.1 Two or more coats on new work Walls with in all leads and lift of materials and as per direction of Engineer-in-charge.	1033.52	120.55	Rupees One hundred twenty and paise fifty five only.	Per Square metre	124591
6	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (Zero point seventy five litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	28.50	128.50	Rupees One hundred twenty eight and paise fifty only.	Per Square metre	3662

7	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (Zero point eighty litre/ Ten square metre of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge	95.76	111.60	Rupees One hundred eleven and paise sixty only.	Per square metre	10687
8	Steel work welded in built up sections, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works with in all leads and lift of materials and as per direction of Engineer-in-charge.	212.50	150.40	Rupees One hundred fifty and paise forty only.	Per Kilogram	31960
9	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows including black enamelled iron butt hinges with necessary screws 40 mm (Forty millimetre) thick 1st class Deodar wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.25	5652.00	Rupees Five thousand six hundred fifty two only.	Per Square metre	24021
	Total	Total				344583


 Executive Engineer,
 Kullu Division,
 HP, PWD Kullu

44

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road to village Kharkha Km. 0/00 to 1/450 .
(SH:- Removal of Slips at various RD's) . Job. 1.

Estimated cost:- Rs. 4,91,343.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.50 m (One point fifty metre) and lead upto 1000 m (One thousand metre) a sper technical specification 302.5 and 1611 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	3927.60	125.10	Rupees One hundred twenty five and paise ten only	Per cubic metre	491343.00
					Total	491343.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road to village Kharkha Km. 0/00 to 1/450 .

Estimated cost:- Rs. 4,83,837.00
Earnest money :- Rs. 9,800.00

Time :- Two months.

(**SH:-** Removal of Slips at various RD's) . Job. 2.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.50 m (One point fifty metre) and lead upto 1000 m (One thousand metre) a sper technical specification 302.5 and 1611 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	3867.60	125.10	Rupees One hundred twenty five and paise ten only	Per cubic metre	483837.00
					Total	483837.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

46

SCHEDULE OF QUANTITY

Name of work:- C/o Lashani Sangtehar road Km. 0/00 to 3/660 .
(SH:- C/o wire crated B/wall at RD. 2/915 to 2/940) .

Estimated cost:- Rs. 3,89,034.00
Earnest money :- Rs. 8,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	34.37	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	7848.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	12.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	4567.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	117.19	3213.75	Rupees Three thousand two hundred thirteen and paise seventy five only.	Per cubic metre	376619.00
					Total	389034.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- C/o Lashani Sangtehar road Km. 0/00 to 3/660.
(SH):- C/o Retaining wall with at RD 3/035 to 3/050).

Estimated cost:- Rs. 2,84,369.00
 Earnest money:- Rs. 5,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	24.07	385.35	Rupees Three hundred Sixty five and paise thirty five only.		Per cubic metre	8794.00
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	6.45	4509.15	Rupees Four thousand five hundred nine and paise fifteen only		Per cubic metre	29084.00
3	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	22.65	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only		Per cubic metre	118968.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	34.20	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.		Per cubic metre	93578.00
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	21.15	1604.95	Rupees One thousand six hundred four and paise ninety five only.		Per cubic metre	33945.00
						Total	284369.00


 Executive Engineer,
 Kulu Division,
 HP.PWD Kulu

48

SCHEDULE OF QUANTITY

Name of work:- C/o Lashani Sangtehar road Km. 0/00 to 3/660

(SH):- C/o wire crated R/wall with PCC Toe wall at RD. 2/952.50 to 2/971.25)

Estimated cost:- Rs. 4,89,044.00

Earnest money:- Rs. 9,800.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	37.78	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13803.00
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 PCC grade 1:4:8 (One cement :Four sand : Eight graded stone aggregate) for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	14.62	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	72477.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	117.18	3213.75	Rupees Three thousand two hundred thirteen and paise seventy five only.	Per cubic metre	376587.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	16.31	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	26177.00
					Total	489044.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

49

SCHEDULE OF QUANTITY

Name of work:- C/o Lashani Sangtehar road Km. 0/00 to 3/660 .

(SH:- C/o wire crated R/wall with PCC Toe wall at RD. 2/933.75 to 2/952.50) .

Estimated cost:- Rs. 4,89,497.00

Earnest money:- Rs. 9,800.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	36.56	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13357.00
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 PCC grade 1:4:8 (One cement : Four sand : Eight graded stone aggregate) for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	14.62	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	72477.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	117.18	3213.75	Rupees Three thousand two hundred thirteen and paise seventy five only.	Per cubic metre	376587.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	16.87	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	27076.00
					Total	489497.00


Executive Engineer,
Kullu Division,
HP PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- C/o Lashani Sangtehar road Km. 0/00 to 3/660.
(SH:- C/o wire crated R/wall with PCC Toe wall at RD. 2/915 to 2/933.75) .

Estimated cost:- Rs. 4,89,949.00
Earnest money:- Rs. 9,800.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	35.34	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	12911.00
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 PCC grade 1:4:8 (One cement :Four sand : Eight graded stone aggregate) for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	14.62	4857.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	72477.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	117.18	3213.75	Rupees Three thousand two hundred thirteen and paise seventy five only.	Per cubic metre	376587.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	17.43	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	27974.00
					Total	489949.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bhunter Bus stop to Parganoo Chowk road Km. 0/00 to 1/200 .

Estimated cost:- Rs. 1,60,115.00

Earnest money:- Rs. 3,400.00

Time :- Two months.

(SH:- C/o C.C. edge wall in Km. 0/078 to 0/098 with 900 mm dia Hume pipe at Km. 0/098)

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	10.80	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	3946.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	27.56	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only	Per cubic metre	143210.00
3	Providing and laying reinforced cement concrete pipe NP3 for culverts on 1st class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement: Two sand) but excluding protection work and back filling and concrete work inhead walls and parapets clause 1106 within all leads and lift of materials and as per direction of Engineer-in-charge.	2.50	5183.55	Rupees Five thousand one hundred eighty three and paise fifty five only.	Per Running metre	12959.00
					Total	160115.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Construction of Mohal (Buins Bai) Bhulang road Km. 0/00 to 11/020
(SH:- ROFD in Km. 10/817.50 to 10/863.50).

Estimated cost:- Rs. 4,85,312.00
Earnest money :- Rs. 9,800.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chibeling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means.	1436.56	337.83	Rupees Three hundred thirty seven and paise eighty three only.	Per cubic metre	485312.00
					Total:-	485312.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

53

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dohranallah to Khairhar road Km. 0/00 to 10/120.
(SH:- C/o Retaining wall at RD 2/369.70 to 2/379)

Estimated cost:- Rs. 4,97,853.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	12.65	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	2888.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	56.27	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	20558.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803, 1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	30.60	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	151698.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702, 704, 1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	58.03	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	304809.00
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	11.16	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	17911.00
	Total	Total				497853.00


 Executive Engineer,
 Kullu Division,
 H.P. PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages due to laying underground 250 mm dia pipe line (L.I.S.)

on Workshop Gadouri road Km. 0/00 to 1/200

(SH:- P/L GSB, G-III in Km. 0/400 to 0/800)

Estimated cost:- Rs. 4,62,923.00

Earnest money :- Rs. 9,400.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Preparation and consolidation of sub grade with power road roller of 8 (Eight) to 12(Twelve) tonne capacity after excavating earth to an average of 22.5 cm (Twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with any lead within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	480.00	91.30	Rupees Ninety one and paise thirty only	Per Square metre	43824.00
2	Construction of granular sub-base by providing close grade material, conforming to specification mixing in a mechanical mixed plant at OMC, carriage of mixed material by tippers to work at site for all leads and lifts in uniform layers of specified thickness with vibratory road roller to achieve the density complete within all leads and lift of materials and as per direction of Engineer-in-charge.	110.40	2673.35	Rupees Two thousand six hundred seventy three and paise thirty five only.	Per Cubic metre	295138.00
3	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	36.00	3443.35	Rupees Four hundred eighty eight and paise seventy five only	Per Cubic Metre	123961.00
					Total	462923.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dohranallah to Barahar road Km. 0/00 to 10/00.
(SH:- C/o Retaining wall at RD 1/450 to 1/460)

Estimated cost:- Rs. 1,83,708.00
Earnest money :- Rs. 3,800.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	18.90	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	4316.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	8.90	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	3252.00
3	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix aggregate foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	4.30	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	19389.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	14.90	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	78262.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	22.88	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	62604.00
6	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	15.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	6255.00
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	6.00	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	9630.00
	Total					183708.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dohranallah to Barahar road Km. 0/00 to 10/00
(SH):- C/o Retaining wall at RD 0/630 to 0/642.50)

Estimated cost:- Rs. 3,73,000.00
 Earnest money :- Rs. 7,500.00
 Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1003.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	47.75	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	10904.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	16.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	6028.00
3	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement : Six sand : Twelve graded stone) for nominal mix aggregate foundations complete as per drawing and technical specification clause 802.803, 1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.00	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	40582.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702, 704, 1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	31.85	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	167291.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour, equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	43.99	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	120365.00
6	Providing weep holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	25.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	9774.00

7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	11.25	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	18056.00
		Total				373000.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dohranallah to Barahar road Km. 0/00 to 10/00
(SH:- C/o Retaining wall at RD 1/225 to 1/242.50).

Estimated cost:- Rs. 3,73,000.00
 Earnest money :- Rs. 7,500.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in	Unit	Amount
			Figure	Words	
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	47.75	228.35	Rupees Two hundred twenty eight and paise thirty five only	10904.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	16.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	6028.00
3	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:0.12 (One cement :Six sand : Twelve graded stone) for nominal mix aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.00	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	40582.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:5 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	31.85	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	167291.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	43.99	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	120365.00

6	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	25.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	9774.00
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material, within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	11.25	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	18056.00
	Total					373000.00

Executive Engineer,
Kullu Division
HP.PWD Kullu

58

Estimated cost:-493945.00
Earnest money :-10000.00
Time :- Two months

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Linger Bansu Road Km. 0/0 to 11/500
(SH:- Removal of slips/debris in various Rd's)

Sr. No	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3948.40	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	493945.00
					Total	493945.00


Executive Engineer
Kullu Division
HP.PWD Kullu

SCHEDULE OF QUANTITY

Estimated cost:- Rs.1,36,664.00
Earnest money :- Rs. 3,000.00

Time :- One month

Name of work:- A/R and M/O non residential/ residential building under Bhunter sub Division HP.PWD Bhunter (SH:- Re-filling of Fire extinguishers and painting and distemper work at Bhunter S/D office)

Sr.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing and fixing powder fire extinguisher (Stored Pressure Type) capacity 9kg (Nine kilogramme) duly ISI marked conforming to IS 15683: 2006 with ISI 4609 marked ABC powder complete with Squeeze grip releases valve, discharge pipe, looking arrangement, Pressure gauge, operation manual, bracket with two screws and sleeves including hauling of material in all leads and lift as per the entire satisfaction and direction of Engineer-in-charge.	3	11000.00	Rupees Eleven Thousand and paise zero only	Each	33000.00
2	Refilling charges co2 type 9.00 kg. capacity at site of work in all respect including carriage of materials with in all leads lifts as per direction of Engineer-in-charge.	15	2250.00	Rupees Two thousand two hundred fifty and paise zero only	Each	33750.00
3	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete. with in all leads lifts as per direction of Engineer-in-charge.	330.04	15.35	Rupees Fifteen and paise Thirty Five only	Per square meter	5066.00
4	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete with in all leads lifts as per direction of Engineer-in-charge.	165.00	103.40	Rupees One hundred Three and paise Forty only	Per square meter	17061.00
5	Applying one coat of Acrylic/Washable emulsion Spectrum quartz king or equivalent finish for interior painting with brushes plain smooth finish composed of acrylic polymere in emulsion inorganic/special pigment siliceous aggregate anti fungicides anti-rusting & foaming in two coat i/c necessary putty to give smooth even surface, sand papered smooth complete. with in all leads lifts as per direction of Engineer-in-charge.	330.0	120.55	Rupees Two thousand two hundred fifty and paise zero only	Per square meter	39786.00
6	Painting wood work with Deluxe Multi surface Paint of required shade, Two or more coat applied @ 0.90 ltr./10 sqm over an under coat of primer applied @0.75 ltr./10sqm of approved brand and manufacture with in all leads lifts as per direction of Engineer-in-charge.	75.34	106.20	Rupees one hundred twenty and paise Twenty only	Per square meter	8001.00
					Total:-	136664.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Estimated cost : Rs. 4,72,000
 Earnest money : Rs. 10000.00
 Time : Two Months

Name of work :- Upgradation, Metalling and tarring on Dohranallah Shillihar Chesta Rolgi road under MLA Priority (SH:- Preparation of DPR)

Sr. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			In Figure	Words		
1	reparation of Detailed Project Report i/c Surveying and Investigation for preparation of manuscript copy of detailed Estimate i.c Cross-sections, Plan, Preparation of Detailed Estimate in the Shape of manuscript copy duly approved from the Circle Office & Chief office. Preparation of approved copies of Detailed Estimate along with relevant working drawings. (Five sets of DPR's and five additional sets of working drawing complete) and soft copies in the form of Compact Disc (C.D.) of below mentioned works including Estimate and Drawings.					
	Upgradation, Metalling and tarring on Dohranallah Shillihar Chesta Rolgi road (SH:- ROFD, M/T, CD works, R/walls, B/walls, road singages)	16.00	29500.00	Twenty Nine Thousand and five hundred only		472000.00
					Total:-	472000.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu.

Estimated Cost: 80000
 Earns Money: 2000
 Time: Two months

SCHEDULE OF QUANTITY

Name of work:- Consultancy services for Construction of Type-IV Residence to the Secretary Distt. Legal Service Authority Kullu at Badah Distt Kullu (HP)

Sub Head:- Preparation of Estimate of whole Project as per Architectural Drawings.

Sr.No.	Description	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Job work for preparing of estimate of whole project as per architectural drawing for the construction of Type-IV Residence to the Secretary Distt. Legal Service Authority Kullu at Badah Distt Kullu (HP). The job work shall also include supplying detailed estimate based on HPSR-2020 duly supported with analysis of rates for scheduled items and on market rate for non-scheduled items. The job work shall include supplying and approval of estimates in quadruplicate along with soft copy in the shape of CD as per direction of Superintending Engineer/Executive Engineer HPPWD Division Kullu	1 No. Job	80000.00	Rupees Eighty thousand only	Per Job	80000.00
					TOTAL	80000.00

Terms and condition:-

Submission of fair copy of quadruplicate duly computerized and approval of the same from Superintending Engineer/ Chief Engineer.

Payment schedule:-

For Estimation work

On submission of working estimate based on HPSR-2020 duly supported with analysis for scheduled items and on market rates non schedule item alongwith 50%

On approval of working estimate based on HPSR-2020 duly supported with analysis for scheduled items and on market rates non schedule item alongwith 50%


 Executive Engineer
 B&R Division Kullu
 HPPWD Kullu

62

SCHEDULE OF QUANTITY

Name of work:- C/o Pecha to Deoghara road Km. 0/00 to 6/850
(SH:- C/o Retaining wall at RD 2/411 to 2/417)

Estimated cost:- Rs. 4,99,424.00
Earnest money:- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	57.90	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	21154.00
2	Drilling of holes 75 cm (Seventy five centimetre) deep for fixing dowels bars 25 mm (Twenty five millimetre) dia within all leads and lift of materials and as per direction of Engineer-in-charge.	15.00	700.00	Rupees Seven hundred only.	Per running metre	10500.00
3	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	22.98	6250.50	Rupees Six thousand two hundred fifty and paise fifty only.	Per cubic metre	143636.00
4	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	3.30	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only.	Per cubic metre	16359.00
5	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	36.96	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only.	Per cubic metre	194131.00
6	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportatin within all leads and lift of materials and as per direction of Engineer-in-charge.	34.60	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	94673.00
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	11.82	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	18971.00
					Total	499424.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

63

SCHEDULE OF QUANTITY

Name of work:- C/o Pecha to Deoghara road Km. 0/00 to 6/850.
(SH:- C/o Retaining wall at RD 2/405 to 2/411)

Estimated cost - Rs. 4,99,599.00
 Earnest money - Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	58.38	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	21329.00
2	Drilling of holes 75 cm (Seventy five centimetre) deep for fixing dowels bars 25 mm (Twenty five millimetre) dia within all leads and lift of materials and as per direction of Engineer-in-charge.	15.00	700.00	Rupees Seven hundred only.	Per running metre	10500.00
3	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	22.98	6250.50	Rupees Six thousand two hundred fifty and paise fifty only	Per cubic metre	143636.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	3.30	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	16359.00
5	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	36.96	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	194131.00
6	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	34.60	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	94673.00
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	11.82	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	18971.00
					Total	499599.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

64

SCHEDULE OF QUANTITY**Name of work:-** C/o Shishamati Bypass road Km. 0/00 to 1/00 .

Estimated cost:- Rs. 3,90,383.00

Earnest money:- Rs. 8,000.00

Time :- Two months.

(SH):- C/o wire crated R/wall with PCC toe wall and laying of NP3 pipes at RD 0/724.05 to 0/731.55).

Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	305.1 30.30	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	11070.00
2	Providing and laying reinforced cement concrete pipe NP3 for culverts on 1st class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement: Two sand) but excluding protection work and back filling and concrete work in head walls and parapets clause 1106 within all leads and lift of materials and as per direction of Engineer-in-charge.	10.00	6997.80	Rupees six thousand nine hundred ninety seven and paise eighty only.	Per Running metre	69978.00
3	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	36.45	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only	Per cubic metre	189405.00
4	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	31.25	3213.75	Rupees Three thousand two hundred thirteen and paise seventy five only	Per cubic metre	100430.00
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material, within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	12.15	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	19500.00
					Total	390383.00


 Executive Engineer,
 Kullu Division
 +91903 Kullu

SCHEDULE OF QUANTITY

Name of work:- RRD due to laying of optical fiber cable on Kullu Karon road km 0/00 to 15/00
(SH):- Construction of PCC Retaining wall at RD 2/00 to 2/017), OFC Deposit.

Estimated cost:- Rs. 4,17,822.00
 Earnest money:- Rs. 8,500.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	49.06	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	17924.00
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 PCC grade 1:4:8 (One cement :Four sand : Eight graded stone aggregate) for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	75.20	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	372796.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	14.45	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	23192.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	10	390.95	Rupees Three hundred ninety and paise ninety five only	Each	3910.00
					Total	417822.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Repair to treasury office building Kullu district Kullu

(SH:- C/o additional male & female WC and bath toilet for security guards etc.).

C
C

Estimated cost:- Rs. 4,95,263.00

Earnest money:-Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 (Fifty) metres lead For thickness of tiles 10 mm (Ten millimetre) to 25 mm (Twenty five millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	26.02	31.20	Rupees Thirty one and paise Twenty only.	Per Square metre	812
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres (Fifty metre) lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/equivalent design mix) with in all leads and lift of materials and as per direction of Engineer-in-charge.	0.98	1451.44	Rupees One thousand four hundred fifty one and paise forty four only.	Per Cubic metre	1422
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. with in all leads and lift of materials and as per direction of Engineer-in-charge.	25.86	11.15	Rupees Eleven and paise fifteen only.	Per Square metre	288
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:4 (1 cement : 4 coarse sand) with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.18	10539.60	Rupees Ten thousand five hundred thirty nine and paise sixty only.	Per Cubic metre	65135
5	15 mm (Fifteen millimetre) cement plaster on rough side of single or half brick wall of mix 1:4 (1 cement : 4 coarse sand) with in all leads and lift of materials and as per direction of Engineer-in-charge.	142.41	384.46	Rupees Three hundred eighty four and paise forty six only	Per Square metre	54751
6	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre (Fifty grams/ litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. 13.42 1 Two or more coats on new work Walls with in all leads and lift of materials and as per direction of Engineer-in-charge.	63.46	120.55	Rupees One hundred twenty and paise fifty five only.	Per Square metre	7650
7	Providing and applying white cement based putty of average thickness 1 mm (One millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	63.46	103.40	Rupees One hundred three and paise forty only.	Per Square metre	6562

8	Providing and laying durastone checked tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm (Six millimetre) thickness, including grouting of joints (Payment for grouting of joints to be made separately) Size of Tile 600x600 mm (Six hundred x Six hundred millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	15.97	1824.00	Rupees One thousand eight hundred twenty four only.	Per square metre	29129
9	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados over 12 mm (Twelve millimetre) thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm (Three point three kilogram per square metre), including pointing in white cement mixed with pigment of matching shade complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	64.62	1405.59	Rupees One thousand four hundred five and paise fifty nine only.	Per Square metre	90830
10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand); 6 graded stone aggregate 40 mm (Forty millimetre) nominal size) with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.29	5212.95	Rupees Five thousand two hundred twelve and paise ninety five only.	Per Cubic metre	17151
11	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) Deodar wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	0.56	129393.44	Rupees One Lac twenty nine thousand three hundred ninety three and paise forty four only.	Per Cubic metre	71813
12	Providing and fixing 40 mm (Forty millimetre) thick panelled shutter for door with deodar wood style rail beading and infill panele of 12 mm (Twelve millimetre) thick phenol bonded prelaminated board both side particle board panel ISI marked 12823 including ISI marked with in all leads and lift of materials and as per direction of Engineer-in-charge.	7.20	6200.00	Rupees Six thousand two hundred only.	Per Square metre	44640
13	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows including black enamelled iron butt hinges with necessary screws 40 mm (Forty millimetre) thick 1st class Deodar wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.31	5652.00	Rupees Five thousand six hundred fifty two only.	Per Square metre	18708

14	Providing and fixing wire gauge shutter using galvanised MS wire gauge of aperture 1.4 mm (One point four millimetre) both direction with wire of dia 0.63 mm (Zero point six three millimetre) for door window and clestory window with hings and necessary screw 35 mm (Thirty five millimetre) klin seasoned wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.31	3085.76	Rupees Three thousand eighty five and paise seventy six only.	Per Square metre	10214
15	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (Zero point seventy five litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	33.09	106.20	Rupees One hundred six and paise twenty only.	Per square metre	3514
16	Providing and fixing bright finished brass handles with screws etc. complete 125 mm (One hundred twenty five millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	5.00	172.70	Rupees One hundred seventy two and paise seventy only.	Each	864
17	Providing and fixing bright finished brass towels bolts (barrel type) with necessary screws etc. complete 150 x 10 mm (One hundred fifty into Ten millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	22.00	147.90	Rupees One hundred forty seven and paise ninety only.	Each	3254
18	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (Ten millimetre) gap for thermal expansion. (i) Single socketed pipes. 110 mm (One hundred ten millimetre) diameter with in all leads and lift of materials and as per direction of Engineer-in-charge.	48.00	550.00	Rupees Five hundred fifty only.	Per Running metre	26400
19	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (Ten millimetre) gap for thermal expansion with in all leads and lift of materials and as per direction of Engineer-in-charge.					
a)	Single tee with door 110x110x110 mm (One hundred ten x One hundred ten x One hundred ten millimetre)	4.00	350.00	Rupees Three hundred fifty only.	Each	1400
b)	Bend 87.5 110 mm (One hundred ten millimetre) bend	10.00	290.00	Rupees Two hundred ninety only.	Each	2900

20	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes conforming to IS-15801, UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, i/c fixing the pipe with clamps at 1.00 m (One point zero metre) spacing. This includes the cost of cutting chases and making good the same including testing of joints complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	48.00	599.98	Rupees Five hundred ninety nine and paise ninety eight only.	Per Running metre	28799	
a)	PN - 16 Pipe. 20mm (Twenty millimetre) OD (SDR-7.4)						
21	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors with in all leads and lift of materials and as per direction of Engineer-in-charge.	9.00	1002.99	Rupees One thousand two and paise ninety nine only	Each	9027	
	Total						495263


 Executive Engineer,
 Kullu Division
 HP, PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Residential building under Kullu division.
(SH:- P/L outer sewer line, renovation of old damaged WC and p/f E/B in room no. 2 etc. in type-3 quarter near 6th circle Kullu).

Estimated cost:- Rs. 3,96,768.00
 Earnest money:-Rs. 8,000.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres (Fifty metre) lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (if/cequivalent design mix) with in all leads and lift of materials and as per direction of Engineer-in-charge.	12.53	1451.44	Rupees One thousand four hundred fifty one and paise forty four only.	Per Cubic metre	18186
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 40 mm (Forty millimetre) nominal size) with in all leads and lift of materials and as per direction of Engineer-in-charge.	7.53	5212.95	Rupees Five thousand two hundred twelve and paise ninety five only.	Per Cubic metre	39253
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	126.62	15.36	Rupees Fifteen and paise thirty six only.	Per Square metre	1945
4	Providing and applying white cement based putty of average thickness 1 mm (One millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	56.98	103.40	Rupees One hundred three and paise forty only.	Per Square metre	5892
5	Repairs to plaster of thickness 12 mm (Twelve millimetre) to 20 mm (Twenty millimetre) in patches of area 2.5 sq.meters (Two point five square metre) and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete With cement mortar 1:4 (1 cement : 4 fine sand) with in all leads and lift of materials and as per direction of Engineer-in-charge.	19.50	384.46	Rupees Three hundred eighty four and paise forty six only	Per Square metre	7497

6	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre (Fifty grams/ litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. 13.42.1 Two or more coats on new work Walls with in all leads and lift of materials and as per direction of Engineer-in-charge.	126.62	120.55	Rupees One hundred twenty and paise fifty five only.	Per Square metre	15264
7	Providing and fixing wire gauge shutter using galvanised MS wire gauge of aperture 1.4 mm (One point four millimetre) both direction with wire of dia 0.63 mm (Zero point sixty three millimetre) for door window and cleftory window with hings and necessary screw 35 mm (Thirty five millimetre) klin seasoned wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.93	4350.64	Rupees Four thousand three hundred fifty and paise sixty four only.	Per Square metre	12747
8	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours. shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm (Twelve millimetre) thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm (Three point three kilogram per square metre), including pointing in white cement mixed with pigment of matching shade complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	33.30	1833.60	Rupees One thousand eight hundred thirty three and paise sixty only.	Per Square metre	61059
9	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm (Six millimetre) thickness, including grouting of joints (Payment for grouting of joints to be made separately) Size of Tile 600x600 mm (Six hundred x Six hundred millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	10.46	1935.50	Rupees One thousand nine hundred thirty five and paise fifty only.	Per Square metre	20245
10	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (Zero point seventy five litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	78.48	106.20	Rupees One hundred six and paise twenty only.	Per Square metre	8335
11	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 110 mm (One hundred ten millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	36.00	550.00	Rupees Five hundred fifty only.	Per running metre	19800

12	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes conforming to IS:15801, UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, i/c fixing the pipe with clamps at 1.00 m (One point zero metre) spacing. This includes the cost of cutting chases and making good the same including testing of joints complete with in all leads and lift of materials and as per direction of Engineer-in-charge. PN - 16 Pipe, 20mm (Twenty millimetre) OD (SDR-7.4)	12.00	466.60	Rupees Four hundred sixty six and paise sixty only.	Per Running metre	5599
13	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre (Ten litre) low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm (Forty millimetre) flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	9379.30	Rupees Nine thousand three hundred seventy nine and paise thirty only.	Each	9379
14	Providing and fixing wash basin with C.I. brackets, 15mm (Fifteen millimetre) dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required White Vitreous China Wash basin size 550x400 mm (Five hundred fifty x Four hundred millimetre) with a 15 mm (Fifteen millimetre) CP Brass single hole basin mixer with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	4685.97	Rupees Four thousand six hundred eighty five and paise ninety seven only.	Each	4686
15	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	2038.15	Rupees Two thousand thirty eight and paise fifteen only.	Each	2038
16	Providing and fixing PTMT jet spray of approved quality and colour with one metre tube pipe with necessary fitting etc. complete within all leads and lifts and other incidentals including carriage of materials in all respect with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	990.12	Rupees Nine hundred ninety and paise twelve only.	Each	990
17	Providing and fixing CP soap Dish Holder having length of 138 mm (One hundred thirty eight millimetre), breadth 102 mm (One hundred two millimetre), height of 75 mm (Seventy five millimetre) with concealed fitting arrangements, weighing not less than 106 gms (One hundred six grams) with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.00	477.39	Rupees Four hundred seventy seven and paise thirty nine only.	Each	1910

18	Providing and fixing C.P. brass and bib cock of approved quality conforming to IS:8931 15mm (Fifteen millimeter) nominal bore with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.00	937.14	Rupees Nine hundred thirty seven and paise fourteen only.	Each	5623
19	Providing and fixing uplasticised PVC connection pipe with PTMT nuts, collar and bush of approved quality and colour 15 mm (Fifteen millimeter) nominal bore with 45 cm (Forty five centimetre) length with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.00	183.15	Rupees One hundred eighty three and paise fifteen only	Each	1099
20	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	1002.99	Rupees One thousand two and paise ninety nine only	Each	2006
21	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm (Fifteen millimeter) nominal bore with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.00	900.24	Rupees Nine hundred and paise twenty four only	Each	5401
22	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 300x16mm (Three hundred x Sixteen millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	172.70	Rupees One hundred seventy two and paise seventy only.	Each	345
23	Providing and fixing oxidised M.S. tower bolts (barrel type) with necessary screws etc. complete. 150x10mm (One hundred fifty x Ten millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.00	147.90	Rupees One hundred forty seven and paise ninety only	Each	887
24	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg (Thirty five kilogram) and door width upto 700 mm (Seven hundred millimetre)), with necessary accessories and screws etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	1647.44	Rupees One thousand six hundred forty seven and paise forty four only.	Each	3295
25	Providing and fixing 19mm (Nineteen millimetre) thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	54.00	1812.15	Rupees One thousand eight hundred twelve and paise fifteen only.	Per Square metre	97856

26	Providing and fixing 19mm (Nineteen millimetre) thick Commercial Board water proof shutters for up boards i/c fixing with nickel plated piano hinges with screws etc complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	12.78	2071.67	Rupees Two thousand seventy one and paise sixty seven only.	Per Square metre	26476
27	Providing and fixing 1.00 mm (One point zero millimetre) thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	12.78	1279.81	Rupees One thousand two hundred seventy nine and paise eighty one only.	Per Square metre	16356
28	Providing and fixing bright finished brass handles with screws etc. complete 125 mm (One hundred twenty five millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	12.00	216.48	Rupees Two hundred sixteen and paise forty eight only.	Each	2598
	Total					396768


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- RRD on Manikaran Barshaini road Km. 0/00 to 15/00 .

(SH):- C/o Toe wall of R/wall from RD 0/710 to 0/750), Job No. 1 (NHPC - Deposit).

Estimated cost:- Rs. 4,92,660.00

Earnest money:- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	320.13	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	116959.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	65.80	5709.75	Rupees Five thousand seven hundred nine and paise seventy five only.	Per cubic metre	375701.00
					Total	492660.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

69

SCHEDULE OF QUANTITY

Name of work:- RRD on Manikaran Barshaini road Km. 0/00 to 15/00

(SH):- C/o Toe wall of R/wall from RD 0/710 to 0/750). Job No. 2 (NHPC - Deposit).

Estimated cost:- Rs. 4,97,890.00
Earnest money:- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	87.20	5709.75	Rupees Five thousand seven hundred nine and paise seventy five only.	Per cubic metre	497890.00
					Total	497890.00


 Executive Engineer,
 Kullu Division
 HP PWD Kullu

70

SCHEDULE OF QUANTITY

Name of work:- RRD on Manikaran Barshaini road Km. 0/00 to 15/00 .

(SH:- C/o Toe wall of R/wall from RD 0/710 to 0/750). Job No. 3 (NHPC - Deposit).

Estimated cost:- Rs. 4,85,785.00

Earnest money:- Rs. 9,800.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	85.08	5709.75	Rupees Five thousand seven hundred nine and paise seventy five only.	Per cubic metre	485785.00
					Total	485785.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu.

71

SCHEDULE OF QUANTITY

Name of work:- RRD on Manikaran Barshaini road Km. 0/00 to 15/00 .

(SH:- C/o Toe wall of R/wall from RD 0/710 to 0/750). Job No. 4 (NHPC - Deposit).

Estimated cost:- Rs. 4,97,890.00

Earnest money:- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	If	Rate in		Unit	Amount
				Figure	Words		
1	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	87.20		5709.75	Rupees Five thousand seven hundred nine and paise seventy five only.	Per cubic metre	497890.00
				90	Total		497890.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

72

SCHEDULE OF QUANTITY

Name of work:- RRD on Manikaran Barshaini road Km. 0/00 to 15/00.

Estimated cost:- Rs. 4,96,977.00

(SH:- C/o Toe wall of R/wall from RD 0/710 to 0/750). Job No. 5 (NHPC - Deposit).

Earnest money:- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	87.04	5709.75	Ruppes Five thousand seven hundred nine and paise seventy five only.	Per cubic metre	496977.00
					Total	496977.00

Executive Engineer,
Kullu Division
HP.PWD Kullu

73

SCHEDULE OF QUANTITY

Name of work:- RRD on Manikaran Barshaini road Km. 0/00 to 15/00.

(SH:- C/o Toe wall of R/wall from RD 0/710 to 0/750). Job No. 6 (NHPC - Deposit).

Estimated cost:- Rs. 4,99,603.00

Earnest money:- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	87.50	5709.75	Rupees Five thousand seven hundred nine and paise seventy five only.	Per cubic metre	499603.00
					Total	499603.00


 Executive Engineer,
 Kullu Division,
 HP PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages due to laying underground 250 mm dia pipe line (L.I.S.) on Workshop Gadouri road Km. 0/00 to 1/200.
(SH:- P/L GSB, G-III in Km. 0/800 to 1/200).

Estimated cost:- Rs. 4,62,923.00
Earnest money :- Rs. 9,400.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Preparation and consolidation of sub grade with power road roller of 8 (Eight) to 12(Twelve) tonne capacity after excavating earth to an average of 22.5 cm (Twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with any lead within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	480.00	91.30	Rupees Ninety one and paise thirty only	Per Square metre	43824.00
2	Construction of granular sub-base by providing close grade material, conforming to specification mixing in a mechanical mixed plant at OMC, carriage of mixed material by tippers to work at site for all leads and lifts in uniform layers of specified thickness with vibratory road roller to achieve the density complete within all leads and lift of materials and as per direction of Engineer-in-charge.	110.40	2673.35	Rupees Two thousand six hundred seventy three and paise thirty five only.	Per Cubic metre	295138.00
3	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, filling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density within all leads and lift including carriage of material in all respect and as per direction of Engineer-in-charge.	36.00	3443.35	Rupees Four hundred eighty eight and paise seventy five only	Per Cubic Metre	123961.00
					Total	462923.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu