



Office of
EXECUTIVE ENGINEER (KULLU DIVISION)
H.P. PUBLIC WORKS DEPARTMENT, KULLU-175101
FAX: 01902-222571, E.mail. ee-kul2-hp@nic.in

No.PW/KD/TA/Tender/2024-2025- **3429-36**
To

Dated:- **18-7-24**

The Executive Engineer, I.T. Cell,
Nigam Bihar Shimla-2.

Subject:- Publishing of Notice inviting tender.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website 29.07.2024 as per notification issued by Secretary (PW) to the Govt. of HP Shimla vide letter No.PBW(S)A(3)1/2020 dated 16.07.2021. As per works mentioned in the Tender Notice is urgent nature of work in the public interest.

DA/As above.


**Executive Engineer,
Kullu Division,
HP. PWD, Kullu.**

Copy alongwith notice inviting tender is forwarded to the following for information and necessary action.

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. Supdt./DAO/HDM of this office.
5. Notice Board.

DA/NIL.


**Executive Engineer,
Kullu Division,
HP. PWD, Kullu.**

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

The Executive Engineer, Kullu Division HP.PWD, Kullu on behalf of the Government of Himachal Pradesh invites the **offline tender i.e. on percentage rates** for the following works from the eligible contractors/Firms registered with HP.PWD, department, so as to reach in the office as per time schedule given below:-

1	Date of receipt of application for tender form.	27.07.2024 upto 4:00 PM			
2	Date of issue/sale of tender form.	27.07.2024 upto 4:00 PM			
3	Date of receipt of tender.	29.07.2024 upto 10:30 AM			
4	Date of opening tender.	29.07.2024 upto 11:00 AM			
Sr. No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	2	3	4	5	6
1	Restoration of rain damages on Sainik Chowk Bhunter to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of embankment with approved material depressed portion between RD 0/00 to 0/200).	4,93,770/-	10,000/-	Two months	350/-
2	Restoration of rain damages on Sainik Chowk Bhunter to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of embankment with approved material depressed portion between RD 0/200 to 0/285).	4,96,520/-	10,000/-	Two months	350/-
3	Restoration of rain damages on Sainik Chowk Bhunter to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of embankment with approved material depressed portion between RD 0/285 to 0/340).	4,87,224/-	10,000/-	Two months	350/-
4	Restoration of rain damages on Sainik Chowk Bhunter to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of embankment with approved material depressed portion between RD 0/340 to 0/540).	4,92,752/-	10,000/-	Two months	350/-
5	Restoration of rain damages on Sainik Chowk Bhunter to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of embankment with approved material depressed portion between RD 0/540 to 0/630).	4,94,045/-	10,000/-	Two months	350/-
6	Restoration of rain damages on Sainik Chowk Bhunter to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of embankment with approved material depressed portion between RD 0/630 to 0/855).	4,97,345/-	10,000/-	Two months	350/-
7	Restoration of rain damages on Sainik Chowk Bhunter to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of embankment with approved material depressed portion between RD 0/855 to 1/050).	4,81,778/-	10,000/-	Two months	350/-

2

8	Restoration of rain damages on Sainik Chowk Bhunter to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- Construction of embankment with approved material depressed portion between RD 0/050 to 1/210).	4,94,402/-	10,000/-	Two months	350/-
9	C/O Ambulance road form Bhutti Chowk to Chamunda Naggar Km. 0/00 to 0/205 (SH:- Construction of Breast wall at Km. 0/185 to 0/194 & 0/194 to 0/200.50).	3,47,661/-	7,000/-	Two months	350/-
10	Restoration of rain damages of Darka Bhunteer road (SH:- Construction of wire crated Breast wall at RD 1/690 to 1/710).	4,97,933/-	10,000/-	Two months	350/-
11	C/O Ambulance road from Bhutti Chowk to Chamunda Naggar Km. 0/00 to 0/205 (SH:- P/L Kharanja stone soling at RD 0/057 to 0/205).	3,88,821/-	7,800/-	Two months	350/-
12	RRD on Ramshilla Bijli Mahadev road Km. 0/00 to 20/050 (SH:- Construction of wire crated Breast wall at Km. 1/865 to 1/885).	3,92,093/-	8,000/-	Two months	350/-
13	RRD on Ramshilla Bijli Mahadev road Km. 0/00 to 20/050 (SH:- Construction of wire crated Breast wall at Km. 1/845 to 1/865).	3,94,161/-	8,000/-	Two months	350/-
14	Restoration of rain damages on Darka Bhunteer road Km. 0/0 to 7/00 (SH:- Removal of slips/muck/debries etc. in various RDs).	4,90,405/-	10,000/-	Two months	350/-
15	Restoration of rain damages on Sainik Chowk Bhunter Manikaran road (Hathithan) (SH:- Construction of RCC Breast wall at Km. 1/010 to 1/025) Job No.1.	4,13,510/-	8,400/-	Two months	350/-
16	Restoration of rain damages on Sainik Chowk Bhunter Manikaran road (Hathithan) (SH:- Construction of RCC Breast wall at Km. 1/010 to 1/025) Job No.2.	4,13,510/-	8,400/-	Two months	350/-
17	Restoration of rain damages on Sainik Chowk Bhunter Manikaran road (Hathithan) (SH:- Construction of RCC Breast wall at Km. 1/010 to 1/025) Job No.3.	4,13,510/-	8,400/-	Two months	350/-
18	Restoration of rain damages on Darka Bhunteer road Km. 0/00 to 7/00 (SH:- Construction of PCC 7 th and 8 th Toe wall at RD 1/690 to 1/703.30).	3,38,012/-	6,800/-	Two months	350/-
19	Restoration of rain damages on Darka Bhunteer road Km. 0/00 to 7/00 (SH:- Construction of PCC 7 th & 8 th Toe wall at RD 1/703.30 to 1/716.60).	3,38,012/-	6,800/-	Two months	350/-
20	A/R and M/O Darka Bhunteer road Km. 0/0 to 7/500 (SH:- Repair of Pot holes in Km. 1/00 to 3/00) Against OFC cable Deposit.	4,72,191/-	9,500/-	Two months	350/-
21	Restoration of rain damages on Doghri Samana road Km. 0/00 to 13/820 (SH:- Construction of retaining wall at RD 3/045 to 3/063).	4,88,522/-	10,000/-	Two months	350/-
22	Restoration of rain damages on Bari Padhar to Peccha road Km. 0/00 to 3/300 (SH:- C/O Retaining wall at RD 2/565 to 2/580).	4,99,889/-	10,000/-	Two months	350/-

23	Restoration of rain damages on Bari Padhar to Peccha road Km. 0/00 to 3/300 (SH:- C/O Retaining wall at RD 3/085 to 3/100).	4,98,894/-	10,000/-	Two months	350/-
24	A/R and M/O Circuit House Kullu (SH:- Dry cleaning of cloth items).	2,24,100/-	4,500/-	Nine months	350/-
25	A/R and M/O Sainik Chowk Bhunter to Ramshilla road Km. 7/00 to 12/930 (SH:- R/O Pot holes in Km. 7/00 to 8/140) Against OFC cable Deposit Job No.1.	4,95,172/-	10,000/-	Two months	350/-
26	A/R and M/O Sainik Chowk Bhunter to Ramshilla road Km. 7/00 to 12/930 (SH:- R/O Pot holes in Km. 8/920 to 10/00 & 0/00 to 0/200) Against OFC cable Deposit/Truck Union Akhara Bazar Kullu.	3,24,946/-	6,500/-	Two months	350/-
27	A/R and M/O Sainik Chowk Bhunter to Ramshilla road Km. 7/00 to 12/930 (SH:- R/O Pot holes in Km. 8/140 to 8/920) Against OFC cable Deposit Job No.2.	4,97,198/-	10,000/-	Two months	350/-
28	A/R and M/O Sainik Chowk Bhunter to Ramshilla road Km. 7/00 to 12/930 (SH:- R/O Pot holes in Km. 8/920 to 10/00) Against OFC cable Deposit Job No.3.	4,81,635/-	9,700/-	Two months	350/-
29	Restoration of rain damages on Kullu Karon road Km. 0/00 to 15/00 (SH:- Removal of slips/muck/debris etc. at various RDs).	4,81,635/-	9,700/-	Two months	350/-
30	RRD on Pahnallah to Linger Bansu road Km. 0/00 to 11/500 (SH:- Construction of wire crated Breast wall at RD 9/090 to 9/120).	3,26,886/-	6,600/-	Two months	350/-
31	Restoration of rain damages on Doghri Samana road Km. 0/00 to 13/820 (SH:- C/O Retaining wall at RD 3/960 to 3/967, 4/170 to 4/174, 3/670 to 3/680 & 3/885 to 3/895 against DC Deposit (NDF).	4,99,295/-	10,000/-	Two months	350/-
32	Restoration of rain damages on Doghri Samana road Km. 0/00 to 13/820 (SH:- C/O Retaining wall at RD 4/600 to 4/604, 4/435 to 4/445, 4/950 to 4/960 & 5/090 to 5/100 against DC Deposit (NDF).	4,99,322/-	10,000/-	Two months	350/-
33	A/R and M/O Sainik Chowk Bhunter to Ramshilla road Km. 7/00 to 12/930 (SH:- R/O pot holes in Km. 8/920 to 10/00) Against OFC cable Deposit Job No.3.	4,97,198/-	10,000/-	Two months	350/-
34	RRD on Sainik Chowk Bhunter to Manikaran Chowk (Hathithan) road Km. 0/00 to 1/850 (SH:- C/O HPC at RD 0/875, 0/972, 1/134).	4,93,484/-	10,000/-	Two months	350/-
35	Balance work for special repair to HIMFED (Milk Chilling Plan) building at Mohal (SH:- C/O Soak fit and providing Plinth Protection).	3,89,581/-	7,800/-	Two months	350/-
36	RRD on Pahnallah to Linger Bansu road Km. 0/00 to 11/500 (SH:- Construction of wire crated Breast wall at RD 9/060 to 9/090).	3,26,886/-	6,600/-	Two months	350/-
37	RRD on Badah Pahnallah road Km. 0/00 to 19/700 (SH:- C/O Retaining wall at RD 9/420 to 9/435).	4,78,228/-	9,600/-	Two months	350/-

38	A/R and M/O type-V Session residence at Kullu (SH:- Painting, distempering, p/I transparent sheet fencing along boundary and renovation of FF WC, C/O additional store/WC and P/F granite top and balcony and outer etc.) Job No.1.	4,82,164/-	9,800/-	Two months	350/-
39	A/R and M/O type-V Session residence at Kullu (SH:- Painting, distempering, p/I transparent sheet fencing along boundary and renovation of FF WC, C/O additional store/WC and P/F granite top and balcony and outer etc.) Job No.2.	4,99,460/-	10,000/-	Two months	350/-
40	Restoration of rain damages on Darka Gadiara road Km. 0/0 to 1/800 (SH:- C/O wire crated retaining wall at RD 0/335 to 0/350).	4,30,890/-	9,000/-	Two months	350/-
41	Restoration of rain damages on link road to village Narayani under GP Mohal Km. 0/0 to 0/230 (SH:- Providing CC pavement in Km. 0/0 to 0/330) Job No.1.	4,89,687/-	10,000/-	Three months	350/-
42	Restoration of rain damages on link road to village Narayani under GP Mohal Km. 0/0 to 0/230 (SH:- Providing CC pavement in Km. 0/0 to 0/330) Job No.2.	4,89,687/-	10,000/-	Three months	350/-
43	Restoration of rain damages on Darka Gadiara road Km. 0/0 to 1/800 (SH:- C/O wire crated retaining wall at RD 0/350 to 0/365).	4,30,232/-	9,000/-	Two months	350/-
44	A/R and M/O Jugruthana Tosh Km. 0/00 to 1/900 (SH:- Providing and laying WBM Grade-III at various reaches) Job No.1.	4,68,318/-	9,500/-	Two months	350/-
45	A/R and M/O Jugruthana Tosh Km. 0/00 to 1/900 (SH:- Providing and laying WBM Grade-III at various reaches) Job No.2.	4,68,318/-	9,500/-	Two months	350/-
46	RRD on Ratocha Dhara Chatrani road Km. 0/00 to 5/00 (SH:- C/O Breast Wall at Km. 1/780 to 1/795).	2,47,255/-	5,000/-	Two months	350/-
47	Construction of Narogi to Shorn road Km. 0/00 to 1/200 (SH:- C/O 3.0 m slab culvert at RD 0/100) Job No.1.	4,00,105/-	8,200/-	Two months	350/-
48	Construction of Narogi to Shorn road Km. 0/00 to 1/200 (SH:- C/O 3.0 m slab culvert at RD 0/100) Job No.2.	4,00,105/-	8,200/-	Two months	350/-
49	Construction of Narogi to Shorn road Km. 0/00 to 1/200 (SH:- C/O 3.0 m slab culvert at RD 0/100) Job No.3.	4,00,105/-	8,200/-	Two months	350/-
50	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 2/585 to 2/735).	4,98,497/-	10,000/-	Two months	350/-
51	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 2/735 to 2/855).	4,50,695/-	9,200/-	Two months	350/-
52	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 2/855 to 3/075).	4,74,968/-	9,600/-	Two months	350/-
53	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 3/075 to 3/210).	3,11,499/-	6,400/-	Two months	350/-

54	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 3/210 to 3/300).	3,63,966/-	7,400/-	Two months	350/-
55	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 2/345 to 2/585).	4,86,278/-	9,800/-	Two months	350/-
56	Construction of link road to village Rohlgi GP Shillirajgiri Km. 0/00 to 3/00 (SH:- Formation cutting in Km. 2/255 to 2/345).	4,82,439/-	9,800/-	Two months	350/-
57	Restoration of rain damages on various roads under Kharahal Section (SH:- Removal of slips of various roads at various RDs)	4,81,635/-	9,700/-	Two months	350/-
58	Construction of link road from Phagra Nallah to Shilidhari Km. 0/00 to 1/900 (SH:- Formation cutting in RD 0/00 to 0/120) Job No.1.	4,96,865/-	10,000/-	Two months	350/-
59	Construction of link road from Phagra Nallah to Shilidhari Km. 0/00 to 1/900 (SH:- Formation cutting in RD 0/120 to 0/270) Job No.2.	4,99,456/-	10,000/-	Two months	350/-
60	C/O 30.48 mtr. Span Bailey Bridge over Jagrain Nallah on Jungruthana to Pulga road (SH:- C/O wire Breast wall at RD 0/010 to 0/020) Under SCSP.	4,64,042/-	9,400/-	Two months	350/-
61	C/O 30.48 mtr. Span Bailey Bridge over Jagrain Nallah on Jungruthana to Pulga road (SH:- F/C 5/7 mtrs. Wide road on Pulga approach Km. 0/105 to 0/150) Under SCSP.	3,38,989/-	6,800/-	Two months	350/-
62	C/O 30.48 mtrs. Span Bailey Bridge over Jagrain Nallah to Jungruthana to Pulga road (SH:- Filling in the Barshaini side approach road) under SCSP.	3,88,542/-	7,800/-	Two months	350/-
63	C/O 30.48 mtrs. Span Bailey Bridge over Jagrain Nallah on Jungruthana to Pulga road (SH:- F/C 5/7 mtrs. Wide road on Pulga approach Km. 0/00 to 0/090) Under SCSP.	4,53,471/-	9,200/-	Two months	350/-
64	C/O 30.48 mtrs. Span Bailey Bridge over Jagrain Nallah on Jungruthana to Pulga road (SH:- C/O R/wall on Pulga side approach at RD 0/120 to 0/136) under SCSP.	4,99,531/-	10,000/-	Two months	350/-
65	Providing road side amenities on Sainik Chowk Bhunter Ramshilla road Km. 0/00 to 13/400 (SH:- C/O Ornamental rain shelter near Nature Park Mohal hill side at Km. 4/440).	4,80,486/-	9,800/-	Two months	350/-
66	C/O road side amenities on Sainik Chowk Bhunter Ramshilla road Km. 0/0 to 7/140 (SH:- Repair of rain shelter and sitting place near Shiv Temple Mohal Km. 4/030).	4,95,240/-	10,000/-	Two months	350/-
67	Restoration of rain damages on Dohranallah to Barahar road Km. 0/00 to 10/120 (SH:- C/O Retaining wall at RD 5/510 to 5/525).	4,78,223/-	9,600/-	Two months	350/-
68	Construction of link road from NH-03 (Jia) to Shankergarh Km. 0/00 to 1/400 (SH:- M/T work between RD 1/140 to 1/400).	4,52,470/-	9,200/-	Two months	350/-
69	Construction of link road from NH-03 (Jia) to Shankergarh Km. 0/00 to 1/400 (SH:- M/T work between RD 0/860 to 1/140).	4,93,926/-	10,000/-	Two months	350/-

70	Construction of link road from NH-03 (Jia) to Shankergarh Km. 0/00 to 1/400 (SH:- M/T work between RD 0/490 to 0/860).	4,93,334/-	10,000/-	Two months	350/-
71	Construction of link road from NH-03 (Jia) to Shankergarh Km. 0/00 to 1/400 (SH:- M/T work between RD 0/060 to 0/160 and 0/260 to 0/490).	4,93,514/-	10,000/-	Two months	350/-
72	Construction of Chharour Nallah to Bhrair road Km. 0/00 to 7/340 (SH:- ROFD in Km. 4/180 to 4/675).	4,62,807/-	9,500/-	Two months	350/-
73	Construction of Chharour Nallah to Bhrair road Km. 0/00 to 7/340 (SH:- ROFD in Km. 4/675 to 4/945).	4,72,373/-	9,500/-	Two months	350/-
74	Construction of Chharour Nallah to Bhrair road Km. 0/00 to 7/340 (SH:- ROFD in Km. 5/410 to 5/560).	4,74,341/-	9,500/-	Two months	350/-
75	Construction of Chharour Nallah to Bhrair road Km. 0/00 to 7/340 (SH:- ROFD in Km. 5/230 to 5/410).	4,78,199/-	9,600/-	Two months	350/-
76	Construction of Chharour Nallah to Bhrair road Km. 0/00 to 7/340 (SH:- ROFD in Km. 4/945 to 5/230).	4,85,624/-	10,000/-	Two months	350/-
77	Construction of Chharour Nallah to Bhrair road Km. 0/00 to 7/340 (SH:- ROFD in Km. 5/560 to 5/785).	4,16,084/-	8,500/-	Two months	350/-
78	Purchase of Printer/Plotter, Scanner in Design Cell at O/O Chief Engineer Mandi Zone various NABARD works under Kullu Division HP.PWD, Kullu.	4,54,622/-	9,200/-	Two months	350/-

The tender documents shall be issued only to those contractor/firm who fulfill the following documents with the application.

1	The valid enlistment/Registration of contractor in Appropriate Class.
2	Permanent account No. (PAN No.).
3	G.S.T. No.
4	Earnest Money in the shape of National Saving certificate/time deposit account in the any of the post office in HP F.D.R. from any Nationalized Bank duly pleaded in favour of the Executive Engineer, Kullu Division HP.PWD, Kullu.
5	The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6	The offer of the tender shall remain valid upto 90 days after the opening of tender.
7	Ambiguous/telephonic conditional tenders of tender by fax/E-mail not be considered and will be summarily be rejected.
8	Executive Engineer, reserve the right to reject or cancel any or all tenders without assigning any reasons.
9	If the date given above happens to be holiday the same shall be processed on next working day.
10	The contractor/firm must quote their rates in words as well as in figures failing which XEN reserve the right to accept/reject any or all tenders.
11	The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12	One contractor shall not have more than two major works in hand at a time.
13	Work should be completed by the contractor within stipulated period.
14	The rates beyond over +5% will be rejected, besides this the Additional Performance security will have to borne @ 20% & 30% for unbalanced bid in case rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively. The tender beyond the limit of -30% will also be excepted.


Executive Engineer,
Kullu Division,
HP.PWD, Kullu.

Dated:- 18-07-24

No.PW/KD/TA/2024-2025-

Copy is forwarded to the following for information and necessary action:-

3437-3497

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6th Circle HP.PWD, Kullu.
4. All the Executive Engineers, in HP.PWD,
5. All the Assistant Engineers, working under this Division.
6. All the registered contractors, in HP.PWD.
7. Supdt./DA/HDM of this office.
8. Notice Board.


Executive Engineer,
Kullu Division,
HP.PWD, Kullu.

CERTIFICATE

It is certified that the above works are required to be carried out immediately being emergent nature of work in the public interest.



**Executive Engineer,
Kullu Division,
HP.PWD, Kullu.**

SCHEDULE OF QUANTITY

Estimated cost- 493770.00
Earnest money :- 10,000.00
Time :- Two months.

Name of work :- Restoration of rain damages on Sainik chowk Bhunter to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850 .
(SH):- Construction of embankment with approved material depressed portion between RD 0/00 to 0/200) .

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m (One point five metre). transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m (One thousand metre) as per Technical Specification Clause 301.5 within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	897.60	550.10	Rupees Five hundred fifty and paise ten only.	Per Cubic metre	493770.00
					Total:-	493770.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Estimated cost:- 496520.00
Earnest money :- 10,000.00
Time :- Two months.

Name of work :- Restoration of rain damages on Sainik chowk Bhunter to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850 .
(SH:- Construction of embankment with approved material depressed portion between RD 0/200 to 0/285) .

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m (One point five metre), transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m (One thousand metre) as per Technical Specification Clause 301.5 within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	902.60	550.10	Rupees Five hundred fifty and paise ten only.	Per Cubic metre	496520.00
					Total:-	496520.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

Estimated cost- 487224.00
 Earnest money :- 10,000.00
 Time :- Two months.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Sainik chowk Bhunter to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850.
 (SH:- Construction of embankment with approved material depressed portion between RD 0/285 to 0/340).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m (One point five metre), transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m (One thousand metre) as per Technical Specification Clause 301.5 within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	885.70	550.10	Rupees Five hundred fifty and paise ten only.	Per Cubic metre	487224.00
					Total:-	487224.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

Estimated cost-492752.00
 Earnest money :- 10,000.00
 Time :- Two months.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Sainik chowk Bhunter to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850.
 (SH):- Construction of embankment with approved material depressed portion between RD 0/340 to 0/540)

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m (One point five metre), transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m (One thousand metre) as per Technical Specification Clause 301.5 within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	895.75	550.10	Rupees Five hundred fifty and paise ten only.	Per Cubic metre	492752.00
					Total:-	492752.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Estimated cost:-494045.00

Earnest money :- 10,000.00

Time :- Two months.

Name of work :- Restoration of rain damages on Sainik chowk Bhunter to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850 .
(SH):- Construction of embankment with approved material depressed portion between RD 0/540 to 0/630) -

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m (One point five metre), transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m (One thousand metre) as per Technical Specification Clause 301.5 within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	898.10	550.10	Rupees Five hundred fifty and paise ten only.	Per Cubic metre	494045.00
					Total:-	494045.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu.

SCHEDULE OF QUANTITY

Estimated cost -497345.00
Earnest money :- 10,000.00
Time :- Two months.

Name of work :- Restoration of rain damages on Sainik chowk Bhunter to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850
(SH):- Construction of embankment with approved material depressed portion between RD 0/830 to 0/855).

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m (One point five metre), transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m (One thousand metre) as per Technical Specification Clause 301.5 within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	904.10	550.10	Rupees Five hundred fifty and paise ten only.	Per Cubic metre	497345.00
					Total:-	497345.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

Estimated cost-481778.00
Earnest money :- 10,000.00
Time :- Two months.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Sainik chowk Bhunter to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850.
(SH:- Construction of embankment with approved material depressed portion between RD 0/855 to 1/050) -

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m (One point five metre), transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m (One thousand metre) as per Technical Specification Clause 301.5 within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	875.80	550.10	Rupees Five hundred fifty and paise ten only.	Per Cubic metre	481778.00
					Total:-	481778.00


Executive Engineer,
Kullu Division
HP.PWD Kullu.

SCHEDULE OF QUANTITY

Estimated cost:-494402.00
Earnest money :- 10,000.00
Time :- Two months.

Name of work :- Restoration of rain damages on Sainik chowk Bhunter to Manikaran Chowk (Hathithan) road Km 0/00 to 1/850.
(SH):- Construction of embankment with approved material depressed portion between RD 0/1/050 to 1/210).

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m (One point five metre), transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m (One thousand metre) as per Technical Specification Clause 301.5 within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	898.75	550.10	Rupees Five hundred fifty and paise ten only.	Per Cubic metre	494402.00
					Total:-	494402.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- C/o Ambulance road from Bhutti Chowk to Chamunda Naggar km 0/00 to 0/205.
(SH:- Construction of Breast wall at Km 0/185 to 0/194 & 0/194 to 0/200.50)

Estimated cost:-Rs. 3,47,661.00
Earnest money :- Rs. 7,000.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1803.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	54.49	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	12443.00
2	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	36.89	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13478.00
3	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	59.66	5195.30	Rupees Five thousand one hundred ninety six and paise thirty only.	Per cubic metre	310011.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	30	390.95	Rupees Three hundred ninety and paise ninety five only.	Per cubic metre	11729.00
					Total	347661.00


Executive Engineer,
Kullu Division,
HP, PWD Kullu.

Name of work:- Restoration of rain damages on Darka Bhumteer road.
(SH:- Construction of wire crated Breast wall at RD 1/690 to 1/710)

Estimated cost:- Rs. 4,97,933.00
Earnest money :- Rs. 10,000.00

Time :- Two months.

SCHEDULE OF QUANTITY

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603 1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	120.00	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	27402.00
2	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	16.20	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	5919.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	144.57	3213.75	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	464612.00
					Total	497933.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Estimated cost:- 3,88,821.00
Earnest money :- 7,800.00
Time :- Two months.

Name of work:- C/o Ambulance road from Bhutti Chowk to Chamunda Naggar Km 0/00 to 0/205 (Sh: P/L Kharanja stone soling at RD 0/057 to 0/205).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil within all leads and lift including of materials and as per direction of Engineer-in-charge.	227.58	365.35	Rupees Three hundred sixty five and paise thirty five only	Per Cubic metre	83146.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. or earth etc. complete within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	191.7	1594.55	Rupees One thousand five hundred ninety four and paise fifty five only	Per Cubic metre	305675.00
					Total:-	388821.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- RRD on Ramshilla -Bijli Mahadev road Km. 0/00 to 20/050
(SH:- Construction of wire crated Breast wall at Km 1/865 to 1/885)

Estimated cost:- Rs. 3,92,093.00
Earnest money :- Rs. 8,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1503.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	164.50	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	14729.00
2	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	8.20	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	2990.00
3	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 PCC grade 1:4:8 (One cement :Four sand : Eight graded stone aggregate) for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.00	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	173505.00
4	Providing and laying of boulder apron laid in wire crates with 4 mtr (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4823 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	62.50	3213.75	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	200859.00
					Total	392093.00


Executive Engineer,
Kullu Division,
HP, PWD Kullu

Name of work:- RRD on Ramshilla -Bijli Mahadev road Km. 0/00 to 20/050 .
(SH):- Construction of wire crated Breast wall at Km 1/845 to 1/865)

SCHEDULE OF QUANTITY

Estimated cost:- Rs. 3,94,161.00
Earnest money :- Rs. 8,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	72.60	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	16578.00
2	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	8.80	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	3215.00
3	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 PCC grade 1:4:8 (One cement :Four sand : Eight graded stone aggregate) for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.00	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	173509.00
4	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	62.50	3213.75	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	200859.00
					Total	394161.00

Executive Engineer,
Kullu Division,
HP. PWD Kullu

Estimated cost-4,90,405.00
 Earnest money :- 10,000.00
 Time :- One month.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Darka Bhumteer road Km. 5/6 to 7/00
 (SH:- Removal of slips/ muck/ debris etc in various Rds)

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of out materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge	3920.10	125.10	Rupees one hundred twenty five and paise ten only.	Per cubic metre	490405.00
					Total	490405.00


 Executive Engineer,
 Kultu Division,
 HP.PWD Kultu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Sainik Chowk Bhunter Manikaran road (Hathithan),
(SH:- Construction of R.C.C. Breast wall at Km 1/010 to 1/025) Job No. 1.

Estimated cost:- Rs. 4,13,510.00
 Earnest money :- Rs. 8,400.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	6.25	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	2283.00
2	Supplying fitting and placing HYSD bar reinforcement Fe 415 in sub structure complete as per drawings and technical specification clauses 1002,1005,1010 and 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	739.10	89.15	Rupees Eighty nine and paise fifteen only	Per Kilogram	65890.00
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm (Twenty millimetre) nominal size) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	51.04	6234.10	Rupees Six thousand two hundred thirty four metre and paise ten only	Per cubic	318209.00
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete within all leads and lift of materials and as per direction of Engineer-in-charge.	178.53	151.95	Rupees One hundred thirty five and paise ninety five only.	Per Kilogram	27128.00
					Total	413510.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Sainik Chowk Bhunter Manikaran road (Hathithan).
(SH:- Construction of R.C.C. Breast wall at Km 1/010 to 1/025) Job No. 2.

Estimated cost:- Rs. 4,13,510.00
 Earnest money :- Rs. 8,400.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	6.25	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	2283.00
2	Supplying fitting and placing HYSD bar reinforcement Fe 415 in sub structure complete as per drawings and technical specification clauses 1002,1005,1010 and 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	739.10	89.15	Rupees Eighty nine and paise fifteen only	Per Kilogram	65890.00
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level. excluding the cost of centering, shuttering and finishing: 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm (Twenty millimetre) nominal size) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	51.04	6234.10	Rupees Six thousand two hundred thirty four and paise ten only	Per cubic metre	318209.00
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in-position and applying a priming coat of approved steel primer all complete within all leads and lift of materials and as per direction of Engineer-in-charge.	178.53	151.95	Rupees One hundred thirty five and paise ninety five only.	Per Kilogram	27128.00
					Total	413510.00


Executive Engineer,
 Kullu Division
 HP.PWD Kullu

17

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Sainik Chowk Bhunter Manikaran road (Hathithan).
 (SH:- Construction of R.C.C. Breast wall at Km 1/010 to 1/025) Job No. 3.

Estimated cost:- Rs. 4,13,510.00
 Earnest money :- Rs. 8,400.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	6.25	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	2283.00
2	Supplying fitting and placing HYSD bar reinforcement Fe 415 in sub structure complete as per drawings and technical specification clauses 1002, 1005, 1010 and 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	739.10	89.15	Rupees Eighty nine and paise fifteen only	Per Kilogram	65880.00
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, siring or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm (Twenty millimetre) nominal size) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	51.04	6234.10	Rupees Six thousand two hundred thirty four and paise ten only	Per cubic metre	318209.00
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete within all leads and lift of materials and as per direction of Engineer-in-charge.	178.53	151.95	Rupees One hundred thirty five and paise ninety five only.	Per Kilogram	27128.00
					Total	413510.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restroration of rain damages on Darka Bhumteer road Km. 0/00 to 7/00 .
(SH:- Construction of PCC 7th & 8th Toe wall at RD 1/690 to 1/703.30).

Estimated cost:- Rs. 3,38,012.00
 Earnest money :- Rs. 6,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	20.78	365.35	Rupees Three hundred sixty five and paise thirty five only.	Per cubic metre	7592.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	60.75	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	301162.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	18.23	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	29256.00
					Total	338012.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Restroration of rain damages on Darka Bhumteer road Km. 0/00 to 7/00.
(SH:- Construction of PCC 7th & 8th Toe wall at RD 1/703.3 to 1/716.60).

Estimated cost:- Rs. 3,38,012.00
Earnest money :- Rs. 6,800.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	20.78	365.35	Rupees Three hundred sixty five and paise thirty five only.	Per cubic metre	7592.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803, 1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone). 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	60.75	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	301162.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material, within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	18.23	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	29258.00
					Total	338012.00


 Executive Engineer,
 Kullu Division,
 HP. PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Darka Bhunteer road Km 0/0 to 7/500.

(SH:- Repair of Pot holes in Km 1/00 to 3/00) Against OFC cable Deposit .

Estimated cost:- Rs. 4,72,191.00

Earnest money :- Rs. 9,500.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	1207.34	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	472191.00
					Total	472191.00


Executive Engineer,
Kullu Division,
HP. PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Doghri Samana road Km 0/00 to 13/820 .

(SH):- Construction of Retaining wall at RD 3/045 to 3/063)

Estimated cost:- Rs. 4,88,522.00

Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	72.18	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	26371.00
2	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone aggregate nominal size in open foundations complete as per drawing and technical specification clause 802.803.1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	22.50	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only.	Per cubic metre	111542.00
3	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	35.58	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	186882.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportatin within all leads and lift of materials and as per direction of Engineer-in- charge.	54.91	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	150245.00
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	8.40	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	13482.00
					Total	488522.00


 Executive Engineer,
 Kullu Division
 HPPLO KULLU

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bari padhar to Pechha road Km. 0/00 to 3/300
(SH:- C/o Retaining wall at RD. 2/565 to 2/580)

Estimated cost - Rs. 4,99,889.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	60.90	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	22250.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	48699.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone aggregate nominal size in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	6.45	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only.	Per cubic metre	31975.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	45.62	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	239617.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	47.74	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	130626.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.318 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	16.65	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	26722.00
					Total	499889.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

23

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bari padhar to Pechha road Km. 0/00 to 3/300.
(SH:- C/o Retaining wall at RD. 3/085 to 3/100)

Estimated cost:- Rs. 4,98,894.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	63.45	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	23181.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	48599.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone aggregate nominal size in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	6.45	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only.	Per cubic metre	31975.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	45.62	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	239617.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	47.74	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	130626.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204,3.8 Granular material, within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	15.45	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	24796.00
					Total	498894.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu.

24

Estimated cost:-2,24,100.00
Earnest money :- 4,500.00
Time :- Nine months.

SCHEDULE OF QUANTITY

Name of work :- A/R and M/O Circuit House Kullu
(SH)- Dry cleaning of cloth items)

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Dry cleaning of cloth item including iron of all items including collection of item from Circuit house Kullu and returned the same to Circuit House with removing of oil, stains and sports etc.						
a	Bed sheet.(Single)	900	30	Rupees Thirty	and paise zero only.	Each	27000
b	Bed sheet.(Double)	800	40	Rupees forty	and paise zero only	Each	32000
c	Quilt cover.	750	50	Rupees fifty	and paise zero only.	Each	37500
d	Bed cover.	150	44	Rupees forty four	and paise zero only.	Each	6600
e	Sofa cover.	350	30	Rupees thirty	and paise zero only.	Each	10500
f	Towel	900	20	Rupees twenty	and paise zero only.	Each	18000
g	Pillow cover.	500	25	Rupees twenty five	and paise zero only.	Each	12500
h	Blanket .	350	120	Rupees one hundred twenty	and paise zero only.	Each	42000
i	Curtain (Large)	500	40	Rupees forty	and paise zero only.	Each	20000
j	Curtain(small)	600	30	Rupees thirty	and paise zero only.	Each	18000
					Total		224100


Executive Engineer,
Kullu Division,
HP PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Sainik Chowk Bhunter to Ramshilla road Km. 7/00 to 12/930 ,
(SH:- R/O Pot holes in Km 7/00 to 8/140) Against OFC cable Deposit (Job 1) .

Estimated cost:- Rs. 4,95,172.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	1266.10	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	495172.00
					Total	495172.00


 Executive Engineer,
 Kullu Division
 HP PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Sainik Chowk Bhunter to Ramshilla road Km. 7/00 to 12/930
 (SH:- R/O Pot holes in Km 8/920 to 10/00 & 0/00 to 0/200) Against OFC cable Deposit/Truck Union
 Akhara Bazar Kullu

Estimated cost:- Rs. 3,24,946.00
 Earnest money :- Rs. 6,500.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/blinding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 by Manual Means Grading-III including carriage of material within all leads and lift of materials and as per direction of Engineer-In-charge.	9.00	3470.05	Rupees Three thousand four hundred seventy and paise zero five only.	Per Cubic metre	31230.00
2	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In-charge.	751.00	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	293716.00
					Total	324946.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

22

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Sainik Chowk Bhunter to Ramshilla road Km. 7/00 to 12/930.
(SH:- R/O Pot holes in Km 8/140 to 8/920) Against OFC cable Deposit (Job 2) .

Estimated cost:- Rs. 4,91,163.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2. 503 and 508.1 within all leads and lift including carriage of material in all respect and as per direction of Engineer-In- charge.	1255.85	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	491163.00
					Total	491163.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

28

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Sainik Chowk Bhunter to Ramshilla road Km. 7/00 to 12/930 .
(SH):- R/O Pot holes in Km 8/920 to 10/00) Against OFC cable Deposit (Job 3)

Estimated cost:- Rs. 4,97,198.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Repair to pot holes by removal of loose material, trimming the sides and clearing of surface by providing tack coat 20 mm (Twenty millimetre) premix carpet and seal coat type-B clause 1904.2, 503 and 508.1 within all leads and lift including carnage of material in all respect and as per direction of Engineer-In-charge.	1271.28	391.10	Rupees Three hundred ninety one and paise ten only.	Per Cubic metre	497198.00
					Total	497198.00


Executive Engineer,
Kulu Division
HP.PWD Kulu

Estimated cost-4,81,635.00
 Earnest money :- 9,700.00
 Time :- Two months

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Kullu Karon road km 0/00 to 15/00
 (SH:- Removal of slips/ muck/debris etc. at various RDs)

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials upto any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3050.00	125.10	Rupees one hundred twenty five and paise ten only.	Per cubic metre	481635.00
					Total	481635.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- RRD on Pahnallah to Linger Bansu road Km. 0/00 to 11/500. c
(SH:- Construction of wire crated Breast wall at RD 9/090 to 9/120) t

Estimated cost:- Rs. 3,26,886.00
Earnest money :- Rs. 6,900.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	28.50	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	6508.00
2	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	21.90	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	8001.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	97.20	3213.75	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	312377.00
					Total	326886.00


Executive Engineer,
Kullu Division
HP PWD Kullu

31

144

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Doghri Samana road Km 0/00 to 13/820

Estimated cost:- Rs. 4,99,295.00

(SH:- C/o Retaining wall at RD 3/960 to 3/967, 4/170 to 4/174, 3/670 to 3/680 & 3/885 to 3/895 against DC deposit

Earnest money :- Rs. 10,000.00

Time :- Two months.

(NDF)

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	42.36	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	15476.00
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement: Six sand : Twelve graded stone) for nominal mix 25 mm (Twenty five millimetre) aggregate foundations complete as per drawing and technical specification clause 802.803, 1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	5.88	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	26514.00
3	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702, 704, 1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	59.94	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	314832.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportatn within all leads and lift of materials and as per direction of Engineer-in- charge.	47.42	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	129762.00
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	7.92	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	12711.00
					Total	499295.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

82

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Doghri Samana road Km 0/00 to 13/820.
(SH:- C/o Retaining wall at RD 4/600 to 4/604, 4/435 to 4/445, 4/950 to 4/960 & 5/090 to 5/100 against DC deposit (NDF))

Estimated cost:- Rs. 4,98,322.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	42.96	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	15695.00
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix 25 mm (Twenty five millimetre) aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	5.88	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	26514.00
3	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:5 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	59.94	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	314832.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportatin within all leads and lift of materials and as per direction of Engineer-in-charge.	47.42	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	129762.00
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material, within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	7.80	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	12519.00
					Total	499322.00


Executive Engineer,
Kulu Division,
HP.PWD Kulu

34

SCHEDULE OF QUANTITY

Name of work:- RRD on Sainik Chowk Bhunter to Manikaran Chowk (Haithian) road Km. 0/00 to 1/850.
(SH:- C/o HPC at RD. 0/875, 0/972, 1/134).

Estimated cost:- Rs. 4,93,484.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	191.41	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	69932.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	32.88	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only	Per cubic metre	170854.00
3	Providing and laying reinforced cement concrete pipe NP33for culverts on 1st class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement: Two sand) but excluding protection work and back filling and concrete work inhead walls and parapets clause 1106 within all leads and lift of materials and as per direction of Engineer-in-charge.	48.75	5183.55	Rupees Five thousand one hundred eighty three and paise fifty five only.	Per Running metre	252808.00
					Total	493484.00

Executive Engineer
Kullu Division
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Balance work for special repair to HIMFED (Milk Chilling Plant) building at Mohal (SH:- C/o Soak pit and providing Plinth Protection).

Estimated cost:- Rs. 3,89,581.00
Earnest money :- Rs. 7,800.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing and fixing insulating board ceiling of approved quality with necessary nails etc. complete (frame work to be paid separately) Natural colour insulating board 12 mm thick (Twelve millimetre) within all leads and lift of materials and as per direction of Engineer-in-charge.	259.20	815.70	Rupees Five hundred eighty two and paise sixty five only.	Per Square metre	211429.00
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan). including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m (Fifty metre) work/jumper work 50% (Fifty percent) each within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	28.44	322.45	Rupees Three hundred twenty two and paise forty five only.	Per cubic metre	9170.00
3	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:8:12 (1 cement : 8 coarse sand : 12 graded stone aggregate 20 mm (Twenty millimetre) nominal size) upto plinth level with Cement mortar 1:5 (1 cement : 5 coarse sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	12.10	5878.95	Rupees Five thousand eight hundred seventy eight and paise ninety five only.	Per cubic metre	71135.00
4	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, balconies and access platform within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	3.24	661.84	Rupees Six hundred sixty one and paise eighty four only.	Per square metre	2144.00
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	78.12	103.55	Rupees One hundred three and paise fifty five only.	Per Kilogram	8089.00
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	0.98	7533.80	Rupees Seven thousand five hundred thirty three and paise eighty only.	Per cubic metre	7458.00
7	Supplying, filling, spreading & leveling stone boulders of size range 5 cm (Five centimetre) to 20 cm (Twenty centimetre), in recharge pit, in the required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.54	1185.00	Rupees One thousand one hundred eighty five only.	Per cubic metre	11305.00

8a	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement: 3 coarse sand (zone II) : 6 graded stone aggregate 20 mm (Twenty millimetre) nominal size) over 75mm (Seventy five millimetre) thick bed of dry brick ballast 40 mm (Forty millimetre) nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth within all leads and lift including cartage of materials and as per direction of Engineer-in-charge.	63.60	866.70	Rupees Six hundred sixty six and seventy only.	Per square metre	42402.00
9a	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required a W.C. pan with ISI marked white solid plastic seat and lid within all leads and lift including cartage of materials and as per direction of Engineer-in-charge.	1.00	6555.00	Rupees Six thousand five hundred fifty five only.	Each	6555.00
10a	Providing and fixing Polyethylene-Aluminium- Polyethylene PE-AL-PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) to e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre (One point zero metre) spacing. This includes the costs of cutting chases or and including testing of joints complete as per direction of the engineer in charge 1620 (20 mm (Twenty metre) OD) pipe within all leads and lift including cartage of materials and as per direction of Engineer-in-charge.	40.00	487.35	Rupees Four hundred ninety seven and thirty five only.	Per metre	19894.00
					Total	389591.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- RRD on Pahnallah to Lijjer Bansu road Km. 0/00 to 11/500.
(SH:- Construction of wire crated Breast wall at RD 9/060 to 9/090)

Estimated cost:- Rs. 3,26,886.00
Earnest money :- Rs. 6,600.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	28.50	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	6508.00
2	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 50 m (Fifty metre) dressing of sides and bottom and back filling the excavated suitable material ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	21.90	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	8001.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	97.20	3213.75	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	312377.00
					Total	326886.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

32

SCHEDULE OF QUANTITY

Name of work:- RRD on Badah Pahnallah road Km. 0/00 to 19/700 .
(SH:- C/o Retaining wall at RD 9/420 to 9/435) .

Estimated cost:- Rs. 4,78,228.00
Earnest money :- Rs. 9,600.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	57.30	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	13084.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of slumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	19.80	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	7234.00
3	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate in open foundations complete as per drawing and technical specification clause 802.803.1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	48699.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702.704.1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	43.98	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	231003.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	62.78	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	144422.00
6	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	31.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	12118.00

7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	13.50	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	21667.00
		Total				478228.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O type-V session Judge residence at Kullu.

(SH:- Painting, distempering, pl transparent sheet fencing along boundary & renovation of FF Wc, clo additional store/MC and P/F granite top and balcony and outer gate etc. (Job No. 1).

Estimated cost:- Rs. 4,82,164.00
Earnest money :- Rs. 9,800.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	523.72	15.36	Rupees Fifteen and paise thirty six only.	Per Square metre	8044
2	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre (Fifty grams/ litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. 13.42.1 Two or more coats on new work Walls with in all leads and lift of materials and as per direction of Engineer-in-charge.	418.97	120.55	Rupees One hundred twenty and paise fifty five only.	Per Square metre	50507
3	Providing and applying white cement based putty of average thickness 1 mm (One millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	407.78	103.40	Rupees One hundred three and paise forty only.	Per Square metre	42164
4	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point ninety-litre/ Ten square metre) over an under coat of primer applied @ 0.75 ltr/10 sqm (Zero point seventy five litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	366.07	106.20	Rupees One hundred six and paise twenty only.	Per Square metre	38877
5	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (Zero point eighty litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	233.39	111.80	Rupees One hundred eleven and paise sixty only.	Per square metre	26046
6	Finishing walls with weather proof exterior grade emulsion of approved design (Apexultima) or its equalised on undercoated wall surface (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc. including sand with in all leads and lift of materials and as per direction of Engineer-in-charge.	160.38	123.05	Rupees One hundred twenty three and paise zero five only.	Per square metre	19735

7	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm (Twelve millimetre) thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm (Three point three kilogram per square metre), including pointing in white cement mixed with pigment of matching shade complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	14.22	1634.58	Rupees One thousand six hundred thirty four and paise fifty eight only.	Per Square metre	23244
8	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm (Twelve millimetre) thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm (Three point three kilogram per square metre), including pointing in white cement mixed with pigment of matching shade complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	58.01	1833.60	Rupees One thousand eight hundred thirty three and paise sixty only.	Per Square metre	106367
9	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works with in all leads and lift of materials and as per direction of Engineer-in-charge.	722.00	120.00	Rupees One hundred twenty only.	Per Kilogram	86640
10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 40 mm (Forty millimetre) nominal size) with in all leads and lift of materials and as per direction of Engineer-in-charge.	5.93	5212.95	Rupees Five thousand two hundred twelve and paise ninety five only.	Per Cubic metre	30913
11	Providing and fixing 40 mm (Forty millimetre) thick panelled shutter for door with deodar wood style rail beading and infill panele of 12 mm (Twelve millimetre) thick phenol bonded prelaminated board both side particle board panel (SI marked 12823 including ISI marked with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.87	5600.00	Rupees Five thousand six hundred only.	Per Square metre	27272
12	Providing and fixing wire gauge shutter using galvanised MS wire gauge of aperture 1.4 mm (One point four millimetre) both direction with wire of dia 0.63 mm (Zero point sixty three millimetre) for door window and clestory window with hings and necessary screw 35 mm (Thirty five millimetre) klin seasoned wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.69	3085.76	Rupees Three thousand eighty five and paise seventy six only.	Per Square metre	11386

13	Providing and fixing bright finished brass handles with screws etc. complete 125 mm (One hundred twenty five millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	28.00	216.48	Rupees Two hundred sixteen and paise forty eight only.	Each	6081
14	Providing and fixing bright finished brass towels bolts (barrel type) with necessary screws etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	20.00	245.37	Rupees Two hundred forty five and paise thirty seven only.	Each	4907
	Total					482164


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O type-V session residence at Kullu. **Estimated cost:-** Rs. 4,99,460.00
(SH):- Painting, distemper, p/l transparent sheet fencing along boundary & renovation of FF WC, c/o Earnest money :- Rs. 10,000.00
 additional store/WC and P/F granite top and balcony and outer gate etc. (Job No. 2). **Time :-** Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Renewing glass panes and refixing existing wooden fillets: Float glass panes of nominal thickness 4 mm (Four millimetre) (weight not less than 10kg/sqm (Ten kilogram/ square metre)) with in all leads and lift of materials and as per direction of Engineer-in-charge.	37.47	1160.10	Rupees One thousand one hundred sixty and paise ten only.	Per Square metre	43469
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (Ten millimetre) gap for thermal expansion, (i) Single socketed pipes, 110 mm (One hundred ten millimetre) diameter with in all leads and lift of materials and as per direction of Engineer-in-charge.	36.00	650.00	Rupees Five hundred fifty only.	Per Running metre	19800
3	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (Ten millimetre) gap for thermal expansion with in all leads and lift of materials and as per direction of Engineer-in-charge.					
a)	Single tee with door 110x110x110 mm (One hundred ten x One hundred ten x One hundred ten millimetre)	15.00	350.00	Rupees Three hundred fifty only.	Each	5250
b)	Bend 87.5 110 mm (One hundred ten millimetre) bend	15.00	290.00	Rupees Two hundred ninety only.	Each	4350
4	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes conforming to IS:15801, UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, i/c fixing the pipe with clamps at 1.00 m (One point zero metre) spacing. This includes the cost of cutting chases and making good the same including testing of joints complete with in all leads and lift of materials and as per direction of Engineer-in-charge.					
a)	PN - 16 Pipe, 20mm (Twenty millimetre) OD (SDR-7.4)	42.00	599.98	Rupees Five hundred ninety nine and paise ninety eight only.	Per Running metre	25199

5	Providing and fixing vitreous china wash down water closet (European type WC pan) with 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1 (One cement : 1 sand) seat and over to be measured and paid separately (one piece) with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	18500.00	Rupees Sixteen thousand five hundred fifty only.	Each	33000
6	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre (Ten litre) low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm (Forty millimetre) flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	9379.30	Rupees Nine thousand three hundred seventy nine and paise thirty only.	Each	9379
7	Providing and fixing plastic seat (Solid/Hollow type) and cover for wash down water closet with C.P. Brass hinges and rubber buffers (White seat cover) with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	483.00	Rupees Four hundred eighty three only.	Each	483
8	Providing and fixing wash basin with C.I. brackets, 15mm (Fifteen millimetre) dia CP Brass single hole basin mixer of approved quality and make. including painting of fittings and brackets, cutting and making good the walls wherever required White Vitreous China Wash basin size 550x400 mm (Five hundred fifty x Four hundred millimetre) with hite vitreous china pedestal with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.00	4885.97	Rupees Four thousand six hundred eighty five and paise ninety seven only.	Each	18744
9	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.00	2038.15	Rupees Two thousand thirty eight and paise fifteen only.	Each	8153
10	Providing and fixing C.P. brass waste for wash basin or sink 32 mm (Thirty two millimetre) dia with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.00	120.80	Rupees One hundred twenty and paise eighty only.	Each	483
11	Providing and fixing 600x450 mm (Six hundred x Four hundred fifty millimetre) bevelled edge mirror of superior glass (of approved quality) complete with 6 mm (Six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	5.00	1620.04	Rupees One thousand five hundred twenty and paise ninety four only.	Each	7605

12	Providing and fixing C.P. brass towel rail complete with c.p. brass brackets fixed to wooden plugs with c.p. brass screws: (i) 600x20 mm (Six hundred x Twenty millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.00	1250.00	Rupees One thousand two hundred fifty only.	Each	5000
13	Providing and fixing 600x120 mm (Six hundred x One hundred twenty millimetre) glass shelf with C.P. brass bracket and guard rail shelf with C.P. brass bracket and guard rail complete, fixed to wooden plugs with C.P. brass screws with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.00	1200.00	Rupees One thousand two hundred only.	Each	3600
14	Providing and fixing C.P. brass and bib cock of approved quality conforming to IS:8931 15mm (Fifteen millimeter) nominal bore with in all leads and lift of materials and as per direction of Engineer-in-charge.	8.00	937.14	Rupees Nine hundred thirty seven and paise fourteen only	Each	7497
15	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm (Fifteen millimeter) nominal bore with in all leads and lift of materials and as per direction of Engineer-in-charge.	15.00	930.24	Rupees Nine hundred and paise twenty four only	Each	13504
16	Providing and fixing waste pipe 32 mm (Thirty two millimetre) PVC waste pipe and sink including PVC waste chock complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.00	250.00	Rupees Two hundred fifty only.	Each	750
17	Providing and fixing Chromium plated brass soap Dish with CP brass brackets fixed to wooden cleats with CP brass screws with in all leads and lift of materials and as per direction of Engineer-in-charge.	10.00	750.00	Rupees Seven hundred fifty only	Each	7500
18	Providing and fixing corner shelf 3 piece set with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.00	850.00	Rupees Eight hundred fifty only	Each	5100
19	Providing and fixing centre hole mixture for wash basin (Bath sence) with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.00	3700.00	Rupees Three thousand seven hundred only	Each	11100
20	Providing and fixing 100 mm (One hundred millimetre) dia Chromium plated grating of superior quality for floor, gully or nahani with in all leads and lift of materials and as per direction of Engineer-in-charge.	8.00	48.30	Rupees Forty eight and paise thirty only	Each	386
21	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and color 15 mm (Fifteen millimetre) nominal bore with 45 cm (Forty five centimetre) length with in all leads and lift of materials and as per direction of Engineer-in-charge.	15.00	146.98	Rupees One hundred forty six and paise ninety eight only.	Each	2206
22	Providing and fixing shower with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	1550.00	Rupees One thousand five hundred fifty only	Each	3100

23	Providing and fixing hand jet faucet with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	1200.00	Rupees One thousand two hundred only.	Each	2400
24	Providing and fixing polycarbonated transparent sheet 1.20 mm (One point twenty millimetre) thick in roofing galvanised J or L hooks bolts and nuts with G.I. Limpet and bitumen rubber washer complete with all accessories as required with in all leads and lift of materials and as per direction of Engineer-in-charge.	30.34	1428.25	Rupees One thousand four hundred twenty six and paise twenty five only.	Per Square metre	43272
25	Providing and laying gang saw cut 18 mm (Eighteen millimetre) thick, mirror polished pre moulded and pre polished machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20mm (Twenty millimetre) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels with in all leads and lift of materials and as per direction of Engineer-in-charge	22.37	6153.04	Rupees Six thousand one hundred fifty three and paise zero four only.	Per Square metre	137644
26	Providing and edge moulding to 18 mm (Eighteen millimetre) thick marble stone counters, vanities etc., including machine polishing to edge to give high gloss finish etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	108.77	340.00	Rupees Three hundred forty only.	Per Square metre	36982
27	Repairs to plaster of thickness 12 mm (Twelve millimetre) to 20 mm (Twenty millimetre) in patches of area 2.5 sq.meters (Two point five square metre) and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete With cement mortar 1:4 (1 cement : 4 fine sand) with in all leads and lift of materials and as per direction of Engineer-in-charge.	113.16	384.45	Rupees Three hundred eighty four and paise forty six only.	Per Square metre	43505
	Total					499460


 Executive Engineer,
 Kullu Division,
 HP. PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Darka Gadlara road km 0/0 to 1/800 .
(SH:- C/o wire crated Retaining wall at RD 0/335 to 0/350)

Estimated cost:- Rs. 4,30,890.00
Earnest money :- Rs. 9,000.00
Time :- Two months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	31.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	11509.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803.1202 & 1203 Nominal Mix 1:4:8 (One cement. Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	21.60	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	107060.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4628 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	85.04	3213.75	Rupees Three thousand two hundred thirteen and paise seventy five only	Per cubic metre	276190.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	22.50	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	36111.00
	Total	Total				430890.00


Executive Engineer,
Kullu Division
HP.PWO Kullu

SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,89,687.00
Earnest money :- Rs. 10,000

Time :- Three months

Name of work:- Restoration of rain damages on Link Road to village Narayani under G.P Mohal km 0/0 to 0/230 (S.H :- Providing C.C pavement in Km. 0/0 to 0/330). Job No-4

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Stone soling properly hand packed filling interstices with Kharija stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification 100mm spread thickness/finished work including materials and labour) Within all leads and lift of materials and as per direction of Engineer-in-charge.	49.82	1450.25	Rupees one thousand Four hundred fifty and paise twenty five only	Per Cubic metre	72251
2	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm (Forty millimetre) nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	66.96	6234.10	Rupees Six thousand two hundred thirty four and paise ten only	Per Cubic metre	417435
		Total				489687


Executive Engineer,
Kullu Division,
HP.PWD Kullu

Estimated cost:- Rs. 4,89,687.00
Earnest money :- Rs. 10,000
Time :- Three months

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Link Road to village Narayani under G.P Mohal km 0/0 to 0/230 (SH :- Providing C.C pavement in Km. 0/0 to 0/330). Job No-II						
Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification 100mm spread thickness(finished work including materials and labour) Within all leads and lift of materials and as per direction of Engineer-in-charge.	49.82	1450.25	Rupees one thousand Four hundred fifty and paise twenty five only	Per Cubic metre	72251
2	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm (Forty millimetre) nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	66.96	6234.10	Rupees Six thousand two hundred thirty four and paise ten only	Per Cubic metre	417435
	Total					489687


Executive Engineer,
Kullu Division
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Reestoration of rain damages on Darfa Gadiara road km 0/0 to 1/800 .

Estimated cost - Rs. 4,30,232.00
Earnest money :- Rs. 9,000.00

SH:- C/o wire crated Retaining wall at RD 0/350 to 0/365)

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of slumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	29.70	365.35	Rupees Three hundred Sixty five and paise thirty five only	Per cubic metre	10851.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	21.50	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	107080.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	85.94	3213.76	Rupees Three thousand two hundred thirteen and paise seventy five only	Per cubic metre	276190.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material, within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	22.50	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	36111.00
	Total					430232.00

Executive Engineer,
Kullu Division,
HP. PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Jungruthana Tosh Km. 0/00 to 1/900 .

(SH:- Providing and laying WBM Grade - III at various reaches) . Job - I

Estimated cost:- Rs. 4,68,318.00

Earnest money :- Rs. 9,500.00

Time :- Two months.

Sr. No.	Description	Qty	Rate In		Unit	Amount
			Figure	Words		
1	Providing laying spreading and compacting stone aggregate of specific size to water bond macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 Kn in stages to proper grade and camber applying and brooming stone screening/ binding material to fill up the interstices of course aggregate watering and compacting to the required density Grading - III as per tech. specification clause 405 by manual means within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	134.96	3470.05	Rupees Three thousand four hundred seventy and paise zero five only.	Per Cubic metre	468318.00
					Total	468318.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Jungruthana Tosh Km. 0/00 to 1/900
(SH:- Providing and laying WBM Grade - III at various reaches) Job - II .

Estimated cost:- Rs. 4,68,318.00
Earnest money :- Rs. 9,500.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing laying spreading and compacting stone aggregate of specific size to water bond macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 Kn in stages to proper grade and camber applying and brooming stone screening/ binding material to fill up the interstices of course aggregate watering and compacting to the required density Grading - III as per tech. specification clause 405 by manual means within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	134.96	3470.05	Rupees Three thousand four hundred seventy and paise zero five only.	Per Cubic metre	468318.00
					Total	468318.00

Executive Engineer,
Kullu Division
HP PWD Kullu

46

SCHEDULE OF QUANTITY

Name of work:- RRD on Ratocha Dhara Chatrani road Km. 0/00 to 5/00 .
(SH:- C/O Breast wall at Km. 1/780 to 1/795).

Estimated cost:- Rs. 2,47,255.00
Earnest money :- Rs. 5,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	26.25	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	5994.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	20.10	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	7344.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702.704, 1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	32.10	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	168604.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	23.87	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	65313.00
					Total	247255.00


Executive Engineer,
Kullu Division,
HP PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Construction of Narogi to Shorn road Km 0/00 to 1/200 .
(SH:- C/O 3.0 m Slab Culvert at RD 0/100) . Job No. 1.

Estimated cost:- Rs. 4,00,105.00
Earnest money :- Rs. 8,200.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1503.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in- charge.	19.95	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	4556.00
2	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable material within all leads and lift of materials and as per direction of Engineer-in- charge.	28.17	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10293.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	10.19	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	53540.00
4	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 (2nd set) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in- charge.	39.59	5840.30	Rupees Five thousand eight hundred forty and paise thirty only.	Per cubic metre	231217.00
5	Providing Plain/ reinforced cement concrete in super structure complete as per drawings and technical specification clauses 802,804,805,806,807,1202 and 1204 RCC grade M-25 (1:1.5:3)(one cement one point five sand three graded stone aggregate nominal mix upto any height within all leads and lift of materials and as per direction of Engineer-in- charge.	3.47	8650.40	Rupees Eight thousand six hundred fifty and paise forty only.	Per Cubic metre	30046.00
6	Supplying fitting and placing TMT bar reinforcement sub structure complete as per drawings and technical specification clauses 1002, 1010 and 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	402.91	86.65	Rupees Eighty six and paise sixty five only	Per Kilogram	34912.00
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 within all leads and lift of materials and as per direction of Engineer-in- charge.	13.16	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	21121.00

8	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303.1 Rubble stone laid in cement mortar 1:3 (One cement : Three sand) within all leads and lift of materials and as per direction of Engineer-in-charge.	1.28	2947.80	Rupees Two thousand nine hundred forty seven and paise eighty only	Per cubic metre	3773.00
9	Providing and laying concrete for plain reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 PCC grade M-15 for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	1.70	6250.50	Rupees Six thousand two hundred fifty and fifty paise fifty only.	Per cubic metre	10647.00
					Total	400105.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

48

SCHEDULE OF QUANTITY

Name of work:- Construction of Narogi to Shorn road Km 0/00 to 1/200.
(SH:- C/O 3.0 m Slab Culvert at RD 0/100). Job No. 2.

Estimated cost - Rs. 4,00,105.00
Earnest money :- Rs. 8,200.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	18.95	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	4556.00
2	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	28.17	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10293.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702, 704, 1202 and 1204 Random rubble masonry in cement mortar 1:5 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.19	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	53540.00
4	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 (2nd sort) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	39.59	5840.30	Rupees Five thousand eight hundred forty and paise thirty only.	Per cubic metre	23127.00
5	Providing Plain/ reinforced cement concrete in super structure complete as per drawings and technical specification clauses 802, 804, 805, 806, 807, 1202 and 1204 RCC grade M-25 (1:1.5:3) (one cement one point five sand three graded stone aggregate nominal mix upto any height within all leads and lift of materials and as per direction of Engineer-in-charge.	3.47	8650.40	Rupees Eight thousand six hundred fifty and paise forty only.	Per Cubic metre	30046.00
6	Supplying fitting and placing TMT bar reinforcement sub structure complete as per drawings and technical specification clauses 1002, 1010 and 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	402.91	86.65	Rupees Eighty six and paise sixty five only	Per Kilogram	34912.00
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 within all leads and lift of materials and as per direction of Engineer-in-charge.	13.16	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	21121.00
8	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303.1 Rubble stone laid in cement mortar 1:3 (One cement : Three sand) within all leads and lift of materials and as per direction of Engineer-in-charge.	1.28	2947.80	Rupees Two thousand nine hundred forty seven and paise eighty only	Per cubic metre	3773.00

9	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 PCC grade M-15 for nominal mix within all leads and lift including cartage of materials and as per direction of Engineer-in-charge.	1.70	6250.50	Rupees Six thousand two hundred fifty and fifty paise fifty only.	Per cubic metre	10647.00
					Total	400105.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

49

SCHEDULE OF QUANTITY

Name of work:- Construction of Narogi to Shorn road Km 0/00 to 1/200 .
(SH:- C/O 3.0 m Slab Culvert at RD 0/100). Job No. 3.

Estimated cost:- Rs. 4,00,105.00
Earnest money :- Rs. 8,200.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	19.95	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	4556.00
2	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre) dressing of sides and bottom and back filling the excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	28.17	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10293.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.19	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	53540.00
4	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 (2nd sort) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	39.59	5840.30	Rupees Five thousand eight hundred forty and paise thirty only.	Per cubic metre	231217.00
5	Providing Plain/ reinforced cement concrete in super structure complete as per drawings and technical specification clauses 802,804,805,806,807,1202 and 1204 RCC grade M-25 (1:1.5:3)(one cement one point five sand three graded stone aggregate nominal mix upto any height within all leads and lift of materials and as per direction of Engineer-in-charge.	3.47	8650.40	Rupees Eight thousand six hundred fifty and paise forty only.	Per Cubic metre	30046.00
6	Supplying fitting and placing TMT bar reinforcement sub structure complete as per drawings and technical specification clauses 1002, 1010 and 1202 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	402.91	86.65	Rupees Eighty six and paise sixty five only	Per Kilogram	34812.00
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 within all leads and lift of materials and as per direction of Engineer-in-charge.	13.16	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	21121.00
8	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303.1 Rubble stone laid in cement mortar 1:3 (One cement : Three sand) within all leads and lift of materials and as per direction of Engineer-in-charge.	1.28	2947.80	Rupees Two thousand nine hundred forty seven and paise eighty only	Per cubic metre	3773

9	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate in open foundations complete as per drawing and technical specification clause 802.803.1202 and 1203 PCC grade M-15 for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	1.70	6250.50	Rupees Six thousand two hundred fifty and fifty paise fifty only.	Per cubic metre	10647
					Total	400105.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohgi GP Shillrajgiri Km. 0/00 to 3/500 .
(SH:- Formation cutting in Km. 2/585 to 2/735)

Estimated cost:- Rs. 4,98,497.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 108.68 Cum @ 300/-per cubic metre amounting to Rs. 32,604/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1311.41	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	498497.00
					Total:-	498497.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu.

51

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohgi GP Shillrajpur Km 0/00 to 3/500.
(SH:- Formation cutting in Km. 2/735 to 2/855).

Estimated cost:- Rs. 4,50,695.00
 Earnest money :- Rs. 9,200.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1. & 1603.2 and sorting out useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required). Recovery for useful material of 98.26 Cum @ 300/- per cubic metre amounting to Rs. 29,478/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1637.70	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	450695.00
					Total:-	450695.00


 Executive Engineer,
 Kullu Division
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohgi GP Shilliragiri Km. 0/00 to 3/500 .
(SH:- Formation cutting in Km. 2/855 to 3/075).

Estimated cost:- Rs. 4,74,968.00
 Earnest money :- Rs. 9,600.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiselling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1.&1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 103.55 Cum @ 300/- per cubic metre amounting to Rs. 31,065/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1725.90	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	474968.00
					Total:-	474968.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohgi GP Shiliraigiri Km. 0/00 to 3/500
(SH:- Formation cutting in Km. 3/075 to 3/210)

Estimated cost - Rs. 3,11,499.00
Earnest money :- Rs. 60,000.00
Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1 & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 87.91 Cum @ 300/- per cubic metre amounting to Rs. 20,373/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1131.80	275.20	Rupees Two hundred seventy five and paise twenty only.		Per cubic metre	311499.00
						Total:-	311499.00


Executive Engineer,
Kullu Division,
HP. PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohigi GP Shiliraigiri Km. 0/00 to 3/500 .
(SH:- Formation cutting in Km. 3/210 to 3/300) .

Estimated cost:- Rs. 3,63,966.00
 Earnest money :- Rs. 7,400.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 16C3.1 & 16C3.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 79.35 Cum @ 300/- per cubic metre amounting to Rs. 23,805/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1322.55	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	363966.00
					Total:-	363966.00

Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohgi GP Shillirajgiri Km. 0/00 to 3/500 .
(SH:- Formation cutting in Km. 2/345 to 2/585) .

Estimated cost:- Rs. 4,86,278.00
Earnest money :- Rs. 9,800.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 106.02 Cum @ 300/- per cubic metre amounting to Rs. 31,806/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1767.00	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	486278.00
					Total:-	486278.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Construction of link road to village Rohgi GP Shillrajpuri Km. 0/00 to 3/500 .
(SH:- Formation cutting in Km. 2/255 to 2/345) .

Estimated cost:- Rs. 4,82,439.00
Earnest money :- Rs. 9,800.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiselling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 105.18 Cum @ 300/- per cubic metre amounting to Rs. 31,554/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect	1753.05	275.20	Rupees Two hundred seventy five and paise twenty only.	Per cubic metre	482439.00
					Total:-	482439.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu.

57

SCHEDULE OF QUANTITY

Estimated cost:-4,81,635.00
Earnest money :- 9,700.00
Time :- Two months

Name of work:- Restoration of rain damages on various roads under Kharahal section
(SH):- Removal of slips of various roads at various RDs.)

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials upto any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3850.00	125.10	Rupees one hundred twenty five and paise ten only.	Per cubic metre	481635.00
					Total	481635.00


Executive Engineer,
Kullu/Division
HP.PWD Kullu

58

SCHEDULE OF QUANTITY

Name of work:- Construction of link road from Phagra Nallah to Shildhari Km. 0/00 to 1/900 .
(SH:- Formation cutting in RD. 0/00 to 0/190) Job No. 1.

Estimated cost:- Rs. 4,96,865.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1.8.1603.2 and sorting out useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 102.26 Cum @ 300/-per cubic metrie amounting to Rs. 30,678/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1843.97	269.45	Rupees Two hundred sixty nine and paise forty five only.	Per cubic metre	496865.00
					Total:-	496865.00


 Executive Engineer,
 Kullu Division,
 HP, PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Construction of link road from Phagra nallah to Shildhari road km 0/00 to 1/500

(SH:- F/c In km 0/120 to 0/270) Job -II

Estimated cost:- Rs. 4,99,456.00

Earnest money :- Rs. 10,000.00

Time :- Two months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiselling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out usefullun useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavatedearth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 81.52 Cum @ 300/-per cubic metre amounting to Rs. 24456/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1989.76	251.01	Rupees two hundred fifty one and paise zero one only.	Per cubic metre	499456.00
					Total:-	499456.00

Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- C/o C/o 30.48 m span Bailey Bridge over Jagrin Nallah on Jungruthana to Pulga road
(SH:- C/o wire Breast wall at RD. 0/010 to 0/020) Under SCSP.

Estimated cost:- Rs. 4,64,042.00
Earnest money :- Rs. 9,400.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	1017.50	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	232346.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	31.36	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	11467.00
3	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	41.18	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only	Per cubic metre	213984.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	16	390.95	Rupees Three hundred ninety and paise ninety five only.	Each	6255.00
					Total	464042.00


Executive Engineer,
Kulu Division
HP.PWD Kulu

61

SCHEDULE OF QUANTITY

Name of work:- C/o 30.48 m span Bailey Bridge over Jagrin Nallah on Jungruthana to Pulga road.
 (SH:- F/c 5/7 mtrs wide road on Pulga approach Km. 0/105 to 0/150). Under SCSP.

Estimated cost:- Rs. 3,38,989.00
 Earnest money :- Rs. 6,800.00
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 54.55 Cum @ 300/- per cubic metre amounting to Rs. 16,365/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1291.14	262.55	Rupees Two hundred sixty two and paise fifty five only.	Per cubic metre	338989.00
					Total:-	338989.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

62

SCHEDULE OF QUANTITY

Name of work:- C/o 30.48 m span Bailey Bridge over Jagrin Nallah on Jungriuthana to Pulga road
(SH:- Filling in the Barshaini side approach road) Under SCSP)

Estimated cost:- Rs. 3,88,542.00
Earnest money :- Rs. 7,800.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Filling in earthwork with approved material obtained from the borrow pits with in all leads and lifts transporting to site, spreading grading to required slopes within all leads and lift of materials and as per direction of Engineer-in-charge.	1155.00	336.40	Rupees Three hundred thirty six and paise forty only.	Per cubic metre	388542.00
		Total				388542.00

Executive Engineer,
Kullu Division
HP, PWD Kullu

63

SCHEDULE OF QUANTITY

Name of work:- C/o 30.48 m span Bailey Bridge over Jagrin Nallah on Jungruthana to Pulga road
 (**SH:-** F/c 5/7 mtrs wide road on Pulga approach Km. 0/00 to 0/090). Under SCSIP.

Estimated cost:- Rs. 4,53,471.00
 Earnest money :- Rs. 9,200.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 86.36 Cum @ 300/- per cubic metre amounting to Rs. 25,908/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1727.18	262.65	Rupees Two hundred sixty two and paise fifty five only.	Per cubic metre	453471.00
					Total:-	453471.00


 Executive Engineer,
 Kullu Division,
 HP PWD Kullu

64 **SCHEDULE OF QUANTITY**

Name of work:- C/o 30.48 m span Bailey Bridge over Jagrin Nallah on Jungnuthana to Pulga road
(SH:- C/o R/wall on pulga side approach at RD 0/120 to 0/136) . Under SCSP .

Estimated cost:- Rs. 4,99,531.00
Earnest money:- Rs. 10,000.00

Time :- Two months

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	31.36	385.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	11457.00
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 PCC grade 1:4:8 (One cement : Four sand : Eight graded stone aggregate) for nominal mix within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	64.00	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	317274.00
3	Providing and laying boulder apron laid in wire crate with 4 mm (Four millimetre) dia wire conforming to IS 280 and 4826 in 150 x 150 mm (One hundred fifty x One hundred fifty millimetre) mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge.	50.00	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	139215.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.68	1604.05	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	171585.00
					Total	499531.00


Executive Engineer,
Kullu Division
HP.PWD Kullu

65

SCHEDULE OF QUANTITY

Name of work:- Providing road side amenities on Sainik chowk Bhunter Ramshila road Km. 0/00 to 13/400 :

Estimated cost - Rs. 4,80,486.00

Earnest money :- Rs. 9,800.00

Time :- Two months.

(SH:- C/o Ornamental rain shelter near Nature Park Mohal hill side at Km. 4/440)

Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m (Fifty metre) work/ jumper work 50% (Fifty percent) each with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.94	183.80	Rupees One hundred eighty three and paise eighty only.	Per Cubic metre	724
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:6:12 (1 Cement : 6 Coarse sand : 12 graded stone aggregate 40 mm (Forty millimetre) nominal size) within all leads and lift of materials and as per direction of Engineer-in-charge.	0.98	4509.15	Rupees Four thousand five hundred nine and paise fifteen only.	Per cubic metre	4419
3	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm (Twenty millimetre) nominal size) upto plinth level : Cement mortar 1:6 (1 cement : 6 coarse sand) Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm (Twenty millimetre) nominal size) at window sills, ceiling level and the like with with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.89	5280.80	Rupees Five thousand two hundred eighty and paise eighty only.	Per Cubic metre	36385
4	Stone filling dry hand packed under floor with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.72	1978.20	Rupees One thousand nine hundred seventy eight and paise twenty only.	Per Cubic metre	3403
5	Providing and fixing ornamental ready made vertical post, with anarkali design 100 mm (One hundred millimeter) dia with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.00	55000.00	Rupees Fifty five thousand only	Each	165000
6	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, with in all leads and lift of materials and as per direction of Engineer-in-charge.	725.76	139.10	Rupees One hundred thirty nine and paise ten only.	Per Kilogram metre	100953

7	Providing and fixing 0.60mm (Zero plmr sixty millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetre) dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. within all leads and lift of materials and as per direction of Engineer-in-charge.	25.08	1620.85	Rupees One thousand six hundred twenty and paise eighty five only.	Per Square metre	40651
8	Providing and fixing 0.60mm (Zero plmr sixty millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetre) dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. within all leads and lift of materials and as per direction of Engineer-in-charge.	11.75	862.45	Rupees Eight hundred sixty two and paise forty five only.	Per running metre	10134
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm (Forty millimetre) nominal size) with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.13	4915.15	Rupees Four thousand nine hundred fifteen and paise fifteen only.	Per Cubic metre	10469
10	Kota stone slab flooring over 20 mm (Twenty millimetre) (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) 25 mm (Twenty five millimetre) thick with in all leads and lift of materials and as per direction of Engineer-in-charge.	27.90	1422.75	Rupees One thousand four hundred twenty two and paise seventy five only.	Per Square metre	39695
11	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.80 ltr/ 10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (Zero point eighty litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	50.55	92.05	Rupees Ninety two and paise zero five only.	Per Square metre	4653
12	Providing and fixing ornamental sitting benches with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.00	16000.00	Rupees Sixteen thousand only.	Each	64000
	Total	Total				480486


Executive Engineer,
Kullu Division,
HP PWD Kullu

66

SCHEDULE OF QUANTITY

Name of work:- C/o road side amenities on Sainik Chowk Bhunter Ramshilla road Km 0/00 to 7/140.
(SH:- Repair of rain shelter and sitting place near Shiv Temple Mohal Km 4/030).

Estimated cost:- Rs. 4,95,240.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres (Fifty metre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.75	1465.35	Rupees One thousand four hundred sixty five and paise thirty five only.	Per Cubic metre	6960
2	Coursed rubble masonry (first sort) with hard stone in foundation and plinth with cement mortar 1:6 (1 cement : 6 coarse sand) with in all leads and lift of materials and as per direction of Engineer-in-charge	3.72	5280.80	Rupees Five thousand two hundred eighty and paise eighty only.	Per Cubic metre	51329
3 (a)	Centering and shuttering including strutting, propping etc. and removal of form work for with Lintels, beams, plinth beams, girders, bressumers and cantilevers with in all leads and lift of materials and as per direction of Engineer-in-charge.	17.79	438.35	Rupees Four hundred thirty eight and paise thirty five only.	Per Square metre	7798
(b)	Centering and shuttering including strutting, propping etc. and removal of form work for with Suspended floors, roofs, landings, balconies and access platform-with in all leads and lift of materials and as per direction of Engineer-in-charge.	8.10	530.30	Rupees Five hundred thirty and paise thirty only.	Per Square metre	4295
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm (Twenty millimetre) nominal size) with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.20	7830.60	Rupees Seven thousand eight hundred thirty and paise sixty only.	Per Cubic metre	25058
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more, with in all leads and lift of materials and as per direction of Engineer-in-charge.	480.00	87.45	Rupees Eighty seven and paise forty five only.	Per Kilogram metre	41976
6	Brick work with common burnt building bricks in super structure in cement mortar Cement mortar 1:4 (1 cement : 4 coarse sand) with in all leads and lift of materials and as per direction of Engineer-in-charge.	0.55	9680.70	Rupees Eighty seven and paise forty five only.	Per Square metre	5324

7	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, with in all leads and lift of materials and as per direction of Engineer-in-charge.	455.60	139.10	Rupees One hundred thirty nine and paise ten only.	Per Kilogram metre	63374
8	Providing and fixing 0.60mm (Zero pinr sixty millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetre) dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge, within all leads and lift of materials and as per direction of Engineer-in-charge.	50.41	1620.85	Rupees One thousand six hundred twenty and paise eighty five only	Per Square metre	81707
9	Providing and fixing 0.60mm (Zero pinr sixty millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetre) dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge, within all leads and lift of materials and as per direction of Engineer-in-charge.	7.10	862.45	Rupees Eight hundred sixty two and paise forty five only	Per Square metre	6123
10	Stone filling dry hand packed under floor with in all leads and lift of materials and as per direction of Engineer-in-charge.	12.81	1978.20	Rupees One thousand nine hundred seventy eight and paise twenty only.	Per Square metre	25341
11	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm (Forty millimetre) nominal size) with in all leads and lift of materials and as per direction of Engineer-in-charge.	8.54	4915.15	Rupees Four thousand nine hundred fifteen and paise fifteen only.	Per Cubic metre	41975
12	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm (Forty millimetre) thick with 20 mm (Twenty millimetre) nominal size stone aggregate with in all leads and lift of materials and as per direction of Engineer-in-charge.	41.98	432.50	Rupees Four hundred thirty two and paise fifty only.	Per Square metre	18156

13	Cement skirting 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm (Forty millimetre) thick with 20 mm (Twenty millimetre) nominal size stone aggregate with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.95	350.00	Rupees Three hundred fifty only.	Per Square metre	1733
14	Providing and laying 60 mm (Sixty millimetre) factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm (Fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	37.50	1250.40	Rupees One thousand two hundred fifty and paise forty only	Per Square metre	46890
15	Providing and fixing ornamental cast iron chair in standard size carriage of materials with in all leads, lifts and other Incidentals and as per specification with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.00	16800.00	Rupees Sixteen thousand eight hundred only	Each	67200
	Total					495240

Executive Engineer,
Kullu Division,
HP.PWD Kullu

Name of work:- Restoration of rain damages on Dohranallah to Barahar road Km. 0/00 to 10/120
(SH:- C/o Retaining wall at RD 5/510 to 5/525)

Estimated cost:- Rs. 4,78,223.00
Earnest money :- Rs. 9,600.00
Time :- Two months.

SCHEDULE OF QUANTITY

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	57.30	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	13084.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	19.80	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	7234.00
3	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix aggregate foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	48699.00
4	Random rubble Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	43.98	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	231003.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carrriage of all labour equipment and materials to various location through all modes of transportation within all leads and lift of materials and as per direction of Engineer-in-charge.	52.78	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	144417.00
6	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 within all leads and lift of materials and as per direction of Engineer-in-charge	31.00	390.95	Rupees Three hundred ninety and paise ninety five only	Each	12119.00

7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge	13.50	1504.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	21667.00
		Total				478223.00


 Executive Engineer,
 Kullu Division,
 HP. PWD Kullu.

68

SCHEDULE OF QUANTITY


Name of work:- Construction of link road from NH-03(Jia) to Shankergarh Km. 0/00 to 1/400 .
(SH:- M/T work between RD 1/140 to 1/400).

Estimated cost - Rs. 4,52,470.00
 Earnest money :- Rs. 9,200.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Unit	Amount
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 by Manual Means Grading-II including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	57.30	3250.50	Rupees Three thousand two hundred fifty and paise fifty only.	Per Cubic metre	186254.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.00 kg/sqm (Zero point seventy - One point zero Kilogram per square metre) using mechanical means with in all leads and lift of materials and as per direction of Engineer-in-charge.	764.00	50.45	Rupees Fifty and paise forty five only.	Per Square metre	38544.00
3	Providing and applying tack coat with bitumen Emulsion (RS-f) using emulsion distributor at the rate @ 0.25 to 0.30 kg/sqm (Zero point twenty five to zero point thirty kilogram per square meter) on the prepared on dry and hungry bituminous surface cleaned with Hydraulic broom as per technical specification clause 503.	764.00	18.00	Rupees Eighteen only.	Per Square metre	13752.00
4	Providing laying and rolling of open graded premix carpet of 20mm (Twenty millimetre) thickness composed of 13.2mm (Thirteen point two millimetre) to 5.6mm (Five point six millimetre) aggregate either using penetration grade (VG-10) bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 KN static roller capacity, finished to required level and grades to be followed by seal coat of either Type-B as per technical specification clause 508 including hauling carriage of all labor and equipment and material to various locations through all modes of transports by mechanical means within all leads and lift of materials and as per direction of Engineer-in-charge.	764.00	215.00	Rupees Two hundred fifteen only.	Per Square Metre	164260.00

5	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using bitumen VG-10 type-B as per technical specification of clause 510 including hauling carriage of all labour and equipments and material to various locations through all modes of transports by mechanical means including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	764.00	65.00	Rupees Sixty five only.	Per Square metre	49660.00
					Total	452470.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Construction of link road from NH-03(Jia) to Shankergarh Km. 0/00 to 1/400
(SH:- M/T work between RD 0/860 to 1/140)

Estimated cost - Rs. 4,93,926.00
Earnest money :- Rs. 10,000.00
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 by Manual Means Grading-III including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	62.56	3250.50	Rupees Three thousand two hundred fifty and paise fifty only.	Per Cubic metre	203319.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.00 kg/sqm (Zero point seventy - One point zero Kilogram per square metre) using mechanical means with in all leads and lift of materials and as per direction of Engineer-in-charge.	834.00	50.45	Rupees Fifty and paise forty five only.	Per Square metre	42075.00
3	Providing and applying tack coat with bitumen Emulsion (RS-I) using emulsion distributor at the rate @ 0.25 to 0.30 kg/sqm (Zero point twenty five to zero point thirty kilogram per square meter) on the prepared on dry and hungry bituminous surface cleaned with Hydraulic broom as per technical specification clause 503.	834.00	18.00	Rupees Eighteen only.	Per Square metre	15012.00
4	Providing laying and rolling of open graded premix carpet of 20mm (Twenty millimetre) thickness composed of 13.2mm (Thirteen point two millimetre) to 5.6mm (Five point six millimetre) aggregate either using penetration grade (VG-10) bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 KN static roller capacity, finished to required level and grades to be followed by seal coat of either Type-B as per technical specification clause 508 including hauling carriage of all labor and equipment and material to various locations through all modes of transports by mechanical means within all leads and lift of materials and as per direction of Engineer-in-charge.	834.00	215.00	Rupees Two hundred fifteen only.	Per Square Metre	179310.00

5	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using bitumen VG-10 type B as per technical specification of clause 510 including hauling carriage of all labour and equipments and material to various locations through all modes of transports by mechanical means including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	834.00	65.00	Rupees Sixty five only.	Per Square metre	54210.00
					Total	493926.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Ruid

SCHEDULE OF QUANTITY

Name of work:- Construction of link road from NH-03(Jia) to Shankergarh Km. 0/00 to 1/400 ,
(SH:- M/T work between RD 0/490 to 0/860).

Estimated cost:- Rs. 4,93,334.00
 Earnest money :- Rs. 10,000.00
 Time :- Two months.

Sr. No.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 by Manual Means Grading-III including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	62.48	3250.50	Rupees Three thousand two hundred fifty and paise fifty only.	Per Cubic metre	203075.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.00 kg/sqm (Zero point seventy - One point zero Kilogram per square metre) using mechanical means with in all leads and lift of materials and as per direction of Engineer-in-charge.	833.00	50.45	Rupees Fifty and paise forty five only.	Per Square metre	42025.00
3	Providing and applying tack coat with bitumen Emulsion (RS-I) using emulsion distributor at the rate @ 0.25 to 0.30 kg/sqm (Zero point twenty five to zero point thirty kilogram per square meter) on the prepared on dry and hungry bituminous surface cleaned with Hydraulic broom as per technical specification clause 503.	833.00	18.00	Rupees Eighteen only.	Per Square metre	14994.00
4	Providing laying and rolling of open graded premix carpet of 20mm (Twenty millimetre) thickness composed of 13.2mm (Thirteen point two millimetre) to 5.6mm (Five point six millimetre) aggregate either using penetration grade (VG-10) bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base. including mixing in a suitable plant, laying and rolling with a three wheel 80-100 KN static roller capacity, finished to required level and grades to be followed by seal coat of either Type-B as per technical specification clause 508 including hauling carriage of all labor and equipment and material to various locations through all modes of transports by mechanical means within all leads and lift of materials and as per direction of Engineer-in-charge.	833.00	215.00	Rupees Two hundred fifteen only.	Per Square Metre	179095.00

5	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using bitumen VG-10 type-B as per technical specification of clause 510 including hauling carriage of all labour and equipments and material to various locations through all modes of transports by mechanical means including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	833.00	65.00	Rupees Sixty five only.	Per Square metre	54145.00
					Total	493334.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Construction of link road from NH-03(Jia) to Shankergarh Km. 0/00 to 1/400.
(SH:- M/T work between RD 0/060 to 0/160 and 0/260 to 0/490)

Estimated cost:- Rs. 4,93,514.00
Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405 by Manual Means Grading-III including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	50.33	3250.50	Rupees Three thousand two hundred fifty and paise fifty only.	Per Cubic metre	163598.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.00 kg/sqm (Zero point seventy - One point zero Kilogram per square metre) using mechanical means with in all leads and lift of materials and as per direction of Engineer-in-charge.	671.00	50.45	Rupees Fifty and paise forty five only.	Per Square metre	33852.00
3	Providing and applying tack coat with bitumen Emulsion (RS-1) using emulsion distributor at the rate @ 0.25 to 0.30 kg/sqm (Zero point twenty five to zero point thirty kilogram per square meter) on the prepared on dry and hungry bituminous surface cleaned with Hydraulic broom as per technical specification clause 503.	993.50	18.00	Rupees Eighteen only.	Per Square metre	17883.00
4	Providing laying and rolling of open graded premix carpet of 20mm (Twenty millimetre) thickness composed of 13.2mm (Thirteen point two millimetre) to 5.6mm (Five point six millimetre) aggregate either using penetration grade (VG-10) bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 KN static roller capacity, finished to required level and grades to be followed by seal coat of either Type-B as per technical specification clause 508 including hauling carriage of all labor and equipment and material to various locations through all modes of transports by mechanical means within all leads and lift of materials and as per direction of Engineer-in-charge.	993.50	215.00	Rupees Two hundred fifteen only.	Per Square Metre	213603.00

5	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using bitumen VG-10 type-B as per technical specification of clause 510 including hauling carriage of all labour and equipments and material to various locations through all modes of transports by mechanical means including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	693.50	65.00	Rupees Sixty five only	Per Square metre	64578.00
					Total	493514.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Construction of Chharour nallah to Bhain road km 0/00 to 7/340

(SH:- ROFD in km 4/180 to 4/675) .

Estimated cost- Rs. 4,62,807.00

Earnest money :- Rs. 9,500.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1.&1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 56.09 Cum @ 300/- per cubic metre amounting to Rs. 16827/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1967.55	235.22	Rupees Two hundred thirty five and paise twenty two only.	Per cubic metre	462807.00
					Total:-	462807.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu

73

SCHEDULE OF QUANTITY

Name of work:- Construction of Chharour nallah to Bhrair road km 0/00 to 7/340
(SH:- ROFD in km 4/675 to 4/945).

Estimated cost:- Rs. 4,72,373.00
Earnest money :- Rs. 9,500.00
Time :- Two months.

Sr. No.	Description	Qty	Rate In		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required settling out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its levelling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 89.99 Cum @ 300/- per cubic metre amounting to Rs. 26998/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1799.86	262.45	Rupees Two hundred sixty two and paise forty five only.	Per cubic metre	472373.00
Total:-						472373.00


Executive Engineer,
Kullu Division,
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Construction of Chharour nallah to Bhrahn road km 0/00 to 7/340

(SH:- ROFD in km 5/410 to 5/560).

Estimated cost:- Rs. 4,74,341.00

Earnest money :- Rs. 9,500.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its levelling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 168.576 Cum @ 300/- per cubic metre amounting to Rs. 50573/- only shall be done on pro-rata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1580.40	300.14	Rupees three hundred and paise fourteen only.	Per cubic metre	474341.00
					Total:-	474341.00


 Executive Engineer,
 Kultu Division,
 HP.PWD Kultu

SCHEDULE OF QUANTITY

Name of work:- Construction of Chharour nallah to Bhrair road km 0/00 to 7/340

(SH:- ROFD in km 5/230 to 5/410) .

Estimated cost :- Rs. 4,78,199.00

Earnest money :- Rs. 9,600.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiselling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 118.94 Cum @ 300/- per cubic metre amounting to Rs. 35683/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1741.28	274.63	Rupees two hundred seventy four and paise sixty three only.	Per cubic metre	478199.00
					Total:-	478199.00


 Executive Engineer,
 Kullu Division,
 H.P. PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Construction of Chharour nallah to Bhain road km 0/00 to 7/340

(SH:- ROFD in km 4/945 to 5/230)

Estimated cost:- Rs. 4,85,624.00

Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1 & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 183.203 Cum @ 300/- per cubic metre amounting to Rs. 54961/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1575.60	308.22	Rupees Three hundred eight and paise twenty two only.	Per cubic metre	485624.00
					Total:-	485624.00


 Executive Engineer,
 Kullu Division,
 HP. PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Construction of Chharour nallah to Bhrain road km 0/00 to 7/340

Estimated cost - Rs. 4,16,084.00

(SH:- ROFD in km 5/560 to 6/785).

Earnest money :- Rs. 8,500.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-In-charge at site according to technical specifications clause 1603,1, & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 84.71 Cum @ 300/- per cubic metre amounting to Rs. 25412/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1569.60	265.09	Rupees two hundred sixty five and paise zero nine only.	Per cubic metre	416084.00
					Total:-	416084.00


 Executive Engineer,
 Kullu Division,
 HP, PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Purchase of Printer /Plotter, Scanner in Design Cell at O/O Chief Engineer Mandi Zone against NABARD work i.e. Balu-ra-Ghera to Tipri Shouth road km 0/ 00 to 4/500 under RIDF-XXVI.

Estimated cost:- Rs. 4,54,622.00
Earnest money :- Rs. 9,200.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Supplying of HP Design jet T2600 36 IN printer/ pplotter/ scanner up to A0 paper size Theoretical minimum line width 0.02 mm (Zero point zero two millimetre) print speed 180 A1/hr, 19.3 sec/A1 print quality colour up to 2400x1200 optimised dpi, liner scan speed scan: up to 7.62 cm/sec (Seven point sixty two centimetre per second) (colour, 200dpi) up to 25.4 cm/sec (Twenty five point four centimetre per second) (grayscale, 200dpi) copy up to 15.24 cm/sec (Fifteen point twenty four centimetre per second) (colour, 200dpi). up to 25.4 cm/sec (Twenty five point four centimetre per second) (grayscale, 200dpi) scan resolution, optical up to 600 dpi, copy reduce/enlarge setting 25 to 400% at 1% increment etc. one paper roll as per direction of Engineer in charge excluding GST within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	1	394499.00	Rupees Four lac six thousand seven hundred only.	Each	394499.00
2	Supplying of HP Design jet T2600 PDF Upgrade Kit as per the direction within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	1	60123.00	Rupees Sixty one thousand three hundred fifty only.	Each	60123.00
					Total	454622.00


 Executive Engineer,
 Kullu Division,
 HP.PWD Kullu