

Himachal Pradesh
Public Works Department
No. PWN/CB/2nd C /Tender/2024-25/ 1259-79

Dated 15.07.2024

To

The Executive Engineer (I.T. Cell)
HPPWD Nirman Bhawan , Nigam Vihar,
Shimla-2
cc-pwd-hp@nic.in

Subject : Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice inviting tenders for uploading on department web-site as per Notification of the Principal Secretary (PW) to the Govt. of Himachal Pradesh Letter No. PBW-(B)A9(3) 1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

(Signature)
Executive Engineer
Nurpur Division
HPPWD Nurpur.

Copy forwarded to the Superintending Engineer 9th Circle HPPWD Nurpur for information please.
Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell) Nigam Vihar Shimla -2 for information and further necessary action.
Copy to the Sub Divisional magistrate (Civil) Nurpur for information.
Copy forwarded to all the Assistant Engineer Under this division.
Copy to the various contractor.
Copy to the Notice Board.

1
Executive Engineer
Nurpur Division
HPPWD Nurpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

TENDER

Sealed percentage rate tenders on the form 6 & 8 are hereby invited by the Executive Engineer Nurgur Division HPPWD., Nurgur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE

1.	Date and time of receipt of application for tender form	22.07.2024	Up to 02.00 PM
2.	Date and time of issue of tender form	23.07.2024	Up to 04.00 PM
3.	Date and time of receipt of tenders	24.07.2024	Up to 11.00AM
4.	Date and time of opening of tenders	24.07.2024	At 3.00 P.M.

The tenders form will be issued against cash payment (non-refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer Nurgur Division HPPWD Nurgur must accompany with each tender.

Sr. No.	Name of work.	Estimated cost (Rs.)	Earnest money	Time limit	Cost of form	Eligible class of Contractor
1.	A/R & M/O Khushinagar Minjgran road Km 0/00 to 12/00 (SH: Repair of pot holes and patches at RD 8/00 to 11/00)	498600.00	10000.00	One Month	350/-	Class -D
2.	A/R & M/O Nurgur to Kopra road Km 0/00 to 6/00 (SH: Repair of pot holes and patches at RD 0/00 to 2/00 and 4/00 to 5/00)	424527.00	10000.00	One Month	350/-	Class -D
3.	Construction of link road to village Samola Km 0/00 to 1/500 (SH: providing and laying wearing Grade-III and 20mm thick premix carpet with seal coat from Km 0/050 to 0/350)	475440.00	10000.00	One Month	350/-	Class -D
4.	A/R & M/O Bodh Chakki Dhar road Km 0/00 to 8/00 (SH: Repair of pot holes and patches at RD 5/00 to 8/00)	497658.00	10000.00	One Month	350/-	Class -D
5.	Construction of link road to Harijan Basti Chandran road (SH: Cause way at RD 0/250 to 0/258 and cement concrete at RD 0/620 to 0/632)	367641.00	7300.00	One Month	350/-	Class -D
6.	Construction of link road to Harijan Basti Chandran road (SH: Cause way at RD 0/640 to 0/660)	367341.00	7300.00	One Month	350/-	Class -D
7.	Construction of link road from Bhol Thakran Patwar Khana to Jogi Mohalla Janglahar road (SH: Construction of cement concrete pavement from RD 1/085 to 1/160)	477150.00	10000.00	One Month	350/-	Class -D
8.	Construction of link road from Bhol Thakran Patwar Khana to Jogi Mohalla Janglahar road (SH: Construction of cement concrete pavement from RD 0/790 to 0/805 and 1/015 to 1/075)	477150.00	10000.00	One Month	350/-	Class -D
9.	Construction of link road from Bhol Thakran Patwar Khana to Jogi Mohalla Janglahar road (SH: providing and laying soling Grade-I 90mm to 45mm , wearing 53mm to 22.45 mm in Km 0/700 to 0/790 and 0/805 to 1/0158)	354968.00	7300.00	One Month	350/-	Class -D
10.	Construction of link road Kherian to Jara Via Khaloon road (SH: Construction of cement concrete pavement from RD 0/055 to 0/100)	286290.00	6000.00	One Month	350/-	Class -D
11.	Construction of link road from Kopra to Harijan Basti Mehti road Km 0/00 to 2/650(SH: Construction of 900mm dia Hume Pipe culvert at RD 1/410 and earth work at RD 0/045 to 0/210)	445934.00	10000.00	One Month	350/-	Class -D
12.	Construction of link road from Kopra to Harijan Basti Mehti road Km 0/00 to 2/650(SH: Construction of 900mm dia Hume Pipe culvert at RD 1/532 and 1/895)	357608.00	7200.00	One Month	350/-	Class -D
13.	Construction of link road to village Hangeri Km 0/00 to 1/00 (SH: Construction of cement concrete pavement at RD 0/00 to 0/065)	297648.00	6000.00	One Month	350/-	Class -D
14.	Construction of link road Panjahra Hadala Barswala road to harijan Basti Ganoh road (SH: Providing and laying wearing Grade- II at RD 0/315 to 0/465 and	304200.00	6200.00	One Month	350/-	Class-D

	cement concrete pavement from RD 0/265 to 0/315) .					
15.	Construction of link road Panjahra Hadala Barswala road to harijan Basti Ganoh road (SH: Construction of 1.00 Mtr span RCC slab culvert at RD 0/265)	337633.00	6800.00	One Month	350/-	Class -D
16.	Construction of veterinary Hospital / Go Sadan Khajan tehsil Nurpur Distts Kangra (SH: Construction of water Tank)	338512.00	6800.00	One Month	350/-	Class -D
17.	A/R & M/O on Mohtali Indora A-II Pucca Tiala road Km 10/00 to 19/260 (SH: Repair of Pot Holes In Km at RD 17/00 to 18/00) (Under MMSRRY 2024-25)	216152.00	4500.00	One Month	350/-	Class -D
18.	A/R & M/O on Mohtali Indora A-II Pucca Tiala road Km 10/00 to 19/260 (SH: Repair of Pot Holes and patches in Km at RD 18/00 to 19/00) (Under MMSRRY 2024-25)	197754.00	4000.00	One Month	350/-	Class -D
19.	A/R & M/O Gangath to Dadoh Phase-I Km 0/00 to 5/00 (SH: Repair of Pot Holes and patches in Km at RD 2/00 to 3/00) (Under MMSRRY 2024-25)	156089.00	3200.00	One Month	350/-	Class -D
20.	A/R & M/O on Lagore to Gehine Km 0/00 to 1/870 (SH: Repair of Pot Holes and patches in Km at RD 0/00 to 1/00) (Under MMSRRY 2024-25)	156352.00	3200.00	One Month	350/-	Class -D
21.	A/R & M/O on Baduhi to Galore Khas Km 0/00 to 6/00 (SH: Repair of Pot Holes and patches in Km at RD 4/00 to 5/00) (Under MMSRRY 2024-25)	179089.00	3600.00	One Month	350/-	Class -D
22.	A/R & M/O on Nurpur to Kullan via Chinwan road Km 0/00 to 5/00 (SH: Repair of Pot Holes and patches in Km at RD 2/00 to 3/00) (Under MMSRRY 2024-25)	139689.00	3000.00	One Month	350/-	Class -D
23.	Restoration of rain damages on Khajan Jatoli Aund road Km 0/00 to 6/200 (SH: Construction of cement concrete pavement from RD 4/998 to 5/050)	204256.00	4000.00	One Month	350/-	Class -D
24.	A/R & M/O Bodh to haral Upparly Km 8/00 to 13/500 (SH: Repair of pot holes at RD 12/00 to 13/00 (MMSRRY)	253178.00	5100.00	One Month	350/-	Class -D
25.	A/R & M/O Bodh to haral Upparly Km 8/00 to 13/500 (SH: Repair of pot holes at RD 13/00 to 13/500 (MMSRRY)	253385.00	5100.00	One Month	350/-	Class -D
26.	A/R & M/O Mamoon to gurchal to Ther Nichli road Km 0/00 to 2/00 (SH: Repair of pot holes at RD 0/00 to 1/00) (MMSRRY)	159116.00	3200.00	One Month	350/-	Class -D
27.	A/R & M/O Suliali to Loharpura road Km 0/00 to 1/350 (SH: Repair of pot holes at RD 0/700 to 1/350 (MMSRRY)	196873.00	4000.00	One Month	350/-	Class -D
28.	A/R & M/O Nurpur Lahru Tunu Hatti road Km 0/00 to 15/390 (SH: Repair of pot holes at RD 8/00 to 9/00 (SH: Repair of pot holes at RD 8/00 to 9/00)(MMSRRY)	152010.00	3100.00	One Month	350/-	Class -D
29.	A/R & M/O Sadwan to Suliali road Km 0/00 to 5/200 (SH: Repair of pot holes at RD 3/00 to 4/00 (MMSRRY)	178268.00	3100.00	One Month	350/-	Class -D
30.	Construction of link road to village Giyali Km 0/00 to 0/080 (SH: Formation cutting and crate work at RD 0/060 to 0/065 C/O 900mm dia Hume pipe culvert at RD 0/075)	390336.00	10000.00	One Month	350/-	Class -D
31.	A/R & M/O Nurpur to Sanjha Nalla road Km 0/00 to 15/390 (SH: providing and laying 30mm thick bituminous concrete in patches in between Km 1/200 to 1/800)	496948.00	10000.00	One Month	350/-	Class -D
32.	Construction of link road from Peer Baba Mandir to Divkeshwar Mandir road Km 0/00 to 1/00 (SH: Construction of V-shape drain with Edge wall at RD 0/410 to 0/710)	224918.00	5000.00	One Month	350/-	Class -D
33.	Restoration of rain damages on various roads under Suliali Sub Division HPPWD Suliali (SZH: Hiring of Excavator -cum-loaders for removal of slips)	493500/-	10000.00	One Month	350/-	Class -D
34.	Restoration of rain damages on various roads under Nurpur Sub Division HPPWD Nurpur (SH: Hiring of Excavator-cum-loaders for removal of slips)	493500/-	10000.00	One Month	350/-	Class -D


35.	Restoration of rain damages on link road to village Sanehra road Km 0/00 to 1/00 (SH: Const of crate work at RD 0/120 to 0/130)	195889/-	4000.00	One Month	350/-	Class -D
36.	A/R Pong Dam Fatehpur Jassur road Km 45/500 to 53/680 (SH: Providing and laying wearing Grade-III 53mm to 22.45mm and 30mm thick bitumeneous concrete at RD 53/200 to 53/220, 53/300 to 53/310, 53/555 to 53/605) (length = 80.00 Mtr)	269878/-	5500.00	One Month	350/-	Class -D
37.	Restoration of rain damages onNurpur Sadwan Malkwal Sanjha Nallah road Km 0/00 to 15/390 (SH: Const of retaining wall at RD 4/500 to 4/517 and RD RD 4/620 to 4/640 Ht. 2.50 Mtr)	366806/-	8000.00	One Month	350/-	Class -D
38.	A/R & M/O Nurpur Sadwan Malkwal Sanjha Nallah road Km 0/00 to 15/390 (SH: Repair of pot holes and patches at RD 13/500 to 15/00)	466200/-	10000.00	One Month	350/-	Class -D
39.	A/R & M/O Residential building under Nurpur Division HPPWD Nurpur (SH: Repair and painting of Superintending Engineer residence building at Nurpur)	430356/-	7200.00	One Month	350/-	Class -D
40.	Restoration of rain damages on various roads ynder Suliali Sub Division HPPWD Suliali (SH: Erecting and fixing of damaged "W" metal beam crash barrier on various roads/ reaches)	492188/-	10000.00	One Month	350/-	Class -D
41.	Restoration of rain damages on Makore Jamun Chakki road Km 0/00 to 3/750 (SH: Construction of U-Shape Drain with Edge wall at RD 3/701 to 3/731 Ht. 2.44 Mtr)	492046/-	10000.00	One Month	350/-	Class -D
42.	Restoration of rain damages on Makore jamun Chakki road KM 0/00 to 3/750 (SH: Construction of U-shape drain with Edge wall at RD 3/735 to 3/765 Ht. 2.44 Mtr)	492046/-	10000.00	One Month	350/-	Class -D
43.	Construction of link road Ladori to Ghaloon road KM 0/00 to 1/700 (SH: providing and laying Interlocking paver block at RD 1/00 to 1/058)	298166/-	6000.00	One Month	350/-	Class -D
44.	Improvement of Bodh Ganoh road Km 0/00 to 6/00 (SH: providing and laying granular sub base 63mm to 45mm, wearing grade-III 53mm to 22.40 mm and 30mm thick bitumeneous concrete at RD 5/060 to 5/110)	190310/-	4000.00	One Month	350/-	Class -D
45.	A/R & M/O Nurpur to sanjha nalla road KM 0/00 to 15/390 (SH: Repair of pot holes Km 1/800 to 2/900)	427008/-	10000.00	One Month	350/-	Class -D
The contractors/firms should possess the following documents (Photocopy to be attached) :-						
1	The contractor/Firms should be enlisted with the HPPWD.					
2	PAN (Permanent Account No.)					
3	Registration under GST					
4	The Earnest money in the shape of National Saving certificate / time deposit account in any of the post office in HP FDR from any nationalized bank duly pledged in favour of the Executive Engineer Nurpur Division HPPWD Nurpur.					
5	The earnest money and cost of tender form for the above works should be submitted with the application for the purchase of tender form. The application received without earnest money & cost of tender form shall summarily be rejected.					
6	The offer of tender shall remain valid upto 75 days after the opening of tender.					
7	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case and will be summarily be rejected.					
8	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s)					
9	If the date given above happens to be holiday the same shall be processed on next working day.					
10	The contractor/firm must quote their rates in words as well as in figures failing which XEN reserves the right to accept/reject any or all tenders.					
11	The tenders forms shall not be issued to those contractors /firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.					
12	One contractor should not have more than two or more works in hand at a time.					
13	Work should be completed by the contractor within stipulated period.					
14	The rates beyond over +5% will be rejected besides this the additional performance security will have to borne at 20% & 30% for unbalanced bid in case rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively. The tender beyond the limit of 30% will also be excepted.					

HIM SUCHNA AVAM JAN SAMPARK.

(Signature)
Executive Engineer,
Nurpur Division, HPPWD, Nurpur,
Telephone No. 01893-220033
e-mail- ee-nur-hp@nic.in
On behalf of Governor of Himachal Pradesh

CERTIFICATE

It is certified that the tenders called vide this office letter No. PWN/CB/2nd C/Tender/2024-25/1259-79 dated 15.07.2024 are urgent in nature and also in the public interest.


Executive Engineer.
Nurpur Division, HPPWD,
Nurpur,

SCHEDULE OF QUANTITY
Name of work:- A/R & M/O Khushinagar Minigram road km 0/0 to 12/00
(SH:- Repair of pot holes and patches at R.D. 8/00 to 11/00)

Estimated:-Rs. 498600.00
Earnest Money :- Rs.10000.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter	1700.00	Rupees one thousand seven hundred only.	Per cubic meter	8500.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilograme) . per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilograme) per ten square metre and seal coal type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilograme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	1300.00 square meter	377.00	Rupees three hundred sixty eight only	Per square meter	490100.00
				Total		498600.00

(Signature)
Executive Engineer
Nurpur Divy (HPPWD)
Nurpur

SCHEDULE OF QUANTITY
Name of work:- A/R & M/O Nurpur to Kopra road km 0/0 to 6/00
(SH:- Repair of pot holes and patches at RD. 0/00 to 2/00 and 4/0 to 5/0)

Estimated:-Rs. 424527.00
Earnest Money :- Rs.10000.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	7.00 cubic meter	1700.00	Rupees one thousand seven hundred only .	Per cubic meter	11900.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilogramme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogramme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity-ten) at the rate of 6.80 kg (six point eighty kilogramme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	1094.50 square meter	377.00	Rupees three hundred sixty eight only	Per square meter	412627.00
			Total			424527.00

Engr-14
Executive Engineer
Nurpur Divy HPPWD
Nurpur


SCHEDULE OF QUANTITY

Name of work: Construction of link road to village Samola km 0/0 to 1/500 (SH Providing and laying wearing grade-III and 20mm thick premix carpet with seal coat from Km. 0/050 to 0/350)

Estimated:-Rs. 475440.00
 Earnest Money :- Rs.10000.00
 Time Limit:- One Month

Sr. No	Description of Items	Quantity	Rate in		Unit	Amount
			figure	Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	72.00 cubic meter	1750.00	Rupees one thousand seven hundred ninety only	Per cubic meter	126000.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on the prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer at the rate of 0.85 kg (zero point eight five kilogram) per square meter, using mechanical means as per technical specifications clause No. 502 including hauling of materials in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	960.00 Square meters	53.00	Rupees fifty three only	Per square meter	50880.00
3	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor on the prepared surface of granular base treated with primer and including cleaning of road surface with hydraulic broom and spraying tack coat at the rate of 0.275 kg. (zero point two two five kilogram) per Square metre using mechanical means as per technical specifications clause No. 503 including hauling of materials in all leads, lifts and as per entire satisfactions and directions of Engineer-in-charge including carriage of materials.. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	960.00 Square meters	29.00	Rupees twenty nine only	Per square meter	27840.00

4	Providing, laying and rolling of open graded premix carpet of 20mm (twenty millimeter) compacted thickness composed of Type-A 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate at the rate of 0.27cum (zero point two seven cubic metre), per ten square meter mixed with bitumen VG-10 (viscosity grade-10) at the rate of 14.60 Kg. (fourteen point six zero kilogram) per ten square metre of road surface, to the required line, grade and level to serve as wearing course on a previously prepared base, including mixing and heating, binder and aggregate in Hot Mix Plant 30/40 (thirty / forty) tonne per hour capacity, transporting mixed materials with tipper and laying with paver finisher to the required grade and camber and rolling with a three Wheel 80-100 (eighty-hundred) KN static road roller capacity finished to required level and grade to be followed by seal coat as per technical specifications clause No. 508 including hauling of materials in all leads, lifts as per the entire satisfaction and direction of Engineer – in-Charge including carriage of materials. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	960.00 Square meters	210.00	Rupees two hundred ten only	Per square meter	201600.00
5	Providing and laying seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 premixed with 6.80 kg (six point eight zero kilogram) VG-10 (viscosity grade-10) premixed with 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) including hauling of materials in all leads, lifts as per the entire satisfaction and direction of Engineer – in-Charge including carriage of materials. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	960.00 Square meters	72.00	Rupees seventy two only	Per square meter	69120.00
				Total		475440.00


 Executive Engineer
 Nupur Divya HPPWD.
 Aunpur

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Bodh Chakki Dhar road km 0/0 to 8/00
(SH:- Repair of pot holes and patches at RD. 5/00 to 8/00) (~~One Deposit~~)

Estimated:-Rs. 497658.00
Earnest Money :- Rs.10000.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter	1700.00	Rupees one thousand seven hundred only .	Per cubic meter	8500.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilogramme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogramme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilogramme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	1297.50 square meter	377.00	Rupees three hundred sixty eight only	Per square meter	489158.00
				Total		497658.00

(Signature)
Executive Engineer
Nurgur Divd HPPWD,
Nurgur


SCHEDULE OF QUANTITY

Name of work: Const. of link road to Harijan Basti Chandrabhan road
(SH C/O Causeway at RD. 0/250 to 0/258 and cement concrete at RD 0/620 to 0/632)

Estimated:-Rs. 367341.00
Earnest Money :- Rs. 7300.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			Figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer-In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	16.28 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	5925.00
2	Construction of granular sub-base by providing well graded materials, spreading in uniform layers with tractor mount grader with rotavator at OMC, and compacting with three Wheel 80-100 (Eighty-hundred) K N static roller to achieve the desired density, complete as per Technical Specification Clause 401 for grading-I Material, as per the entire satisfaction and directions of Engineer-in-Charge . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.44 cubic meter	1340.00	Rupees one thousand three hundred forty only .	Per cubic meter	9970.00
3	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	7.44 cubic meter	4450.00	Rupees four thousand four hundred fifty only	Per cubic meter	33108.00
4	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement: three sand: six graded /crushed stone aggregate 40mm) (forty millimeters) nominal size in or under water and curing complete including pumping, or bailing out water . dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental . The rate including octroi, royalty, Mallana, toll tax, G ST or other taxes imposed by the Government	48.50 cubic meter	4850.00	Rupees four thousand eight hundred fifty only	Per cubic meter	235225.00

5	Providing and laying mechanically mixed and vibrated cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (one cement: two sand: four graded and stone aggregate 20mm (twenty millimeters) nominal size for plain reinforced concrete including cost of form work curing in bed block complete as per drawings and MORD technical specifications etc. use 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including cartage of materials within all leads and lifts and other incidentals. The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	15.25 cubic meter	5450.00	Rupees five thousand four hundred fifty only	Per cubic meter	83113.00
						367341.00


 Executive Engineer
 Nurgur Divn (PPWD)
 Patpur

SCHEDULE OF QUANTITY
Name of work: Const. of link road to Harijan Basti Chandranan road
(SH C/O Causeway at RD. 0/640 to 0/660)

Estimated:-Rs. 367341.00
 Earnest Money :- Rs. 7300.00
 Time Limit:- one Month

Sr. No	Description of Items	Quant	Rate (in Rupees)		Unit	Amount
		ity	Figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	16.28 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	5925.00
2	Construction of granular sub-base by providing well graded materials, spreading in uniform layers with tractor mount grader with rotavator at OMC, and compacting with three Wheel 80-100 (Eighty-hundred) K N static roller to achieve the desired density, complete as per Technical Specification Clause 401 for grading-1 Material, as per the entire satisfaction and directions of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.44 cubic meter	1340.00	Rupees one thousand three hundred forty only.	Per cubic meter	9970.00
3	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	7.44 cubic meter	4450.00	Rupees four thousand four hundred fifty only	Per cubic meter	33108.00
4	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement; three sand; six graded /crushed stone aggregate 40mm) (forty millimeters) nominal size in or under water and curing complete including pumping, or bailing out water, dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	48.50 cubic meter	4850.00	Rupees four thousand eight hundred fifty only	Per cubic meter	235225.00

5	Providing and laying mechanically mixed and vibrated cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (one part cement two sand four graded crushed stone aggregate 20mm (twenty millimeters) nominal size for Road reinforced concrete including cost of form work curing in bed block complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, Malkana, toll tax, G S T or any other taxes imposed by the Government.	15.25 cubic meter	₹450.00	Rupess Five thousand four hundred only	Per cubic meter	8313.00
						367341.00


64-14
 Executive Engineer
 Nurpur Division HPPWD
 Kurpur

SCHEDULE OF QUANTITY

Name of work: Construction of link road from Bhul Thakran Patwar Khanna to Jogi Mohalla Janglahar road
(SH : Construction of cement concrete pavement from RD. 1/085 to 1/160)

Estimated:-Rs. 477150.00
Earnest Money :- Rs. 10000.00
Time Limit:- Two Month

Sr. No	Description of Items	Quant ity	Rate (in Rupees)		Unit	Amount
			In figure	In Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight-ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	90.00 cubic meter	85.00	Rupees eighty five only	Per cubic meter	7650.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1 : 4 : 8 (one cement : four sand : eight graded crushed /broken stone aggregate 40mm (forty millimeter) nominal size in open foundation . in or under water including pumping or bailing out water, dewatering, removal of slush as required at site, which may arise at the time of laying under water complete as per drawings and M.O.R.D. technical specifications Clause 802, 803, 1202, and 1203 as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	30.00 cubic meter	4450.00	Rs. Four thousand four hundred fifty only	Per cubic meter	133500.00
3	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in foundation and plinth complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer – in-Charge including carriage of materials within all leads and lifts and other incidental .. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	60.00 cubic meter	5600.00	Rs. Five thousand six hundred seventy five only	Per cubic meter	336000.00
				Total		477150.00


Executive Engineer
Nurpur Division (HPPWD)
Nurpur

SCHEDULE OF QUANTITY

Name of work: Construction of link road from Bhol Thakran Patwar Khanna to Joyi Mohalla Janglahar road
(SH : Construction of cement concrete pavement from RD. 0/790 to 0/805 and 1/015 to 1/075)

Estimated:-Rs. 477150.00
Earnest Money :- Rs. 10000.00
Time Limit:- Two Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In figure	In Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level. watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight -ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	90.00 cubic meter	85.00	Rupees eighty five only	Per cubic meter	7650.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1 : 4: 8(one cement : four sand : eight graded crushed /broken stone aggregate 40mm (forty millimeter) nominal size in open foundation . in or under water including pumping or bailing out water, dewatering, removal of slush as required at site, which may arise at the time of laying under water complete as per drawings and M.O.R.D. technical specifications Clause 802, 803, 1202, and 1203 as per drawing and technical specification clause 802,803, 1202, 1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax. G.S.T or other taxes imposed by the Government	30.00 cubic meter	4450.00	Rs. Four thousand four hundred fifty only	Per cubic meter	133500.00
3	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in sed block complete as per drawings and MORDD technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	60.00 cubic meter	5600.00	Rs. Five thousand six hundred seventy five only	Per cubic meter	336000.00
				Total		477150.00

(Signature)
Executive Engineer
Nurpur Divn (MPPWD)
Harpur.

Name of work: Construction of link road from Bhul Thakran Patwar Khanna to Jogi Mohalla Janglahar road
(SH Providing and laying soling grade-I 90mm o 45mm , wearing 53mm to 22.45mm in km.
0/700 to 0/790 and 0/805 to 1/0158)

SCHEDULE OF QUANTITY

Estimated:-Rs. 354968.00

Earnest Money :- Rs. 7300.00

Time Limit:- Two Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In figure	In Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight -ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	360.00 cubic meter	85.00	Rupees eighty five only	Per cubic meter	30600.00
2	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness using template hand packing, rolling with three wheel 80-100 (eighty / hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, cum (zero point two seven cubic metres) per ten square metres, and binding materials at the rate of 0.27 zero point zero eight cubic meter) to fill up the intersices of coarse aggregate, watering and compacting to the required density grading -I, 90mm to 45mm (ninety millimeters to forty five millimeters) size, 100mm (hundred millimeters) compacted thickness as per technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	100.50 cubic meter	1575.00	Rupees one thousand five hundred seventy five only	Per cubic meter	158288.00
3	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static cum (zero point two two cubic metres) per ten square metres, to fill up the intersices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres) sizes, 100mm (one hundred millimeters) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	96.00 cubic meter	1730.00	Rupees one thousand seven hundred thirty only	Per cubic meter	166080.00
				Total		354968.00

Executive Engineer
Nurpur
Nurpur
Nurpur


HPPWD

Name of work: Construction of link road Kherian to Jara via Khatloon road
(SH : Construction of cement concrete pavement from RD. 0/055 to 0/100)

SCHEDULE OF QUANTITY

Estimated:-Rs. 286290.00
Earnest Money :- Rs. 6000.00
Time Limit:- Two Month

St. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight -ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	54.00 cubic meter	85.00	Rupees eighty five only	Per cubic meter	4590.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1 : 4: 8(one cement : four sand : eight graded crushed /broken stone aggregate 40mm (forty millimeter) nominal size in open foundation . in or under water including pumping or bailing out water, dewatering, removal of slush as required at site, which may arise at the time of laying under water complete as per drawings and M.O.R.D. technical specifications Clause 802, 803, 1202, and 1203 as per drawing and technical specification clause 802,803, 1202, 1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	18.00 cubic meter	4450.00	Rs. Four thousand four hundred fifty only	Per cubic meter	80100.00
3	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in foundation and plinth complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental .. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	36.00 cubic meter	5600.00	Rs. Five thousand six hundred seventy five only	Per cubic meter	201600.00
				Total		286290.00


Executive Engineer
Nurpur District (HPPWD)
Nurpur


Name of work: Const. of link road from Kopra to H.rijan Basti Meht road km 0/000 to 2/650
(S11 C/O 900mm dia Hume pipe culvert at RD 1/410 and earth work at RD 0/045 to 0/210)

SCHEDULE OF QUANTITY
Estimated:-Rs. 445934.00
Earnest Money :- Rs.100000.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area by in ordinary / hard rock (blasting prohibited) with rock breakers by mechanical means including cutting and trimming of sides slopes / breaking rock loading in tippers and disposing of excavated earth upto any lift and leads as per technical specification clause 302.3.5 including shoring and strutting and pumping and bailing out water (surface and sub soil water) complete as per entire satisfaction and as per the direction of Engineer-in-Charge Including carriage of materials within all leads and lifts and other incidental	756.43 cubic meter	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic meter	219478.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In – Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	39.88 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	14516.00
3	Providing and laying 1:3:6 (one cement: three sand: six graded /crushed stone aggregate 20mm nominal size in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work in plain/ reinforced concrete for open foundation complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	1.84 cubic meter	4450.00	Rupees four thousand four hundred fifty only	Per cubic meter	8188.00
4	Providing and laying mechanically mixed and vibrated cement concrete grade M-15(M-fifteen) in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form in Toe walls complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	12.90 cubic meter	5125.00	Rupees five thousand one hundred twenty five only	Per cubic meter	66113.00

	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement: five sand: ten graded crushed stone aggregate 40mm (four millimeters) nominal size in or under water including curing, complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	18.96 cubic meter	3750.00	Rupees three thousand seven hundred fifty only		71100.00
6	Providing weep holes in brick masonry / stone masonry, plain / reinforced concrete abutment, wing wall, return wall with 100mm dia P.V.C. pipe extending through the full width of the structures with slope of (1V) 20(H) towards drawing face complete including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	8.00 Number	305.00	Rupees three hundred five only	Each	2440.00
7	Back filling with stone boulder behind abutment, retaining walls, and return walls etc. compacted to firm condition complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	7.65 cubic meter	950.00	Rupees nine hundred fifty only	Per cubic meter	7268.00
8	Providing and laying mechanically mixed and vibrated cement concrete grade M-15 (M-fifteen) in or under water and curing complete including pumping, or bailing out water, dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form in cradle bedding complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	1.70 cubic meter	5225.00	Rupees five thousand two hundred twenty five only	Per cubic meter	8883.00
8	Providing and laying to level o slope 900mm (nine hundred millimeters) dia meter reinforced cement concrete pipes NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding the cost of excavation, protection work, back filling concrete and masonry work in head walls and parapets a per drawing and M O R D technical specification clause 1108 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	10.00 running meter	4600.00	Rupees four thousand six hundred only	Per running meter	46000.00
10	Filling with earth marshy soil in foundation trenches as per drawing and technical specifications clause 305.3.9 and as per the direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	7.6 cubic meter	110.00	Rupees one hundred ten only	Per cubic meter	836.00

Providing and laying cement concrete 1:2:4 (one cement: two sand : four graded broken /crushed stone aggregate 40mm(forty millimeters) nominal size vibrate 1 and mechanically mixed and curing complete excluding the cost of centering and shuttering in all work upto plinth level and as per approved drawing ,design including carriage of materials within all leads . lifts and other incidentals The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	0.19 cubic meter	5850.00	Rupees five thousand eight hundred fifty only Total	Per cubic meter	1112.00 445934.00
---	------------------------	---------	--	-----------------------	----------------------



 Executive Engineer
 Nurgur Divd HPWD,
 Bhatpur

SCHEDULE OF QUANTITY
Name of work: Const. of link road from Kopra to Harijan Basti Mehtu road km 0/000 to 2/650
(SIH C/O 900mm dia Hume pipe culvert at RD 1/532 and 1/895)

Estimated:-Rs. 357608.00
Earnest Money :- Rs. 7200.00
Time Limit:- one Month

Sr. No	Description of Items	Quant ity	Rate (in Rupees)		Unit	Amount
			Figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	59.82 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	21774.00
2	Providing and laying 1:3:6 (one cement: three sand: six graded /crushed stone aggregate 20mm nominal size in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work in plain/ reinforced concrete for open foundation complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	2.8 cubic meter	4450.00	Rupees four thousand four hundred fifty only	Per cubic meter	12460.00
3	Providing and laying mechanically mixed and vibrated cement concrete grade M-15(M-fifteen)in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form in Toe walls complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	19.8 cubic meter	5125.00	Rupees five thousand one hundred twenty five only	Per cubic meter	101475.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size. in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	32.5 cubic meter	3750.00	Rupees three thousand seven hundred fifty only		121875.00

5	Providing weep holes in brick masonry / stone masonry, plain / reinforced concrete abutment, wing wall, return wall with 100mm dia P.V.C. pipe extending through the full width of the structures with slope of 1(V) 20(H) towards drawing face complete including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	12.00 cubic meter	305.00	Rupees three hundred five only	Each	3660.00
6	Back filling with stone boulder behind abutment, retaining walls, and return walls etc. compacted to firm condition complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	11.6 cubic meter	950.00	Rupees nine hundred fifty only	Per cubic meter	11020.00
7	Providing and laying mechanically mixed and vibrated cement concrete grade M-15 (M-fifteen) in or under water and curing complete including pumping, or bailing out water, dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form in cradle bedding complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	2.55 cubic meter	5225.00	Rupees five thousand two hundred twenty five only	Per cubic meter	13324.00
8	Providing and laying to level o slope 900mm (nine hundred millimeters) dia meter reinforced cement concrete pipes NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding the cost of excavation, protection work, back filling concrete and masonry work in head walls and parapets a per drawing and M O R D technical specification clause 1108 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	15.00 running meter	4600.00	Rupees four thousand six hundred only	Per running meter	69000.00
8	Filling with earth marshy soil in foundation trenches as per drawing and technical specifications clause 305.3.9 and as per the direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	11.50 cubic meter	110.00	Rupees one hundred ten only	Per cubic meter	1265.00
10	Providing and laying cement concrete 1:2:4 (one cement: two sand : four graded broken /crushed stone aggregate 40mm(forty millimeters) nominal size vibrated and mechanically mixed and curing complete excluding the cost of centering and shuttering in all work upto plinth level and as per approved drawing ,design including carriage of materials within all leads, lifts and other incidentals The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	0.3 cubic meter	5850.00	Rupees five thousand eight hundred fifty only	Per cubic meter	1755.00
				Total		357608.00


 Executive Engineer
 Nurpur Division HPPWD,
 Patna

SCHEDULE OF QUANTITY
Name of work: Construction of link road to village Hangera km 0/00 to 1/00 (SH: Construction of cement concrete pavement at RD 0/00 to 0/065)

Estimated:-Rs. 297648.00
Earnest Money :- Rs. 6000.00
Time Limit:- Two Month

Sr. No	Description of Items	Quant ity	Rate (in Rupees)		Unit	Amount
			In figure	In Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight -ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	62.40 cubic meter	85.00	Rupees eighty five only	Per cubic meter	5304.00
2	Construction of granular sub-base by providing well graded materials, spreading in uniform layers with tractor mount grader with rotavator at OMC, and compacting with three Wheel 80-100 (Eighty-hundred) K N static roller to achieve the desired density, complete as per Technical Specification Clause 401 for grading-I Material, as per the entire satisfaction and directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	20.80 cubic meter	1375.00	Rupees one thousand six hundred eighty five only	Per cubic meter	28496.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1 : 4: 8 (one cement : four sand : eight graded crushed /broken stone aggregate 40mm (forty millimeter) nominal size in open foundation . in or under water including pumping or bailing out water, dewatering, removal of slush as required at site, which may arise at the time of laying under water complete as per drawings and M.O.R.D. technical specifications Clause 802, 803, 1202, and 1203 as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	20.80 cubic meter	4450.00	Rs. Four thousand four hundred twenty five only	Per cubic meter	92556.00
4	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in foundation and plinth complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental .. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	21.20 cubic meter	5450.00	Rs. Five thousand six hundred seventy five only	Per cubic meter	170040.00
				Total		297648.00


Executive Engineer
Nurpur Divd HPPWD
Nurpur.

SCHEDULE OF QUANTITIES

Name of work: Construction of link road Panjhara Adhula Barswahan road to Harjan Basti Chamla road
(SIT: Providing and laying wearing grade-II at R.D. 0/315 to 0/465 and cement concrete pavement from RD 0/265 to 0/315)

Estimated:-Rs. 304200.00
Earnest Money :- Rs. 6290.00
Time Limit:- Two Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In figure	In Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight-ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	192.00 cubic meter	85.0	Rupees eighty five only	Per cubic meter	16320.00
2	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 0.20 cum (zero point two zero cubic metres) per ten square meters, and binding materials at the rate of 0.06 cum (zero point zero six cubic metre) per ten square meter to fill up the interstices of coarse aggregate, watering and compacting to the required density grading-II, 63mm to 45mm (sixty three millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	48.00 cubic meter	1685.00	Rupees one thousand six hundred eighty five only	Per cubic meter	80880.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1 : 4 : 8 (one cement : four sand : eight graded crushed/broken stone aggregate 40mm (forty millimeter) nominal size in open foundation. in or under water including pumping or bailing out water, dewatering, removal of slush as required at site, which may arise at the time of laying under water complete as per drawings and M.O.R.D. technical specifications Clause 802, 803, 1202, and 1203 as per drawing and technical specification clause 802, 803, 1202, 1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	16.00 cubic meter	4425.00	Rs. Four thousand four hundred twenty five only	Per cubic meter	70800.00
4	Providing and laying mechanically mixed and vibrated cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (one cement: two sand: four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in feed block complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental .. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	24.00 cubic meter	5675.00	Rs. Five thousand six hundred seventy five only	Per cubic meter	136200.00
	Total					304200.00

(Signature)
Executive Engineer
Nurpur Dist. HPPWD
Nurpur.

SCHEDULE OF QUANTITIES

Name of work :- Construction of link road Panjhara Adhala Barswalan road to Harijan Basti Ganoh road
(SH: Construction of 1.00 meter span RCC slab culvert at RD. 0/265)

Estimated cost Rs. 337633.00
Earnest money Rs. 6800.00
Time limit :- Three month

Sr. No.	Description of items	Qty.	Rate in Figures	Words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	32.97 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	12001.00
2	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement: three sand: six graded /crushed stone aggregate 40mm) (forty millimeters) nominal size in or under water and curing complete including pumping, or bailing out water, dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	12.68 cubic meter	4590.00	Rupees four thousand five hundred ninety only	Per cubic meter	58201.00
3	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in sub structure for all type of structure complete of plain cement concrete grade M-15 (M-fifteen) nominal mix 1:2½:5 (one cement: two and half sand : five graded crushed stone aggregate 20mm (twenty millimeters) including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 804, 805, 806 , 807 1202 and 1204 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G.S.T. or other taxes imposed by the Government	30.93 cubic meter	5225.00	Rupees five thousand two hundred twenty five only	Per cubic meter	161609.00
4	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	10.00 Number	305.00	Rupees three hundred five only	Each	3050.00
5	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in sub structure for all type of sub-structure complete of plain cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (one cement: two sand : four graded crushed stone aggregate 20mm (twenty millimeters) including cost of form work in bed block and dirt wall as per drawings and M.O.R.D. technical specifications clause 802, 804, 805, 806 , 807 1202 and 1204 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G.S.T or other	2.45 cubic meter	6125.00	Rupees six thousand one hundred twenty five only	Per cubic meter	15006.00

taxes imposed by the Government					
6	Supplying, fitting and placing HYSD bar reinforcement in super structures complete as per drawing and technical specification clause 1002, 1010 and 1202 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	0.486 metric tonne	87525.00	Rupees eighty seven thousand five hundred twenty five only	Per metric tonne 42537
7	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete for all type of structure complete of plain cement concrete grade M-30 nominal mix (1:1½:3 (one cement: one and half sand : three graded /crushed stone aggregate 20mm (twenty millimeters) nominal size, and curing complete including cost of form work excluding cost of reinforcement in super structures as per drawing and technical specifications clause 800 and 1205.4, and 1205.5 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	3.60 cubic meter	7317.00	Rupees seven thousand three hundred seventeen only	Per cubic meter 26341.00
8	Providing and laying mechanically mixed and vibrated cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in floors etc. complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental .. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	0.29 cubic meter	5850.00	Rupees five thousand eight hundred fifty only	Per cubic meter 1696.00
9	Providing and laying mechanically mixed and vibrated reinforced cement of nominal mix (1:1:2 :one cement; one sand : two graded crushed stone aggregate 20mm (twenty millimeters) nominal size, grade M-30 (M-thirty) and curing complete in wearing course including reinforcement and cost of form work as per drawing and M.O.R.D. technical specifications clause 800 and 1206.3 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	0.94 cubic meter	15592.00	Rupees fifteen thousand five hundred ninety two only	Per cubic meter 14656.00
10	Back filling with stone boulder behind abutment, retaining walls, and return walls etc. compacted to firm condition complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	2.67 cubic meter	950.00	Rupees nine hundred fifty only	Per cubic meter 2536.00
			Total		337633.00


Schedule of Quantity
Name of Work :- Construction of Veterinary Hospital /Go-Sadam Khajlan Utsil Nurpur Dist/ Kangra HP
(Site Construction of Water Tank)

Estimated Cost :- Rs.338512.00
 Earnest Money : Rs. 6800.00

Time Limit Two month

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	87.50 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	31850.00
2	Providing form work with steel plates 3.15mm (Three point one five millimeters) thick welded with angle iron in frames 30x30x5mm (Thirty into thirty into five millimeters) so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, heights of propping and centering in all heights below supporting floor to ceiling upto any heights and removal of the same for in-situ-reinforced concrete and plain concrete work in: Lintel, Beams, cantilevers, girders and lintels, sides and soffits of beams, beam haunchings, cantilevers, girders, bressumers and lintels upto any heights/ depths upto all floor level including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, G S T malkana and all other taxes as imposed by the Government.	17.64 Square Metre	387.15	Rupees three hundred eighty seven and paise fifteen only	Per Square Metre	6829.00
3	Providing form work with steel plates 3.15mm (Three point one five millimeters) thick welded with angle iron in frames 30x30x5mm (Thirty into thirty into five millimeters) so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, heights of propping and centering in all heights below supporting floor to ceiling upto any heights and removal of the same for in-situ-reinforced concrete and plain concrete work in: Flat surfaces such as soffits of suspended floors, roofs, landing and the like upto any thickness / heights/ depths upto all floor level including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, G S T malkana and all other taxes as imposed by the Government.	50.40 Square Metre	468.30	Rupees four hundred sixty eight and paise thirty only	Per Square Metre	23602.00
4	Boulder filling tightly hand packed with hard stone under floor complete as directed by the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental charges. The rate including of octroi, royalty, Malkana, toll tax, G.S.T. or other taxes imposed by the Government.	3.53 cubic meter	1200	Rupees twelve hundred only	Per cubic meter	4234.00
5	Providing and laying cement concrete 1:5:10 (one cement, five sand : ten graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete excluding the cost of form work in foundation and plinth in all depths	3.65 cubic meter	3750.00	Rupees three thousand seven hundred fifty only	Per cubic meter	13703.00
6	Randum rubble masonry polygonal rubble masonry (uncoursed / brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement: six	29.20 cubic	5425.00	Rupees five thousand four	Per cubic	158401.00

	sand : twelve graded stone aggregate 20mm nominal size) a plinth level in cement mortar 1:6 (one cement: six sand) and curing complete including carriage of materials within all leads and lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST or any other taxes imposed by the Government.	meters		hundred twenty five only	meter	
7	Providing and laying mechanically mixed and vibrated cement concrete 1:2:4 (One cement : two sand : four graded crushed stone aggregate 20mm (Twenty millimetres) nominal size) mix designed, so as to give a compressive strength corresponding to RCC Grade M-20 (M-Twenty) including curing complete as per H.P.W.D. specification or as directed by Engineer-in-Charge, excluding the cost of form work and reinforcement for reinforced concrete work in independent piers, columns, and pillars in all depths/thickness upto all floor level, including carriage of materials within all leads and lifts and other incidentals. The rate includes, royalty charges, octroi, G S T, malkhana and all other taxes as imposed by the Government.	7.28 Cubic Metres	6234.10	Rupees six thousand two hundred thirty four and paisa ten only	Per Cubic Metre	45372.00
8	Providing and laying Mild steel/ tor steel reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all heights including cost of binding wires and other incidentals due for its completion complete and carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, G S T, malkhana and all other taxes as imposed by the Government.	375.00 Kilograms	98.50	Rupees ninety eight and paisa fifty only	Per Kilograms	36938.00
9	15mm (fifteen millimetres) thick cement plaster with cement mortar 1:6 (One cement : six sand) in single coat on fair side of brick/ concrete/ stone walls for interior plastering upto floor all level including arrises, internal rounded angles, chamfers and/or rounded angles in all girth and finished even and smooth complete, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, G S T, malkhana and all other taxes as imposed by the Government.	58.80 Square Metres	265.00	Rupees two hundred sixty five only	Per Square Meter	15582.00
10	Brick work using Second class common burnt clay building bricks in super structure above plinth level upto all heights/ floor level in cement mortar 1:6 (One cement : six sand) and curing complete upto all floor level including carriage of materials within all leads and lifts and other incidental charges.	0.07 Cubic Metres	6164.00	Rupees Six thousand one hundred sixty four only	Per Cubic Meter	451.00
11	Providing and fixing cast iron cover with frame (light duty single seal pattern-1) 455 x 610mm (four hundred fifty five into six hundred ten millimeters) internal dimension total weight of cover and frame to be not less than 38 kg. (thirty eight kilogramme) (Weight of cover 23 kg. (twenty three kilogramme) and weight of frame 15 kg.)(fifteen kilogramme) with 300mm (three hundred millimeters) thick walls of square rubble masonry coursed with hard stone of approved quality in cement mortar 1:3(one cement; three sand) complete including carriage of material within all leads and lifts and other incidentals	1.00 Number	1550.00	Rupees one thousand five hundred fifty only	Per Square Meter	1550.00
			Total			338512.00


 Executive Engineer
 Nurpur Divisional PWD
 Nurpur

Work:- A/R & M/O on Mohali Indora A-11 Pucca Tiyala road km. 10/00 to 19/260 (SH: Repair of pot holes and patches in km. at RD 17/00 to 18/00
 of MMSRRY 2024-25)

SCHEDULE OF QUANTITY

Estimated:-Rs. 216152.00
 Earnest Money :- Rs 4500.00
 Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter	1700.00	Rupees one thousand seven hundred only .	Per cubic meter	8500.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero kilogram) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogram) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilogram) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	550.80 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	207652.00
			Total			216152.00


 Executive Engineer
 Nurpur Divya HPPWD\

SCHEDULE OF QUANTITY

of work:- A/R & M/O on Mohitahi Indora A-II Pucca Tiyaala road km. 10/00 to 19/260 (SH: Repair of pot holes and patches in km. at RD 18/00 to 19/00 under MMSRRY 2024-25)

Estimated:-Rs. 197754.00
Earnest Money :- Rs 4000.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter	1700.00	Rupees one thousand seven hundred only,	Per cubic meter	8500.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero kilograme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilograme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilograme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	502.00 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	189254.00
			Total			197754.00


Executive Engineer
Nurpur Division HPWD
Nurpur

SCHEDULE OF QUANTITY

Work:- A/R & M/O on Gangath to Dadoh Face-1 km. 0/00 to 5/00 (SH: Repair of pot holes and patches in km. at RD 2/00 to 3/00.
(Under MMSRRY 2024-25)

Estimated:-Rs. 156089.00
Earnest Money :- Rs 300.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading-III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	3.00 cubic meter	1700.00	Rupees one thousand seven hundred only .	Per cubic meter	5100.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilogramme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogramme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilogramme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	400.50 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	150989.00
			Total			156089.00

(Signature)
Executive Engineer
Nurpur Division (HPPWD)
Nurpur

SCHEDULE OF QUANTITY

Work:- A/R & M/O On Lagor to Gaimhi km 0/00 1/870 (SH: Repair of pot holes and patches in km. at RD 0/00 to 1/00
(Under MMSRRY 2024-25)

Estimated:-Rs. .156352.00
Earnest Money :- Rs 300.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	3.00 cubic meter	1700.00	Rupees one thousand seven hundred only .	Per cubic meter	5100.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilogramme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogramme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilogramme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	401.20 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	151252.00
				Total		156352.00


Executive Engineer
Nupur Divya APPWD
Aurpur

SCHEDULE OF QUANTITY

of work:- A/R & M/O On Badhni to Galor Khas km. 0/00 to 6/00 (SH: Repair of pot holes and patches in km. at RD 4/00 to 5/00
(Under MMSRRY 2024-25)

Estimated:-Rs. 179089.00
Earnest Money :- Rs 3600.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the intersices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	4.00 cubic meter	1700.00	Rupees one thousand seven hundred only	Per cubic meter	6800.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilogram) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogram) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilogram) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	457.00 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	172289.00
			Total			179089.00


Alfred Khari
Executive Engineer
Nurpur Divn (PPWD)
Nurpur

SCHEDULE OF QUANTITY

Work:- A/R & M/O On Nurpur to Kulam via Chinwan km 0/00 to 5/00 (Silt: Repair of pot holes and patches in km. at RD 2/00 to 3/00)
(Under MMSRRY 2024-25)

Estimated:-Rs. 139689.00
Earnest Money :- Rs 3000.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -11 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres) sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	3.00 cubic meter	1700.00	Rupees one thousand seven hundred only .	Per cubic meter	5100.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero kilogram) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogram) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilogram) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	357.00 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	134589.00
				Total		139689.00


Executive Engineer
Nurpur Divn PPDWD
Nurpur

Name of work: Restoration of rain damages on Khajjan Jatoli Aund road km 0/0 to 6/200
(SH: Construction of cement concrete pavement from RD 4/998 to 5/050)

SCHEDULE OF QUANTITY

Estimated:-Rs. 204256.00
Earnest Money :- Rs. 4000.00
Time Limit:- One Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1 : 4 : 8 (one cement : four sand : eight graded crushed /broken stone aggregate 40mm (forty millimeter) nominal size in open foundation . in or under water including pumping or bailing out water, dewatering, removal of slush as required at site, which may arise at the time of laying under water complete as per drawings and M.O.R.D. technical specifications Clause 802, 803, 1202, and 1203 as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	16.64 cubic meter	4250.00	Rs. Four thousand two hundred fifty only	Per cubic meter	70720.00
2	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in bed block complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental .. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	24.96 cubic meter	5350.00	Rs. Five thousand three hundred fifty only	Per cubic meter	133536.00
			Total			204256.00

Schedule of quantity checked and approved for Rs. 204,256 only

(Signature)
Executive Engineer
Nurpur Divn./HPPWD
Nurpur.

SCHEDULE OF QUANTITY

Work:- A/R & M/O Boddh to Haral uppari km. 8/00 to 13/500
(Sub Head : Repair of pot holes at RD 12/00 to 13/00 (MMSRRY)

Estimated:- Rs. 253178.00
Earnest Money :- Rs.5100.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter	1750.00	Rupees one thousand seven hundred only .	Per cubic meter	8750.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilogramme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogramme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilogramme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	648.35 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	244428.00
			Total			253178.00


Executive Engineer
Nurpur Diya HPPWD
Nurpur

SCHEDULE OF QUANTITY

Work:- A/R & M/O Bodd to Haral upparti km. 8/00 to 13/500
(Sub Head : Repair of pot holes at RD 13/00 to 13/500 (MMSRRY)

Estimated:- Rs. 253385.00
Earnest Money :- Rs.5100.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter	1750.00	Rupees one thousand seven hundred only .	Per cubic meter	8750.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero kilogramme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogramme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilogramme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	648.90 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	244635.00
			Total			253385.00

(Signature)
Executive Engineer
Nurpur Divn HPPWD
Nurpur

SCHEDULE OF QUANTITY

Work:- A/R & M/O Mamoon to Gurchal to Ther Nihit Road km 0/00 to 2/00
(Sub Head : Repair of pot holes at RD 0/00 to 1/00 (MMSRRY)

Estimated:- Rs 159116.00
Earnest Money :- Rs.3200.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the intersices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter	1750.00	Rupees one thousand seven hundred only .	Per cubic meter	8750.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilograme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilograme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilograme) per ten square meter as per technical specification Clause 1904.2,503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	398.85 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	150366.00
				Total		159116.00

(Signature)
Executive Engineer
Nurpur Divy HPPWD/
Purpur

SCHEDULE OF QUANTITY

Work:- A/R & M/O suliati to Loharpura road km. 0/00 to 1/350
(Sub Head : Repair of pot holes at RD 0/700 to 1/350 (MMSRRY)

Estimated:- Rs 196873.00
Earnest Money :- Rs.4000.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter	1750.00	Rupees one thousand seven hundred only .	Per cubic meter	8750.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilogramme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogramme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilogramme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	499.00 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	188123.00
			Total			196873.00


Executive Engineer
Nurpur Divy/HPPWD/
Nurpur

SCHEDULE OF QUANTITY

name of work:- A/R & M/O Nurpur Lahru Tunuhatti road km. 0/00 to 15/390

(Sub Head : Repair of pot holes at RD 8/00 to 9/00 (MMSRRY)

Estimated:- Rs 152010.00
Earnest Money :- Rs.3100.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter	1750.00	Rupees one thousand seven hundred only	Per cubic meter	8750.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero kilogram) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogram) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilogram) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	380.00 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	143260.00
			Total			152010.00

(Signature)
Executive Engineer
Nurpur Divn HPPWD
Nurpur

SCHEDULE OF QUANTITY

Work:- A/R & M/O Sadwan to Suliali road km 0/00 to 5/200
(Sub Head : Repair of pot holes at RD 3/00 to 4/00 (MMSRRY)

Estimated:- Rs 178268.00
Earnest Money :- Rs.3100.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate		Unit	Amount
			Figure	Words		
1	Providing laying spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter	1750.00	Rupees one thousand seven hundred only.	Per cubic meter	8750.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilogramme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilogramme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilogramme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	449.65 square meter	377.00	Rupees three hundred seventy seven only	Per square meter	169518.00
			Total			178268.00

(NA-117)
Executive Engineer
Nurpur Divd HPPWD
Nurpur

258 30

SCHEDULE OF QUANTITY

Name of work :- Construction of link road to village Gyal km 0/0 to 0/080 (SH: Formation cutting and crate work at RD.0/060 to 0/065, C/O 900mm dia Hume pipe culvert at RD 0/075

Estimated cost Rs. 390336.00
Earnest money Rs. 10000 .00

Time limit :- Two month

Sr. No.	Description of items	Qty.	Rate in	Words	Unit	Amount
			Figures			
1	Excavation in soil in hilly area by in ordinary rocks by mechanical means including cutting and trimming of sides slopes and disposing of excavated earth upto any lift and leads as per technical specification clause 1603.2 including shoring and strutting and pumping and bailing out water (surface and sub soil water) complete as per entire satisfaction and as per the direction of Engineer-in-Charge Including carriage of materials within all leads and lifts and other incidental.	691.16 cubic meter	209.00	Rupees two hundred nine only	Per cubic meter	144452.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	34.06 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	12398.00
3	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement: three sand: six graded /crushed stone aggregate 40mm) (forty millimeters) nominal size in or under water and curing complete including pumping, or bailing out water, dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	1.95 cubic meter	4600.00	Rupees four thousand six hundred only	Per cubic meter	8970.0
4	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in sub structure for all type of structure complete of plain cement concrete grade M-15 (M-fifteen) nominal mix 1:2½:5 (one cement: two and half sand : five graded crushed stone aggregate 20mm (twenty millimeters) including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 804, 805, 806, 807 1202 and 1204 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	16.10 cubic meter	4950.00	Rupees four thousand nine hundred fifty only	Per cubic meter	79695.00

5	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	1.50 cubic meter	3625.00	Rupees three thousand six hundred twenty five only	Per cubic meter	5438.00
6	Providing and laying to level o slope 900mm (nine hundred millimeters) dia meter reinforced cement concrete pipes N/P-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding the cost of excavation, protection work, back filling concrete and masonry work in head walls and parapets as per drawing and M O R D technical specification clause 1108 and as per direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, malkana, toll tax, sale tax and other taxes imposed by the Government.	10.00 running meter	4650.00	Rupees four thousand six hundred fifty only	Per running meter	46500.00
7	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to I:S:280 and I:S 4826 in 100 mm x 100mm (hundred into hundred) mesh (woven diagonally) including 10% extra for lapse and joints laid with stone boulders weighting not less 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 as per directions of the Engineer-in-charge The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government	31.25 Cubic meter	3050.00	Rs. three thousand fifty only	Per cubic meter	95313.00
			Total			390336.00

Schedule of quantity checked & approved for Rs 390336/- only

(Signature)
Executive Engineer,
Nurpur Division HPPWD
Nurpur.

Name of work :- V/R & M/O Nupur to Sanjha Nalla road km 0.0 to 15/390 (SI)-Providing and laying 30mm thick bitumen concrete in patches in between km 1/200 to 1/800)

SCHEDULE OF QUANTITY

Estimated cost Rs.496948.00
Earnest money Rs.10000.00

Time Limit = One Month

Sr. No	Description of items.	Rates in			Unit	Amount
		Quantity	Figures	Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres) sizes 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 complete including carriage of materials within all leads and lifts and other incidental charges. The rate is including octroi, royalty, Malkana toll tax, G S T or other taxes imposed by the Government.	5.00 cubic meter	1750.00	Rupees One thousand Seven hundred fifty only	Per cubic meter	8750.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion pressure distributor at the rate of 0.225 kg. (zero point two two five kilogramme) per square meter on the prepared bituminous surface cleaned with hydraulic broom as per technical specifications 503 including hauling of materials in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental charges. The rate is including octroi, royalty, Malkana toll tax, G S T or other taxes imposed by the Government.	1505.45 square meter	29.00	Rupees Twenty Nine only	Per square meter	37858.00
3	Providing and laying 30mm (thirty millimeter) compacted thick bituminous concrete with minimum 40-60 TPH (forty -sixty tonne per hour) hot mix Batch type/ Drum type plant with electronic control grading-II using crushed aggregate 13mm (thirteen millimeter) nominal size of specified grading premixed with bituminous binder VG-30 ((viscosity grade-thirty) @ 5.40 to 5.60% (five point four zero to five point six zero percent) of mix weight transported to site, laid with censor paver finisher hydraulic with censor control to the required grade, level and alignment over a previously prepared surface and rolling complete with smooth Wheel roller 8-10 (eight to ten) tonne capacity for initial break down rolling and vibratory roller 8-10 (eight-ten) tonne capacity or pneumatic tyre roller of 12-15 (twelve- fifteen tonne) with tyre pressure of atleast 0.56 MPa (zero point five six) for intermediate rolling and finish rolling with 6-8 (six to eight) tonne smooth wheeled tandem roller to achieve the desired compaction as per MORTH technical specification clause 509 including hauling of materials in all leads, lifts and as per the direction and entire satisfaction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, G S T or other taxes imposed by the Government.	39.16 cubic meter	11500.0	Rupees eleven thousand five hundred only	Per cubic meter	450348.00
					Total	496948.00

Schedule of quantity checked and approved by 12/4/2018

Executive Engineer
Nupur Division HP PWD
Nupur

32

Name of work :- Construction of link road from Peer Baba Mandir to Divkeshwar Mandir road km.
0/0 to 1/0. (SH: Construction of V-shape drain with edge wall at RD 0/410 to 0/710)

Estimated cost Rs. 224948.00
Earnest money Rs. 5000.00
Time limit :- Two month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	60.00 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	21840.00
2	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement: three sand: six graded /crushed stone aggregate 40mm) (forty millimeters) nominal size in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 as per directions of Engineer-in-charge and including cartage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	44.25 cubic meter	4590.00	Rupees four thousand five hundred ninety only	Per cubic meter	203108.00
			Total			224948.00

Executive Engineer
Nurpur Divn HPPWD,
Nurpur

SCHEDULE OF QUANTITY
Name of work :- Restoration of rain damages on various roads under Suliali Sub Division HPPWD
Suliali (SH:- Hiring of Excavator-cum- loaders for removal of slips)

Estimated cost Rs.493500.00
 Earnest money Rs.10000.00

Time Limit= One Month

Sr. No	Description of items.	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Hiring of JCB/Backhoe Excavator –cum- loader for removal of slips or for cutting / widening work of road in all kinds of soils and disposing of all excavated earth or un serviceable materials from the road surfaces upto an y leads, lifts and upto any height an d depth as per directions and specifications of Engineer-in- Charge. Any loss to public / private property or any accidents etc. happened during the course of said period/ executions shall be absolute responsibility of the JCB/ Excavator owner. The fuel and operation staff of machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the contractor/ owner. The daily log book will be maintained at site, which should be duly verified by the Engineer in Charge. The rate including octroi royalty, malkana, toll tax, G S T or any other taxes imposed by the government.	470.00 Hour	1050.00	Rupees one thousand fifty only	Per Hour	493500.00
						493500.00

(Signature)
 Executive Engineer
 Nurgur Division HP PWD
 Nurgur

Name of work :- Restoration of rain damages on various roads under Nurpur Sub Division HPPWD
 Nurpur (SH:- Hiring of Excavator-cum- loaders for removal of slips)

Estimated cost Rs.493500.00
 Earnest money Rs.10000.00
 Time Limit= One Month

Sr. No	Description of items.	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Hiring of JCB/Backhoe Excavator –cum- loader for removal of slips or for cutting / widening work of road in all kinds of soils and disposing of all excavated earth or un serviceable materials from the road surfaces upto an y leads, lifts and upto any height an d depth as per directions and specifications of Engineer-in- Charge. Any loss to public / private property or any accidents etc. happened during the course of said period/ executions shall be absolute responsibility of the JCB/ Excavator owner. The fuel and operation staff of machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the contractor/ owner. The daily log book will be maintained at site, which should be duly verified by the Engineer in Charge. The rate including octroi royalty, malkana, toll tax, G S T or any other taxes imposed by the government.	470.00 Hour	1050.00	Rupees one thousand fifty only	Per Hour	493500.00
						493500.00

(Signature)
 Executive Engineer
 Nurpur Division HP PWD
 Nurpur

SCHEDULE OF QUANTITY

Restoration of rain damages on little road to village Sonkhra road km. 000 to 1/000 (SH : Const. of crate work at RD. 0/120 to 0/130)

Estimated: Rs. 195889.00

Earnest Money: Rs. 4000.00

Time Limit: one Month

Sl. No.	Description of Items	Quantity	Rate (in Rupees)	Unit	Amount (in Rupees)
			Figure		
1	Earth work for excavation for 2.25 of road structure such as retaining walls, breast walls, culverts, drains and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock dressing (wedging out rocks) (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer-In-Charge including setting out and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	15.53	762.00	Per cubic meter	5589.00
2	Providing and laying of boulder armor laid in wire crates with 4mm dia G.I. wire conforming to I.S. 2280 and I.S. 4826 in 100 mm x 100mm (hundred into hundred) mesh (woven diagonally) including 10% extra for lapse and joints laid with stone boulders weighing not less 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 as per directions of the Engineer-in-charge. The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	62.50	3000.00	Per cubic meter	187500.00
3	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structure graded and compacted to meet requirement of Tables 300.1 and 300.2 as per technical specifications clause 301.5 as per directions of Engineer-in-charge. The rates is including royalty, malkana, toll tax, G.S.T or any other taxes and carriage of materials within all leads and lifts and other incidental.	30.00	90.00	Per cubic meter	2700.00
				Total	195889.00

Schedule of quantity checked and approved for Rs. 195889.00 only

Executive Engineer
Nurpur Dist. (MPPWD)
Nurpur

SCHEDULE OF QUANTITY

Name of work: aA/R & M/O Pong Dam Fatehpur Jassur road km 45/500 to 53/680 (SH Providing and laying wearing grade-III 53mm to 22.45mm and 30mm thick bituminous concrete at RD. 53/200 to 53/220. 53/300 to 53/310. 53/555 to 53/605) Length = 80.00 mtr)

Estimated:-Rs.269878.00
Earnest Money :- Rs.5500.00
Time Limit:- One Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading-III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter	1750.00	Rupees one thousand seven hundred fifty only	Per cubic meter	8750.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on the prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer at the rate of 0.85 kg (zero point eight five kilogram) per square meter, using mechanical means as per technical specifications clause No. 502 including hauling of materials in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	560.00 Square meters	53.00	Rupees fifty three only	Per square meter	29680.00
3	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor on the prepared surface of granular base treated with primer and including cleaning of road surface with hydraulic broom and spraying tack coat at the rate of 0.275 kg. (zero point two two five kilogram) per Square metre using mechanical means as per technical specifications clause No. 503 including hauling of materials in all leads, lifts and as per entire satisfactions and directions of Engineer-in- charge including carriage of materials.. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government..	560.00 Square meters	29.00	Rupees twenty nine only	Per square meter	16240.00

4	Providing and laying 30mm (thirty millimeter) compacted thick bituminous concrete with minimum 40-60 TPH (forty-sixty tonne per hour) hot mix Batch type/ Drum type plant with electronic control grading-II using crushed aggregate 13mm (thirteen millimeter) nominal size of specified grading premixed with bituminous binder VG-30 ((viscosity grade-thirty) @ 5.40 to 5.60% (five point four zero to five point six zero percent) of mix weight transported to site, laid with censor paver finisher hydraulic with censor control to the required grade, level and alignment over a previously prepared surface and rolling complete with smooth Wheel roller 8-10 (eight to ten) tonne capacity for initial break down rolling and vibratory roller 8-10 (eight- ten) tonne capacity or pneumatic tyre roller of 12-15 (twelve- fifteen tonne) with tyre pressure of atleast 0.56 MPa (zero point five six) for intermediate rolling and finish rolling with 6-8 (six to eight) tonne smooth wheeled tandem roller to achieve the desire compaction as per MORTH technical specification clause 509 including hauling of materials in all leads , lifts and as per the direction and entire satisfaction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	16.80 Square meters	12810.00	Rupees twelve thousand eight hundred ten only	Per cubic meter	215208.00
						269878.00


 Executive Engineer
 Nampur Divn HPPWD,
 Aharpur

SCHEDULE OF QUANTITY

Name of work: Restoratio of rain damages on Nurpur Sadwan Malikwal Sanjha Nallah road km. 0/0 to 15/390
(SH: Const. of Retaining wall at RD . 4/500 to 4/517 and RD 4/620 to 4/640 Ht. 2.50 mtr)

Estimated:-Rs.366806.00
Earnest Money :- Rs. 8000.00

Time Limit:- One Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			Figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	37.62 cubic meter	364.00	Rs. Three hundred sixty four only.	Per cubic meter	13694.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 4: 8 (one cement: four sand : eight graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete, as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	77.58 cubic meter	4250.00	Rs. four thousand two hundred fifty only	Per cubic meter	329115.00
3	Back filling with stone boulder behind abutment, retaining walls, and return walls etc. compacted to firm condition complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	21.45 cubic meter	950.00	Rupess nine hundred fifty only	Per cubic meter	13943.00
4	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental ..	31.00 No.	305.00	Rs three hundred five only	Each	9455.00
			Total			366806.00

(Signature)
Executive Engineer
Nurpur Divd HPPWD
Nurpur

SCHEDULE OF QUANTITY
Name of work:- A/R & M/O Nurpur Sadwan Malikwal Sanjha Nallah road km 0/0 to 15/390
(SH:- Repair of pot holes and patches at RD. 13/500 to 15/00)

Estimated:-Rs. 465200.00
Earnest Money :- Rs.10000.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the intersities of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	6.00 cubic meter	1750.00	Rupees one thousand seven hundred only .	Per cubic meter	10500.00
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilograme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilograme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilograme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	1206.10 square meter	377.00	Rupees three hundred sixty eight only	Per square meter	454700.00
			Total			465200.00


Executive Engineer
Nurpur Divn HPPWD
Nurpur

Name of Work: - A/R & M/O various HPPWD Residential building Nurpur (SH: Painting, distempering
And wood work in Superintending Engineer's residence Nurpur etc.)

Schedule of Quantity

Estimated Cost: - Rs. 430356.00
Earnest Money : Rs. 9000.00
Time Limit : Two month

Sr. No	Description of item	Quantit y	Rate in		Unit	Amount
			Figure	words		
1	Repairs to plaster in patches and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete With cement mortar 1:4 (one cement : four sand) including carriage of materials with in all leads and lifts. The rate including of octroi, royalty, Malkana, toll tax, G.S.T. or other taxes imposed by the Government.	55.00 square meter	295.00	Rupees two hundred ninety five only	Per Square meter.	16225.00
2	Removing of old paint, priming and other scraping from any surfaces, concrete surfaces and sand papering the wall surface smooth including necessary repairs to scratches completed The rates are inclusive of all taxes, toll tax, G S T or any other taxes imposed by the Govt.	657.48 square meter	12.50	Rupees twelve and paisa fifty only	Per square meter	8219.00
3	Providing and Applying plaster of paris putty over plastered surfaces after thoroughly brushing the surface free from mortar drops, dust, loose material and other foreign matter sand papered smooth to give final finish to the surfaces complete	100.00 Square meters	95.00	Rupees ninety five only	Per square meter	9500.00
4	Distempering (two coats) with acrylic distemper (ready mixed) of approved brand and manufacture and of required shade on decorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth, priming coat with distemper primer complete as per directions of Engineer in charge. The rate including Royalty, Malkhana, Octroi, Toll Tax G S T or any other taxes imposed by the Government	1172.78 Square meter	155.00	Rupees one hundred fifty five only	Per Square meter.	181781.00
5	Providing Sal wood work in frames of doors, windows, clerestory windows and other frames wrought, framed and fixed in position complete including carriage of material with in all leads and lifts. The rate including Royalty, Malkhana, Octroi, Toll Tax G.S.T. Sales tax or any other taxes imposed by the Government	0.24 cubic meter	105250.00	Rupees one lakh five thousand two hundred fifty only	Per Cubic meter	24839.00
6	Providing and fixing 35mm(thirty five millimeters) thick second class teak wood paneled glazed shutters for doors, windows, and clerestory windows including bright finished black enamelled iron butt hinges with necessary screws including carriage of materials in all leads	8.78 Square meter	3850.00	Rupees three thousand eight hundred fifty only	Per square meter	33803.00

	and lifts.					
7	Providing and fixing 35mm(thirty millimeters) thick second class teak wood wire gauge shutters using galvanized M.S.wire gauge of 1.S.gauge designation 85-G (eighty five-G)with wire of dia 0.56mm (zero point five six millimeters)for doors, windows, and clerestory windows including bright finished black enamelled iron butt hinges with necessary screws and carriage of materials within all leads and lifts The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST or any other taxes imposed by the Government	18.98 square meter	4150.00	Rupees four Thousand one hundred fifty only	Per square meter	78767.00
8	Applying priming coat over new wood and other wood based surfaces after and including preparing the surfaces by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering and knotting with ready mixed paint brushing wood primer pink including carriage of materials in all leads and lifts.	55.50 square meter	52.00	Rupees fifty two only	Per square meter	2886.00
9	Painting two or more coats (excluding priming coat) on decorated wood and wood based surfaces with enamel paint of approved brand and manufactured (Nerolac/ Assian) to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete with enamel paint other than white complete as per directions of Engineer in charge. The rate including Royalty, Malkhana, Octroi, Toll Tax G S T or any other taxes imposed by the Government	263.63 Square meter	108.00	Rupee one hundred eight only	Per Square meter.	28472.00
10	Painting two coats(excluding priming coat) on decorated steel and other metal surfaces under coat with ready mixed paint brushing to give an even shade including cleaning the surfaces of all dirt, dust, and other foreign matter, with ready mixed paint other than white complete as per directions of Engineer in charge. The rate including Royalty, Malkhana, Octroi, Toll Tax G S T or any other taxes imposed by the Government	237.25 Square meter	112.00	Rupees one hundred twelve only	Per Square meter.	26572.00
11	Providing and fixing anodized aluminum sliding doors bolts,(anodized transparent or dyed to required colour and shade with bolts and nuts/screws etc. complete including carriage of materials with in all leads and lifts	12.96	239.60	Rupees two Hundred thirty nine and paisa sixty only	Each	2875.00
12	a) 300 x 16mm (three hundred into sixteen)millimeter. Providing and fixing anodized aluminum tower bolts, (Barrel type)anodized transparent or dyed to required colour and shade with bolts and nuts/screws etc. complete including carriage of materials with in all leads and lifts	46.94	72.20	Rupees seventy two and paisa twenty only	Each	3321.00
13	a) 250 x 10mm (two hundred forty into ten millimeter.) Providing and fixing 125mm aluminium handles, ISI marked, anodised transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of materials with in all leads and lifts	23.46	79.00	Rupees seventy nine only	Each	1817.00

14	Providing and fixing aluminium casement slays, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete including carriage of materials with in all leads and lifts	20.00 Number	59.05	Rupees fifty nine and paisa zero five only		1181.00
15	Supplying and fixing plain glass panes 4mm (four millimeters) thick with putty in steel doors windows and clerestory windows including removal of broken glass panes where-ever necessary and nails as per directions of Engineer-in-charge including carriage of materials with in all lead and lifts and other incidental charges. The rate includes, royalty charges, octroi, G S T, malkana and all other taxes as imposed by the Government	10.20 square meter	990.00	Rupees nine hundred ninety only	Per square meter	10098.00
			Total			430356.00


 Executive Engineer
 Nurpur Divya HPPWD
 Harpur

Name of work :-

SCHEDULE OF QUANTITY

Restoration of rain damages on various roads under Suliali Sub Division HPPWD Suliali
(SH:- Erecting and fixing of damaged "W" metal beam crash Barrier on various roads/ reaches)

Estimated cost Rs. 492188.00
Earnest money Rs. 10000.00

Time limit : One month

Sr. No.	Description of items	Qty.	Words	Rate in Figures	Unit	Amount
1	Erecting and Fixing of damaged "W" metal beam crash Barrier comprising of 3mm (three millimeters) thick corrugated sheet metal beam rail 70cm (seventy centimeter) above road ground level fixed on ISMC series channels vertical post 150x75x 5mm (one hundred fifty into seventy five into five millimeters) spaced 2 (two) meter centre to centre 1.80 M (one point eight zero meter) high 1.10 (one point one zero meter) meter below ground (road level) all steel parts and fliment to be galvanised by welding of all fittings to conform to IS: 1367 and IS 1364 metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm , 330 mm long fitted duly welded as per clause 810 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government	787.50 running meter	625.00	Rs. Six hundred twenty five only	Per running meter	492188.00
						492188.00

(Signature)
Executive Engineer,
Nurpur Division HPPWD
Nurpur

Name of work :- Restoration of rain damages on Makore Jammam Chakki road km 0/0 to 3/750
(SH: Const. of U-shape drain with edge wall at RD. 3/701 to 3/731 Ht 2.44 mtr)

Estimated cost Rs.492046.00
Earnest money Rs.10000.00
Time limit :- Two month

Sl. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	114.00 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	41496.00
2	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement: three sand: six graded /crushed stone aggregate 40mm) (forty millimeters) nominal size in or under water and curing complete including pumping, or bailing out water, dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	6.00 cubic meter	4550.00	Rupees four thousand four hundred fifty only	Per cubic meter	27300.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	118.00 cubic meter	3600.00	Rupees three thousand six hundred only	Per cubic meter	418900.00

3	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614.709.1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	15.00	290.00	Rupees two hundred ninety only	Each	4350.00
				Total		4920+6.00

*Schedule of quantities checked and
Approved for Rs 492046/-*

(Signature)
Executive Engineer,
Nurpur Division HPPWD
Nurpur.

SCHEMATIC OF QUANTITY

Name of work :- Restoration of rain damages on Malkore Jammuan Chakki road km 0/0 to 3/750 (Site Const. of U-shape drain with edge wall at RD. 3/735 to 3/765 Mt 2.44 mtr

Estimated cost Rs.492046.00
Earnest money Rs.10000.00

Time limit :- Two month

Sl. No.	Description of items	Qy.	Rate in	Words	Unit	Amount
			Figures			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	114.00 cubic meter	364.00	Rupess three hundred sixty four only	Per cubic meter	41496.00
2	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement: three sand: six graded /crushed stone aggregate 40mm) (forty millimeters) nominal size in or under water and curing complete including pumping, or bailing out water . dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 .as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	6.00 cubic meter	4550.00	Rupess four thousand four hundred fifty only	Per cubic meter	27300.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	118.00 cubic meter	3600.00	Rupess three thousand six hundred only	Per cubic meter	418900.00

3	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry. plain/reinforced concrete abutment. wing wall. return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614.709.1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	15.00	290.00	Ruppes two hundred ninety only	Each	4350.00
				Total		492046.00

*Schedule of quantity checked and
Approved For Rs = 492046/-*

(MB-117)
Executive Engineer.
Nurpur Division HPPWD
Karnapur

Name of work: Construction of link road Ladori to Ghaloon km 0/00 to 1/700
(SH: Providing and laying inter locking paver block at RD 1/00 to 1/058)

SCHEDULE OF QUANTITY

Estimated:-Rs. 298166.00
Earnest Money :- Rs. 6000.00
Time Limit:- Two Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In figure	In Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight-ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	55.68 cubic meter	105.00	Rupees one hundred five only	Per cubic meter	5846.00
2	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	18.56 cubic meter	4450.00	Rupees four thousand four hundred fifty only	Per cubic meter	82592.010
3	Providing and laying (I S I marked) inter locking concrete block pavement having thickness 80mm (eighty millimeters) over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer -in-charge including carriage of materials. The rates is inclusive royalty, toll tax, G S T or any other taxes imposed by the Government.	185.60 Square meter	1130.00	Rupees one thousand one hundred thirty only	Per square meter	209728.00
			Total			298166.00

(Signature)
Executive Engineer
Nurpur Divn/HPPWD.
Nurpur

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Nurpur to Sanjha Nalla road km 0/0 to 15/390 (SH:-Repair of Pot holes km 1/800 to 2/900)

Estimated cost Rs.427008.00
Earnest money Rs.100000.00

Time Limit= One Month

Sr. No	Description of items.	Quantity	Figures	Rates in	Unit	Amount
				Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -All 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres) sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 complete including carriage of materials within all leads and lifts and other incidental charges. The rate is including octroi, royalty, Malkana toll tax, G S T or other taxes imposed by the Government.	5.00	1750.00	Rupees One thousand Seven hundred fifty only	Per cubic meter	8750.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion pressure distributor at the rate of 0.225 kg (zero point two two five kilogramme) per square meter on the prepared bituminous surface cleaned with hydraulic broom as per technical specifications 503 including hauling of materials in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental charges. The rate is including octroi, royalty, Malkana toll tax, G S T or other taxes imposed by the Government.	1011.95	29.00	Rupees Twenty Nine only	Per square meter	29347.00
3	Providing and laying 30mm (thirty millimeter) compacted thick bituminous concrete with minimum 40-60 TPH (forty -sixty tonne per hour) hot mix Batch type/ Drum type plant with electronic control grading-II using crushed aggregate 13mm (thirteen millimeter) nominal size of specified grading premixed with bituminous binder VG-30 (viscosity grade-thirty) @ 5.40 to 5.60% (five point four zero to five point six zero percent) of mix weight transported to site, laid with sensor paver finisher hydraulic with sensor control to the required grade, level and alignment over a previously prepared surface and rolling complete with smooth Wheel roller 8-10 (eight to ten) tonne capacity for initial break down rolling and vibratory roller 8-10 (eight- ten) tonne smooth wheeled capacity or pneumatic tyre roller of 12-15 (twelve- fifteen tonne) with tyre pressure of atleast 0.56 MPa (zero point five six) for intermediate rolling and finish rolling with 6-8 (six to eight) tonne smooth wheeled tandem roller to achieve the desired compaction as per MORTH technical specification clause 509 including hauling of materials in all leads, lifts and as per the direction and entire satisfaction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, G S T or other taxes imposed by the Government.	30.36	12810.0	Rupees eleven thousand eight hundred ten only	Per cubic meter	388912.00
					Total	427008.00

(Signature)
Executive Engineer
Nurpur Division HP PWD
Nurpur

SCHEDULE OF QUANTITY

Name of work: Improvement of Both Ganoh road km 0/00 to 6/00 (SH Providing and laying Granular sub base, 63mm o 45mm , wearing grade-III 53mm to 22.45mm and 30mm thick bituminous concrete At RD 5/060 to 5/110)

Estimated:-Rs. 190310.00
Earnest Money :- Rs.4000.00
Time Limit:- One Month

Sr. No	Description of Items	Quantity	Rate		Unit	Amount
		y	In figure	In Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight -ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	60.00 cubic meter	85.00	Rupees eighty five only	Per cubic meter	5100.00
2	Construction of granular sub-base by providing well graded materials, spreading in uniform layers with tractor mount grader with rotavator at OMC, and compacting with three Wheel 80-100 (Eighty-hundred) K N static roller to achieve the desired density, complete as per Technical Specification Clause 401 for grading-I Material, 100mm (one hundred millimetres) compacted thickness including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	30.00 cubic meter	1295.00	Rupees one thousand two hundred ninety five only	Per cubic meter	38850.00
3	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II 63mm to 45mm (sixty three millimetres to forty five millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	15.00 cubic meter	1750.00	Rupees one thousand seven hundred fifty only	Per cubic meter	26250.00
4	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	15.00 cubic meter	1790.00	Rupees one thousand seven hundred ninety only	Per cubic meter	26850.00

5	Providing and applying primer coat with bitumen emulsion (SS-1) on the prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer at the rate of 0.85 kg (zero point eight five kilogram) per square meter, using mechanical means as per technical specifications clause No. 502 including hauling of materials in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	200.00 Square meters	53.00	Rupees fifty three only	Per square meter	10600.00
6	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor on the prepared surface of granular base treated with primer and including cleaning of road surface with hydraulic broom and spraying tack coat at the rate of 0.275 kg. (zero point two two five kilogram) per Square metre using mechanical means as per technical specifications clause No. 503 including hauling of materials in all leads, lifts and as per entire satisfactions and directions of Engineer-in-charge including carriage of materials.. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government..	200.00 Square meters	29.00	Rupees twenty nine only	Per square meter	5800.00
6	Providing and laying 30mm (thirty millimeter) compacted thick bituminous concrete with minimum 40-60 TPH (forty –sixty tonne per hour) hot mix Batch type/ Drum type plant with electronic control grading-II using crushed aggregate 13mm (thirteen millimeter) nominal size of specified grading premixed with bituminous binder VG-30 ((viscosity grade-thirty) @ 5.40 to 5.60% (five point four zero to five point six zero percent) of mix weight transported to site, laid with censor paver finisher hydraulic with censor control to the required grade, level and alignment over a previously prepared surface and rolling complete with smooth Wheel roller 8-10 (eight to ten) tonne capacity for initial break down rolling and vibratory roller 8-10 (eight-ten) tonne capacity or pneumatic tyre roller of 12-15 (twelve- fifteen tonne) with tyre pressure of atleast 0.56 MPa (zero point five six) for intermediate rolling and finish rolling with 6-8 (six to eight) tonne smooth wheeled tandem roller to achieve the desire compaction as per MORTH technical specification clause 509 including hauling of materials in all leads, lifts and as per the direction and entire satisfaction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.00 cubic meter	12810.00	Rupees twelve thousand eight hundred ten only	Per cubic meter	76860.00
7						190310.00


 Executive Engineer
 Nurpur Divd HPPWD.
 Nurpur