

No.PW/RGH/Estt-Tender/2024-25-
To

Himachal Pradesh
Public Works Department

1504-53

Dated:- 25-06-2024

The Director,
Information and Public Relation,
Suchna Avam Jan Sampark Bhawan,
Near HP.Admn.Tribunal Shimla-2.

Subject:- Publication of Notice Inviting Tender Advertisement.

Jai Hind.


Enclose please find herewith the Notice Inviting Tender to be opened on
09.07.2024 for publication in Giri Raj weekly and two other regional news papers Himachal Pradesh.

Encl: - As above


Executive Engineer,
Rajgarh Division,
HP.PWD.Rajgarh.

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD.Shimla-1.
2. The Chief Engineer (South) HP.PWD.Shimla-1.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (I.T) Cell, O/O Engineer-In-Chief, HPPWD Nigam Vihar Shimla-2 for uploaded Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer,
Rajgarh Division,
HP.PWD. Rajgarh.

**HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT
NOTICE INVITING TENDER**

Sealed Items rates tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD so as to reach in this office 09.07.2024 upto 10:30 AM and shall be opened on the same day at 11:00 AM in the presence of intending contractors or their authorised representative who may link to be present. The tender form be had from his office against cash payment (non refundable) during working hours.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Rajgarh Division HPPWD Rajgarh must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.


Sr. No.	Tender Sechedule	
1.	Last date for tender receipt of application for tender form	06.07.2024 upto 5:00 PM
2.	Last date of sale of tender forms.	08.07.2024 upto 5:00 PM
3.	Date of receipt of tender forms	09.07.2024 upto 10:30AM
4.	Date of opening of tenders	09.07.2024 at 11:00 AM

Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of form	Eligible Class of contractor
1	Restoration of rain damage on Solan Meenus road Km 24/345 to 61/00 (SH:- Clearance of hill side drain , Removal of slips and unlined drain between km 48/00 to 55/00).	4,87,525/-	10,000/-	Two months	350/-	Class-"C&D"
2	Restoration Rain damages on Neripul Pulbhal road km 0/00 to 14/ 565 (SH:- Construction of PCC Retaining wall between km 4/430 to 4/436.50).	4,38,440/-	10,000/-	Two months	350/-	Class-"C&D"
3	A/R & M/O Solan Meenus road km 24/345 to 61/0 (Providing and laying Interlocking paver blocks between Km 38/620 to 38/700)	4,99,137/-	10,000/-	Two months	350/-	Class-"C&D"
4	A/R & M/O Solan Meenus road km 24/345 to 61/0 (Providing and laying Interlocking paver blocks between Km 38/530 to 38/610)	4,99,350/-	10,000/-	Two months	350/-	Class-"C&D"
5	Restoration rain damages on Banethi Bagthan Rajgarh Chandol road Km 48/0 to 87/0 (SH:- C/O Unlined drain between Km 55/0 to 60/0, 61/0 to 64/0 and 66/0 to 68/0).	4,14,000/-	8,500/-	One month	350/-	Class-"C&D"
6	Restoration of rain damages on Solan Meenus road km 24/345 to 61/0 (SH:- Providing and Laying patch work in between Km. 36/500 to 37/500).	4,99,124/-	10,000/-	Two months	350/-	Class-"C&D"
7	Restoration of rain damages on Solan Meenus road km 24/345 to 61/0 (SH:- Providing and Laying patch work in between Km. 38/500 to 40/0).	1,99,780/-	4,000/-	One month	350/-	Class-"C&D"
8	Restoration of rain damages on Solan Meenus road km 24/345 to 61/0 (SH:- Providing and Laying patch work in between Km. 37/500 to 38/500).	4,99,473/-	10,000/-	Two months	350/-	Class-"C&D"

Certificate :- It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The above Job for consultancy work and consultants should be working with HPPWD.
2. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST on the tender along with copy of the same be attached with the application.
3. The contractor/Firms should attached copy of the Registration/Renewal with the application.
4. The contractor/bidder should quoted in percentage rates.
5. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
6. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
7. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
8. The offer shall remain valid upto 75 days.
9. The above Job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW)B)A(3)1/2020 dt. 22.07.2020. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.
10. The Executive Engineer reserve the right any or all the tenders without assigning any reason.
11. The tender document shall be issued to only those contractors who submit registration of GST No.


 Executive Engineer
 HPPWD Division Rajgarh
 Distt Sirmour HP
 on behalf of Governor of Himachal Pradesh
 Tel. No. 01799-221023 Mail: ee-raj-hp@nic.in

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damage on Solan Meenus road Km 24/345 to 61/00 (SH:- Estimated cost:-Rs.4,87,525/-
Clearance of hill side drain , Removal of slips and unlined drain between km 48/00 to 55/00). **Earnest money:-** Rs. 1,000/-
Time Limit:- Two Months

Sr No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures	in words	
1	2	3	4	5	6	7
1	Removal of earth from the choked hill side drain manually and Dressing it on the berms /Shoulder portion or dispose it on the valley side/Dumping site to be arranged by the contractor ,including all leads, lifts and carriage of materials as per direction of Engineer - in - Charge.	7000.00	Per Running metre	44.40	Rupees forty four and paise forty only.	3,10,800.00
2	Removal of land slide in hilly area ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per H.P.PWD. spesification, including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts as per direction of Engineer - in - Charge.	300.00	Per Cubic metre	92.00	Rupees ninety two and paise zero only.	27,600.00
3	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site. by mechanical means as per H.P.PWD. spesification, including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts including all incidental charges.	2500.00	Per Running metre	59.65	Rupees fifty nine and paise sixty five only.	149125.00
					G.Total	487525.00
	Quoted rates precentage in figure					
	Quoted rates precentage in word					


 Executive Engineer,
 Rajgarh Division,
 H.P.PWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of work: - Restoration Rain damages on Neripul Pulbhal road km 0/00 to 14/ 565 (SH:- Estimated cost: - Rs.4,38,440/-
Construction of PCC Retaining wall between km 4/430 to 4/436.50).
Earnest money: - Rs. 10,000/-
Time Limit: - Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	53.240	Per Cubic Metre	255.20	Rupees hundred five and paise twenty only.	13587.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 40 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	77.090	Per Cubic Metre	5371.00	Rupees thousand three hundred seventy one and paise nil only.	414050.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	13.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	3598.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	9.36	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	7205.00
				G.Total		438440.00
	Quoted rates percentage in figure					
	Quoted rates percentage in word					


 Executive Engineer,
 Rajgarh Division,
 PWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of work : A/R & M/O Solan Meenus road km 24/345 to 61/0 (Providing and laying Interlocking paver blocks between Km 38/620 to 38/700)

Estimated cost: - Rs.4,99,137/-
Earnest money: - Rs. 10,000/-
Time Limit: -Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				In figures.	In words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	1.68	Per Cubic Metre.	255.20	Rupees Two hundred fifty five and paise twenty only.	429.00
2	Providing and laying Interlocking Concrete Block Pavements having thickness 80 mm (eighty millimetre)as per drawings and Technical Specification Clause 1504 (one thousand five hundred four) and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations. in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	320.00	Per square Metre	1410.90	Rupees thousand four hundred ten and paise ninety only.	451488.00

Providing and Laying in position cement concrete of specified grade excluding the cost of Centering and shuttering - All work up to plinth level in 1:2:4 (one cement isto two sand isto four graded stone agg. 20 (Twenty) mm nominal size) mechanically mixed and vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	6.72	Per Cubic Metre	7026.80	Rupees thousand twenty six and paise eighty only.	47220.00
				Total:	499137.00
Quoted rates precentage in figure					
Quoted rates precentage in word					


 Executive Engineer
 Rajgarh Division
 H.P.D.W.D. Rajgarh

SCHEDULE OF QUANTITY

Name of work : A/R & M/O Solan Meenus road km 24/345 to 61/0 (Providing and laying Interlocking paver blocks between Km 38/530 to 38/610)

Estimated cost: - Rs.4,99,350/-

Earnest money: - Rs. 10,000/-

Time Limit: -Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	1.69	Per Cubic Metre.	255.20	Rupees Two hundred fifty five and paise twenty only.	431.00
2	Providing and laying Interlocking Concrete Block Pavements having thickness 80 mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (one thousand five hundred four) and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	320.00	Per square Metre	1410.90	Rupees One thousand four hundred ten and paise ninety only.	451488.00

aiding and Laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level in 1:2:4 (one cement isto four graded stone agg. 20 (Twenty) mm nominal size) mechanically mixed and vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	6.75	Per Cubic Metre	7026.80	Rupees thousand two hundred six and paise eighty only.	47431.00
				Total:	499350.00
Quoted rates percentage in figure					
Quoted rates percentage in word					


 Executive Engineer
 Raygach Division
 JPRWD Rajgarh

SCHEDULE OF QUANTITY

Name of work:- Restoration rain damages on Banethi Bagthan Rajgarh Chandol road Km 48/0 to 87/0 (Estimated cost: - Rs.4,14,000/-
 Earnest money: - Rs. 8,500/-
 Time Limit: - One Months
 SH:- C/O Unlined drain between Km 55/0 to 60/0, 61/0 to 64/0 and 66/0 to 68/0).

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site. as per Technical Specification Clause 405(Four hundred Five) By Mechanical means as per HPPWD specification , including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts to the entire satisfaction as per direction of Engineer - in - Charge.	9000.00	Per running Metre.	46.00	Rupees forty six and paise nil only.	414000.00
					G.Total	414000.00
	Quoted rates percentage in figure					
	Quoted rates percentage in word					


 Executive Engineer
 Rajgarh Division
 HPPWD Rajgarh

SCHEDULE OF QUANTITY

Name of work : Restoration of rain damages on Solan Meenus road km 24/345 to 61/0 (SH:- Providing and Laying patch work in between Km. 36/500 to 37/500).

Estimated cost:-Rs.4,99,124/-
Earnest money:- Rs. 10,000/-
Time Limit:- One Month.

Sr. No	Description items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and revelling as per technical specification Clause 1906 including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	89.39	Per square Metre.	187.00	Rs. Rupees One hundred eighty seven and paise nil only.	16716.00
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 (zero point seventy to one point zero) kg/sqm using mechanical means as per Technical Specification Clause 502.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	89.39	Per Square metre.	64.42	Rupees sixty four and Paise forty two only.	5759.00
3	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surfaces providing tack coat with bitumen emulsion, 20mm thick premix carpet using cationic bitumen emulsion and seal coat type-B with bitumen emulsion as per technical specification clause 1904.2, 503 and 508.2.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	1191.92	Per Square metre.	399.90	Rupees Three hundred ninety nine and Paise ninety only.	476649.00
				Total:		499124.00
	Quoted rates precentage in figure					
	Quoted rates precentage in word					


 Executive Engineer
 Rajgarh Division
 HPWD Rajgarh

SCHEDULE OF QUANTITY

Name of work : Restoration of rain damages on Solan Meenus road km 24/345 to 61/0 (SH:- Providing and Laying patch work in between Km. 38/500 to 40/0).

Estimated cost:-Rs.1,99,780/-

Earnest money:- Rs. 4,000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and revelling as per technical specification Clause 1906 including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	35.78	Per square Metre.	187.00	Rs. Rupees One hundred eighty seven and paise nil only.	6691.00
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 (zero point seventy to one point zero) kg/sqm using mechanical means as per Technical Specification Clause 502.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	35.78	Per Square metre.	64.42	Rupees sixty four and Paise forty two only.	2305.00
3	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surfaces providing tack coat with bitumen emulsion, 20mm thick premix carpet using cationic bitumen emulsion and seal coat type-B with bitumen emulsion as per technical specification clause 1904.2, 503 and 508.2.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	477.08	Per Square metre.	399.90	Rupees Three hundred ninety nine and Paise ninety only.	190784.00
					Total:	199780.00
	Quoted rates percentage in figure					
	Quoted rates percentage in word					


 Executive Engineer
 Rajgarh Division
 H.P.PWD Rajgarh

SCHEDULE OF QUANTITY

Name of work : Restoration of rain damages on Solan Meenus road km 24/345 to 61/0 (SH-1) Providing and Laying patch work in between Km. 37/500 to 38/500).

Estimated cost-Rs. 4,99,473/-
Earnest money: - Rs. 10,000/-
Time Limit: - One Month.

Sr. No	Description items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and relling as per technical specification Clause 1906 including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	89.46	Per square Metre.	187.00	Rs. Rupees One hundred eighty seven and paise nil only.	16729.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 (zero point seventy to one point zero) kg/sqm using mechanical means as per Technical Specification Clause 502.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	89.46	Per Square metre.	64.42	Rupees sixty four and Paise forty two only.	5763.00
3	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surfaces providing tack coat with bitumen emulsion, 20mm thick premix carpet using cationic bitumen emulsion and seal coat type-B with bitumen emulsion as per technical specification clause 1904.2, 503 and 508.2.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	1192.75	Per Square metre.	399.90	Rupees Three hundred ninety nine and Paise ninety only.	476981.00
					Total:	499473.00
	Quoted rates percentage in figure					
	Quoted rates percentage in word					


Executive Engineer
Raigarh Division
HPPWD Raigarh