

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited on Form No.7 &8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works 05-08-2024 upto 11:00 A.M and shall be opened on the same day on 11:30 A.M. in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.

The earnest money in the shape of National Saving Certificate, FDRs/TDRs/ Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

S N	Tender Schedule				
1	Last date for tender receipt of application for tender form	02-08-2024 up to 4:00 PM			
2	Last date of sale of tender forms	03-08-2024 up to 4:00 PM			
3	Date of receipt of tender forms	05-08-2024 up to 11:00 A.M			
4	Date of opening of tenders	05-08-2024 at 11:30 A.M			
Sr. No	Name of Work	Estimat ed cost	Earnest Money	Time Limit	Cost of Form
1	R/R damages on link road to Dr. Y.S Parmar Birth Palace Chalanag Km 0/0 to 0/560(SH:- C/O PCC R/wall at Rd 0/114 to 0/131	455954	10000	three month	350/-
2	R/R damages on Kanyon Shirla Anji road Km 0/0 to 6/480(SH:- C/O R/wall at RD 2/010 to 2/020, 2/340 to 2/351)	417666	10000	three month	350/-
3	R/R damages on Dungaghat Bagthan road km 0/0 to 12/450 (ROFD at RD 10/777 to 10/820, C/O R/wall at RD 6/05 to 6/017)	342545	7000	Three month	350/-
4	R/R damages on Dungaghat Bagthan road km 0/0 to 12/450 (C/O R/wall at RD 6/155 to 6/168, C/O wing wall of existing culverts at Rd 6/075)	417633	8500	Three month	350/-
5	C/O Shakol to Bagula road in km 0/00 to 1/270 (SH:- C/O wire crate at RD 0/45 to 0/090 height 2.5 mtr MNP	469331	9500	Three month	350/-
6	R/R damages on Kerry Shutiya Bagthan road Km 0/0 to 23/00 (SH:- C/O PCC B/Wall at Rd 10/105 to 10/131)	499440	10000	Three Month	350/-
7	R/R damages on Banalag Dhamesha Pachpir road Km 0/0 to 12/00 (SH:- C/O B/wall between RD 2/330 to 2/345 & R/wall between RD 5/900 to 5/915).	498560	10000	Three Month	350/-

Certificate:-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
4. Conditional and telegraphic tender will not be accepted and rejected straightway. Tender received after due date and time shall not entertained.
5. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
6. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
7. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
8. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.

Executive Engineer
Sarahan Division,
H.P.PWD Sarahan

No.PW/SRN/Estt-Tender/2022-23-1741-91

Dated:- 20/7/2024

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Shimla-171002.
2. The Chief Engineer (South) HP.PWD, Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. 7. All Intending Bidders/Contractors.
8. Notice Board.

Executive Engineer
Sarhan B&R Division.
P.PWD, Sarhan.

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on link road to Dr. Y S Parmar Birth place Chanalag km 0/0 to 0/560 (SH:- C/O PCC R/Wall at RD 0/114 to 0/131)

Estimated cost:- Rs. 4,55,954/-

Earnest money:- Rs 10,000

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	50.15	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	9729.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	90.100	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	425020.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	26.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	7028.00

4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	19.21	Per Cubic Metre.	738.00	Rupees Hundred eight and paise zero Only.	seven thirty paise	14177.00
							455954.00


 Executive Engineer
 Sarahan Division
 HPPWD, Sarahan

SCHEDULE OF QUANTITY

Estimated cost:-Rs. 4,70,906/-

Name of work:-R/R Damages on Kanyon Shirila Anji road km 0/0 to 6/480 (SH:- C/O R/Wall at RD 2/010 to 2/020,2/340 to 2/351)

Earnest money:- Rs 10,000

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	20.10	Per Cubic Metre.	261.00	Rupees two hundred sixty one and paise nil only	5246.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	86.10	Per Cubic Metre.	5166.45	Rupees five thousand one hundred sixty six and paise forty five only	444831.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	28.000	Each	280.00	Rs. Two Hundred eighty and paise nil only	7840.00

4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various 'locations' through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	16.45	Per Cubic Metre.	789.60	Rupees seven hundred ninety six only	12989.00
						470906.00



Executive Engineer
Sarahan Division
HPPWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:-R/R. Damages on Dungaghat Bagthan road km 0/0 to 12/450 (SH:-ROFD at RD 10/777 to 10/820, C/O R/Wall at RD 6/05 to 6/017) ✓


Estimated cost:-Rs. 3,42,545/-

Earnest money:- Rs. 7,000 ✓

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 107.74 cum (one hundred seven point seventy four) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	646.42 ✓	Per cubic Metre	279.00 ✓	Rupees two hundred seventy nine and paise nil only ✓	180351.00
2	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	13.82 ✓	Per Cubic Metre.	261.00 ✓	Rupees two hundred sixty one and paise nil only ✓	3607.00

3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	29.42 ✓	Per Cubic Metre.	5166.45 ✓	Rupees five thousand one hundred sixty six and paise forty five only ✓	151997.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	10.000 ✓	Each	280.00 ✓	Rs. Two Hundred eighty and paise nil only ✓	2800.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	4.80 ✓	Per Cubic Metre.	789.60 ✓	Rupees seven hundred eighty nine and paise sixty only ✓	3790.00
					Total	342545.00


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:-R/R Damages on Dungaghat Bagthan road km 0/0 to 12/450 (SH:- C/O R/Wall at RD 6/155 to 6/168, C/O Wing walls of existing culverts at RD 6/075)


Estimated cost:-Rs. 4,17,633/-

Earnest money:- Rs 8,500

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	18.14	Per Cubic Metre.	261.00	Rupees two hundred sixty one and paise nil only	4735.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	75.39	Per Cubic Metre.	5166.45	Rupees five thousand one hundred sixty six and paise forty five only	389499.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	42.000	Each	280.00	Rs. Two Hundred eighty and paise nil only	11760.00

4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	14.74 ✓	Per Cubic Metre.	- 789.60 ✓	Rupees seven hundred eighty nine and paise sixty only	11639.00 ✓
					Total	417633.00 ✓


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

Estimated cost 4,64,881/-
 Earnest money:- 9,500/-
 Time limit :- Three months

SCHEDULE OF QUANTITY

Name of work:- C/O Shakol to Bagula Road in km 0/00 to 1/270(SH:-C/O wire crate at RD 0/45 to 0/1000 Height 2.5 mtr MNP

Sr. No	Description Items of work	Unit	QTY	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	Per Cubic Metre	54.00	261.00	Rupees two hundred sixty one and paise nil only	14094.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	Per Cubic Metre	154.69	2942.90	Rupees two thousand nine hundred forty two and paise ninety only	455237.20
						469331


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Kerry Shutiya Bagthan road km 0/0 to 23/00 (SH:- C/O PCC B/Wall at RD 10/105 to 10/131)

Estimated cost:- Rs. 4,99,440/- ✓

Earnest money:- Rs 10,000 ✓

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	51.75 ✓	Per Cubic Metre.	261.00 ✓	Rupees two hundred sixty one and paise nil only. ✓	13507.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	93.08 ✓	Per Cubic Metre.	5166.45 ✓	Rupees five thousand one hundred sixty six and paise forty five only. ✓	480893.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall-with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	18.000 ✓	Each	280.00 ✓	Rs. Two Hundred eighty and paise nil only. ✓	5040.00
						499440.00

Executive Engineer
K.S. Sarahan Division
HPPWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Banalag Dhamesha Panchpir road km 0/0 to 12/00 (SH:- C/O B/wall Between RD 2/330 to 2/345 & R/Wall Between RD 5/900 to 5/915)

Estimated cost:- Rs. 4,98,560/-

Earnest money:- Rs 10,000

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	28.76	Per Cubic Metre.	261.00	Rupees two hundred sixty one and paise nil only	7506.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	91.68	Per Cubic Metre.	5166.45	Rupees five thousand one hundred sixty six and paise forty five only	473660.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	30.000	Each	280.00	Rs. Two Hundred eighty and paise nil only	8400.00


4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	11.39 ✓	Per Cubic Metre.	789.60	Rupees seven hundred ninety and paise sixty only	8994.00 ✓
						498560.00 ✓


Ts estimate no. Letter no.

Dated :-

DNIT No. For the year 2024-25

Draft Schedule of Quantity approved for Rs. 498560.00 ✓ only.

 Executive Engineer

 Sarahan Division

HP, PWD, Sarahan