

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO.PW/AD/EA-I/Tender/24- 3513
To


Dated 21/8/2024

The Executive Engineer(IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2
Department,HP,Secretariat,
Shimla-2

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in
respect of this office for uploading the same on departmental website.

Encl:- Copy of NIT


Executive Engineer,
Arki Divn.HP,PWD,Arki

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed item rate/percentage rate tender on Form No. 6&8 are hereby invited by the Executive Engineer, Arki Division, HP, PWD. Arki on behalf of the Governor of Himachal Pradesh for the following works from the competent (In this regard the decision of the Executive Engineer shall be final) contractors enlisted with HP, PWD in appropriate class whose registration stood renewed as per revised instruction and also registered dealers under the Himachal Pradesh sales Tax Act, 2017 so as to reach in this office on before 30.08.2024. upto 11:30 AM and the same shall be opened on the same day at 12:00 P.M. in the presence of the intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on 31.08.2024 upto 4:30 P.M and the application for issue of tender form shall be received on 02.09.2024 upto 5:00 P.M

The amount of Earnest Money in the shape of NSCs/FDR deposit at call of any of the Post Office/Bank pledged in favour of Executive Engineer, Arki Division, HP, PWD, Arki must be accompanied with the application for tender documents. Please note no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be deot open for 20 days. The Executive Engineer reserve right to reject any tender or all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

S.N o	Name of work	Estimated cost.	Earnest money	Form	Cost, of form	Time
1.	A/R & M/o Jabal Manlog kalan Ukhoo Panjali Jainagar road at RD 16/0 to 20/0	4,78,873/-	9600/-	6&8	350/-	1Months
2	R/R damages on KBSB road km. 0/0 to 8/0 (SH:-C/o R/wall in km. 2/970 to 2/985)	4,89,664/-	9800/-	6&8	350/-	1Months
3	C/o Gamberpul Banoh Narwar road km. 0/0 to 4/500 (SH:-C/o R/wall in km. 2/560 to 2/571)	4,80,198/-	9700/-	6&8	350/-	1Months
4	A/R & M/o Jabal Manlog kalan Ukhoo Panjali Jainagar road at RD 20/0 to 24/765)	4,91,103/-	9900/-	6&8	350/-	1Months

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Arki Divn. HP, PWD, Arki

Certificate

Certified that the tenders called vide this notice inviting tender for 4(Four) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Arki Divn. HP, PWD, Arki

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O Jabal Manlog Kalan Ukhoo Panjli Jainagar road km 20/000 to 24/000

Estimated Cost:-Rs 4,78,873/- only

Earnest Money : Rs 9600 /-only

Time -One Months

S.N o.	Sub head and items of work	Qty.	Rate	In figure		In words		Unit	Amount
1	2	3						6	7
1	Construction of unlined surface drain of average cross-section area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3 mtrs and lead of 50 mtrs (average lead 25 mtrs) as per technical specification clause 307 as per WORD specifications complete as per direction by the Engineer-In-Charge.	3830.00						Per running metre	
2	Surface dressing of road berms removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge:	7149.00						Per square metre	
								Total:-	

Executive Engineer
Arki Division,
HPPWD, Arki

SCHEDULE OF QUANTITY

Name of work:-Restoration of Rain damages on KBSB road km 0/000 to 8/000 (SH:-C/o Retaining wall in km 2/790 to 2/985)

Estimated Cost: -Rs 4,89,664/- only

Earnest Money : Rs 9800/- Only

Time - One Month

S.N	Sub head and items of work	Qty.	Rate		Unit	Amount
			In figure	In words		
1	2	3			6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	40.50	cum		Per cubic metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	104.40	Cum		Per cubic metre	
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	27.45	Cum		Per cubic metre	
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality including carriage of material within all leads and lifts.	96.40	Rmt		Per running metre	
					Total:-	

Executive Engineer
Arki Division,
HPPWD, Arki

SCHEDULE OF QUANTITY

Name of work:-Restoration of Rain damages on Gamberpui Baroh narwad Sari Dhani road km 0/000 to 4/500 (SH:-C/o Retaining wall in km 2/560 to 2/571)

Estimated Cost: -Rs 4,80,198/- only
Earnest Money : Rs 9700/-only
Time - One Month

S.N o.	Sub head and items of work	Qty.	Rate	Unit	Amount
			In figure In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	32.67	cum	Per cubic metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10 (40mm)	103.40	Cum	Per cubic metre	
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	27.39	Cum	Per cubic metre	
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality including carriage of material within all leads and lifts.	87.90	Rmt	Per running metre	
	Total:-				

Executive Engineer
Arki Division,
HPPWD, Arki

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O Jabal Manlog Kalan Ukhoor Panjli Jainagar road km 16/000 to 20/000

Estimated Cost: -Rs 4,91,103/- only

Earnest Money : Rs 9900 /-only

Time -One Months

S.N o.	Sub head and items of work	Qty.	Rate	Unit	Amount
			In figure	In words	
1	Construction of unlined surface drain of average cross-section area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3 mtrs and lead of 50 mtrs (average lead 25 mtrs) as per technical specification clause 307 as per MORD specifications complete as per direction by the Engineer-In-Charge.	3870.00	Rmt.	Per running metre	
2	Surface dressing of road berms removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge.	7740.00	Sqm	Per square metre	
				Total:-	

Executive Engineer
Arki Division,
HPPWD, Arki