



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
INVITATION FOR BIDS (IFB)

Office 01783-260033

Email : ee-cho-hp@nic.in

No. PW.CHD.CB.E-9/2024- 3404-3503

Dated : 09/08/2024

NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited by the Executive Engineer HPPWD Chopal District Shimla H.P. in form No. 6 & 8 on behalf of Governor of H.P for the following works from the contractors of appropriate class enlisted with HPPWD. The tenders shall be opened in the presence of the contractors/firms or their representative who wish to be present.

TIME SCHEDULE OF TENDER

1. Date and time of receipt of application for tender form : 20.08.2024 up to 04:00 PM
2. Date and time of issue of tender form : 20.08.2024 04:00 PM to 05:00 PM
3. Date and time of receipt of tenders : 21.08.2024 11:00 AM
4. Date and time of opening of tender : 21.08.2024 11:30 AM

The tender forms will be issued to only those contractors who qualify the criteria after the scrutiny of application forms.

Sl. No	Name of Work	Estimated Cost	EMD	Cost of tender	Time Limit	Eligible class of contractor
1.	C/o Bhoot Kainchi to H.B. Dunglech road km. 0/0 to 3/565 (SH: C/o PCC. R/Wall at R.D. 1/390 to 1/405) under SCDP (D-32) 5054-04-789-01)	240014.00	4800.00	350.00	Two months	Class D or above
2.	R/R damages on Banipul Mashrain Tharoch road km. 0/0 to 18/0 (SH: C/o B/Wall at R.D. 17/320 to 17/340)	382279.00	7646.00	350.00	Two months	Class D or above
3.	R/R damages to Dhartua to Makrog road km. 0/0 to 9/450 (SH: C/o R/Wall in PCC.at R.D. 3/773 to 3/780)	498650.00	9973.00	350.00	Two months	Class D or above
4.	C/O Dehra nallah to Dehra km. 0/0 to 1/0 (SH: C/o R/wall at R.D. 0/150 to 0/162) under MNP (5054-04-337-02)	198307.00	3966.00	350.00	Two months	Class D or above
5.	A/R & M/O to Dhabas to Baghar road km. 0/0 to 9/0 (SH: C/o R/Wall at RD. 0/735 to 0/747)	489434.00	9789.00	350.00	Two months	Class D or above
6.	C/o road from Katali to Kaftu road km 0/0 to 1/750 (SH: C/o B/Wall at R.D. 1/210 to 1/235)	352788.00	7056.00	350.00	Two months	Class D or above
7.	C/o link road from Prem Nagar to Gadrahal Harijan Basti road km 0/0 to 2/500 (SH:- C/o 5/7 mtr wide formation cutting at RD. 1/345 to 1/630) under SCDP (D-32) 5054-04-789-01)	476715.00	9534.00	350.00	Two months	Class D or above
8.	C/O link road from Kelvi to Lohana road km 0/0 to 5/0 (SH: P/L Kharanja stone soling between km RD. 3/500 to 3/860) under SCDP (D-32) 5054-04-789-01)	482922.00	9658.00	350.00	Two months	Class D or above
9.	Restoration of rain damages on various roads under Chambi section, Chopal Sub-Division (SH:- Hiring of JCB for removal of slip/ debris etc.)	153000.00	3060.00	350.00	15 days	Class D or above
10.	Restoration of rain damages on various roads under Pulbahal section, Chopal Sub-Division (SH:- Hiring of JCB for removal of slip/ debris etc.)	183600.00	3672.00	350.00	15 days	Class D or above
11.	R/R damages on Marog to Matal road km0/0 to 18/500 (SH: C/O R/Wall at R.D. 1/150 to 1/170)	417811.00	8356.00	350.00	Two months	Class D or above
12.	R/R damages on Marog to Matal road km0/0 to 18/500 (SH: C/O R/Wall at RD. 16/180 to 16/292)	278201.00	5564.00	350.00	Two months	Class D or above


13.	C/O road from Tharoch to Chhajpur km 0/0 to 6/0 (SH:- Widening of existing road between km 4/600 to 5/165) under MNP.	480609.00	9612.00	350.00	Two months	Class D or above
14.	Restoration of rain damages on various roads under Shallu Sub-Division Nerwa (SH:- Hiring of JCB. For removal of slips clearance of side drain etc.)	170200.00	3404.00	350.00	15 days	Class D or above
15.	C/o road from Nerwa to H.B. Katainh road km. 0/0 to 6/0 (SH: C/o wire crate R/wall at R.D. 1/230 to 1/237.50, 5/940 to 5/964.50 & 5/964.50 to 5/974.50) under SCDP (D-32) 5054-04-789-01)	492879.00	10000.00	350.00	One month	Class D or above

TERMS AND CONDITIONS:-

1. The earnest money in the shape of National Saving Certificate, Time Deposit Account in any of the post office in HP/FDR of any Bank duly pledged in favour of Executive Engineer, Chopal Division HPPWD Chopal must be accompanied with the application for receipt of tender form along with cost of tender form in cash (Non refundable).
2. The conditional tender(s) and the application received without earnest money will summarily be rejected without assigning any reason(s).
3. The contractors/firms should possess the following documents (photo copy to be self attested with application for obtaining the tenders documents :-
 - a. Latest enlistment/renewal orders with application.
 - b. GST Number issued by the Sale Tax Department.
 - c. PAN (Permanent Account Number) issued by the Income Tax Department shall contain scanned copies of EPF issued from competent authority.
4. The Executive Engineer, Chopal Division HPPWD Chopal reserves the right to reject any tender without assigning any reason(s).
5. Only two number tender forms will be issued to the eligible contractor. If he bids for more than two works, only the first two works in sequence will be opened.
6. The work shall has to be started within fifteen days from the date of award. If the contractor fails to start the work within fifteen days, the work shall be cancelled and earnest money deposited will be forfeited.
7. The Cess Charges @ 1% will be deducted from the gross amount of work done of the contractor.
8. The work will be completed by the contractor within the stipulated period.
9. The contractor/firms are required to insert the rate of percentage in words as well as in figures, failing which Executive Engineer reserves the right to accept/reject any/overall tender.
10. The tender shall be issued to only those contractor/firms who are eligible suitable and competent.
11. The tender forms shall be issued to eligible contractors depending upon their past performance and work experience.
12. The contractor/firm having necessary documents and past adequate experience shall be preferred.
13. The contractor who has failed to start/complete the work already allotted in his favour within stipulated period shall not be issued tender forms.
14. A contractor enlisted in a particular class is eligible to tender for his own class and one step below.
15. In case the tender opening/sale date falls on a holiday, the fixed eventualities shall take place on the next working day at the same time and venue.
16. GST will be deducted as per rates fixed by the Government.

CERTIFICATE


It is certified that tender for the above works are urgently required please.


Executive Engineer,
Chopal Division HPPWD Chopal
On behalf of Governor of H.P.

Copy forwarded for information to :-


1. The Chief Engineer (Shimla Zone) HPPWD Shimla.
2. The Superintending Engineer, 04th Circle, HPPWD Shimla.
3. The Deputy Commissioner, Shimla.
4. The SDO(C) Chopal/Kupvi Tehsil Chopal/Kupvi District Shimla H.P.
5. The BDO Chopal Tehsil Chopal District Shimla H.P.
6. All the Assistant Engineers working under this Division.
7. All the intending contractors in HPPWD.
8. Notice Board.


Executive Engineer
Chopal Division



CERTIFICATE

Certified that the tender(s) of work(s) as called vide this
office NIT No. PW.CHD.CB.C-9/2024- 3404-3503 dated
09/08/24 are of urgent nature work(s).


Executive Engineer
Chopal Div. HPPWD Chopal
On behalf of Governor of H.P.

SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 240014
Earnest Money	Rs. 5000
Time Allowed	One Month

Name of work : C/O Bhoot Kenchi to HB Dunglech road km 0/00 to 3/565 (SH : C/O PCC R/wall at R.D. 1/390 to 1/405) Under SCDP (D-32) 5054-04-789-01						
Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.85	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	5639
2	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	43.20	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre.	224640
3	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wingwall return wall with 100 mm dia PVC pipe extending through the full width of the structure with slopes of (1V:20H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	27.30	200.00	Rupees two hundred and paisa zero only	Per running metre.	5460
4	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.50	950.00	Rupees nine hundred fifty and paisa zero only	Per cubic metre.	4275
					Total	240014
	Quoted rate in figure.					
	Quoted rate in words.					


EXECUTIVE ENGINEER
BAR DIVISION HARYANA

SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 382279
Earnest Money	Rs. 8000
Time Allowed	One Month

Name of work : R/R Damages on BMT road km 0/00 to 18/00						
(SH : C/O wire crated B/wall at R.D. 17/320 to 17/335)						
Sl. No	Description of item	Qty.	Rate	In words	Unit	Amount
			In figure			
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	270.00	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	56700
2	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	23.40	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre	121680
3	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	70.31	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre	203899
	Quoted rate in figure.				Total	382279
	Quoted rate in words.					

**Executive Engineer,
B&R Division Hyderabad**

SCHEDULED OF QUANTITY.

Name of work : S/R/R Dmng Dharmata to Makrog road km 0/00 to 9/450				Estimated Cost		Rs. 498650
(SH : C/O R/wall in PCC 1:4:8 at R.D. 3/773 to 3/780)				Earnest Money		Rs. 10000
				Time Allowed		One Month
Sl. No	Description of item	Qty.	Rate	In words	Unit	Amount
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr and a lead upto 20mts as per drawing and technical specifications clause 1603.2 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	48.30	195.00	Rupees one hundred ninety five and paisa zero only	Per cubic metre.	9419
2	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.25	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	2573
3	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	83.16	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre.	432432
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concret abutment wingwall return wall with 100 mm dia PVC pipe extending throught the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.00	200.00	Rupees two hundred and paisa zero only	Per running metre.	6000
5	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.63	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre.	48227
Quoted rate in figure.					Total	498650
Quoted rate in words.						

Executive Engineer
S&R Division H.P.P.V.
Chopel

SCHEDULED OF QUANTITY.

Name of work : C/O road from Dehra Nallah to Dehra road km 0/00 to 1/00

(SH : C/O R/wall at R.D. 0/150 to 0/162) Under deposit work.

Estimated Cost	Rs. 198307
Earnest Money	Rs. 4000
Time Allowed	One Month

Sl. No	Description of item	Qty.	Rate	In words	Unit	Amount
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr and a lead upto 20mts as per drawing and technical specifications clause 1603.2 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.60	195.00	Rupees one hundred ninety five and paisa zero only	Per cubic metre	1677
2	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.00	195.00	Rupees one hundred ninety five and paisa zero only	Per cubic metre	1755
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	38.64	4790.00	Rupees four thousand seven hundred ninety and paisa zero only	Per cubic metre	185086
4	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.44	950.00	Rupees nine hundred fifty and paisa zero only	Per cubic metre	4218
5	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22.00	253.70	Rupees two hundred fifty three and paisa seventy only	Per running metre	5571
	Quoted rate in figure.				Total	198307
	Quoted rate in words.					

Signature
B&R Division Hapur

SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 489434
Earnest Money	Rs. 10000
Time Allowed	One Month

Name of work : A/R & M/O Dhabas to Baghar road km 0/00 to 9/00
(SH : C/O R/wall at R.D. 0/735 to 0/747)

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	32.40	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	6804
2	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	61.28	5200.00	Rupees five thousand two hundred and two paisa zero only	Per cubic metre.	318656
3	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wingwall return wall with 100 mm dia PVC pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	54.00	200.00	Rupees two hundred and two paisa zero only	Per running metre.	10800
4	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to 280 and Is-4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	39.06	2900.00	Rupees two thousand nine hundred and two paisa zero only	Per cubic metre.	113274
5	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	42.00	950.00	Rupees nine hundred fifty and paisa zero only	Per cubic metre.	39900
	Quoted rate in figure.				Total	489434
	Quoted rate in words.					

Executive Engineer,
S&R Division H.P.P.
(Baghar)

SCHEDULED OF QUANTITY.

(6)

Name of work : C/O road from Katali to Kafu road km 0/00 to 1/750

(SH : C/O B/wall at R.D. 1/210 to 1/235)

Estimated Cost	Rs. 352788
Earnest Money	Rs. 7200
Time Allowed	One Month

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax.	96.00	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	20160
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is: 4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	78.12	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre.	226548
3	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	19.50	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre.	101400
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wingwall return wall with 100 mm dia PVC pipe extending through the full width of the structure with slopes of (iv):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00	195.00	Rupees one hundred ninety five and paisa zero only	Per running metre.	4680
	Quoted rate in figure.				Total	352788
	Quoted rate in words.					

214
Executive Engineer,
P&R Division Hapur,
Distt. Sonapatna

SCHEDULED OF QUANTITY.

(7)

Name of work : C/O Link road from Prem Nagar to Gadtrahal Harijan Basti road km 0/00 to 2/500

(SH : Cutting 5/7 metre wide at RD 1/345 to 1/630 .) SCDP (D-32) 5054-04-789-01

Estimated Cost	Rs. 476715
Earnest Money	Rs. 10000
Time Allowed	One Month

Sl. No.	Description of item	Qty.	Rate	In words	Unit	Amount
			In figure			
1	Excavation in earth work in hilly area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformity with the requirement of technical specification for Rural Roads clause 1600 and 300, 8.3 (ii)(iv)(v) to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material in specified manner, trimming, filling of uneven ness, blind age and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. At least 265 Cubic metre useful stone shall be recovered from the contractor in each running bill as per pro-rata basis if fails recovery @ Rs. 300/- (Rupees three hundred) per cum will be made. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. Including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2040.00	233.68	Rupees two hundred thirty three and paisa sixty eight only	Per cubic metre	476715
					Total	476715
	Quoted rate in figure.					
	Quoted rate in words.					

Signature
Executive Engineer
B & R Division Haridwar
Uttarakhand

SCHEDULED OF QUANTITY.

78

Estimated Cost	Rs. 482922
Earnest Money	Rs. 10000
Time Allowed	One Month

Name of work : C/O Link road from Kelvi to Lohana road km 0/00 to 5/00

(SH : C/O Stone Soling at RD 3/500 to 3/860 .) under SCDD (D-32) 5054-04-789-01

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	178.20	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	37422
2	Stone soling properly hand packed filling intereries with kharanja stone and consolidation with power road roller to the required gradient and camber including spreading watering and rolling of widding materials moorum or earth etc including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	178.20	2500.00	Rupees two thousands five hundred and paisa zero only	Per cubic metre.	445500
	Quoted rate in figure.				Total	482922
	Quoted rate in words..					

31
Executive Engineer
B&R Division
Chennai

SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 153000
Earnest Money	Rs. 1000
Time Allowed	10 Days

Name of work : R/R damage on Chambi Section Under Chopal Sub-Division.

(SH : Hiring of JCB for removal of slips/debris etc. on various Rds .)

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Hiring of excavator -cum-loader for removal of slips, dressing of berms etrcnimum six hour per day including P.O.L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of engineer in Charge at site, any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in Charge and as per HPPWD specification of 1990 vol. 1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	150.00	1020.00	Rupees one thousand twenty and paisa zero only	Per Hour	153000
	Quoted rate in figure.				Total	153000
	Quoted rate in words.					

Conditions :-

- 1 All the POL charges shall be borne bt the contractor.
- 2 All the repair of machineres shall be done by the contractor.
- 3 For any minor/major repair or any accident, contractor shall be responsible.
- 4 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.

2/1
Executive Engineer
B&R Division HPPWD
Chopal

SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 183600
Earnest Money	Rs. 1000
Time Allowed	10 Days

Name of work : R/R damage on Pulbahal section Under Chopal Sub-Division.

(SH : Hiring of JCB for removal of slips/debris etc. on various Rds .)

Sl. No	Description of item	Qty.	Rate	In words	Unit	Amount
1	Hiring of excavator-cum-loader for removal of slips, dressing of berms etrcmininum six hour per day including P.O.L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of engineer in Charge at site, any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in Charge and as per HPPWD specification of 1990 vol. 1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	180.00	1020.00	Rupees one thousand twenty and paisa zero only	Per Hour	183600
	Quoted rate in figure.				Total	183600
	Quoted rate in words.					

Conditions :-

- 1 All the POL charges shall be borne bt the contractor.
- 2 All the repair of machineries shall be done by the contractor.
- 3 For any minor/major repair or any accident, contractor shall be responsible.
- 4 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.

2/11
Executive Engineer,
B&R Division HPPWD,
Chopel

SCHEDULED OF QUANTITY.

(11)

Name of work : R/R damage on Marog to Matial road km 0/00 to 18/500

(SH : C/O R/wall at R.D. 1/150 to 1/170)

Estimated Cost	Rs. 417811
Earnest Money	Rs. 8400
Time Allowed	One Month

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	49.05	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	10301
2	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	75.50	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre.	392600
3	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.00	950.00	Rupees nine hundred fifty and paisa zero only	Per cubic metre.	11400
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concret abutment wingwall return wall with 100 mm dia PVC pipe extending through the full width of the structure with slopes of (1/4):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.00	195.00	Rupees one hundred ninety five and paisa zero only	Per running metre.	3510
	Quoted rate in figure.				Total	417811
	Quoted rate in words.					

9/1
Executive Engineer
R/R DIVISION HPTV

SCHEDULED OF QUANTITY.

(12)

Estimated Cost	Rs. 278201
Earnest Money	Rs. 5600
Time Allowed	One Month

Name of work : R/R damage on Marog to Matal road km 0/00 to 17/500

(SH : C/O R/wall at RD 16/280 to 16/292.)

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.78	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	6464
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming IS: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	56.25	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre.	163125
3	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.28	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre.	89856
4	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.28	950.00	Rupees nine hundred fifty and paisa zero only	Per cubic metre.	16416

5	Providing weep holes in brick masonry plain/reinforced concrete abutment wing wall retaining wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (v) 20 (h) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.00	195.00	Rupees one hundred ninety five and paisa zero only	Per running metre.	2340
	Quoted rate in figure.				Total	278201
	Quoted rate in words.					


 Executive Engineer,
 S&R Division HPTV
 Durgam

SCHEDULED OF QUANTITY.

13

Estimated Cost	Rs. 480609.00
Earnest Money	Rs. 10000.00
Time Allowed	One Month.

Name of work : C/o road from Tharoch to Chapur road km 0/00 to 6/00

(SH: Widening of existing road between R D 4/600 to 5/165) Under MNP.

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Excavation in earth work in hilly area all heights and depths, in all kinds of soil including saturated soil comprising of mixed soil ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock all earth work in cutting excavation including rock excavation shall be carried out true to lines grade sides slopes width camber super elevation and level as shown on the drawings or as directed by the Engineer in Charge in conformity with the requirement of technical specification of rural roads clause 1600 and 83 (ii) (iv) (v) to achieve designed formation width including hauling and stacking of material useful construction at suitable sites and safe disposal of Excavated Muck in specified manner in all leads and lifts trimming, filling of unevenness blind age and finishing of the road to specified dimensions or as directed by the Engineer in Charge for smooth riding At least 118.47 cubic metre useful stone shall be recovered from the contractor in each running bill as per pro-rata basis @ Rs.300/- per cum will be made any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	2464.66	195.00	(Rupees one hundred ninety five and paisa zero) only	Per cubic metre	480609.00
	Quoted rate in figure.					480609.00
	Quoted rate in words.					

Signature
 Section Engineer
 P&R Division HPPV
 Chapur

SCHEDULED OF QUANTITY.

14

Estimated Cost	Rs. 170200
Earnest Money	Rs. 3500
Time Allowed	One Month

Name of work : R/R damage on Various road under Shailu Sub Division Nerwa.

(SH : Hiring of JCB for removal of slips clearance of side drain etc)

Sl. No	Description of item	Qty.	Rate In figure	In words	Unit	Amount
1	removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of the contractor which shall to the duly compensated by him in all cases including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1480.00	115.00	Rupees one hundred fifteen and paise zero only	Per cubic metre.	170200
	Quoted rate in figure.				Total	170200
	Quoted rate in words.					

Shailu Engineer,
R/R Division HPPW
Chopel

SCHEDULED OF QUANTITY.

(15)

Estimated Cost	Rs. 492879
Earnest Money	Rs. 10000
Time Allowed	One Month

Name of work : C/O road from Nerva to HB Katainh road km 0/00 to 6/00

(SH : C/O wire crate R/wall at RD 1/230 to 1/237.50, 5/940 to 5/964.50 & 5/964.50 to 5/974.50)

SCDP (D-32) 5054-04-785-01

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 m and a lead upto 20 m as per drawing and technical specification clause 1603.1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	57.80	195.00	Rupees one hundred ninety five and paisa zero only	Per cubic metre.	11271
2	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.75	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	1418
3	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0 4/0 28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	29.90	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre.	155480
4	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	110.31	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre.	319899

5	Providing weep holes in brick masonry plain/reinforced concrete abutment wing wall retaining wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (v) 20 (h) towards drawing face complete as per drawing and technical specification clause 614.709.1204.3.7. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00	200.00	Rupees two hundred and paise zero only	Per running metre.	1600
6	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.38	950.00	Rupees nine hundred fifty and paise zero only	Per cubic metre.	3211
					Total	492879
	Quoted rate in figure.					
	Quoted rate in words.					


 Executive Engineer,
 Back Division Highway
 Department