



Office of  
EXECUTIVE ENGINEER (JND)  
Himachal Pradesh Public Works Department JNR-175015,  
Ph.01908-222033,Fax 222033,e-mail:ere-jog-hp@nic.in

**"CORRIGENDUM"**

The following amendment may be read in the tender which called by the Executive Engineer, B&R Division, HP PWD, Joginder Nagar office vide NIT No. PW-JND-B&R-EA-I/NIT/press/2023-24-6476-6525 dated 20-07-2024 and scheduled to be opened on 29-08-2024 at 11 30 AM

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction & M/T of Link road Village Patku to Changrehar upto Galu School km. 0/00 to 3/500 (SH:- Formation Cutting in km. 2/930 to 3/430)	Rs.4,95,315/-	Rs.9,900/-	Rs.350/-	Class "D"	Three Months
2	A/R & M/O various Non Residential building under HP PWD, Division Joginder Nagar (SH:- Providing and fixing Ceiling, Railing, plastering, Sanitary fitting and steel work in Divisional office Building.)	Rs.3,13,854/-	Rs.6,300 /-	Rs.350/-	Class "D"	Three Months
3	A/R & M/O various Residential/ Non- Residential building under HP PWD Division Joginder Nagar (SH:- Providing and fixing Solar light)	Rs.86,786/-	Rs.1,700 /-	Rs.350/-	Class "D"	Two Months

**INSTEAD OF:-**

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction & M/T of Link road Village Patku to Changrehar upto Galu School km. 0/00 to 3/500 (SH:- Formation Cutting in km. 2/930 to 3/430)	Rs.4,86,071/-	Rs.9,700/-	Rs.350/-	Class "D"	Three Months
2	A/R & M/O various Non Residential building under HP PWD, Division Joginder Nagar (SH:- Providing and fixing Ceiling, Railing, plastering, Sanitary fitting and steel work etc.)	Rs.3,13,854/-	Rs.6,300 /-	Rs.350/-	Class "D"	Three Months
3	A/R & M/O various Residential/ Non- Residential building under HP PWD Division Joginder Nagar (SH:- Providing and fixing Solar light)	Rs.1,02,354/-	Rs.2,100 /-	Rs.350/-	Class "D"	Three Months

Other terms and conditions shall remain un-changed.

Executive Engineer,  
B&R Division, HP PWD.,  
Joginder Nagar.

No. PW-JND-B&R/EA-I/Tender/2024-25- 9281-9305

Dated:- 14/08/2024

Copy forwarded to the following:-

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,  
B&R Division HP PWD,  
Joginder Nagar.



# **SCHEDULE OF QUANTITY**

Name of work : <b>A/R &amp; M/O to Various Non-Residential Buildings Under HP.PWD., Division Joginder Nagar (SH: Providing and Fixing Ceiling, Railing, Plastering, Sanitary fitting and Steel work in Divisional Office Building)</b>					Estimate Cost: Earnest Money: Time Limit :			3,13,854.00 6,300.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit		Rate		AMOUNT	
					Figures	Words	Rs.	P
1	15mm (Fifteen millimeter) cement plaster in single coat on the Rough side in cement mortar 1:6 (one Cement : six Sand). of brick/concrete/stone walls for plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	112.27	Per Square Metre					
2	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on undecorated wall surfaces(two coats)to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	112.27	Per square metre					
3	Providing and fixing floor mounted, white vitreous china single piece, double traps syphonic water closet of approved brand make, shape, size and pattern including integrated white vitreous china cistern of capacity 10 (ten) litres with dual flushing system, including all fittings and fixtures with seat cover, cistern fittings, nuts, bolts and gasket etc including making connection with the existing P S trap, complete in all respect as per directions of Engineer-in-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each					
4	Providing and fixing vitreous china dual purpose closet suitable for use as squatting pan or European type water closet (Anglo Indian W.C pan) with seat & lid fixed with C.P. brass hinges and rubber buffers, 10 (ten) litre low level flushing cistern with fitting and brackets, 40 mm (Forty millimeter) flush bend, 20 mm (twenty millimeter) over flow pipe, with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each					



Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1732.80	Per Kilogramme			
6	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (zero point five millimeter) (+ 0.05 %) (plus zero point zero five percent) total coated thickness with zinc coating 120 (one hundred twenty ) grams per sqm as per IS: 277, in 240 (two hundred forty) mpa steel grade, 5-7 (five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.00	Per Square metre			
7	Providing and fixing cushion at seat and back on benches. Seat/back cushion should be made of foam covered with best quality fabric. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.38	Per Square metre			
8	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty with Float glass panes of nominal thickness 4 mm (four millimeter) (weight not less than 10kg/sqm)(ten kilogramme per square meter). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.63	Per Square metre			




Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
9	Providing and fixing wash basin with C.I. brackets, 15 mm (fifteen millimeter) C.P. brass pillar taps, 32 mm (thirty two millimeter) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require White Vitreous China Wash basin size 630x450 mm (six hundred thirty by four hundred fifty millimeter) with a single 15 mm (fifteen millimeter) C.P. brass pillar tap as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
10	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 600 mm (six hundred millimeter) long towel rail with total length of 645 mm (six hundred forty five millimeter) , width 78 mm (seventy eight millimeter) and effective height of 88 mm, (eighty eight millimeter) weighing not less than 190 gms. (one hundred ninety millimeter). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.00	Each			
11	Providing and fixing 15 mm (fifteen millimeter) nominal bore C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931 .The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
12	Providing and fixing 600x450 mm (six hundred by four hundred fifty millimeter) beveled edge mirror of superior glass (of approved quality) complete with 6 mm (six millimeter) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.00	Each			
13	Providing and fixing 15 mm (fifteen millimeter) nominal bore C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms.(six hundred ninety grammes) . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each			



Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
14	Providing and fixing PVC connection pipe with brass unions 45cm (fourty five centimeter) long 15mm (fifteen millimeter) nominal bore complete with all accessories as required as per the direction of Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
15	Providing and fixing 8 mm (eight millimeter) dia C.P. / S.S. Jet with flexible tube upto 1 (one) metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.00	Each			
16	Providing and laying 60mm (Sixty millimeter) thick factory made cement concrete interlocking paver block of M -30 (thirty) grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	19.38	Per Square metre			
17	Providing and fixing M.S. tube hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	236.00	Per Kilogramme			
18	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with Cement mortar 1:6 (one cement isto six coarse sand) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.77	Per Cubic metre			


No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
19	Providing and fixing vitreous China pedestal for wash basin complete recessed at the back for the reception of pipes and fittings as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
	<b>Total</b>					

  
 Executive Engineer  
 B & R Division HP.PWD,  
 Joginder Nagar



**SCHEDULE OF QUANTITY**

Name of work :- A/R & M/O to Various Residential Buildings Under HP.PWD., Division Joginder Nagar (Sh: Providing and Fixing Solar Light System in Type -III & Type -IV PWD Qtrs. )				Estimate Cost: Earnest Money: Time Limit :			86,786.00 1,700.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	Rs.	P
				Figures	Words			
1	Providing and fixing double side Solar Street light including 15 (fifteen) watt 2 (two) Nos light and 60 (sixty) watt solar pannel and with necessary structure having 6 (six) meter 75mm (seventy five milimeter) diameter G.I. Pole complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each					
2	Providing and Fixing 40 (Fourty) watt three in one wall mount Solar Street light with necessary structure complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each					
		<b>Total</b>						

  
 Executive Engineer  
 B & R Division HP.PWD.  
 Joginder Nagar