



**Office of
Executive Engineer B&R Division HP.PWD, Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in**

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P.) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 12-09-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 10-09-2024 up to 10:00 A.M. to 12:30 P.M. and tender form can be had from this office on 11-09-2024 from 2.00 P.M. to 5.00 P.M. The earnest money as shown against each in the shape of F.D.R. of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost tender form	Eligible Class of Contractor	Time
1	Restoration of rain damages on Majhamu Kundanu Kufroo road km. 0/00 to 6/50 (SH:- C/O Retaining wall to protection of Sinking portion at km. 1/180 to 1/195).	Rx.2,12,021/-	Rx.4,200/-	Rx.350/-	Class "D"	Three Months
2	Construction of Dhaghon Salehra Fagla road km. 0/00 to 3/500 (SH:- C/O Providing and laying Wearing Grade-II at km. 0/00 to 0/400).	Rx.2,76,903/-	Rx.5,500/-	Rx.350/-	Class "D"	Three Months
3	Restoration of rain damages on various roads under Joginder Nagar Sub Division HP PWD, Joginder Nagar (Harabag Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc).	Rx.99,560/-	Rx.2,000/-	Rx.350/-	Class "D"	One Months
4	Restoration f Joginder Nagar Sarkaghat Ghumarwin road. in km. 0/00 to 34/300 (SH:- Construction of Breast wall at km. 5/905 to 5/912).	Rx.1,63,205/-	Rx.3,300/-	Rx.350/-	Class "D"	Three Months
5	Restoration of rain damages on Dhelu Yora Machhyal via Takroo road km. 0/00 to 2/00 (SH:- Providing and laying of wearing G-II & Cement concrete pavement in berms at km. 0/300 to 0/400 & 0/450 to 0/495 & 0/725 to 0/765).	Rx.4,19,974/-	Rx.8,400/-	Rx.350/-	Class "D"	Three Months
6	A/R & M/O on various Non Residential Buildings under Joginder Nagar Division HP PWD, Joginder Nagar Distt. Mandi (H.P.) (SH:- Providing and fixing Aluminum Cabin in 1 st floor at Divisional Office Joginder Nagar).	Rx.64,515/-	Rx.1,700/-	Rx.350/-	Class "D"	Two Months
7	Restoration of rain damages Joginder Nagar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SH:- Construction of Retaining wall at km. 15/450 to 16/465).	Rx.1,95,439/-	Rx.4,000/-	Rx.350/-	Class "D"	Three Months
8	A/R & M/O various road under Joginder Nagar Division HP PWD, Joginder Nagar (SH:- Providing and applying thermoplastic Strips, side continuous line and Zebra Crossing on Sandapattan Baxhai Banwar Kotli road (MDR-57) at km. 32/00 to 35/00 & Darkoti to Nichla Bhadyara km. 8/00 to 9/00).	Rx.4,64,346/-	Rx.8,900/-	Rx.350/-	Class "D"	Three Months
9	Restoration of rain damages on various roads under Lad Bharol Sub Division HP PWD, Lad Bharol (Tullah Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc).	Rx.99,560/-	Rx.2,000/-	Rx.350/-	Class "D"	One Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/Firm shall have his registration and GST No. the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033


No. PW-JND-B&R-EA-I/NIT/Press/2023-24- 7721-70

Dated:- 02/08/2024

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.65	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry/plant or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	22.00	Each			
	Total					


 Executive Engineer
 B & R Division HP PWD,
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of Dhaghol Salehra Fagla road km 0/00 to 1/500 (Sub Head:- Providing and laying Wearing Grade-II at km 0/00 to 0/400)					Estimate Cost: Earnest Money: Time Limit :		2,76,903.00 5,500.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit		Rate		AMOUNT Rs.	P
					Figures	Words		
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the intersities of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	96.08	Per Cubic metre					
	Total							

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

Estimated Cost:-	99060.00
Earnest Money:-	2000.00
Time:-	one month

Name of work:- Restoration of rain damages on various roads under Joginder Nagar Sub Division No.II, HPPWD Joginder Nagar (Harabag Section). (SH: Hiring of excavator cum loader for removal of slips, dressing of berms, cleaning of road side drains, debris and C/o road side katcha drains etc.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one, point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc, i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	75.00			Per working hours	
						Total:-

Executive Engineer,
B&R Division HP PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Joginder Nagar Sarkaghat Ghumarwin Road km 0/00 to 34/300 (SH: Construction of Breast wall at km 5/905 to 5/912)					Estimate Cost: 1,63,205.00 Earnest Money: 3,300.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.52	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	19.95	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	29.82	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Dhelu Yora Machhyal via Tikroo road km 0/00 to 2/00 (S.H. : Providing and laying of Wearing G-II & Cement Concrete pavement in berms at km 0/300 to 0/400 & 0/450 to 0/495 & 0/725 to 0/765)					Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of coarse aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.50	Per Cubic metre				
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS.383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and emire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	55.97	Per Cubic metre				
Total							


 Executive Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of work : A/R & M/O on Various No-Residential Buildings Under Joginder Nagar Division HP.PWD Joginder Nagar Distt. Mandi (H.P.) (SH: Providing and Fixing Aluminum Cabin in 1st floor at Divisional Office Joginder Nagar)				Estimate Cost: Earnest Money: Time Limit :		84,515.00 1,700.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber, neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge, (Glazing, paneling and dash fasteners to be paid for separately) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket require (Fittings shall be paid for separately) for fixed portion Powder coated aluminium (minimum thickness of powder coating 50 (fifty micron) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	91.76	Per Kilogramme				
2	Providing and fixing machine moulded aluminium covering of approved pattern & design, made out of machine cut aluminium sheet and machine holed for receiving dash fastener, over expansion joints on vertical surfaces/ceiling floors, the fixing on plate in one row on one side of joint only shall be done with stainless steel dash fasteners of 8 mm (eight millimeter) dia and 75 mm (Seventy five millimeter) long hole including providing aluminium washers 2 mm (two millimeter) thick & 15 mm dia (fifteen millimeter diameter) . at a staggered pitch of 200mm (two hundred millimeter) centre to centre including drilling holes in the receiving surface and providing expandable plastic sleeves in holes etc. complete as per direction of Engineer-in-charge Powder coated aluminium sheet 2.5mm (two point five millimeter) thick (minimum thickness of powder coating 50 (fifty micron) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	79.49	Per Kilogramme				
3	Providing and fixing 250x16mm (two hundred fifty by sixteen millimeter) Size anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each				

Description of work

No. or Qty.	Unit	Rate		AMOUNT Rs. P
		Figures	Words	
4. Providing and fixing anodized aluminium tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 250x10mm (Two hundred fifty into ten millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	Each			
5. Providing and fixing anodized aluminium handle anodized transparent or dyed to required shade or colour with necessary screws etcetra complete, 125mm (one hundred twenty five millimeter) size as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	Each			
6. Providing and fixing aluminium hanging floor Single rubber door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	Each			
7. Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg (thirty five kilogramme) and door width upto 700 mm (seven hundred millimeter)), with necessary accessories and screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	Each			
Total				

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages Joginder Nagar Sarkaghat Ghumarwin Road km 0/00 to 34/300 (SH: Construction of Retaining wall at km 16/450 to 16/465)					Estimate Cost: 1,98,489.00 Earnest Money: 4,000.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.70	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plumbs and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.40	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.10	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	14.00	Each			
	Total					


 Executive Engineer
 B & R Division HP, PWD,
 Jopinder Nagar

SCHEDULE OF QUANTITY

Name of Work : A/R & M/O Various road under Joginder Nagar Division HPPWD Joginder Nagar (SH: Providing and Applying Thermoplastic Strips, Side continuous line and Zebra Crossing on Sandapattan Bashai Banwar Kotli Road (MDR-57) at km 33/00 to 35/00 & Darkoti to Nichla Bhadyara km 8/00 to 9/00					Estimate Cost: Earnest Money: Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Road marking with hot applied thermoplastic compound with reflectorising glass baard on bitumenous surface. Providing and laying of hot applied thermoplastic compound 2.5mm (two point five millimeter) thick including reflectorising glass beads @ 250 gm/sqm (two hundred fifty grammes per square meter) area thickness of 2.5mm (two point five millimeter) is exclusive of surface applied glass beads as per IRC:35. The finished surface to be uniform and free from streaks and holes as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	612.30	Per cubic metre			
Total						

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Schedule of Quantity

Estimated Cost:- 99050.00
 Earnest Money:- 2000.00
 Time:- One month

Name of work:- Restoration of rain damages on various roads under Lad-Bharoi Sub-Division HP PWD, Lad-Bharoi (Tullah Section) (Sub Head:- Hiring of excavator cum loader for removal of slips dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/towner at his own risk shifting machinery from one place to other place will be absolute responsibility of the contractor. only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-in-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
Total:-						


 Executive Engineer-
 B&R Division HP PWD,
 Jalandhar Nagar