

Himachal Pradesh  
Public Works Department  
No. PWN/CB/2<sup>nd</sup> C /Tender/2024-25/ 1845-54

Dated 01/08/2024


To

The Executive Engineer ( I.T. Cell)  
HPPWD Nirman Bhawan, Nigam Vihar,  
Shimla-2  
cc-pwd-hp@nic.in


Subject: Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice inviting tenders for uploading on department web-site as per Notification of the Principal Secretary (PW) to the Govt. of Himachal Pradesh Letter No. PBW-(B)A9(3) 1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.


  
Executive Engineer  
Nurpur Division  
HPPWD Nurpur.

Copy forwarded to the Superintending Engineer 9<sup>th</sup> Circle HPPWD Nurpur for information, please.  
Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell) Nigam Vihar Shimla -2 for information and further necessary action.  
Copy to the Sub Divisional magistrate ( Civil) Nurpur for information.  
Copy forwarded to all the Assistant Engineer Under this division.  
Copy to the various contractor.  
Copy to the Notice Board.

  
Executive Engineer  
Nurpur Division  
HPPWD Nurpur.

CERTIFICATE

It is certified that the tenders called vide this office letter No. PWN/CB/2<sup>nd</sup> C/ Tender/2024-25/ 1845-54 dated 01.08.2024 are urgent in nature and also in the public interest.

  
Executive Engineer,  
Nurpur Division,  
HPPWD, Nurpur.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**TENDER**

Scaled item rate tenders on the form 6 & 8 are hereby invited by the Executive Engineer Nurpur Division HPPWD.. Nurpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

**TENDER SCHEDULE**

1.	Date and time of receipt of application for tender form	16.08.2024	Up to 02.00 PM
2.	Date and time of issue of tender form	17.08.2024	Up to 04.00 PM
3.	Date and time of receipt of tenders	19.08.2024	Up to 11.00AM
4.	Date and time of opening of tenders	19.08.2024	At 3.00 P.M.

The tenders form will be issued against cash payment (non-refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P. duly pledged in the name of the Executive Engineer Nurpur Division HPPWD Nurpur must accompany with each tender.

Sr. No.	Name of work.	Estimated cost (Rs.)	Earnest money	Time limit	Cost of form	Eligible class of Contractor
1.	Restoration of rain damages on Rinna PanoduPachan road Km 0/00 to 3/00 (SH: C/O G.I. wire crtae work at RD 2/450 to 2/472.50) R/S	448159/-	10000.00	One Month	350/-	Class -D
2.	Restoration of rain damages on Bhadwar to Sudiyal road Km 0/00 to 10/00 (SH: Const of crate work at RD 2/890 to 2/905 and 4/325 to 4/350)	484384/-	10000.00	One Month	350/-	Class -D
3.	A/R & M/O Madanpur to sanoh road Km 0/00 to 4/475 (SH: Const. of Retaining wall at RD 3/315 to 3/338) Height 3.50 Mtr	374765/-	8000.00	One Month	350/-	Class -D
4.	Restoration of rain damages on Makore jamun Chakki road Km 0/00 to 3/750 (SH: Const of Pushta Type retaining wall at RD 3/723 to 3/729)	491382/-	10000.00	One Month	350/-	Class -D
5.	Restoration of rain damages on Jounta to Khel road Km 0/00 to 6/555 (SH: C/O G.I. wire crate work at RD 2/450 to 2/463.75( 4 layers)	498480/-	10000.00	One Month	350/-	Class -D
6.	C/O MohtaliIndora A-I –A-II to PuccaTiala road Km 10/00 to 19/260 (SH: Providing and fixing “W” metal Beam Crash Barrier at RD 13/090 to 13/138 ( length = 48.00) Mtr	235816/-	5000.00	One Month	350/-	Class -D
7.	Restoration of rain damages on Bihari Di Hatti to Baranda road Km 3/500 to 4/00 ( SH: Providing and laying wearing Grade-II in Km 4/100 to 4/140)	80000/-	2000.00	One Month	350/-	Class -D
8.	Restoration of rain damages on Charuri to Mehta road Km 0/00 to 2/00(SH: providing and laying 25mm thick Mix Seal surfacing at various reaches from Km 0/00 to 2/00)	488207/-	10000.00	One Month	350/-	Class -D
9.	A/R & M/O Nagabari to Nalla road Km 8/00 to 19/300 (SH: providing and laying Bitumen mecadum in patches in between Km 11/00 to 12/00)	421116/-	10000.00	One Month	350/-	Class -D
10.	Restoration of rain damages on Gangath to Dadoh –II Km 0/00 to 5/00 (SH: C/O G.I. wire crate work at RD 0/825 to 0/840 ( length = 15.00 Mtr)	464155/-	10000.00	One Month	350/-	Class -D

11.	Construction of link road from Minjgram to connect Rohiyathar road Km 0/00 to 1/800 (SH: Const of Retaining wall at RD 1/700 to 1/717.75 Ht. 4.88 Mtr 8.8)	499451/-	10000.00	One Month	350/-	Class -D
12.	Construction of link road from Minjgram to connect Rohiyathar road Km 0/00 to 1/800 (SH: Const of retaining wall at RD 1/700 to 1/717.75 Ht. 4.88 Mtr 1.8)	499451/-	10000.00	One Month	350/-	Class -D
13.	A R & M O Mohali Indora A-II-I to PuccaTiala road Km 10/00 to 19/260 (SH: To facilitate the working of Drawing Branch in Nurpur Division HPPWD Nurpur)	208635/-	4300.00	One Month	350/-	Class -D
14.	Restoration of rain damages on Bassa to haler road Km 0/00 to 2/300 (SH: Const of Parapets and cement concrete pavement at RD 0/00 to 0/500)	387791/-	8000.00	One Month	350/-	Class-D
15.	A R & M O various residential building in HPPWD Colony at Nurpur (SH: Plastering, painting and distemping in boundary wall and Driver room)	235529/-	5200.00	One Month	350/-	Class-D
16.	Restoration of rain damages on Tikka Nagrota HathiDhar road Km 0/00 to 9/00 (SH: C/O Crate work at RD 0/195 to 0/211)	495338/-	10000.00	One Month	350/-	Class -D
17.	Restoration of rain damages on Jounta to Khel road Km 0/00 to 6/555 (SH: C/O crate work at RD 4/710 to 4/760) Two layer	498157/-	10000.00	One Month	350/-	Class -D
18.	Improvement of link road from Shah Da More to Bharmoli via Tund road (SH: providing and laying interlocking concrete paver block 80mm thick at RD 1/372 to 1/467)	480909/-	10000.00	One Month	350/-	Class -D
19.	Restoration of KhajjanhatliKotPlahri road Km 0/00 to 9/00 (SH: Const of R/wall at RD 2/050 to 2/068)	423895/-	10000.00	One Month	350/-	Class -D
20.	Restoration of rain damages on MakorejamunChakki road Km 0/00 to 3/750 (SH: Const of Pushta Type Retaining wall at RD 3/707 to 3/713)	492382/-	10000.00	One Month	350/-	Class -D
21.	Restoration of rain damages on Makore Jamun Chakki road Km 0/00 to 3/750 (SH: Const of Pushta Type retaining wall at RD 3/715 to 3/721)	491382/-	10000.00	One Month	350/-	Class -D
22.	Restoration of rain damages on Madanpur sanoh road Km 0/00 to 4/475 (SH: C/O Crate work at RD 4/200 to 4/215)	219225/-	4500.00	One Month	350/-	Class -D
23.	Restoration of rain damages on Jounta to Khel road Km 0/00 to 6/555 (SH: C/O G.I. wire carte work from RD 2/890 to 2/902.50)	197268/-	4000.00	One Month	350/-	Class -D
24.	Restoration of rain damages on TikkaNagrotaHathiDhar road Km 0/00 to 9/00 (SH: C/O G.I. wire crate work from RD 6/210 to 6/220.50) 2 <sup>nd</sup> step	196041/-	4000.00	One Month	350/-	Class -D
25.	Restoration of rain damages on TikkaNagrotaHathiDhar road Km 0/00 to 9/00 (SH: C/O G.I. wire crate work from RD 1/020 to 1/027)	198031/-	4000.00	One Month	350/-	Class -D

6	Restoration of rain damages on Tikka Nagrota HathiDhar road Km 0/00 to 9/00 (SH: C/O G.I. wire crate work from RD 8/810 to 8/822.50) 2 <sup>nd</sup> Step	196656/-	4000.00	One Month	350/-	Class -D
27.	Restoration of rain damages on TikkaNagrotaHathiDhar road Km 0/00 to 9/00 (SH: C/O G.I. wire crate work from RD 2/440 to 2/452.50)	196347/-	4000.00	One Month	350/-	Class -D
<b>The contractors/firms should possess the following documents (Photocopy to be attached) :-</b>						
1	The contractor/Firms should be enlisted with the HPPWD.					
2	PAN (Permanent Account No.)					
3	Registration under GST					
4	The Earnest money in the shape of National Saving certificate / time deposit account in any of the post office in HP FDR from any nationalized bank duly pledged in favour of the Executive Engineer Nurpur Division HPPWD Nurpur.					
5	The earnest money and cost of tender form for the above works should be submitted with the application for the purchase of tender form. The application received without earnest money & cost of tender form shall summarily be rejected.					
6	The offer of tender shall remain valid upto 75 days after the opening of tender.					
7	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case and will be summarilybe rejected.					
8	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s)					
9	If the date given above happens to be holiday the same shall be processed on next working day.					
10	The contractor/firm must quote their rates in words as well as in figures failing which XEN reserves the right to accept/reject any or all tenders.					
11	The tenders forms shall not be issued to those contractors /firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.					
12	One contractor should not have more than two or more works in hand at a time.					
13	Work should be completed by the contractor within stipulated period.					
14	The rates beyond over +5% will be rejected besides this the additional performamnce security will have to borne @ 20% & 30% for unbalanced bid in case rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively. The tender beyond the limit of 30% will also be excepted.					

HIM SUCHNA AVAM JAN SAMPARK.

*(Signature)*  
 Executive Engineer,  
 Nurpur Division, HPPWD,  
 Nurpur,  
 Telephone No. 01893-220033  
 e-mail- ee-nur-hp@nic.in

On behalf of Governor of Himachal Pradesh

# SCHEDULE OF QUANTITY

Estimated Cost: Rs. 448159/-

Earnest Money: Rs. 10000/-

Time Limit: One Month

Name of Work:- Restoration of rain damages on Rinna Panodu Pachan road Km 0/00 to 3/00.  
(SH :- C/O G.I.Wire Crate at RD 2/450 to 2/472.50). R.H.S

Sr.No	Description of Item	Qty.	In Figures	Rate	In Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable matreial.	130.16	364.00	Rupees Three Hundred Sixty Four only.	Per cum	47378.00	
2	Providing and laying boulder approne laid in wire crates with 4mm (four millimeters) dia G.I. wire confirming to i:s: 280 and 4826 in 100mmx100mm (Hundred into hundred) mesh (oven diagonally) including 10% extra for lapse and joints laid with stone boulders weighting not less 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 and as per directions and entire satisfaction of Engineer-in- charge. The rates is including royalty, malkana, toll tax, sale tax or any other taxes and carriage of materials withIn all leads and lifts and other incidental.	140.63	2850.00	Rupees Two Thousand Eight Hundred Fifty only.	Per cum	400781.00	
3	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5	68.40	60.00	Rupees Sixty only.	Per cum	4104.00	
Total :-							448159.00

*Schedule of Quantity Checked and  
Approved By R.S 448159.00 only*

*(Signature)*  
Executive Engineer,  
Nurpur division,  
HPPWB Nurpur.

### SCHEDULE OF QUANTITY

Name of work: Restoration of rain damages on Bhadwar to Sudiyal road km. 0/0 to 10/00 (SH : Const. of crate work at RD. 2/890 to 2/905 and 4/325 to 4/350)

Estimated:-Rs. 484384.00  
Earnest Money :- Rs.4500.00  
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			Figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	62.40 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	22714.00 ✓
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to I:S:280 and I:S 4826 in 100 mm x 100mm ( hundred into hundred ) mesh ( woven diagonally ) including 10% extra for lapse and joints laid with stone boulders weighting not less 25 kg. ( twenty five kilogram ) each as per drawing and technical specifications clause 1301 as per directions of the Engineer-in-charge The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	151.36 cubic meter	3050.00	Rupees three thousand fifty only	Per cubic meter	461670.00 ✓
Total						484384.00

*Schedule of quantity checked and Approved For Rs. 484384/-*

  
Executive Engineer  
Nupur Dign HPPWD

Nupur

Name of work: A/R & M/O Madanpur to Sanoh road km 0/0 to 4/475 ( SH: Const. of Retaining wall at RD. 3/315 to 3/338) Height 3.50 mtr.

# SCHEDULE OF QUANTITY

Estimated:-Rs. **3747651**  
 Earnest Money :- Rs. **373865.00**  
 Time Limit:- Two Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	44.39 cubic meter	360.00	Rs. Three hundred sixty four only.	Per cubic meter	15080.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 ( one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete, as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	82.00 cubic meter	3540.00	Rs. Three thousand five hundred forty only	Per cubic meter	<del>292080.00</del> <b>325680.</b>
3	Back filling with stone boulder behind abutment, retaining walls, and return walls etc. compacted to firm condition complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	25.30 cubic meter	850.00	Rupees seven hundred fifty only	Per cubic meter	21505.00
4	Providing and laying 100mm ( One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) ( one vertical : twenty horizontal ) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental ..	40.00 Number	290.00	Rs two hundred ninety only	Each	11600.00
				<b>Total</b>		<b>374865.00</b>

*Schedule of quantity checked and approved for Rs 374865/-*

Executive Engineer  
 Nurgpur Dym HRPWD  
 Nurgpur

# SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Makore Jamman ( bakki road km 0/0 to 3/750  
(SH: Const. of pushpa type Retaining wall at RD. 3/723 to 3/729 )

Estimated cost Rs. 491382.00  
Earnest money Rs.10000.00  
Time limit :-Two month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	25.50 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	9282.00
2	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 ( M-ten ) nominal mix 1:3:6 ( one cement: three sand: six graded /crushed stone aggregate 40mm) ( forty millimeters ) nominal size in or under water and curing complete including pumping, or bailing out water . dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 ,as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	79.10 cubic meter	4550.00	Rupees four thousand four hundred fifty only	Per cubic meter	359905.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 ( one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	32.50 cubic meter	3550.00	Rupees three thousand five hundredfifty only	Per cubic meter	115375.00

4	Providing and laying boulder filling as per specification to a thickness of not less than 600mm ( six hundred millimeters ) with smaller size towards and provided over the entire surface behind abutment, wing walls, return walls and retaining / breast walls to the full height compacted to firm condition complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	6.00 cubic meter	750.00	Rupees seven hundred fifty only	Per cubic meter	4500.00
5	Providing and laying 100mm ( One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) ( one vertical : twenty horizontal ) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614.709.1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental ..	8.00 No	290.00	Rupees two hundred ninety only	Each	2320.00
			Total			491382.00

*Schedule of Quantity checked And Approved For Rs = 491382/-*

*(Mk-127)*  
Executive Engineer,  
Nurpur Division HPPWD  
Murpur.

# SCHEDULE OF QUANTITY

Estimated Cost: Rs 498480/-  
 Earnest Money: . 2000/-  
 Time Limit- One Month

Name of Work : Restoration of rain Damages on Jounta to Khel road km. 0/00 to 6/555  
 (SH- C/O G.I.Wire Crate Work at RD 2/450 to 2/463.75 (4Layers)

Description of item				
	Qty.	Unit	Amount	
1 Providing and laying boulder apprene laid in wire crates with 4mm (four millimeters) dia G.I. wire confirming to I.S. 280 and 4826 in 100mmx100mm (Hundred into hundred) mesh (oven diagonally) including 10% extra for lapse and joints laid with stone boulders weighting not less 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 and as per the direction and entire satisfactions of Engineer-in-charge including the cost of form work and curing complete, including carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax G S T or other taxes imposed by the Government.	165.50	3000.00 P/Cum.	496500.00	
2 Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 and as per the direction and entire satisfactions of Engineer-in-charge including the cost of form work and curing complete, including carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax G S T or other taxes imposed by the Government.	22.00	90.00 P/Cum	1980.00	
		Total	498480.00	

*Schedule of quantity checked and approved for Rs 498480/-*

*(Signature)*  
 Executive Engineer  
 Nurpur Division HP PWD  
 Nurpur

# SCHEDULE OF QUANTITY

Estimated Cost Rs. 235816/-

Earnest Money Rs-2000/-

Time Limit: One Month

Name of Work :- C/O Mohali Indora A1- A-II to Pucca Tiala road km 10/00 to 19/260

(SH: Providing and fixing "W" metal Beam Crash Barriers at RD 13/090 to 13/138 (Length = 48.00 Mtr.

Sr.No.	Description	Qty	Rate	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material as per directions and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rates is including octroi, royalty, malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	5.57	362.00	P/Cum	2016.00
2	Providing and laying mechanically mixed and vibrated cement concrete grade M-20 (M-twenty ) nominal mix 1:2:4 ( one cement: two sand: four graded /crushed stone aggregate 20mm ( twenty millimetres ) nominal size for plain /reinforced concrete including cost of form work curing in open foundation complete as per drawings and MORO technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	5.57	5350.00	P/Cum	29800.00
3	Providing and erecting "W" metal beam crash Barrier comprising of 3mm ( three millimetres ) thick corrugated sheet metal beam rail 70cm ( seventy centimetre ) above road ground level fixed on ISMC series channels vertical post 150x75x5mm ( one hundred fifty into seventy five into five millimetres ) spaced 2 ( two ) meter below ground ( road level ) all steel parts and fitment to be galvanised by hot dip process all fittings to conform to IS: 1367 and IS 1364 metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm , 330 mm long complete as per clause 810 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, sale tax, GST or any other taxes imposed by the Government	48.00	4250.00	P/Rmt	204000.00
Total					235816.00

*Signature*  
Executive Engineer

Nurpur Division H.P.PWD

Nurpur.

7

Name of work: Restoration of rain damages on Bihari Di Hatti to Baranda road km 3/500 to 4/00 (SH Providing and laying wearing grade-II in km 4/100 to 4/140 )

Estimated:-Rs. 80000.00  
Earnest Money :- Rs.1600.00  
Time Limit:- One Month

Sr. No	Description of Items	Quantity	Rate in		Unit	Amount
			figure	I/Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum ( zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading-II 63mm to 45mm ( sixty three millimetres to forty five millimetres) sizes, 75mm ( seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	50.00 cubic meter	1600.00	Rupees one thousand six hundred only	Per cubic meter	80000.00
				Total		80000.00

*(Signature)*  
Executive Engineer  
Nurpur Division HPPWD.  
Murpur

## SCHEDULE OF QUANTITY

Name of work :- Restoratio of rain damages on Charuri to Melha road km 0/0 to 2/0  
(SH:-Providing and laying 25mm thick Mix seal Surfacing at various reaches from km 0/0 to 2/0 )

Estimated cost Rs. 488207.00  
Earnest money Rs.10000.00  
Time Limit : One Month

Sr No	Description of items.	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Providing and applying tack coat with Bitumen emulsion ( RS-1 ) using emulsion pressure distributor at the rate of 0.225 kg. ( zero point two two five kilogramme ) per square meter on the prepared bituminous surface cleaned with hydraulic broom as per technical specifications 503 including hauling of materials in all leads , lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental charges. The rate is including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	1557.28 square meter	29.00	Rupees Twenty Nine only	Per square meter	45161.00
2	Providing, laying and rolling of close-graded mix seal surfacing materials of 25mm ( twenty five millimeter ) compacted thickness composed of 11.2 mm ( eleven point two millimeter ) to 0.9 mm ( zero point nine millimeter ) Type-A aggregate at the rate of 0.338 cum/ 10 sqm ( zero point three three eight cubic meter per ten square meter ) with penetration grade bitumen S-90 ( S- ninety ) at the rate of 27.50 Kg. ( twenty seven point five zero kilogram ) per ten square metre of road surface, to the required line, grade and level to serve as wearing course on a previously prepared base, including mixing and heating, binder and aggregate in Hot Mix Plant 30/40 ( thirty / forty ) tonne per hour capacity, transporting mixed materials with tipper and laying with paver finisher to the required grade and camber and rolling with a three Wheel 80-100 ( eighty- hundred ) KN static road roller capacity finished to required level and grade as per technical specifications clause No. 509 including hauling of materials in all leads , lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	1557.28 square meter	284.50	Rupees two hundred eighty four and paisa fifty only	Per square meter	443046.00
					Total	488207.00


*(Signature)*  
Executive Engineer  
Nurpur Division HP PWD  
Nurpur

# SCHEDULE OF QUANTITY

Name of work: A/R & M/O Nagabari to Nallah road km 8/0 to 19/300 (SH Providing and laying Bitumen macadam in patches in between km 11/0 to 12/0)

Estimated:-Rs. 421116.00  
Earnest Money :- Rs.10000.00  
Time Limit:- One Month

Sr. No	Description of Items	Quantity	Rate in		Unit	Amount
			figure	Words		
1	Providing and laying 50mm ( fifty millimeter) thick bituminous macadam with hot mix plant using crushed aggregate of grading as per table 500.4 premixed with bituminous binder transported at site upto a lead of 1000 m (one thousand meter ) laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per technical specifications clause 504 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	47.53 cubic meter	8860.00	Rupees eight thousand eight hundred sixty only	Per cubic meter	421116.00
				Total		421116.00

  
Executive Engineer  
Nurpur Divd HPPWD.  
Nurpur


# SCHEDULE OF QUANTITY

10

Name of Work : Restoration of rain Damages on Gangath to Dadoh -II km 0/00 to 5/00  
(SH- C/O G.I.Wire Crate Work at RD 0/825 to 0/840 (Length= 15.00 Mtr.)

Estimated Cost: Rs 464155/-  
Earnest Money: . 8000/-  
Time Limit- One Month

Sr.No	Description of item	Qty.	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, 50mtr dressing of sides and bottom and back filling in trenches with excavated suitable material and as per the direction and entire satisfactions of Engineer -in -charge including the cost of form work and curing complete, including carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax G S T or other taxes imposed by the Government.	46.88	P/Cum	17064.00
2	Providing and laying boulder aprone laid in wire crates with 4mm (four millimeters) dia G.I. wire confirming to I.S. 280 and 4826 in 100mmx100mm (Hundred into hundred) mesh (oven diagonally) including 10% extra for lapse and joints laid with stone boulders weighting not less 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 and as per the direction and entire satisfactions of Engineer -in -charge including the cost of form work and curing complete, including carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax G S T or other taxes imposed by the Government.	140.63	P/Cum	435953.00
3	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 and as per the direction and entire satisfactions of Engineer -in -charge including the cost of form work and curing complete, including carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax G S T or other taxes imposed by the Government.	123.75	P/Cum	11138.00
			Total	464155.00

  
Executive Engineer  
Nurpur Division HP PWD  
Nurpur

**SCHEDULE OF QUANTITY**

Name of work: Construction of link road from Minigra to connect Behi Pathar road km. 0/0 to 1/800  
(SIH: Const. of Retaining wall at RD. 1/700 to 1/717.75 Ht. 4.88 mtr Right side )

Estimated:-Rs. 499451.00  
Earnest Money :- Rs. 10000.00  
Time Limit:- Two Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	52.90 cubic meter	364.00	Rs. Three hundred sixty four only.	Per cubic meter	19256.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 ( one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete, as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	129.40 cubic meter	3400.00	Rs. Three thousand four hundred only	Per cubic meter	439960.00
3	Providing and laying 100mm ( One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) ( one vertical : twenty horizontal ) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental..	30.00 No.	290.00	Rs two hundred ninety only	Each	8700.00
4	Back filling with stone boulder behind abutment, retaining walls, and return walls etc. compacted to firm condition complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 as per directions of Engineer-in- charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	37.10 cubic meter	850.00	Rupess eight hundred fifty only	Per cubic meter	31535.00
				<b>Total</b>		<b>499451.00</b>

*Schedule of Quantity for Retaining wall*

Executive Engineer  
Nurpur Divn. PWD  
Nurpur

# SCHEDULE OF QUANTITY

Name of work: Construction of link road from Minjgran to connect Behi Pathiar road km. 0/0 to 1/800  
(SH: Const. of Retaining wall at RD. 1/700 to 1/717.75 Ht. 4.88 mtr ~~left~~ side )

Estimated:-Rs. 499451.00  
Earnest Money :- Rs. 10000.00  
Time Limit:- Two Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiselling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	52.90 cubic meter	364.00	Rs. Three hundred sixty four only.	Per cubic meter	19256.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 ( one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water. dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete, as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	129.40 cubic meter	3400.00	Rs. Three thousand four hundred only	Per cubic meter	439960.00
3	Providing and laying 100mm ( One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) ( one vertical : twenty horizontal ) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental ..	30.00 No.	290.00	Rs two hundred ninety only	Each	8700.00
	Back filling with stone boulder behind abutment, retaining walls, and return walls etc. compacted to firm condition complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	37.10 cubic meter	850.00	Rupees eight hundred fifty only	Per cubic meter	31535.00
				Total		499451.00

*Schedule of quantity checked and total*  
*approved for Rs. 499451/- only*

*(Signature)*  
Executive Engineer  
Nurpur Division (P.P.W.D.)  
Nurpur

## SCHEDULE OF QUANTITY

Name of work: A/R & M/O Mohitai Indora All-1 to Pucca Tiala road km 10/0 to 19/260 )  
 (SH: To facilitate the working of Drawing Branch in Nurpur Division HPPWD, Nurpur )

Estimated:-Rs. 208635.00  
 Earnest Money :- Rs.4200.00  
 Time Limit:- 10 Month

Sr. No	Description of Items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	To facilitate the working of Drawing Branch of Nurpur Division HPPWD Nurpur for the period of financial year 2024-25 ( 305 days) to provide all related services on hiring basis complete as per directions / instructions of Engineer in Charge within all leads and lifts and other incidental. The rates is including G.S.T or any other taxes imposed by the Government	305 days	684.05	Rupees six hundred eighty four and paisa zero five only	Per day	208635.00
				Total		208635.00

(Ak-7)   
 Executive Engineer  
 Nurpur Divn/HPPWD/  
 Nurpur

# SCHEDULE OF QUANTITY

Name of work: Restoration of damages on Bassa to Haler road km 0/0 to 2/300 ( SH: Const. of parapets and cement and Concrete pavement at RD 0/0 to 0/500 )


Estimated:-Rs. 387791.00

Earnest Money :- Rs.8000.00

Time Limit:- One Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			Figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In – Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	56.25 cubic meter	364.00	Rs. Three hundred sixty four only.	Per cubic meter	20475.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1 : 4 : 8 ( one cement: four sand :eight graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete, as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	32.50 cubic meter	4450.00	Rs. four thousand four hundred fifty only	Per cubic meter	100125.00
3	Providing and laying ( I S I marked ) inter locking concrete block pavement having thickness 80mm ( eighty millimeters ) over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer -in-charge including carriage of materials. The rates is inclusive royalty, toll tax, G S T or any other taxes imposed by the Government.	112.00 Square meter	1130.00	Ruppes one thousand one hundred thirty only	Per square meter	126560.00
4	Providing and laying mechanically mixed and vibrated cement concrete grade M-20( M-twenty ) nominal mix 1:2:4 ( one cement: two sand :four graded /crushed stone aggregate 20mm ( twenty millimeters ) nominal size for plain /reinforced concrete including cost of form work curing in bed block complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental .. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	20.25 cubic meter	5600.00	Rs. Five thousand six hundred only	Per cubic meter	113400.00

5	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in sub structure for all type of structure i.e. in parapets complete of plain cement concrete grade M-15 (M-fifteen) nominal mix 1:2½:5 (one cement; two and half sand : five graded crushed stone aggregate 20mm (twenty millimeters) including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 804, 805, 806, 807 1202 and 1204 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	5.25 cubic meter	5225.6 0	Rupees three thousand one hundred seventy and paisa sixty only	Per cubic meter	27431.00
						387991.00

  
 Executive Engineer  
 Nurpur Dyn HPPWD,  
 Nurpur


**Schedule of Quantity**  
Name of Work: -A/R & M/O various residential building in HPWD Colony Nurpur  
SH: Plastering, painting and distempering in boundary wall and Driver room)

Estimated Cost: - Rs. 225529.00  
Earnest Money : Rs. 5200.00  
Time Limit One month

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figure	words		
1	Distempering (two coats) with acrylic distemper ( ready mixed ) of approved brand and manufacture and of required shade on decorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth, priming coat with distemper primer complete as per directions of Engineer in charge. The rate including Royalty, Malkhana, Octroi, Toll Tax G S T or any other taxes imposed by the Government	94.33 Square meter	96.85	Rupees sixty nine and paisa eighty five only	Per Square meter.	9136.00
2	Providing and fixing 35mm( thirty five millimeters) thick second class teak wood paneled glazed shutters for doors, windows, and clerestory windows including bright finished black enamelled iron butt hinges with necessary screws including carriage of materials in all leads and lifts. .	6.90 Square meter	3550.00	Rupees three thousand five hundred fifty only	Per square meter	24495.00
3	Providing and fixing 35mm(thirty millimeters) thick second class teak wood wire gauge shutters using galvanized M.S.wire gauge of I.S.gauge designation 85-G ( eighty five-G )with wire of dia 0.56mm (zero point five six millimeters)for doors, windows, and clerestory windows including bright finished black enamelled iron butt hinges with necessary screws and carriage of materials within all leads and lifts The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST or any other taxes imposed by the Government	1.80 square meter	4150.00	Rupees four Thousand one hundred fifty only	Per square meter	7470.00
4	Applying priming coat on decorated wood and wood based surfaces with enamel paint of approved brand and manufactured ( Nerolac/ Assian) to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete with enamel paint other than white complete as per directions of Engineer in charge. The rate including Royalty, Malkhana, Octroi, Toll Tax G S T or any other taxes imposed by the Government	15.36 Square meter	65.00	Rupee sixty five only	Per Square meter.	995.00
5	Painting two or more coats (excluding priming coat) on decorated wood and wood based surfaces with enamel paint of approved brand and manufactured ( Nerolac/ Assian) to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete with enamel paint other than white complete as per directions of Engineer in charge. The rate including Royalty, Malkhana, Octroi, Toll Tax G S T or any other taxes imposed by the Government	15.36 Square meter	108.00	Rupee one hundred eight only	Per Square meter.	1659.00
6	Painting two coats(excluding priming coat ) on decorated steel and other metal surfaces under coat with ready mixed paint brushing to give an even shade including cleaning the surfaces of all dirt, dust, and other foreign matter, with ready mixed paint other than white complete as per directions of	14.90 Square	112.00	Rupees one hundred twelve only	Per Square meter.	1669.00

	Engineer in charge. The rate including Royalty, Malkhana, Octroi, Toll Tax G S T or any other taxes imposed by the Government	meter				
7	Providing and fixing anodized aluminium sliding doors bolts, (anodized transparent or dyed to required colour and shade with bolts and nuts/screws etc. complete including carriage of materials with in all leads and lifts a) 300 x 16mm (three hundred into sixteen) millimeter.	2.00 Each	239.60	Rupees two Hundred thirty nine and paisa sixty only	Each	479.00
8	Providing and fixing anodized aluminium tower bolts, (Barrel type) anodized transparent or dyed to required colour and shade with bolts and nuts/screws etc. complete including carriage of materials with in all leads and lifts a) 250 x 10mm (two hundred forty into ten millimeter.)	6.00 Each	85.60	Rupees eighty five and paisa sixty only	Each	510.00
9	Providing and fixing 125mm aluminium handles, ISI marked, anodised transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of materials with in all leads and lifts	6.00 Each	79.00	Rupees seventy nine only	Each	474.00
10	Providing and fixing aluminium casement stays, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete	5.00 Number	76.00	Rupees seventy six only	Each	380.00
11	Supplying and fixing plain glass panes 4mm (four millimeters) thick with putty in steel doors windows and clerestory windows including removal of broken glass panes where-ever necessary and nails as per directions of Engineer-in-charge including carriage of materials with in all lead and lifts and other incidental charges. The rate includes, royalty charges, octroi, G S T, malkana and all other taxes as imposed by the Government	3.30 square meter	1025.00	Rupees one thousand twenty five only	Per Square meter.	3382.00
12	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	13.56	364.00	Rs. three hundred sixty four only	Per cubic meter	4936.00
13	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 ( M-ten ) nominal mix 1:3:6 ( one cement: three sand: six graded /crushed stone aggregate 40mm) ( forty millimeters ) nominal size in or under water and curing complete including pumping, or bailing out water, dewatering, removal of slush, as required at site which may arise at the time of laying under	13.56 cubic meter	4580.00	Rupees four thousand five hundred eighty only	Per cubic meter	62105.00

	water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government					
14	20mm (twenty millimetres) thick cement plaster with cement mortar 1:4 (One cement : four sand) in single coat on fair side of brick/ concrete/ stone walls for interior plastering upto floor all level including arrises, internal rounded angles, chamfers and/or rounded angles in all girth and finished even and smooth complete	290.48 Square Metres	265.00	Rs. Two hundred sixty five only	Per Square meter.	76972.00
15	Finishing wall with deluxe multi surface paint of approved brand and manufacture of required shade on undecorated wall surfaces ( two or more coats ) to give an even shade after thoroughly brushing the surface to remove all dirt, dust and remains of loose powdered materials	290.48 square meters	106.25	Rs one hundred six and paisa twenty five only	Per Square meter.	30864.00
				Total		225529.00

  
 Executive Engineer  
 Nurpur Division HPPWD  
 Nurpur

## SCHEDULE OF QUANTITY

Name of work: Restoration of rain damages on Tikla Nagrota Hadhi Dhar road km 0/0 to 9/00 ( SH:- C/O Crate work at RD. 0/195 to 0/211)

Estimated:-Rs. 495338.00

Earnest Money :- Rs. 10000.00

Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	98.08 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	35701.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to I.S.280 and I.S.4826 in 100 mm x 100mm ( hundred into hundred ) mesh ( woven diagonally ) including 10% extra for lapse and joints laid with stone boulders weighing not less 25 kg. ( twenty five kilogram ) each as per drawing and technical specifications clause 1301 as per directions of the Engineer-in-charge The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	152.34 cubic meter	2870.00	Rupees two thousand eight hundred seventy only	Per cubic meter	435497.00
3	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structure graded and compacted to meet requirement of Tables 300.1 and 300.2 as per technical specifications clause 301.5 as per directions of Engineer-in-charge. The rates is including royalty , malkana, toll tax , G.S.T or any other taxes and carriage of materials within all leads and lifts and other incidental.	51.75 cubic meter	80.00	Rupees eighty only	Per cubic meter	4140.00
			Total			495338.00

*Schedule of Quantity Check and*  
*Approved Mr. R.S. 495338.00 only*  
 Executive Engineer  
 Nurpur Division HPPWD  
 Nurpur

11

S/N 6 = 12

Name of work: Restoration of rain damages on Jounia to Khel road km 0/0 to 6/555 ( SH:-  
C/O Caste work at RD. 4/710 to 4/760 two layer

Estimated:-Rs. 498157.00  
Earnest Money :- Rs. 10000.00  
Time Limit:- Two Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	85.08 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	30969.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to I.S:280 and I.S 4826 in 100 mm x 100mm ( hundred into hundred ) mesh ( woven diagonally ) including 10% extra for lapse and joints laid with stone boulders weighting not less 25 kg. ( twenty five kilogram ) each as per drawing and technical specifications clause 1301 as per directions of the Engineer-in-charge The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	156.25 cubic meter	2990.00	Rupees two thousand eight hundred seventy only	Per cubic meter	467188.00
Total						498157.00

*Schedule of Quantity Cleared And  
Approved For Rs = 498157 + on*

*(Signature)*  
Executive Engineer  
Nurpur Division HPPWD  
Nurpur

Name of work: Improvement of link road from Shaha Da More to Bharmoli via Tund road ( SH: Providing and Laying interlocking concrete paver block 80mm thick at RD 1/372 to 1/467)

### SCHEDULE OF QUANTITY

Estimated:-Rs. ~~498909.00~~ <sup>1,50,909.00</sup>

Earnest Money :- Rs.10000.00

Time Limit:- Two Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			figure	Words		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1 : 4 : 8 ( one cement: four sand :eight graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete. as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	31.35 cubic meter	4140.00	Rs. four thousand one hundred forty only	Per cubic meter	129789.00
2	Providing and laying ( I S I marked ) inter locking concrete block pavement having thickness 80mm ( eighty millimeters ) over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer -in-charge including carriage of materials. The rates is inclusive royalty, toll tax, G S T or any other taxes imposed by the Government.	313.50 Square meter	1120.00	Rupees one thousand twenty only	Per square meter	351120.00
				Total		480909.00

*Schedule of quantity checked and approved for Rs. 1,50,909/- on*

*(Signature)*  
Executive Engineer  
Nurpur Division HPWD  
Nurpur

**SCHEDULE OF QUANTITY**  
Name of work: Restoration of rain damages on Khajjan Hatli Kot Plahari road Km 0/0 to 9/0  
(SH: Const. of Retaining wall at RD. 2/050 to 2/068 Ht. 4.26 mtr )

Estimated:-Rs. 424554.00  
Earnest Money :- Rs. 10000.00

Time Limit:- One Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
		ty	figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	54.54 cubic meter	364.00	Rs. Three hundred sixty four only.	Per cubic meter	19853.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 ( one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete, as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi. royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	106.56 cubic meter	3550.00	Rs. Three thousand five hundred fifty only	Per cubic meter	378288.00
3	Back filling with stone boulder behind abutment, retaining walls, and return walls etc. compacted to firm condition complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 as per directions of Engineer-in- charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	15.75 cubic meter	825.00	Rupees eight hundred fifty only	Per cubic meter	12994.00
3	Providing and laying 100mm ( One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) ( one vertical : twenty horizontal ) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental ..	44.00 No.	305.00	Rs three hundred five only	Each	13420.00
				Total		424554.00

  
Executive Engineer  
Nurpur Division HPPWD  
Nurpur

# SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Mahore Jammam Chakki road km 000 to 3/750  
(SH: Const. of pushra type Retaining wall at RD. 3/707 to 3/713 )

Estimated cost Rs. 292382.00  
Earnest money Rs.10000.00

Time limit :- Two month

Sr. No.	Description of items	Qty.	Rate in	Words	Unit	Amount
		Figures				
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	25.50 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	9282.00
2	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 ( M-ten ) nominal mix 1:3:6 ( one cement: three sand: six graded /crushed stone aggregate 40mm) ( forty millimeters ) nominal size in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 ,as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	79.10 cubic meter	4550.00	Rupees four thousand four hundred fifty only	Per cubic meter	359905.0
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 ( one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	32.50 cubic meter	3550.00	Rupees three thousand five hundredfifty only	Per cubic meter	115375.00

4	Providing and laying boulder filling as per specification to a thickness of not less than 600mm ( six hundred millimeters ) with smaller size towards and provided over the entire surface behind abutment. wing walls, return walls and retaining / breast walls to the full height compacted to firm condition complete cas per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana. toll tax. G S T or other taxes imposed by the Government	6.00 cubic meter	750.00	Rupees seven hundred fifty only	Per cubic meter	4560.00
5	Providing and laying 100mm ( One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry. plain/reinforced concrete abutment. wing wall. return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) ( one vertical : twenty horizontal ) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614.709.1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	8.00 No	290.00	Rupees two hundred ninety only	Each	2320.00
				Total		491382.00

*Schedule of quantity checked And  
Approved For Rs= 491382 per*

*(Signature)*  
Executive Engineer,  
Nurpur Division HPPWD  
Nurpur.

**SCHEDULE OF QUANTITIES**  
**Name of work :- Restoration of rain damages on Mahore Jammun Chalkki road km 0/0 to 3/750**  
**(SH: Const. of pushra type Retaining wall at RD. 3/715 to 3/7721 )**

Estimated cost Rs. 491382.00  
 Earnest money Rs. 10000.00  
 Time limit :- Two month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	25.50 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	9282.00
2	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 ( M-ten ) nominal mix 1:3:6 ( one cement: three sand: six graded /crushed stone aggregate 40mm ) ( forty millimeters ) nominal size in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802. 803. 1202 and 1203 .as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	79.10 cubic meter	4550.00	Rupees four thousand four hundred fifty only	Per cubic meter	359905.0
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 ( one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	32.50 cubic meter	3550.00	Rupees three thousand five hundredfifty only	Per cubic meter	115375.00

4	Providing and laying boulder filling as per specification to a thickness of not less than 600mm ( six hundred millimeters ) with smaller size towards and provided over the entire surface behind abutment, wing walls, return walls and retaining / breast walls to the full height compacted to firm condition complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	6.00 cubic meter	750.00	Rupees seven hundred fifty only	Per cubic meter	4500.00
5	Providing and laying 100mm ( One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) ( one vertical : twenty horizontal ) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614.709.1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	8.00 No	290.00	Rupees two hundred ninety only	Each	2320.00
			Total			491382.00

*Schedule of quantity checked and  
Approved Eng Rs= 491382 ru*

*GA-14*  
Executive Engineer,  
Nurpur Division HPPWD  
Nurpur.

# SCHEDULE OF QUANTITY

Name of work: Restoration of rain damages on Madanpur to Snoh road km. 0/0 to 4/475 (SH : Const. of crate work at RD. 4/200 to 4/215 )

Estimated:-Rs. 219225.00

Earnest Money :- Rs.4500.00

Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount (in Rupees)
			Figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	13.13 cubic meter	364.00	Rupees three hundred sixty four only	Per cubic meter	4779.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to I:S:280 and I:S 4826 in 100 mm x 100mm ( hundred into hundred ) mesh ( woven diagonally ) including 10% extra for lapse and joints laid with stone boulders weighing not less 25 kg. ( twenty five kilogram ) each as per drawing and technical specifications clause 1301 as per directions of the Engineer-in-charge The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	70.31 cubic meter	3050.00	Rupees three thousand fifty only	Per cubic meter	214453.00
				Total		219225.00

*Schedule of Quantity checked and Approved For Rs = 219225 four*

Executive Engineer  
Nurpur Divy/HPPWD  
Nurpur

# SCHEDULE OF QUANTITY

Name of work: Restoration of rain drainages on Jomta to Khel road km 0/0 to 6/555  
( SH:- C/O G I Wire crete work from RD. 2/890 to 2/902.50 )


Estimated:-Rs. 197268.00

Earnest Money :- Rs.8000.00

Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	59.06 cubic meter	364.00	Rs. Three hundred sixty four only	Per cubic meter	21498.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to I:S:280 and I:S 4826 in 100 mm x 100mm ( hundred into hundred ) mesh ( woven diagonally ) including 10% extra for lapse and joints laid with stone boulders weighing not less 25 kg. ( twenty five kilogram ) each as per drawing and technical specifications clause 1301 as per directions of the Engineer-in-charge The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	58.89 Cubic meter	3000.00	Rs. Three hundred only	Per cubic meter	175770.00
					Total	197268.00

*Schedule of quantity checked and  
A Approved for Rs = 197268/-*

  
Executive Engineer  
Narupur Divd HPPWD  
Narupur

# **SCHEDULE OF QUANTITY**

Name of work: Restoration of rain damages on Tikka Nagrota Hathi Dhar road km 0/0 to 9/0  
( SH- C/O G I Wire crate work from RD. 6/210 to 6/222.50 ) 2<sup>nd</sup> step )

Estimated:-Rs. 196041.00  
Earnest Money :- Rs.8000.00  
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In -Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	55.69 cubic meter	364.00	Rs. Three hundred sixty four only	Per cubic meter	20271.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to I:S:280 and I:S 4826 in 100 mm x 100mm ( hundred into hundred ) mesh ( woven diagonally ) including 10% extra for lapse and joints laid with stone boulders weighting not less 25 kg. ( twenty five kilogram ) each as per drawing and technical specifications clause 1301 as per directions of the Engineer-in-charge The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	58.89 Cubic meter	3000.00	Rs. Three hundred only	Per cubic meter	175770.00
				Total		196041.00

*Schedule of quantity checked And Approved by Rs 196041/-*

*(Signature)*  
Executive Engineer  
Nurpur Divn HPPWD  
Nurpur

# SCHEDULE OF QUANTITY

Name of work: Restoration of rain damages on Tikka Nagrola Hathi Dhar road km 0/0 to 9/0  
( SH:- C/O G I Wire crate work from RD. 1/020 to 1/027)

Estimated:-Rs. 198031.00  
Earnest Money :- Rs.80000.00  
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In – Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	26.30 cubic meter	364.00	Rs. Three hundred sixty four only	Per cubic meter	9573.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to I:S:280 and I:S 4826 in 100 mm x 100mm ( hundred into hundred ) mesh ( woven diagonally ) including 10% extra for lapse and joints laid with stone boulders weighting not less 25 kg. ( twenty five kilogram ) each as per drawing and technical specifications clause 1301 as per directions of the Engineer-in-charge The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	62.82 Cubic meter	3000.00	Rs. Three hundred only	Per cubic meter	188460.00
				Total		198033.00

*Schedule of quantity checked and  
Approved For D-198033 for*

*(Signature)*  
Executive Engineer  
Nurpur Digh HPPWD.,  
Nurpur

## SCHEDULE OF QUANTITY

Name of work: Restoration of rain damages on Tikka Nagrota Hathri Dhar road km 0/0 to 9/0  
( SH:- C/O G I Wire crate work from RD. 8/810 to 8/822.50) 2<sup>nd</sup> step )

Estimated:-Rs. 196656.00  
Earnest Money :- Rs.8000.00  
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In – Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	57.38 cubic meter	564.00	Rs. Three hundred sixty four only	Per cubic meter	20886.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to I:S:280 and I:S 4826 in 100 mm x 100mm ( hundred into hundred ) mesh ( woven diagonally ) including 10% extra for lapse and joints laid with stone boulders weighting not less 25 kg. ( twenty five kilogram ) each as per drawing and technical specifications clause 1301 as per directions of the Engineer-in-charge The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	58.89 Cubic meter	3000.00	Rs. Three hundred only	Per cubic meter	175770.00
				Total		196656.00

*Schedule of Quantity checked and  
Approved For As = 196656 Ru*

*(Signature)*  
Executive Engineer  
Nurpur Dwn HPPWD.,  
Dharpur

26

# SCHEDULE OF QUANTITY

Name of work: Restoration of rain damages on Tikka Nagrota Harhi Dhar road km 0/0 to 9/0  
( SH:- C/O G I Wire crate work from RD. 2/440 to 2/452.50 )

Estimated:-Rs. 196347.00  
Earnest Money :- Rs.8000.00  
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and as per direction / entire satisfaction of the Engineer- In - Charge including setting out, and including dressing of sides and bottom and back filling in trenches including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	56.53 cubic meter	364.00	Rs. Three hundred sixty four only	Per cubic meter	20577.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to I:S:280 and I:S 4826 in 100 mm x 100mm ( hundred into hundred ) mesh ( woven diagonally ) including 10% extra for lapse and joints laid with stone boulders weighting not less 25 kg. ( twenty five kilogram ) each as per drawing and technical specifications clause 1301 as per directions of the Engineer-in-charge The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	58.89 Cubic meter	3000.00	Rs. Three hundred only	Per cubic meter	175770.00
		Total				196347.00

*Selected at quantity checked and  
Approved by AS-196347 for*

*(Signature)*  
Executive Engineer  
Nurpur Diya HPPWD

Nurpur