




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS,
AS CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2024
~~24~~- 8862-70 DATED 28-08-2024 ARE URGENT
NATURE AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before 11.09.2024 up to 11.30 A.M and will be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on 10.09.2024 between 2.00 PM up to 4.30 P.M and the application for issue of tender forms shall be received on 09.09.2024 up to 12.00 Noon.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Repair of Building, Stairs and other works with Boundary wall GHS Baragran (SH: Providing Plinth protection in GMS Baragran (Deposit work BSP/2023/27)	Rs.1,98,381/-	Rs.4,000/-	Rs.350/-	One Month
2	Mahila Mandal Bhawan janehad (SH: Balance work slab, Beams masonry work Ground Floor) (Deposit work VK V/2024/49)	Rs.2,90,846/-	Rs.5,900/-	Rs.350/-	Two Months
3	C/O Upper floor of Kaushal Sudhar Sabha Patt (SH: P/L Brick work, cement plaster Distempering work etc.) (Deposit work SDP/2023/975)	Rs.4,82,945/-	Rs.9,700/-	Rs.350/-	Two Months
4	C/O Shamshan Ghat at Ustchar (SH: P/L M-20 and 1:3:6, R.R. masonry, S.R. masonry etc.) (Deposit work VK V/2023/1645)	Rs.4,08,696/-	Rs.8,200/-	Rs.350/-	Two Months
5	Construction of link road to village Kothikohar to Lal Chakka km 0/00 to 4/500 (SH: Construction of R/wall in wire crates at km 0/645 to 0/656) (Deposit work BSP/2024/14)	Rs.1,98,294/-	Rs.4,000/-	Rs.350/-	Two Months
6	C/O Link road from main road to village Lahar via Patt G.P. Gunehar (SH: P/L Kharnja stone Soling at Km 0/200 to 0/300 & C.C. Pavement at Km 0/200 to 0/302) (Deposit work VK V/2023/460)	Rs.3,71,403/-	Rs.7,500/-	Rs.350/-	One Month
7	Development of Ground at Gram Panchayat Panjala (SH: C/O U-Shape Drain and Grating) (Deposit work SDP/2023/983)	Rs.1,98,105/-	Rs.4,000/-	Rs.350/-	Two Months
8	C/O Pulli on Laah Nallah (SH: C/O Approaches, flooring, railing on damaged slab culvert) (Deposit work VK V/2024/43)	Rs.3,98,214/-	Rs.8,000/-	Rs.350/-	Two Months
9	C/O Road from Main Road Bhirdi to Jogi Basti at Bhirdi Km 0/00 to 0/100 (SH: C/O R/Wall at RD 0/00 to 0/008 and Edge wall at RD 0/00 to 0/011 and P/L Kharnja Stone Soling, C.C. Pavement at RD 0/00 to 0/060) (Deposit work VK V/2024/48)	Rs.3,44,209/-	Rs.6,900/-	Rs.350/-	Two Months
10	C/O Mahila Mandal Bhawan Village Hadi (SH: Site Development & C/O Bhawan upto floor level) (Deposit work VK V/2024/47)	Rs.2,96,409/-	Rs.6,000/-	Rs.350/-	Two Months
11	Community Bhawan/Mahila Mandal Bhawan Near Khanodia Basti Nagehar (SH: P/L M-20 in Columns & Plinth Beam, R.R. masonry upto plinth Level) (Depot work SDP/2023/387)	Rs.1,64,320/-	Rs.3,400/-	Rs.350/-	Two Months
12	C/O Store/Godown at Mahakal Temple (SH: Balance work, Brick Masonary and Conc. 1:3:6 in foundation and Plinth) (Deposit work)	Rs.69,298/-	Rs.1,400/-	Rs.350/-	One Month
13	Providing way side facility at Bhullana (SH: C/O Rain Shelter) (Deposit work SDP/2023/1137)	Rs.1,08,440/-	Rs.2,200/-	Rs.350/-	Two Months
14	Mahila Mandal Bhawan Sunchar (SH: P/L Kota stone flooring ground floor and vitrified tile flooring in first floor) (Deposit work VK V/2024/51)	Rs.1,90,309/-	Rs.3,900/-	Rs.350/-	Two Months
15	Restoration of Rain Damages on Govt. Sr. Sec. School Chobin (SH: C/O R/Wall for Protection of Toilet and Ground) (Deposit work)	Rs.2,97,235/-	Rs.6,000/-	Rs.350/-	Two Months
16	R/D Manghlota to Pantehar Road Km 0/00 to 40/00 (SH: C/O R/wall at RD 3/230 to 3/242)	Rs.3,33,673/-	Rs.6,700/-	Rs.350/-	Two Months
17	A/R & M/O various road under Bir Sub Division Bir (SH: Supplying and stacking of Granular sub base)	Rs.2,49,831/-	Rs.5,000/-	Rs.350/-	One Month
18	Restoration of rain damages on Utrala to Surahi Pass road (Km 0/00 to 13/00) (SH: Removal of slips at various reaches)	Rs.4,99,228/-	Rs.10,000/-	Rs.350/-	Two Months
19	Restoration of rain damages on various roads under Deol Section (SH: Hiring of JCB for removal of slips, dressing of road berms, filling depressions, clearance of Drain and Culvert)	Rs.3,74,000/-	Rs.7,500/-	Rs.350/-	Two Months

E.E.

20	Restoration of Rain Damages on Paprola to Utrala road km 0/00 to 12/00 (SH: C/O R/wall at RD 6/200 to 6/209.80)	Rs.4,94,593/-	Rs.9,900/-	Rs.350/-	Two Months
21	C/O Road from Banwar Kuran to Village Uldhar Km 0/00 to 3/00 (SH: Providing laying G-II at RD 0/00 to 0/290 and V-Shape Drain at RD 0/00 to 0/200)	Rs.3,80,955/-	Rs.7,700/-	Rs.350/-	Two Months
22	C/O Dharaman Sungal Jadyala Majherna Chatter Ghar Sagoor Road km 0/00 to 3/00 (SH: Providing and laying C.C. Pavement & Kharnja Soling at Km 0/140 to 0/240)	Rs.4,29,640/-	Rs.8,600/-	Rs.350/-	Two Months
23	C/O Bir Palampur Road Km 0/00 to 40/00 (SH: C/O R/wall at RD 12/920 to 12/930)	Rs.2,13,524/-	Rs.4,300/-	Rs.350/-	Two Months
24	C/O Road from Village Banwar Kuran to Village Uldhar Km 0/00 to 3/00 (SH: C/O R/wall at RD 0/055 to 0/065 & B/wall at RD 0/110 to 0/126)	Rs.4,19,129/-	Rs.8,400/-	Rs.350/-	Two Months
25	C/O Lohardi to Andarli Mallahan Road Km 0/00 to 2/500 (SH: Providing and laying Kharnja Soling at Km 0/00 to 0/250)	Rs.2,62,046/-	Rs.5,300/-	Rs.350/-	Two Months
26	Restoration of rain damages on various Roads under Baijnath Sub Division (Chadhiar Section) (SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & cleaning of slush from catchpit of culverts)	Rs.2,53,000/-	Rs.5,100/-	Rs.350/-	Two Months
27	C/O Link Road from Bir Palampur road to Village Bari 0/00 to 1/200 (SH: Construction of Sub grade and Providing and laying hard stone Soiling at km 0/400 to 0/890)	Rs.4,98,036/-	Rs.10,000/-	Rs.350/-	Two Months
28	R/R Damages on Barot Polling Road Km 0/00 to 8/050 (SH: Balance work of Repair of 2.00 mtr. span slab culvert and Wing Wall at RD 4/307 to 4/315)	Rs.2,91,571/-	Rs.5,900/-	Rs.350/-	One Month
29	C/O Link Road Dharamshala Dadh Holta Chadhiar to Saklani Basti Km 0/00 to 2/060 (SH: P/L C.C. Pavement & WBM G-II at Km 0/315 to 0/454)	Rs.4,97,535/-	Rs.9,900/-	Rs.350/-	Two Months
30	C/O Link Road from Rainabari to Balh (SH: C/O R/Wall at Km 0/00 to 0/017 & 0.60 mtr. Span RCC slab culvert at RD 0/040)	Rs.3,48,243/-	Rs.6,900/-	Rs.350/-	Two Months
31	C/O link road from Rainabari to Balh (SH: Cutting in earth work in Km 1/070 to 1/205)	Rs.4,47,883/-	Rs.9,000/-	Rs.350/-	Three Months
32	C/O Bhirdi to Balh Road via Sunka Ram House Km 0/00 to 2/00 (SH: P/L Tack Coat with Seal Coat at Km 0/00 to 0/250)	Rs.95,275/-	Rs.2,000/-	Rs.350/-	One Month
33	Construction of Tashizong to Bheth Jhikli Bheth Upperli Ghorpith Averi Km 0/00 to 8/915 & Construction of Chobin Sansai & Kothi kohli Via Patel Nagar road Km 0/00 to 13/860 (SH: Supply and fixing Computer system with UPS.)	Rs.1,84,000/-	Rs.3,700/-	Rs.350/-	One Month

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Bajinath Division,
H.P. PWD, Bajinath.
For & On behalf of the Governor of H.P.

NO:-PWD/BD/TA/NIT/2024-25/-

8862-70

Dated:- 28.08.2024

- Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Bajinath Division,
H.P. PWD, Bajinath.

DNIT/DRAFT SCHEDULE OF QUANTITY

①

Name of work: Repair of Building ,Stairs and other works with Boundary wall GMS Baragran .
(Sh:- Providing Plinth protection in GMS Baragran).(Deposit works BSP/2023/27)

Estimate Cost: 1,98,381.00/-
Earnest Money: 4,000.00/-
Time Limit :One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	5.07	Per Cum				
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	28.13	Per Cubic metre				
Total							

Executive Engineer
Bajjnath Division
H.P.P.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- Mahila Mandal Bhawan Janehar

(SH:- Balance work slab , Beams Masonary work Ground Floor) Deposit work (VK V/2024/49)

Estimate Cost:2,90,846.00

Earnest Money:5,900.00

Time Limit : Two Months

Sr.no	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in side soffits of beam hunching cutovers walls up to any width etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	25.83	Per square metre			
2	Providing form work with steel plates 3.15mm thick welded with angle iron in frames 30x30x5cm (thirty into thirty into five) . So as to give fair finish including centering, shuttering strutting and propping etcetera with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4mtr and removal of the same for insitu-reinforced concrete and plain concrete work in Flat surfaces such as soffits of suspended floors, roofs, landing and the like floor etc upto 200mm (two hundred millimeter) 'in thickness The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	49.67	Sqm			
3	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in edges of slabs and breaks in floors and walls up to any width. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	30.68	Per running metre			

②(b)

4	Providing and laying mechanically mixed and vibrated reinforced cement concrete work grade M-20 design mix to obtain the minimum compressive strength of M-20 N/mm ² with cement contents not less than of 320kg/m ³ (three hundred twenty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in stair cases (except spiral stair cases) excluding landing but including preparing of top surface and finishing of nosing upto all floor level and curing complete including carriage of material within all leads, lifts and other incidental charges complete in all respect as per direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	9.73	Per cubic metre			
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	957.00	P/kg			
6	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Sal wood The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.38	Cum			
7	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	10.88	Per cubic metre			

Executive Engineer

H.P.R. Vaidya, ...

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - C/O Upper floor of Kaushal Sudhar Sabha Patt.

(SH: P/L Brick work , cement plaster Distempering work etc)(Deposit work SDP/2023/975)

Estimate Cost:4,82,945.00

Earnest Money:9,700.00

Time Limit : Two Month

Sr.no	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.56	Per cubic metre			
2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).Sal wood The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.88	Cum			
3	Providing and fixing 40 mm (Forty millimetre) thick panelled glazed or panelled and glazed shutter second class Deodar wood for doors, windows and clear story windows including bright finished black enamelled iron hings with necessary screws as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	22.27	Per Square Metre			
4	Providing and fixing 40 mm (Forty millimetre) thick second class Deodar wood wire gauge shutters using galvanised MS wire gauge of IS gauge designation 85G with wire of dia 0.56 mm (Zero decimal five six millimetre) for doors, windows and clearstory windows including bright finished black enamelled iron hings with necessary screws as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	25.27	Per square metre			
5	Providing and fixing 12mm (Twelve millimetre) Thick Prelaminated board in matt finished ISI marked NO 12823 as per approved shade of viromica / kit ply / nona pan / green ply both side BWP phenol bonded exterior / interior grade panelled shutter with frame of first class Deodar wood including bright finished black enameled butt hinges with necessary screws 40 mm (Forty millimetre) thick shutter as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.00	Per square metre			
6	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.Fixed to openings /wooden frames with rawl plugs screws etc.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	222.75	kg			

7	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete :250x16 mm (two fifty into sixteen millimetre) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each			
8.A	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :250x10 mm (two hundred fifty into ten millimeter) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	4.00	Each			
8.B	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :150x10 mm (one hundred fifty into ten millimeter) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	162.00	Each			
9A	Providing and fixing 125 mm (one hundred twenty five millimeter) size oxidized M.S. handles with the necessary screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	3.00	Each			
9.B	Providing and fixing 100mm (one hundred millimeter) size oxidized M.S. handles with the necessary screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	108.00	Each			
10	Providing and fixing 200 mm (Two hundred fifty millimeter) size oxidized M.S. hooks and eyes. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	27.00	Each			
11	Providing and fixing 10mm (ten millimeter) thick anti skid water proof stain and impet resistant heavy duty vetrified tiles Niteco or equivalent 600x600mmx10mm (Six hundred by six hundred by ten millimeter) manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm (twelve millimeter) thick cement mortar 1:3 (one cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	64.89	Per square metre			

③(1)

12	20mm (Twenty millimeter) thick cement plaster in single coat on the fair side of brick/concrete/stone walls for interior plastering upto any floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimeters) in girth, in rough side with cement mortar 1:6 (one cement isto six sand) complete including curing as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	54.36	Per square metre			
13	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:6 (1Cement:6 Sand). . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	74.27	Per square metre			

Executive Engineer
Bajnath Division
H.P.R.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

4/10

Name of work :- C/O Shamshan Ghat at Usthad . (SH:-P/L M-20 and 1:3:6 , R R masonry S R masonry Etc .(Deposit work VK V/2023/1645)				Estimate Cost:4,08,696.00 Earnest Money:8,200.00 Time Limit : Two Month		
Sr.no	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil-water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.46	Per Cum			
2.a	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and Centering and shuttering including strutting, propping etc.code no. 5.9.1 Foundations footing bases of column etc for mass concrete The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	17.64	sqm			
2.b	Providing form work with steel plates 3.15mm(three point fifteen).thick welded with angle iron in frame 30x30x5mm (thirty inti thirty into five) . so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 (four) Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in Square, rectangular or polygonal in plan column pillar posts and sturts The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	26.24	Sqm			
2.c	Providing form work with steel plates 3.15mm(three point fifteen).thick welded with angle iron in frame 30x30x5mm (thirty inti thirty into five) . so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 (four) Mtrs. and removal of the same for insitu-reinforced concrete Centering and shuttering including strutting, propping etc. and removal of form work for :Beams Cantilever girder etc	4.32	sqm			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 20 mm nominal size) . as per the direction and entire satisfaction of Engineer-in-Charge.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	2.88	Per cubic metre.			

4(b)

4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	15.96	Per cubic metre			
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1596.00	P/kg			
6	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	10.51	Per cubic metre			
7	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 20mm (twenty) millimeter nominal size mechanical mixed in cement mortar 1:6 (one cement six sand) including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.54	Per cubic metre			
8	Square rubble masonry coursed with hard stone of approved quality in foundation and plinth including racking out joints in cement mortar 1:6 (one cement : six sand) and curing complete including carriage of materials within all leads and lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.86	Per cubic metre			
9	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). 2nd class Sal wood The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.274	Cum			

Executive Engineer
Bajjnath Division
H.P.P.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

5

Name of work: Construction of link road to village Kothikohar to Lal Chakka km 0/00 to 4/500. (SH : Construction of R/wall in wire crates at km 0/645 to 0/656)(Deposit work BSP/2024/14)				Estimate Cost: 1,98,294.00/- Earnest Money: 4,000.00/- Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost	9.24	Per Cubic metre			
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS 4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 1301 Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	63.36	Per Cubic metre			
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1604.7 and section 300, as per direction of Engineer-In-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	9.57	Per Cubic metre			

Executive Engineer
Baljnath Division
N.P.P.W.D., Baljnath

DNIT/DRAFT SCHEDULE OF QUANTITY

6

Name of work :- C/O Link Road from Main Road to Village Lahar Via Patt GP Gunehar .

(SH:-P/L Kharanja stone Soling at km 0/200 to 0/300 & C. C Pavement at km 0/200 to 0/302) (Deposit work VK V/2023/460)

Estimate Cost: 3,71,403.00/-

Earnest Money: 7500.00/-

Time Limit : One Month

SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qrv.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soiling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested graident and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	40.95	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	41.77	Per Cubic metre			
Total						

Executive Engineer
 Baljnath Division
 H.P.P.W.D., Baljnath

DNIT/DRAFT SCHEDULE OF QUANTITY

⑦

Name of Work : Development of Ground at Gram Panchayat Panjala

(S H : C/O U-shape Drain and Grating)(Deposit work SDP/2023/983)

Estimate Cost: 1,98,105.00/-

Earnest Money: 4000.00/-

Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	28.50	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	29.63	Per cubic metre			
3	Steel work welded in built up sections,trusses and framed work,including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint.In beams joists channels ,angles , tee ,flats with connecting plates or angle cleats as in main and cross beams,hip and jack rafters,purlins connected to common rafters and the like.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge	200	Per Kilogram			

Executive Engineer
Bajjnath Division
H.P.P.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

(8) (a)

Name of work : C/O Pulli on Laah Nallah

(Sh:- C/O Approaches , flooring , railing on damaged slab culvert) (Deposit work VK V/2024/43)

Estimate Cost: 3,98,214.00/-

Earnest Money: 8,000.00/-

Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	33.66	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	56.30	Per cubic metre			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	7.24	Per Cum			

4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.00	Each			
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	2.70	Per Cubic metre			
6	20mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises,internal rounded angles,chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth.Cement Mortar 1:6 (1 Cement:6 Sand). The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	45.60	Sqm			
7	Providing and laying hard stone Soiling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested graident and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	2.70	Per Cubic metre			
8	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:4:8 (one cement : four sand :Eight graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.35	Per Cum			

Q b

9	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams, joists, channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	165	Per Kilogram				

(B) (C)

Executive Engineer
Bajjnath Division
H.P.P.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

90

Name of work : C/O Road from Main Road Bhirdi to Jogi Basti at Bhirdi km 0/00 to 0/100

(Sh: C/O R/wall at RD 0/00 TO 0/008 and Edge Wall at RD 0/00 to 0/011 and P/L Kharnja Stone Saling , C C Pavement at RD 0/00 to 0/060) (Deposit works VK V/2024/48)

Estimate Cost: 3,44,209.00/-

Earnest Money: 6,900.00/-

Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	6.35	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	14.96	Per Cum			
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - In- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	5.94	Per cubic metre			

4	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.36	Per Cum			(2) (5)
5	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	7.00	Each			
6	Providing and laying hard stone Soiling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	27.45	Per Cubic metre			
7	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete. of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	27.45	Per Cubic metre			

Executive Engineer
 Balljan Division
 H.P.P.W.D., Balljan

DNIT/DRAFT SCHEDULE OF QUANTITY

10 (a)

Name of work :- C/O Mahila Mandal Bhawan Village Hadi .

(SH:- Sife Development & C/O Bhawan upto floor level) (Deposit work VK V /2024/47)

Estimate Cost:2,96,409.00

Earnest Money:6,000.00

Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	65.52	cum			
2	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental,the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	28.08	Per Cum			
3.a	Centering and shuttering including strutting, propping etc. and removal of form work for :Foundations, footings, bases for columns The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	15.68	sqm			
3.b	Centering and shuttering including strutting, propping etc. and removal of form work for :Columns, piers, abutments, pillars, posts and struts The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	6.36	sqm			
3.c	Centering and shuttering including strutting, propping etc. and removal of form for :beam cantiliver plint beams The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	12.96	sqm			

4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand); 6 graded stone aggregate 20 mm nominal size) : as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	3.74	Per cubic metre.			
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- All work up to plinth foundations, footings, bases for columns level : 1:2:4 (One Cement : Two coarse sand) : Four graded stone aggregate 20 mm (twenty millimeter) nominal size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	9.37	Per cubic metre			
6	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:3:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	15.19	Cum.			
7	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	9.00	Per Cum			
8	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H), towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	14.00	Each			
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	937.00	P/kg			

Executive Engineer
Bajnath Division
H.P.R.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

(11) (a)

Name of work :- Community Bhawan /Mahila Mandal Bhawan Near Khanodia Basti Nagchar (SH:- P/L M-20 in Columns & Plinth Beam , R R masonry upto Plinth Level) (Deposit work SDP/2023/387)				Estimate Cost:1,64,320.00 Earnest Money:3,400.00 Time Limit : Two Months		
Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.82	Per Cum			
2	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and Centering and shuttering including strutting, propping etc.code no. 5.9.1 Foundations footing bases of column etc for mass concrete The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	17.52	sqm			
3	Providing form work with steel plates 3.15mm(three point fifteen).thick welded with angle iron in frame 30x30x5mm (thirty inti thirty into five) . so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 (four) Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in Square, rectangular or polygonal in plan column pillar posts and sturts The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	17.17	Sqm			
4	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs, landings and the like floor etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other Incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	13.04	Per square metre			

(11) (b)

5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.86	Cum.			
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) in foundation Footings and Basis of columns The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	3.49	Per cubic metre			
7	Providing and laying mechanically mixed and vibrated reinforced cement concrete work grade M 20 design mix to obtain the minimum compressive strength of M-20 N.mm ² with cement contents not less than of 320kg/m ³ (three hundred twenty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in suspended floor, roofs, landing and shelves and their support balconies beams girders bressumers and cantilevers upto floor all level and curing complete including carriage of material within all leads, lifts and other incidental charges complete in all respect as per the direction of Engineer-in-Charge.	2.06	Per cubic metre			
8	Providing and laying cement concrete work 1:2:4 (1 Cement:2 Sand:4 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and Coulmn Pillar Posts & sturts and the like and mass concrete. reinforcement for reinforced concrete work in : The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.30	Per cubic metre			
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	822.00	P/kg			
10	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 20mm (twenty) millimeter nominal size mechanical mixed in cement mortar 1:6 (one cement six sand) including curing and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.23	Per cubic metre			

Executive Engineer
 Baljath Division
 H.P.W.D., Baljath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Store/Godown at Mahankal Temple (SH:- Balance work Brick Masonary and Conc. 1:3:6 in foundation and Plinth) (Deposit work)				Estimate Cost: 69298.00
				Earnest Money: 1400.00
				Time Limit : One Month

SCHEDULE OF WORKS						
Sl. No.	Description of work	No.or Qty.	Unit	Rates		AMOUNT Rs. P
				Figures	Words	
1	Brick work using common burnt clay building bricks in foundation and plinth in : Cement Mortar 1:6 (1 Cement : 6 Sand) Second Class Bricks-The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.94	Cum.			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 20 mm nominal size) . as per the direction and entire satisfaction of Engineer-In Charge.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	5.27	Per cubic metre.			

Executive Engineer
Bajjnath Division
N.R.P.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

13 (a)

Name of Work: - Providing way side facility at Bhullana

(Sub Head : C/O Rain Shelter). (Deposit work SDP/2023/1137)

Estimate Cost: 1,08,440.00

Earnest Money: 2200.00

Time Limit : Two Months

SCHEDULE OF WORKS

SL. No.	Description of work	No.or Qty.	Unit	Rates		AMOUNT Rs. P
				Figures	Words	
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.60	Per cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.80	Per cubic metre			
3	Stone filling under floor complete as per PWD specification. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.80	Per Cubic metre			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	3.60	Per cubic metre			
5	Providing and Fixing 100 mm (hundred millimeter) diameter mild steel hollow pipe (heavy grade) embedded Square /Round bar complete as per PWD specification, including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	15.00	Per running metre			
6	Providing and fixing pre-painted sheet roofing of kotar metal single skin trapezoidal sheeting 0.60mm (sixty millimetre) thickness having 1060mm (one thousand sixty millimetre) cover width cover all width 1126mm (one thousand one hundred twenty six millimetre) , 28mm (twenty eight millimetre) crest depth at 353mm (three hundred fifty three millimetre) 2.50mm (two point fifty millimetre) the main crest with at top 25mm (twenty five) and at lower 81mm (eighty one millimetre) base metal of coil rolled steel coil with zinc waiting top coat with regular modified polysters coating of approved shade and balancing reverse coat with self topping screws 5.5mm (five decimal five millimetre) dia and 55mm (fifty five millimetre) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	19.11	Per square metre			
7	Providing and fixing plating M.S. B.P. sheet 1.66mm (one decimal sixty six millimetre) thick to 2.00mm in evels board/ Facia / Sofit / Ceiling including cutting fixing jointing with gass/electric welding to steel roof members and applying a coat of red lead primer complete as per PWD specification (frame work is to be measured paid for separately). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.64	Per square metre			

(13) (6)

8	Painting two or more coats(excluding priming costs) on new steel and other metal surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	38.40	Per square metre			
9	Kota stone slab 20 mm (twenty millimeter) thick base of cement mortar 1:4 (one cement :four sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slabs including rubbing and polishing 20 25 mm thick The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	15.00	Per square metre			
10	Providing plinth protection 50mm (fifty millimeters) thick cement concrete 1:3:6 (one cement isto three sand isto six aggregate) 20mm (twenty millimeters) nominal size crushed/broken stone aggregate including finishing the top surfaces of concrete smooth including curing complete as per PWD specification, drawing and design including entire carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	11.28	Per square metre			
11	Writing letters or figures on any surface with synthetic enamel paint (sops , comas,hypens and the like not to be measured and paid separately indian letters / figures complete as per PWD specification, drawing and design including entire carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	900.00	Per centimeter metr			

Executive Engineer
Bajjnath
H.P.P.W. Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

(14) (a)

Name of work :- Mahila Mandal Bhawan Sunehar (SH:- P/L Kota stone flooring ground floor and Vitrified tile flooring in first floor) (Deposit work VK V/2024/51)				Estimate Cost: 1,90,309.00 Earnest Money: 3,900.00 Time Limit : Two Months		
Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying of Kota stone slab flooring 20mm (average) thick base of cement mortar 1:4 laid over slury mixed with pigment match the shade of slab 20 mm . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	41.26	Per square metre			
2	Providing and fixing 10mm(ten millimeter) thick anti skid water proof stain and impsect resistant heavy duty vetrified tiles Nitco or equivalant 600x600mmx10mm (Six hundred into six hundred into ten millimeter) manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (one cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	50.56	Per square metre			
3	Providing and fixing 12mm (Twelve millimetre) Thick Prelaminated board in matt finished ISI marked NO 12823 as per approved shade of viromica / kit ply / nona pan / green ply both side BWP phenol bonded exterior / interior grade panelled shutter with frame of first class Deodar wood including bright finished black enameled butt hinges with necessary screws 40 mm (Forty millimetre) thick shutter as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.85	Per square metre			
4	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :125 mm (One twenty five millimetre) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	2.00	Each			
5	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete 150x10 mm (one hundred fifty into ten millimeter) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	2.00	Each			
6	Providing and fixing 250x16mm (two hundred fifty by sixteen milimeter) Size anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each			

(14) (b)

7	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	381.24	kg			
8	Distempering (two coats) with synthetic washable distemper of Asian/ Nerolac brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including and priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	133.46	Per square metre			
9	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	21.29	sqm			
10	Painting two coat (excluding priming coat) on previously painted steel & other metal surfaces with readymixed paint other than white, brushing oil, grease to give an even shade including cleaning the surface of all dirt, dust and other foreign matter The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	47.65	Per square metre			

Executive Engineer
 Baijnath Division
 H.P.P.W.D., Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: Restoration of Rain Damages on Govt Sr. Sec school Chobin .
(Sh:- C/O R/wall for Protection of Toilet and Ground).(Deposit work)

Estimate Cost: 2,97,235.00/-

Earnest Money: 6,000.00/-

Time Limit :Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate	Words	AMOUNT Rs. P
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	23.97	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in- Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	57.63	Per cubic metre			
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.00	Each			
Total						

Exe. Engineer
Bai Division
H.I. W.D., Baijnath

D.N.LT/SCHEDULE OF QUANTITY

Name of work:- R/D Manghlota to Pantehar Road Km 0/00 to 40/00.
(SH:- C/O R/wall at RD 3/230 to 3/242.)

Estimate Cost:- 333673.00/-
Earnest Money:- 6700.00 /-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m (one point five zero meter) in width or 10 sqm), (ten square meter) including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five zero meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m(Fifty meter).All kinds of soil.with in all leads by any mode of trasportation and other incidental ,as per direction and entire satisfaction of Engineer -in -charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	24.36	cum			
2	Proiding and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete in plain cement concrete 1:5:10 (one cement: five sand: ten graded stone aggreegate)40mm (fourty millimeters nominal size) to obtain the minimum compressive strength in or under water and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	60.72	cum			
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	22.00	Each			
4	Back filling with granular material behind abutment wing walls, return wall complete as per drawing and MORD technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals.	20.16	cum			
Total						

Executive Engineer
Bailjnath Division
H.P.P.W.D., Bailjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

17

Name of work :- A/R & M/O Various road under Bir Sub Division Bir
(SH:-Supplying and Stacking of Granular sub-base.)

Estimate Cost: 2,49,831.00/-
Earnest Money: 5,000.00/-
Time Limit :One Month


SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Supplying and Stacking of Granular sub-base with local materials (Table 400.13) by mix in place method normal complete as per Clause 401.4 as per Technical Specification Clause 408.as per direction of Engineer with in all leads and lifts and other incidental.the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	135.00	Per Cubic metre			
	Total					

Executive Engineer
Bajjnath Division
H.P.P.W.D., Bajjnath

D.N.I.T/ SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Uttrala to Surahi Pass (km 0/00 to 13/00)				Estimated Cost:- 499228.00		
(SH:- Removal of slips at various reaches .)				Earnest Money:- 10,000.00		
				Time:- Two Months		
SR. No.	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				In Figure	Figures	
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cuut material with in lift upto 1.50 mtr. And less than 100 mtr. As per technical specification 302.3.5 and 1611. Including carriage of materials within leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4125.85	Per cum			
Total:-						


 Executive Engineer
 Baljnath Division
 H.P.R.W.D., Baljnath

SCHEDULE OF QUANTITY

19

Name of work:-Restoration of rain damages on various roads under Deol Section.

(SH:-Hiring of JCB for removal of slips, dressing of road berms, filling depressions, clearance of Drain and Culvert)

Estimate Cost 374000.00
Earnest Money 7500.00
Time Two months

Sr.No.	Description of item	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of JCB (Excavator cum Loader) having bucket capacity .50 cum including P.O.L. charges, shifting charges and other ancillary equipment as required at site of work for removal of slips in all heights in all kinds of soils such as kankar, moorum, shingle, boulders, decomposed or soft variety of soil with spade work, pick work, jumper work, soft rock, hard rock, if and when required. The disposal of this unserviceable material has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place, the contractor shall be liable for it. All salvaged material such as quarried stone shall have to be neatly stacked along road side on road berms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly The work shall have to be carried out as per the instructions of the Engineer-in-Charge including all leads and lifts.	340.00			Per Hour	
	Total					

Executive Engineer
Bajjnath Division
H.P.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

20

Name of work: Restoration of Rain Damages on Paprola to Ultrala road km 0/00 to 12/00 .
(Sh:- C/O R/Wall at RD 6/200 to 6/209.80).

Estimate Cost: 4,94,593.00/-
Earnest Money: 9,900.00/-
Time Limit :Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	25.28	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	94.08	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	13.62	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	27.00	Each			
Total						

Executive Engineer
Baljnath Division
N.P.P.W.D., Baljnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O Road from Banwar Kuran to Village Uldhar km 0/00 to 3/00 (S H :Providing laying G-II at rd 0/00 to 0/290 and V-shape Drain at Rd 0/00 to 0/200 .)				Estimate Cost: 3,80,955.00/- Earnest Money: 7700.00/- Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	36.75	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	28.50	Per cubic metre			
3	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the intersitices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	70.80	Per Cubic Metre			

Execd. Engineer
 B.I. Division
 H.P.F.M.O., Baljnath

DNIT/DRAFT SCHEDULE OF QUANTITY

22

Name of work :- C/O Dharaman Sungal Jadiyala Majhera Chattar Ghar Sagoor Road km 0/00 to 3/00.
(SH:-Providing and laying C. C Pavement & Kharnja Soling at km 0/140 to 0/240)

Estimate Cost: 4,29,640.00/-
Earnest Money: 8,600.00/-
Time Limit :Two Month/5

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P.
1	Providing and laying hard stone Soiling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested graidient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	48.82	Per Cubic metre				
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	48.82	Per Cubic metre				
Total							

Executive Engineer
Bajnath Division
H.P.P.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Bir Palampur Road Km 0/00 to 40/00.
(Sh:- C/O R/Wall at RD 12/920 to 12/930).

Estimate Cost: 2,13,524.00/-

Earnest Money: 4,300.00/-

Time Limit :Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during de-watering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental,the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	11.40	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	35.80	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	7.20	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	6.00	Each			
Total						

Execd By Engineer
Bajnath Division
H.P.P.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

24

Name of work: C/O Road from Village Banwar Kuran To Village Uldhar km 0/00 to 3/00
(Sh:- C/O R/Wall at RD 0/055 to 0/065 & B/wall at RD 0/110 to 0/126).

Estimate Cost: 4,19,129.00/-
Earnest Money: 8,400.00/-
Time Limit :Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	42.02	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	77.72	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	6.30	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	24.00	Each			
Total						

Executive Engineer
Bajjnath Division
H.P.R.W.D., Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Lohardi to Andril Mallahan Road Km 0/00 to 2/500
(SH:-Providing and laying Kharanja Soling at km 0/00 to 0/250)

Estimate Cost: 2,62,046.00/-
Earnest Money: 5,300.00/-
Time Limit :Two Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Preparation of sub grade by dressing to camber earthwork for the cutting involved for sub grade to be paid for separately depending upon the classification of soil complete as per PWD specification and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	866.25	Per Square metre			
2	Providing and laying hard stone Soiling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	129.94	Per Cubic metre			
Total						

Executive Engineer
Bajjnath Division
H.P.P.W.D., Bajjnath

DNIT/SCHEDULE OF QUANTITY

Estimated Cost:- 2,53, 000.00

Earnest Money:- 5100.00

Time Limit:- Two Months

Name of work:- : Restoration of Rain Damages on Various roads under Baijanth sub Division (Chadhiar Section).
(SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & Cleaning Of Slush from Catchpit of culverts)

Sr. No.	Description of items	Quantity	Rates (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In words		
1	2	3	4	5	6	7
1.	Hiring of Hydraulic Excavator having capacity of 0.9 Cum (zero point nine) in working condition per hour basis excluding Sunday Holiday, for rainy seasons as and when required. The operational and maintenance charges POL charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator. the rate including hauling / carriage of materials to various location of transportation in all leads , lifts and other incidental complete in all respect and entire satisfactions of Engineer -in -Charge. The rates are inclusive all taxes levy by the govt time to time including GST .	230.00 Hours			Per Hour	
	Total					

Executive Engineer
Baijanth Division
H.P.P.W.D., Baijanth

DNIT/DRAFT SCHEDULE OF QUANTITY

(27)

Name of Work : C/O Link Road from Bir Palampur road to village Bari 0/00 to 1/200 . (SH:-Construction Of Subgrade and Providing and laying hard stone Soiling at km 0/400 to 0/890)	Estimate Cost: 4,98,036.00/- Earnest Money: 10,000.00/- Time Limit : Two Months
---	--

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
					Words	
1	Construction Of Subgrade and earthen shoulders with approved material obtained from borrow pits with in all lifts and leads transporting to site spreading grading to required slope and compacted to meet requirements as per Technical Specification Clause 408.as per direction of Engineer including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	235.20	Per Cubic Metre			
2	Providing and laying hard stone Soiling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	246.96	Per Cubic metre			
Total						

Executive Engineer
 Baljona Division
 H.P.P.W.D., Baljnath

D.N.I.T/ SCHEDULE OF QUANTITY

Name of work :- R/R Damages on Barot Polling Road Km 0/00 to 8/050.

(Sh:- balance Work of Repair of 2.00 mtr span slab culvert and Wing Wall at RD 4/307 to 4/315).

Estimated Cost: Rs. 291571.00

Earnest Money: Rs. 5,900.00

Time Limit : One Month

SCHEDULE OF WORKS

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m (one point fifty meter) in width or 10 sqm), including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point fifty meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m(Fifty meter).All kinds of soil.with in all leads by any mode of trasportation and other incidental ,as per direction and entire satisfaction of Engineer -in -charge. The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Government.	16.96	Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge.The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Government.	47.28	Cum			
3	Back filling behind abutments, wing walls and return walls complete as per drawing and M.O.R.D. technical specification clause 1203 and 1604 and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	4.80	Cum			
TOTAL						

Executive Engineer
Bajinath Division
H.P.P.W.D., Bajinath

DNIT/DRAFT SCHEDULE OF QUANTITY

29

Name of Work : C/O Link Road Dharmshala Dadh Holta Chadhiar to saklani Basti km 0/00 to 2/060
(SH:-P/L C. C Pavement & W B M G-II at km 0/315 to 0/454)

Estimate Cost: 4,97,535.00/-
Earnest Money: 9,900.00/-
Time Limit : Two Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
					Words	
1	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the intersitices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	8.35	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilogramms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	66.77	Per Cubic metre			
Total						

Executive Engineer
Bajnath Division
H.P.P.W.D. Bajnath

(30) (a)

D.N.I.T/ SCHEDULE OF QUANTITY

Name of work :- C/O Link Road from Rainabari to Balh.

(Sh:- C/O R/wall at Km 0/00 to 0/017 & 0.60 mtr. Span RCC slab culvert at RD 0/040).

Estimated Cost: Rs.

348243.00

Earnest Money: Rs.

6,900.00

Time Limit :

Two Months

SCHEDULE OF WORKS

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5mtr (one point fifty meter) in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 mtr, (one point fifty meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50mtr (Fifty meter). All kinds of soil. with in all leads by any mode of trasportation and other incidental ,as per direction and entire satisfasation of Engineer -in -charge . The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	27.47	Cum			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty milimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge . including carriage of material within all leads and lifts and other incidentals . The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	42.50	Cum			
3	Back filling behind abutments, wing walls and return walls complete as per drawing and M.O.R.D. technical specification clause 1203 and 1604 and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	17.00	Cum			

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge.The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	15.00	Each			
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 M-10 The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	2.59	Cum			
6	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 and 1204 M-15 The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	10.55	Cum			
7	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 800, 1205.4 and 1205.5 RCC M-25 The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	1.68	Cum			
8	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	170.00	Kg			
TOTAL						


 Executive Engineer
 Bajjnath Division
 H.P.P.W.D. Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :C/O link road from Rainabari to Balh (SH: Cutting in earth work in km 1/070 to 1/205)				Estimate Cost: 4,47,883.00/- Earnest Money:9,000.00/- Time Limit : Three Months		
Sr. No	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 224.76 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1461.95	Per cubic metre			
	Total					

Ap
Executive Engineer
Bajnath Division
H.P.P.W.D., Bajjnath

D.N.I.T/SCHEDULE OF QUANTITY

Name of work :-C/O Bhardi to Balh Road via Sunka Ram House Km 0/00 to 2/00.
(Sh:- P/L Tack Coat with Seal Coat at Km 0/00 to 0/250).

Estimated Cost: Rs. 95275.00

Earnest Money: Rs. 2,000.00

Time Limit : One Month

SCHEDULE OF WORKS

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the Rate of 0.225 kg (zero point two hundred twenty five) per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	800.63	Sqm			
2	Providing and laying seal coat sealing the voids in a bituminous surface laid the specified levels grade and cross fall using type A type C type C as per technical specification clause 510 type B VG-10.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	800.63	Sqm			
TOTAL						

Executive Engineer
Baljnath Division
H.P.R.W.D. Baljnath

33

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - Construction of Tashizong to Bheth Jhikhi Bheth Upperli Ghorpith Averi km 0/00 to 8/915 & Construction of Chobin Sansai & Kothi Kohli Via Patel Nagar road km 0/00 to 13/860 .
(SH: Supply and fixing Computer system with UPS .)

Estimate Cost: 1,84,000.00
Earnest Money: 3700.00
Time Limit : One Month

SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Rate to be entered by the Bidder in		AMOUNT Rs. P
				Figures	Words	
1	Providing and instalation Dell AIO Desktop Optiplex -5400 with Intel Core i5-12100T-12th Gen. Processor 8GB DDR4 RAM expandable upto 16GB,1TB Hd Drive (7200RPM) 24" Led clour display with FHD (1920x1080) interrated HD Graphics & webcam 2xUSB 3.0, 2xUSB 2.0, Audio jack/VGA/HDNI/DP port, 10/100/1000M complant LAN USB keyboard & USB Mouse internal spkr, connectivity 802.11b/g/n/ac, PL-Window 10Pro 64bit.O.S with three year onsite warranty.	2.00	Each			
2	Providing and installation of 650 V A Legend Sn:24BOU1104R03219000	2.00	Each			

Executive Engineer
Bajjnath Division
H.P.P.W.D. Bajjnath